Adobe® Photoshop® CC Help

Legal notices

For legal notices, see http://help.adobe.com/en_US/legalnotices/index.html.

Last updated 11/30/2015

Contents

Chapter 1: What's new

New features summary 1

Chapter 2: Photoshop and mobile apps

Photoshop family of mobile apps 113
More Photoshop companion apps 114

Chapter 3: Workspace

Workspace basics 123
Use tools 130
Touch gestures 134
Technology previews 134
Customize keyboard shortcuts 135
Metadata and notes 137
Specify columns for an image 139
Rulers 139
Panels and menus 140
Place files 145
Place Photoshop images in other applications 147
Plug-ins 151
Key shortcuts 152
Presets 153
Memory and performance 156
Preferences 157
Show or hide non-printing Extras 158
Position with the Ruler tool 159

Position elements with snapping 160
How to tune Photoshop for peak performance 161

Chapter 4: Web, screen, and app design
Design Space (Preview) 162
Artboards 175
Export artboards, layers, and more 183
Device Preview 186
Copy CSS from layers 190
Work with web graphics 190
Modify slice layout 192
HTML options for slices 196
Create web photo galleries 198
Slice web pages 205

Chapter 5: Image and color basics
Resize images 209
Image essentials 211
Image size and resolution 214
Acquire images from cameras and scanners 220
Create, open, and import images 222
Viewing images 226
Color modes 231
Match, replace, and mix colors 234
Distort filters are unavailable 239
Invalid JPEG Marker error | Opening images 239
Image information 241
High dynamic range images 245
Customize indexed color tables 252
Customize color pickers and swatches 254
Convert between color modes 256
About color 261
Color and monochrome adjustments using channels 263
Erase parts of an image 266
Choose colors 269
Viewing multiple images 275
Blending modes 277
Choose colors in the Color and Swatches panels 281
Add a conditional mode change to an action 283
Add swatches from HTML CSS and SVG 283

Chapter 6: Layers
Layer basics 284
Nondestructive editing 288
Create and manage layers and groups 289
Select, group, and link layers 291
Mask layers 293

Layer opacity and blending 298
Move, stack, and lock layers 301
Layer comps 302
Work with Smart Objects 305
Apply Smart Filters 311
Align and distribute layers 314
Combine multiple images into a group portrait 317
Manage layers and groups 317
Generate image assets from layers 320
Layer effects and styles 326
Extract assets 335
Mask layers with vector masks 337
Combine images with Auto-Blend Layers 338
Reveal layers with clipping masks 339
Load selections from a layer or layer mask's boundaries 341
Knockout to reveal content from other layers 341
Edit layer masks 343
Layers 101 343

Chapter 7: Selecting
Make quick selections 344
Make selections 346
Select with the marquee tools 347
Select with the lasso tools 348
Select a color range in an image 351
Adjust pixel selections 353
Extract an object from its background 359
Select the image areas in focus 361
Save selections and alpha channel masks 365
Move, copy, and delete selected pixels 368
Duplicate, split, and merge channels 373
Create a temporary quick mask 375
Convert between paths and selection borders 377
Channel calculations 378
Channel basics 380
Refine a selection 383
Selecting areas of a photo 383

Chapter 8: Image adjustments
Perspective Warp 384
Reduce camera shake blurring 392
Healing brush examples 398
Export color lookup tables 426
Adjust image sharpness and blur 427
Understand color adjustments 433
Convert a color image to black and white 439
View histograms and pixel values 440

Target images for press 446
Make quick tonal adjustments 448
Apply a Brightness/Contrast adjustment 452
Adjust color and tone with Levels and Curves eyedroppers 453
Adjust HDR exposure and toning 454
Levels adjustment 455
Adjust image color and tone 458
Adjustment and fill layers 459
Apply special color effects to images 463
Apply the Color Balance adjustment 465
Curves adjustment 466
Adjust hue and saturation 470
Adjust shadow and highlight detail 473
Auto color corrections 475
Using adjustment layers 475
Dodge or burn image areas 476

Chapter 9: Camera Raw
New features summary 477
Introduction to Camera Raw 482
Vignette, grain, and dehaze effects in Camera Raw 489
Automatic perspective correction in Camera Raw 491
How to make non-destructive edits using Camera Raw 494
Radial Filter in Camera Raw 494
Manage Camera Raw settings 497
Open, process, and save images in Camera Raw 502
Repair images with the Enhanced Spot Removal tool in Camera Raw 505
Make local adjustments in Camera Raw 508
Rotate, crop, and adjust images 513
Sharpening and noise reduction in Camera Raw 515
Correct lens distortions in Camera Raw 517
Make color and tonal adjustments in Camera Raw 519
Process versions in Camera Raw 525
Adjust color rendering for your camera in Camera Raw 526
New features summary 528
Camera Raw 7 plug-in 530
Enhancing Raw images 530

Chapter 10: Repair and restoration
Content-Aware Patch and Move 531
Retouch and repair photos 533
Correct image distortion and noise 540
Using Content-Aware Patch 543
Using Content-Aware Move and Extend 543
Basic troubleshooting steps to fix most issues 543

Chapter 11: Reshaping and transforming

Transform objects 547
Adjust crop, rotation, and canvas size 550
Crop and straighten photos 554
Create panoramic images with Photomerge 557
Warp images, shapes, and paths 560
Vanishing Point 563
Content-aware scaling 577
Use the Liquify filter 579
Free transformations of images, shapes, and paths 584
New Crop tool 586
Wide-angle lens correction 586
Correcting perspective 586
Straightening a crooked image 586

Chapter 12: Drawing and painting

Modify shapes 587
About drawing 588
Draw shapes 590
Painting tools 594
Create and modify brushes 596
Manage paths 602
Generate a pattern using the Pattern Maker 604
Gradients 606
Fill and stroke selections, layers, and paths 612
Draw with the Pen tools 616
Brush presets 621
Paint with the Mixer Brush 623
Manage pattern libraries and presets 625
Edit paths 626
Create patterns 634
Draw or paint with a graphics tablet 635
Create textured brushes 635
Add dynamic elements to brushes 637
Paint stylized strokes with the Art History Brush 641
Paint with a pattern 642
Add color to paths 642
Vector Shapes 644
New shape, type, and design tools 645

Chapter 13: Text

Format characters 646
Format paragraphs 651
Troubleshoot fonts | Photoshop CC 2014, CC, CS6, CS5 657
Create type effects 666
Edit text 671
Line and character spacing 676

Asian type 679
Arabic and Hebrew type 685
Text Engine error using type tool in Photoshop CC | Windows 8 688

Chapter 14: Video and animation
Video editing | CC, CS6 689
Edit video and animation layers 691
Audio doesn't play in video files encoded with Dolby Digital AC3 695
Video and animation overview 696
Preview video and animations 701
Paint frames in video layers 704
Create timeline animations 706
Create images for video 712
Create frame animations 717
Import video files and image sequences 724
Video workflow 727

Chapter 15: Filters and effects
Use the Blur Gallery 728
Filter basics 736
Filter effects reference 740
Add Lighting Effects 750
Use the Adaptive Wide Angle filter 753
Use the Oil Paint filter 754
Smudge image areas 756

Chapter 16: Save and export
Supported file formats 757
Save files in graphics formats 757
Save images 762
File formats 765
Save and export video and animations 771
Save PDF files 778
Digimarc copyright protection 786

Chapter 17: Printing
Print 3D objects 789
Print from Photoshop 798
Print with color management 801
Contact Sheets and PDF Presentations 803
Print photos in a picture package layout 804
Printing spot colors 807
Print images to a commercial printing press 810
Duotones 815
Troubleshoot printing problems | Photoshop 818
Improve color prints from Photoshop 823

Chapter 18: Automation

Create data-driven graphics 828
Scripting 833
Process a batch of files 833
Play and manage actions 838
Add conditional actions 841
About actions and the Actions panel 842
Recording tools in actions 843
Photoshop UI toolkit for plug-ins and scripts 843
Batch Actions 846

Chapter 19: 3D and technical imaging

Creative Cloud 3D Animation (Preview) 847
3D painting 853
3D panel enhancements | Photoshop CC 858
Essential 3D concepts and tools 861
Photoshop and MATLAB 865
Measurement 867
Image Stacks 873
DICOM files 876
Count objects in an image 879
Combine and convert 3D objects 881
3D texture editing 882
3D workflow 885
3D rendering and saving 888
3D panel settings 892
Create 3D objects and animations 903
New 3D reflections and dragable shadows 908
Streamlined 3d controls 908

Chapter 20: Color management

Understanding color management 909
Keeping colors consistent 911
Color settings 914
Working with color profiles 918
Color-managing documents for online viewing 923
Color-managing documents when printing 923
Color-managing imported images 928
Proofing colors 929

Chapter 1: What's new

New features summary

The 2015 releases of Photoshop CC roll out exciting new features for designers and digital photographers. Read on for a quick introduction to these features and links to resources offering more information.

Note: For answers to common questions asked about the 2015 release of Photoshop CC, see the FAQ.

For a summary of features introduced in earlier releases of Photoshop CC, see:

- Feature summary | Photoshop CC 2014 releases
- Feature summary | Photoshop CC 2013 releases

Photoshop CC 2015.1 (November 2015 release)

Artboard improvements

Enhanced in this release of Photoshop CC

Artboards are much easier to work with in this release of Photoshop CC.

- Quickly add new artboards to a document by clicking the intuitive + icons alongside a selected artboard. Option/Alt+click to duplicate the selected artboard.



- Use guides and grids to precisely place elements within an artboard. With an artboard selected, drag guides from the ruler to the canvas. These guides now move with the artboard. When you duplicate the artboard, the associated guides are duplicated as well.
- Filter layers in the Layers panel by artboard.
- Align selected layers within an artboard.
- Quickly dissolve an artboard into its constituent elements.
- Lock the position of an artboard on the canvas.



- Prevent auto-nesting into or out of an artboard.

- Specify your preferred artboard matte color and border type. Select Preferences > Interface > Appearance > Artboards.



For more information, see **Artboards**.

Improvements to Creative Cloud Libraries integration

Enhanced in this release of Photoshop CC

Find content faster by searching across your libraries and across Adobe Stock. Drag and drop assets to and from the Layers panel, add your favorite brushes, and share your library with others. And get content into libraries faster with a new bulk import dialog box.

Additionally, you can now also quickly create a library from assets contained in a document.

For more information, see **Creative Cloud Libraries in Photoshop**.



Design Space (Preview) enhancements

Enhanced in this release of Photoshop CC

Enhancements to Design Space (Preview) in this release further streamline and optimize design workflows with the following enhancements:

- A unified sampling experience
- Efficient masking
- Robust app and cross-document search
- Integrated layer and batch export.

Design Space (Preview) now also offers access to Creative Cloud Libraries as well as seamless movement to and from standard Photoshop CC.

For more information, see **Design Space (Preview)**.

Oil paint filter

Reintroduced in this release of Photoshop CC

The Oil Paint filter, reintroduced in this release of Photoshop CC, lets you quickly give an image the visual appearance of a classic oil painting.

For more information, see **Use the Oil Paint filter**.

Touch workspace and gestures

Enhanced in this release of Photoshop CC

If you own a Photoshop-supported Windows-powered device, such as the Surface Pro, you can use these convenient touch gestures while using Photoshop on it:

- Two-finger pan
- Two-finger pan and zoom
- Two-finger pan and rotate
- Five-finger cycle screen mode
- Two-finger reset or restore view
- Two-finger step back in history (Undo)
- Two-finger step forward in history (Redo)
- Three-finger history scrub
- Two-finger free transform (Pan, zoom, and rotate)

For more information, see **Touch capabilities and customizable workspaces**.

Use 3D models in 2D designs

New in this release of Photoshop CC

(Currently available only in English) Composite human characters from Adobe Fuse CC (Preview) into any Photoshop project from a layout to a final design and even print the characters with a 3D printer. Easily adjust camera angles and lighting within Photoshop CC to get just the look you want. Simply start with a model created in Adobe Fuse CC (Preview), apply poses and animations to it in the Properties panel in Photoshop CC, incorporate it into your image or design, and even add effects.

For more information, see .



Start and Recent Files workspaces

New in this release of Photoshop CC

The brand new Start workspace in Photoshop gives you quick access to your recent files, libraries, and presets. Depending on your subscription status, this workspace may also display content tailored for your requirements. You can also look for the right Adobe Stock asset for your project directly from within the Start workspace.

Photoshop displays the Start workspace at launch or whenever no documents are open.

For more information, see:

- Workspace basics
- **Start and Recent Files workspaces**



To quit the Start workspace, simply press the Esc key. If you so prefer, you can choose to disable this workspace. Select Preferences > General and then deselect Show Start Workspace When No Documents Are Open.

Recent Files workspace

The new Recent Files workspace in Photoshop displays your recent files in a pane for ready access when you're opening files. You can view the files as a list or in the thumbnail view. You can also search for Adobe Stock assets directly from within the Recent Files workspace.

The Recent Files pane is disabled by default. You can enable it by selecting Preferences > General > Show Recent Files Workspace When Opening Files.

Enhanced export experience

Enhanced in this release of Photoshop CC

Export faster and with better compression for all file formats, especially JPEG. Additionally, while exporting assets, you can now do the following:

- Add metadata, such as copyright, to your exported files.
- Export assets at multiple sizes.
- Convert exported files to the sRGB color space.
- Select multiple assets at once while making file setting changes—for Quick Export and assets exported using the Export As dialog.

  For more information, see **Export artboards, layers, and more**.



Customizable toolbar

Enhanced in this release of Photoshop CC

Customize the Photoshop toolbar by destacking, regrouping and even removing tools. You can also save and share customized toolbars as presets. Select Edit > Toolbar.

For more information, see .



Quickly find the right font

Enhanced in this release of Photoshop CC

Quickly find the fonts you use often by starring individual fonts as favorites or selecting from recently used fonts. Narrow down your search by filtering fonts by classification, like serif or sans serif, or by visual similarity.

Try: Select the Type tool and, while working with the font list, click the Show Similar Fonts icon.

For more information, see .



A Filter fonts by classification ***B*** *Show synchronized fonts from Typekit* ***C*** *"Star" favorite fonts* ***D*** *Show similar fonts*

Deeper integration with Adobe Stock

Enhanced in this release of Photoshop CC



You can now search for Adobe Stock assets and view the search results right within the Libraries panel. License your chosen asset straightaway from within the Libraries panel or continue to use its watermarked preview until you're ready to license it. When you license the stock asset, all linked instances of the asset in your open documents are automatically updated to the high-resolution stock asset without the watermark. Effects that you apply to the watermarked stock asset are preserved when you license it later.

For more information, see these resources:

- **Use Adobe Stock in apps supporting Creative Cloud Libraries**
- **Photoshop and Adobe Stock**

Modifier Keys palette

New in this release of Photoshop CC

The new Modifier Keys palette lets you access frequently-used keyboard modifiers—Shift, Ctrl, and Alt—on Windows-powered touch devices, such as the Surface Pro. Select Window > Modifier Keys.

3D imaging

Enhanced in this release of Photoshop CC

New Depth Map options

Photoshop now provides two additional Depth Map options—Solid Extrusion and Double-Sided Solid Extrusion.

- 3D > New Mesh From Layer > Mesh Preset > Solid Extrusion
- 3D > New Mesh From Layer > Mesh Preset > Two Sided Solid Extrusion

Render still 3D objects

You can now render still 3D objects using the Render Video dialog (3D > Render Document To File).

Import and export SVG files

Enhanced in this release of Photoshop CC

Open and place native SVG files—which can rescale for any size device or any resolution—in your Photoshop designs. Just double-click the object to edit it in Adobe Illustrator. Also export SVG image assets using the new export experience.

Camera Raw | New features

Enhanced in this release of Photoshop CC



For a summary of the latest features in Camera Raw, see New features summary.

Other enhancements

- The Glyphs panel now displays the most-recently-used glyphs. See Most-recently-used glyphs .
- Updated and refined Welcome experience
- Ability to resize the Export As dialog
- Improved PNG interface in the Export As dialog for exporting to PNG-32 or PNG-8
- Persistent file type and quality settings between Exports
- Set type layer position on canvas (X/Y) in the Properties panel
- Option to skip transform when placing a Libraries object
- New option to save to Libraries while pasting a Smart Object from Adobe Illustrator
- Better default shape stroke value (1 px instead of 3 pt)
- New 16 pt preset value for Font Size
- Hyphenation now defaults to Off.
- Several new Designer Favorites in the Glyphs panel
- While moving a layer to a layer group or artboard, you can now choose to move it to bottom of the Z-order instead of top. Hold down the Shift key while moving the layer.
- Device Preview: Option to check for devices connected to the computer. See Check for devices.
- Support for exporting as sRGB
- Options to better control Healing tool results. For more information, see Healing brush examples.
- Locked Layers are now not auto-nested.
- Option to revert to the old Healing Brush
- Improved baseline alignment of several dialogs and widgets
- New keyboard modifier (Shift) to control if layers get added to the bottom of groups
- Improvements to Copy/Paste/Drag functionality between documents, the clipboard, and Creative Cloud Libraries
- Artboard and marquee snapping improvements

- New artboard preference for matte Color and Border Type
- The Align command now works with a single selected layer within an artboard.
- Artboard custom presets are now displayed in the Artboard tool bar/property presets menu.
- Updated video presets with Digital Cinema Initiatives (DCI) 4K and 8K; HDTV has moved up the list
- You'll no longer encounter the No Layers Selected error while clicking with the Move tool outside the canvas.

What's changed

- Sync Settings has been removed in Photoshop CC 2015.1. The existing service in Photoshop CC and CC 2014 will become unavailable in the near future. To migrate your presets/settings from an earlier version of Photoshop CC to this release, see Migrate settings .
- PNG format changes for asset export. The Format pop up menu now includes a simplified PNG option.
  - Selecting Transparency with PNG generates 32-bit PNG assets.
  - Selecting Smaller File generates 8-bit PNG assets.
  - Leaving the above options deselected generates 24-bit PNG assets.
- The 3D Render Quality slider setting has now been moved to the Render Video dialog. It was earlier part of the 3D Preferences dialog.

Photoshop CC 2015 (June 2015 release)

Artboards

New in this release of Photoshop CC



If you are a web or UX designer, you increasingly find yourself designing websites or apps for multiple devices. Artboards, new in the 2015 release of Photoshop CC, help streamline your design process by giving you an infinite canvas on which you can lay out designs for different devices and screens. While creating artboards, you can choose from a wide variety of preset sizes or define your own custom artboard size.

Artboards are useful even if you normally design for just one screen size. For example, while designing a website, you can use artboards to view designs for different pages side-by-side and in context.

For more information, see **Artboards**.

Creative Cloud Libraries

Enhanced in this release of Photoshop CC

Creative Cloud Libraries integration in Photoshop is now enhanced:

Library-linked assets When you use a graphic from the Libraries panel, a library-linked asset is created. This asset behaves in much the same way as a locally linked smart object, but with the benefit of the asset being in the cloud. Also, when you create a new library graphic from a smart object, the corresponding layer is converted to a library-linked asset.

Adobe Stock integration with Libraries You can now add a watermarked stock image to any of your libraries directly by using the Adobe Stock website. You can then use the watermarked image in your Photoshop documents as a library-linked asset. When you choose to license the image—which you can do directly from within the Libraries panel—all instances of the watermarked asset in your open documents are updated to the high-resolution licensed image.

Performance improvements Libraries integration in Photoshop now offers reduced disk usage, more efficient bandwidth utilization, and faster propagation of library changes between Creative Cloud applications.

For more information, see Creative Cloud Libraries in Photoshop.

Adobe Stock

New in this release of Photoshop CC

Adobe Stock is a new service that provides designers and businesses with access to 45 million high-quality, curated, royalty-free images, illustrations, and vector graphics for all their creative projects. You can search for Adobe Stock content directly from within Photoshop. Select File > Search Adobe Stock.

Adobe Stock is also deeply integrated with Creative Cloud Libraries. You can now add a watermarked stock image to any of your libraries directly by using the Adobe Stock website. You can then use the watermarked image in your Photoshop documents as a library-linked asset. When you choose to license the image—which you can do directly from within the Libraries panel—all instances of the watermarked asset in your open documents are updated to the high-resolution licensed image.

For more information, see:

- **Photoshop and Adobe Stock**
- **Using Adobe Stock**
- Find assets on Adobe Stock

Design Space (Preview)

New in this release of Photoshop CC

Important: Design Space (Preview) requires Mac OS X 10.10 or Windows 8.1 64-bit OS or later and is currently displayed only in English.

Design Space (Preview) is aimed at becoming a modern design experience inside Photoshop streamlined for the requirements of web, UX, and mobile app designers. It's an HTML5/CSS/JS layer built on top of Photoshop. We've separated out standard Photoshop from the interface so that we can use this layer to create new UI, smarter interactions, and top-requested features. This release is a Technology Preview, which means it's an early look at this new direction. It's rough and the feature set is limited, but we wanted to get this out early so we can start hearing from you.

To enable Design Space (Preview), select Preferences > Technology Previews, and then choose Enable Design Space (Preview).

Help us shape Design Space (Preview) into the experience you want. Give us feedback @psdesign.

For more information and a list of known issues in this release, see **Design Space (Preview)**.



A Tools B Distribute and Align C Transform D Style E Layers

Export artboards, layers, and more

New in this release of Photoshop CC

You can now export artboards, layers, layer groups, and Photoshop documents as JPEG, GIF, PNG, PNG-8, or SVG image assets.

Select the artboards, layers, and layer groups in the Layers panel. Right-click the selection, and then select one of the following from the context menu:

- Quick Export As[image_format]
- Export As...

To export the current Photoshop document or all artboards in it, select File > Export As [image_format] or File > Export > Export As...

For more information, see **Export artboards, layers, and more**.



Layer styles

Enhanced in this release of Photoshop CC

The Layer Style dialog now lets you apply multiple effects—strokes, inner shadows, color overlays, gradient overlays, drop shadows, and so forth—to a single layer style. Also, more than one instance of some effects can now be applied to a layer style.

Follow these steps:

1. Select Layer > Layer Style, and then select an option.
2. Select the effects you want to add to the layer style. Effects with a icon can be applied more than once in the layer style.
3. Adjust the settings for the effects. For example, adjust the size and opacity of a stroke.
4. Click OK to apply the effects to the layer style.

UI changes to the Layer Style dialog

You can now use the left pane of the Layer Style dialog to perform the following operations:

- Change the effect stacking order
- Delete effects
- Through a new flyout menu, accessible by clicking the icon:
  - Manage which effects appear in the section

- Delete hidden effects
- Reset any changes you've made to the default state of the left pane

Device Preview and the Preview CC companion app

New in this release of Photoshop CC



Get real-time previews of your Photoshop designs on multiple iOS devices with the new Device Preview feature in Photoshop and the Adobe Preview CC mobile app. Changes you make in Photoshop CC are displayed in Preview CC in real time. You can reliably connect multiple iOS devices to Photoshop using USB or over Wi-Fi.

If you have a document with artboards, Device Preview attempts to show you the correct artboard by matching the size and position of the artboard with the size of the connected device. You can also use the navigation bar to preview a specific artboard on the device or swipe through artboards that have matching widths.

Preview CC supports iOS devices running iOS 8 or later.

For more information, see:

- Device Preview
- Adobe Preview CC FAQ

Blur Gallery | Restore noise in blurred areas

New in this release of Photoshop CC



Sometimes after you apply a Blur Gallery effect, the blurred area of the image looks synthetic or unnatural. You can now restore noise/grain to a blurred image area to give it a more realistic appearance.

Set the options in the blur Effects panel on the Noise tab.

For more information, see **Restore noise in blurred areas**.

Glyphs panel

New in this release of Photoshop CC

Photoshop now has a new panel that lets you work more efficiently with glyphs.

To access the Glyphs panel, do one of the following:

- Select Type > Panels > Glyphs panel.
- Select Window > Glyphs. For more information, see **Glyphs panel** .



Content-aware move with tranform

Enhanced in this release of Photoshop CC

The Content-Aware Move tool now incorporates a Transform On Drop option. This new option allows for the transformation—scaling, rotating, and flipping—of the foreground object before it is blended into the new location. This option is particularly useful when moving/replicating an object to a different depth and when rescaling is required.

Selecting the Transform On Drop option enables the familiar Transform tool menu that allows you to scale and rotate the object after it is moved to the new location.

- To apply the transformation from the opposite corners, rather than just one side, hold the Option (Mac) or Alt (Windows) key while performing the transform operation.
- Right-clicking the Transform tool area presents a context menu offering the ability to flip horizontally and vertically.

Once you've made the necessary changes, commit the changes. The content-aware move tool now begins to blend the object with its surroundings and fills in the old location.

Note: *If the Transform On Drop option is not enabled, the Content-Aware Move tool behaves as in earlier releases of Photoshop. The blending process in this case begins right after the mouse click is released.*

Camera Raw | New features

For a summary of the latest features in Camera Raw, see New features summary.

3D printing

Enhanced in this release of Photoshop CC

Export as PDF or SVX files You can now export 3D models as PDF or SVX files.

While specifying the 3D print settings, select Print To: Local. Then, select PDF File or SVX File as the printer.

For more information about 3D printing, see Print 3D objects.



Control bump map depth You can now control the depth or height of bump maps for printing. Follow these steps:

? Open a 3D file containing a bump map.



? In the 3D panel, choose Scene. Then, select the 3D Print Settings tab in the Properties panel.



? Under Surface Detail, specify appropriate values for the Min and Max fields. These values determine the new depth of the bump maps.



Updated PLA profile for MakerBot The MakerBot PLA profile has been updated for more reliable printouts.

Simplify meshes in preparation for printing See Simplify meshes .

3D imaging

Enhanced in this release of Photoshop CC

Simplify meshes The 3D menu now has a new command (3D > Simplify Meshes) that lets you reduce the number of triangles in a mesh to a more manageable number. The command algorithmically reduces the number of triangles to the number you specify while attempting to maintain the fidelity of the model. This enhancement is useful for reducing the complexity of a file in preparation for 3D printing.

You can view a live preview of mesh simplification changes before they're implemented.


Simplify 3D Mesh
3D Move:
Mesh Settings
Simplify:
65024
Original Size: 65024
Estimated Size: 100%
Material Settings
Generate Normal Map(s)
2048 x 2048
px
Preview Settings
Shadows
Preview Simplification
Mesh Overlay
Cancel
OK



Improved export UI The UI for exporting 3D layers as Collada DAE, Flash 3D, Google Earth KMZ, 3D PDF, STL, U3D, VRML, and OBJ formats is now improved.

Select 3D > Export 3D Layer.



Export a single mesh A 3D scene typically comprises many elements or meshes. You can now right-click a mesh in the overall scene and export it individually.

Right-click the mesh in the 3D panel and choose Export Mesh from the context menu. This functionality currently exports meshes only in Collada or KMZ formats.

Generate better bump maps and normal maps Photoshop now lets you tweak your bump or normal maps using tools such as Blur, Detail Scale, and High/Medium/Low Frequency.

Select Filter > 3D > Generate Bump Map or Filter > 3D > Generate Normal Map.


Generate Bump Map
3D Move:
Lighting Preset:
Day Lights
Bump Details
Invert Height
Blur:
0.5
Detail Scale:
80%
Contrast Details
Low
Medium
High
5%
6%
59%
Material Preview
Bump:
100%
Tile
U/X:
1
V/Y:
1
Offset
U/X:
0%
V/Y:
0%
Object:
Sphere
Cancel
OK



Create bump maps or normal maps from diffuse textures You can now create bump maps or normal maps from diffuse textures. The texture attached to the diffuse texture is automatically loaded as filters for the purpose of creating bump maps or normal maps. Once you're satisfied with the way your map is looking, Photoshop applies the generated bump map or normal map to those textures.

Follow these broad steps:

1 Open the file containing the diffuse map.

2 Ensure that the desired texture is selected in the 3D panel.



? Click the folder icon next to Bump or Normal in the Properties panel. Then, from the context menu, select Generate Bumps From Diffuse or Generate Normals From Diffuse.



1 Specify appropriate settings in the Generate Bump Map or Generate Normal Map dialog.

2 Click OK to generate the map.

Convert a vertex color to a texture color 3D-scanned PLY files typically have vertex colors and no textures. You can convert a vertex color to a texture color. Do the following:

1 Open the PLY file.

2 In the Layers panel, under Textures in a 3D layer, double-click the diffuse to open the texture.

3 Select 3D > Create Painting Overlay > Vertex Colors.

UI toolkit for plug-ins and scripts

Enhanced in this release of Photoshop CC

The UI toolkit for building Photoshop plug-ins and scripts has been enhanced to support HiDPI/Retina displays. Also, plug-ins built using the toolkit now look more consistent with the overall Photoshop UI.

For more information, see **Photoshop UI toolkit for plug-ins and scripts**.

Other enhancements

- In earlier releases of Photoshop, while painting with the Healing Brush, you'd see a semi-transparent gray area and a progress bar before the healed content became visible. In the 2015 release of Photoshop CC, Healing Brush changes render in real time as you paint.
- The Content-Aware Move tool now has a Transform On Drop option. When this option is enabled, you can scale the part of the image that you've just moved to its new location.
- Preference panels are organized better.
- Photoshop now uses 80% less energy when idling.
- The Welcome screen loads faster.
- There's a new command to release all RAM and scratch disk use. Hold down the Option/Alt key and select About Photoshop. Or, select Edit > Purge > All.
- The Photomerge dialog now has a Content Aware Fill Transparent Areas option. Use this option to give your panoramas that picture-perfect finish.
- Most adjustments (Image > Adjustments) can now be applied as smart filters. Convert the layer to a smart object and then apply an adjustment to it.
- Syncing performance for Creative Cloud Libraries has improved.
- Moving a layer to a group now moves it to the top of the Z-order instead of the bottom.
- Step backward/forward operations no longer change the layer selection.
- A new preference lets you revert Esc behavior while entering text.

What's changed

- Experimental features are now called technology previews. For more information, see Technology previews.
- Scale the UI 200 percent for high-density displays is no longer a technology preview feature. It is now part of standard Photoshop functionality. To enable this feature, select Preferences > Interface > UI Scaling: 200.
- The File > Save For Web option is now File > Export > Save For Web (Legacy). For more information, see Save For Web in Photoshop CC 2015 .
- The following options have moved to the File > Export submenu:
  - Export Layers To Files
  - Export Layer Comps To PDF
  - Export Layer Comps To Files
- Extract assets functionality has been replaced with more intuitive options to export artboards, layers, layer groups, and documents as image assets. See Export artboards, layers, and morefor information about these newer export options.
- The Digimarc plug-in is no longer installed by default. You can, optionally, install it directly from http://www.digimarc.com/products/guardian/images/photoshop-plug-in.

Chapter 2: Photoshop and mobile apps

Photoshop family of mobile apps

Adobe Photoshop Fix

Use Adobe Photoshop Fix to combine the power of Adobe Photoshop desktop software with the convenience of mobile for a creative, easy-to-use photo retouching experience on your iPhone or iPad. Heal, smooth, liquify, lighten, and make other edits and adjustments to your photos to get the precise look you want. What's more, the Adobe Creative Cloud connected workflows in Fix open up limitless creative possibilities.

Download: iTunes

Adobe Photoshop Fix FAQ

Get started with Photoshop Fix

Adobe Photoshop Mix

Use Adobe Photoshop Mix to combine the power of Adobe Photoshop software with the convenience of mobile for a creative, easy-to-use photo editing experience on your iPhone, iPad, or Android phone. The ability to cut out images, mix them, and edit images non-destructively means your original photo stays untouched. Additionally, the Creative Cloud-connected workflows in Mix open up limitless creative possibilities.

Download: iTunes | Google Play

Adobe Photoshop Mix FAQ

Get started with Photoshop Mix

Adobe Preview CC

Adobe Preview CC is a Photoshop companion iOS app that lets you preview designs in real-time as you edit them in Photoshop. Using Preview CC, you can make sure designs appear on actual devices exactly how you want them to appear. Preview CC speeds up the design process and reduces the time required to test on multiple screen sizes. If you have a document with artboards, Device Preview attempts to show you the correct artboard by matching the size and position of the artboard with the size of the connected device.

Download: iTunes

Adobe Preview CC FAQ

Photoshop Help | Device Preview

Adobe Lightroom for mobile

Bring beautiful images to light with Adobe Lightroom. Powered by the magic of Adobe Photoshop technology, Lightroom for mobile enables you to craft and share professional-quality images from your smartphone or tablet. And when you're ready to take your photography further, our trial of the Adobe Creative Cloud Photography plan enables you to view, organize, edit, and share your photography across mobile devices, desktop, and the web. It's all your photography—all in one place.

Download: iTunes | Google Play

Adobe Lightroom for mobile FAQ

Get started with Lightroom for mobile

Adobe Photoshop Sketch

Adobe Photoshop Sketch brings inspiration, expressive drawing, and your creative community together in one place on your iPhone or iPad. Turn your ideas into sketches and share them on Behance for instant feedback. Sketch gives you the freedom to find inspiration, explore ideas, and get feedback from trusted peers—wherever you are.

Download: **iTunes**

Adobe Photoshop Sketch FAQ

Get started with Photoshop Sketch

See also:

Photoshop and design Download URLs for all Adobe mobile apps

More Photoshop companion apps

Note: *To troubleshoot issues with companion apps, please visit the Adobe companion apps user forum. Phone support is not provided. Ask questions, request features, and report problems at feedback.photoshop.com.*

Connecting Photoshop companion apps to Photoshop

Adobe® Photoshop® communicates with Adobe Nav for Photoshop, Adobe Color Lava for Photoshop, and Adobe Eazel for Photoshop using a wireless network. Photoshop and the apps must be on the same wireless network to connect. To check your wireless network, do the following:

- On Mac OS, click the Wi-Fi icon in the OS menu bar to choose a wireless network.
- In Windows XP, choose Start > Control Panel > Network And Internet Connections > Network Connections > Wireless Network Connection.
- In Windows Vista/Windows 7, choose Start > Control Panel > Network And Internet Connections > Network And Sharing Center.
- On the iPad, tap Settings and then tap Wi-Fi.

Note: *For more information about connecting Photoshop and its companion apps, see the support document Troubleshoot companion app connectivity problems | Photoshop or watch Getting started with Photoshop companion apps for Photoshop CS5 on Adobe TV. For general information on setting up and troubleshooting wireless networks, visit Apple Support or Microsoft Windows Help & How-To.*

Photoshop connection settings

Note: *Using Photoshop with Adobe Nav, Adobe Color Lava, and Adobe Eazel requires Photoshop 12.0.4 or later. If necessary, choose Help > Updates to install the latest version of Photoshop.*

Establish Photoshop as a remote connection to the apps.

1 In Photoshop, choose Edit > Remote Connections.



2 In the Service Name field of the Remote Connections dialog box, enter a descriptive name.

3 In the Password field, enter a six-digit password.

4 Select Enable Remote Connections and then click OK.

Companion app wireless connection settings

1 In Adobe Nav, Adobe Color Lava, or Adobe Eazel, tap the PS icon in the lower-right corner of the app.

2 In the Connections window, tap your Photoshop service.

3 Enter the six-digit password and tap Connect.

When the connection is established, the PS icon turns blue .

Companion app IP connections

If a wireless network is unavailable, you can create a direct IP connection between Adobe Nav, Adobe Color Lava, or Adobe Eazel and Photoshop.

1 In Adobe Nav, Adobe Color Lava, or Adobe Eazel, tap the PS icon in the lower-right corner of the app.

2 In the Connections window, tap New.

3 Enter the IP address and password from the Photoshop Remote Connections dialog box.

4 Click Connect.

When the connection is established, the PS icon turns blue .

Note: *For help troubleshooting IP connections, see the support document Troubleshoot companion app connectivity problems | Photoshop.*

Using Adobe Nav

Adobe Nav for Photoshop allows you to select and manage Photoshop tools on the iPad. Adobe Nav also allows you to browse open Photoshop documents using the iPad while you are working in Photoshop on your computer. Using Adobe Nav to access tools and documents gives you more space and flexibility for working on your images in Photoshop.

Note: *Adobe Nav is available in English, French, German, and Japanese. Other language versions of Photoshop can connect to Adobe Nav, but only in those languages. Adobe Nav requires Photoshop 12.0.4 or later. To download the latest version of Photoshop, choose Help > Updates.*

For a video tutorial on using Adobe Nav, visit the Adobe CS5.5 update page of the NAPP website. Or see Russell Brown's Photoshop apps update video for information about new Adobe Nav features for the iPad 2.

Connect to Photoshop

Adobe Nav must be connected to Photoshop. For instructions on how to connect Adobe Nav to Photoshop, see Connecting Photoshop companion apps to Photoshop.

Adobe Nav Tools mode

Adobe Nav Tools mode allows you to select and work with Photoshop tools. Adobe Nav displays up to 16 tools at a time. You can customize Tools mode to include the tools you most commonly use, or the tools you use for a particular task, such as painting.



***A** Tool buttons **B** Edit options **C** Switch to Tools mode **D** Switch to Document mode **E** Connect to Photoshop **F** Toolbox*

- To enter Tools mode, tap at the bottom of the app.
- To select a tool to use in Photoshop, tap it. The selected tool has a white background.

***Note:** To specify tool options, use the Options bar in Photoshop.*

- To display a 100% view of the active image, tap the Actual Pixels button.
- To cycle through screen modes, tap the Screen Mode button. See Change the screen modefor more information.
- To reverse the foreground and background colors, tap the Switch Colors icon . To restore the defaults, tap the Default Colors icon .

***Note:** The toolbox in Adobe Nav shows the selected foreground and background colors. To actually select foreground or background colors, use the toolbox in Photoshop. See Choose colors in the toolbox.*

- To add, delete, or move tools, tap Edit. Then, do one of the following:
  - To move a tool, drag it.
  - To delete a tool, tap the X in the upper-left corner of the tool button.
  - To add a tool, drag it from the menu at right onto the grid.

    Tools that are in the grid are blue in the menu.

- To return to Tools mode, tap Done.

Adobe Nav Document mode

Document mode allows you to select, view, and open new Photoshop documents from Adobe Nav.



- To enter Document mode, tap at the bottom of the app.

  The blue dot to the left of the filename indicates the active document.
- To make a different document active in Photoshop, tap its thumbnail.
- To view information about a document, including size and resolution, tap its thumbnail twice. Tap twice again to return to thumbnail view.
- To create a new, untitled document in Photoshop, tap New or tap the new document placeholder thumbnail.

  New documents are 1024 x 768 pixels, 72 dpi, and sRGB.
- To duplicate a document, drag its thumbnail to the new document placeholder thumbnail.
- To zoom in on a thumbnail, pinch it open up to four times. To return to thumbnail view, pinch closed.
- To rearrange documents, drag a thumbnail to a new location.

Using Adobe Color Lava

Adobe Color Lava for Photoshop lets you create themed color swatches on the iPad. When Adobe Color Lava is connected to Photoshop, you can set Adobe Color Lava swatches as the foreground color. You can also add Adobe Color Lava colors to the Photoshop Swatches panel as you work. Or, you can e-mail Adobe Color Lava themes as swatch libraries to share them with other people on other computers.

Note: *Adobe Color Lava is available in English, French, German, and Japanese. Other language versions of Photoshop can connect to Adobe Color Lava, but only in those languages. Adobe Color Lava requires Photoshop 12.0.4 or later. To download the latest version of Photoshop, choose Help > Updates.*

For a video tutorial on using Adobe Color Lava, visit the Adobe CS5.5 update page of the NAPP website. Or see Russell Brown's Photoshop apps update video for information about new Adobe Color Lava features for the iPad 2.



A Clean finger well ***B*** *Canvas* ***C*** *Color wells* ***D*** *Swatches* ***E*** *Connect to Photoshop* ***F*** *Switch to Theme Library mode* ***G*** *Load a photo*

Mix colors in Adobe Color Lava

To mix colors in Adobe Color Lava, select colors from the sample wells and then "paint" with your finger on the canvas.

- To load a color, tap its color well. The selected color has a thicker white border.
- To switch between RGB and grayscale, tap the inner ring of the color wells.
- To edit hue, saturation, and brightness values, double-tap a color well. To accept the HSB settings, tap .
- To remove color from your fingertip, tap the clean finger well once or twice.
- To reset the color wells to their defaults, tap .
- To erase the canvas, tap .
- To create a new theme, tap the New button.
- To load a photo into the canvas, tap the camera icon . Then, choose an image from an iPad photo album.

Work with swatches in Adobe Color Lava

Swatch sets appear on the right side of the Adobe Color Lava app. The active, or selected, swatch is larger than the other four swatches.

- To select a swatch, tap it. When you mix colors, Adobe Color Lava replaces the color in the selected swatch with the color you are painting.
- To set a swatch as the foreground color in Photoshop, tap it.
- To edit swatch sets, tap the Theme Library mode button .

Manage themes in Adobe Color Lava

Theme Library mode allows you to work with up to 300 swatch sets, or themes.

A Color themes *B Edit themes* *C Switch to Color Mixer mode* *D Connect to Photoshop*

- To select a theme, tap it.
- To edit the selected theme, tap the Color Mixer mode button .
- To set a swatch in a theme as the foreground color in Photoshop, tap it.
- To see the RGB, HSL, and hexadecimal values for each swatch in a theme, double-tap the theme.



- To rename or delete a theme, tap the Edit button or touch and hold a theme. Then, do one of the following:
  - Tap the X in the upper-left corner of a theme to delete it.
  - Tap a theme name to rename it.

Share Adobe Color Lava themes

For instructions on how to connect Photoshop and Adobe Color Lava, see Connecting Photoshop companion apps to Photoshop.

1 When you are connected to Photoshop, tap to enter Theme Library mode.

2 Tap a theme twice to open the theme details. Then, tap either of the following buttons:

Send To Photoshop Theme colors appear in the Swatches panel.

E-mail Opens an e-mail message so you can send the theme to someone. The e-mail includes a .png preview of the theme, a .png preview of the canvas, and a .ase swatch library file. For instructions on loading a swatch library in Photoshop, see Manage swatch libraries.

Using Adobe Eazel

Adobe Eazel for Photoshop lets you paint watercolor pictures on a canvas. Each stroke goes on "wet" and takes a few seconds to "dry." The paints blend according to the options you choose and the wetness of the previous stroke. You can save Eazel artwork to the iPad photo gallery, and can bring it into Photoshop for further editing or compositing.

Note: *Adobe Eazel is available in English, French, German, and Japanese. Other language versions of Photoshop can connect to Adobe Eazel, but only in those languages. Adobe Eazel requires Photoshop 12.0.4 or later. To download the latest version of Photoshop, choose Help > Updates.*

For a video tutorial on using Adobe Eazel, visit the Adobe CS5.5 update page of the NAPP website.



A *Brush sample* ***B*** *Finger controls* ***C*** *Canvas*

Note: *Adobe Eazel automatically detects right and left hands.*

Brush sample Shows the color, size, and opacity of the current brush.

Thumb control Undo, redo, and erase all.

Index finger control Choose a color.

Third finger control Adjust the brush size.

Fourth finger control Change paint opacity.

Fifth finger control Save artwork and send it to Photoshop.

Adobe Eazel work modes

Adobe Eazel offers two work modes: persistent and ephemeral. In *persistent* mode, all five finger controls stay visible onscreen while you specify options. To work in persistent mode, do the following:

1 Touch all five fingers to canvas at once, then lift.

2 Tap, or touch and drag, a setting to adjust it.

3 Touch the canvas to accept the change.

4 Touch the canvas again to set another option, or tap a second time to start painting.

In *ephemeral* mode, only one control appears onscreen at a time. The control appears only for as long as your finger interacts with it. To work in ephemeral mode, do the following:

1 Place all five fingers on the canvas and lift all but the finger whose options you want to adjust.

2 Drag the finger to adjust the setting or, with the fifth finger, tap to select an option.

3 Touch the canvas again to set another option or start painting.

Choose colors in Adobe Eazel

Adobe Eazel keeps five color swatches in a palette available under your index finger. The selected swatch has a flashing border.



***A** Color swatches **B** Brush sample **C** Current color **D** Color wheel*

- To choose a swatch, drag your index finger to it and lift.
- To change a swatch, drag your index finger to it to select it. Continue to drag to the color wheel or to a color in the artwork on the canvas.

Specify stroke size and opacity in Adobe Eazel

- To make the brush larger, drag up with your third finger. To make the brush smaller, drag down with your third finger. The brush sample updates as you drag.
- To make the paint more opaque, drag up with your fourth finger. To make the paint more transparent, drag down with your fourth finger. The brush sample updates as you drag.

Undo, redo, and erase in Adobe Eazel

- To undo your last stroke, use your thumb to choose or swipe from right to left.
- To redo your last stroke, use your thumb to choose or swipe from left to right.
- To erase the canvas, use your thumb to choose or swipe up.

Save Adobe Eazel artwork and send it to Photoshop

You can save Adobe Eazel artwork to the iPad gallery as .jpeg photo. Then, you can use the Photos app to e-mail it to someone, use it as wallpaper, or print it. You can also send Adobe Eazel artwork to Photoshop, where you can open it for additional editing or compositing.

Note: *For instructions on how to connect Photoshop and Adobe Eazel, see Connecting Photoshop companion apps to Photoshop.*

- To save artwork to the iPad, choose Settings with your fifth finger and then tap the Save To Photos button.
- To send artwork to Photoshop, choose Settings with your fifth finger and then tap the Transmit to Photoshop button.

  Adobe Eazel sends image data to Photoshop, which opens the artwork at 4096-x-3092 resolution. In Photoshop, you can save Adobe Eazel artwork in any supported file format.

Note: *Adobe Eazel artwork may look slightly different in Photoshop. Due to rendering, minor geometrical differences occur.*

Chapter 3: Workspace

Workspace basics

Note: *If you're wondering whether Photoshop or Lightroom is the right application for your requirements, this article will help you decide: Choosing the right photo app .*

You create and manipulate your documents and files using various elements, such as panels, bars, and windows. Any arrangement of these elements is called a workspace. (The workspaces of different Adobe creative applications share similar appearances so that you can move between the applications easily.) You can adapt Photoshop to the way you work by selecting from several preset workspaces or by creating one of your own.

Start workspace

The Start workspace in Photoshop gives you quick access to your recent files, libraries, and presets. Depending on your subscription status, the Start workspace may also display content tailored for your requirements. You can also look for the right Adobe Stock asset for your project directly from within the Start workspace.

Photoshop displays the Start workspace at launch or whenever no documents are open.

Note: *If necessary, customize the number of recent files displayed. Select Preferences > File Handling and then specify the desired value (0-100) in the Recent File List Contains... field.*



To quit this workspace, simply press the Esc key.

Work with the Start workspace

Toggle between tile and list views Click the Tile icon ( ) or the List icon ( ).

Find a stock asset Enter a keyword in the Search Stock field. Photoshop displays the search results from Adobe Stock in a new browser window.

Access your assets Open a recently-opened file or a library. Else, create a new document using a preset.

Disable the Start workspace

1 Select Preferences > General.

2 Deselect Show Start Workspace When No Documents Are Open.

A first look at the Photoshop working area

A: Tools panel | B: History panel | C: Color panel | D: Creative Cloud Libraries panel | E: Layers panel

Interactive image | Click the highlighted areas in the image to view more information about them

Workspace overview

- The Application bar across the top contains a workspace switcher, menus (Windows only), and other application controls. On the Mac for certain products, you can show or hide it using the Window menu.
- The Tools panel contains tools for creating and editing images, artwork, page elements, and so on. Related tools are grouped.
- The Options bar Control panel displays options for the currently selected tool.
- The Document window displays the file you're working on. Document windows can be tabbed and, in certain cases, grouped and docked.
- Panels help you monitor and modify your work. Panels can be grouped, stacked, or docked.
- The Application frame groups all the workspace elements in a single, integrated window that lets you treat the application as a single unit. When you move or resize the Application frame or any of its elements, all the elements within it respond to each other so none overlap. Panels don't disappear when you switch applications or when you accidentally click out of the application. If you work with two or more applications, you can position each application side by side on the screen or on multiple monitors.

  If you are using a Mac and prefer the traditional, free-form user interface, you can turn off the Application frame.

Usability features

The Photoshop workspace is easy to use and includes a number of usability features:

- Different brightness levels: Choose Edit > Preference (Windows) or Photoshop > Preferences (Mac OS) and select a Color Theme swatch in the Interface section.

To quickly decrease brightness, press Shift + 1; to increase brightness, press Shift + 2. (On Mac OS, it's necessary to also press the FN key.)

- On-image displays: Stay informed as you use your favorite tools. On-image displays show selection dimensions, transformation angles, and more. To change the placement of the displays, choose an option from the Show Transformation Values in the Interface preferences.

- Maximized screen space: Click the button at the bottom of the toolbar to switch between Standard and Fullscreen display modes.

Hide or show all panels

- To hide or show all panels, including the Tools panel and Control panel, press Tab.
- To hide or show all panels except the Tools panel and Control panel, press Shift+Tab.

You can temporarily display hidden panels if Auto-Show Hidden Panels is selected in Interface preferences. Move the pointer to the edge of the application window (Windows) or to the edge of the monitor (Mac OS) and hover over the strip that appears.

Display panel options

? Click the panel menu icon in the upper-right corner of the panel.

You can open a panel menu even when the panel is minimized.

In Photoshop, you can change the font size of the text in panels and tool tips. In the Interface preferences, choose a size from the UI Font Size menu.

Reconfigure the Tools panel

You can display the tools in the Tools panel in a single column, or side by side in two columns.

? Click the double arrow at the top of the Tools panel.

Manage windows and panels

You can create a custom workspace by moving and manipulating Document windows and panels. You can also save workspaces and switch among them.

Rearrange, dock, or float document windows

When you open more than one file, the Document windows are tabbed.

- To rearrange the order of tabbed Document windows, drag a window's tab to a new location in the group.
- To undock (float or untab) a Document window from a group of windows, drag the window's tab out of the group.

Note: *You can also choose Window > Arrange > Float in Window to float a single Document window, or Window > Arrange > Float All In Windows to float all of the Document windows at once.*

- To dock a Document window to a separate group of Document windows, drag the window into the group.
- To create groups of stacked or tiled documents, drag the window to one of the drop zones along the top, bottom, or sides of another window. You can also select a layout for the group by using the Layout button on the Application bar.
- To switch to another document in a tabbed group when dragging a selection, drag the selection over the document's tab for a moment.

Dock and undock panels

A *dock* is a collection of panels or panel groups displayed together, generally in a vertical orientation. You dock and undock panels by moving them into and out of a dock.

- To dock a panel, drag it by its tab into the dock, at the top, bottom, or in between other panels.
- To dock a panel group, drag it by its title bar (the solid empty bar above the tabs) into the dock.

- To remove a panel or panel group, drag it out of the dock by its tab or title bar. You can drag it into another dock or make it free-floating.





You can prevent panels from filling all the space in a dock. Drag the bottom edge of the dock up so it no longer meets the edge of the workspace.

Move panels

As you move panels, you see blue highlighted *drop zones*, areas where you can move the panel. For example, you can move a panel up or down in a dock by dragging it to the narrow blue drop zone above or below another panel. If you drag to an area that is not a drop zone, the panel floats freely in the workspace.

Note: *The position of the mouse (rather than the position of the panel) activates the drop zone, so if you can't see the drop zone, try dragging the mouse to the place where the drop zone should be.*

- To move a panel, drag it by its tab.
- To move a panel group, drag the title bar.



A Title bar ***B*** *Tab* ***C*** *Drop zone*

Press Ctrl (Windows) or Command (Mac OS) while moving a panel to prevent it from docking. Press Esc while moving the panel to cancel the operation.

Add and remove panels

If you remove all panels from a dock, the dock disappears. You can create a dock by moving panels to the right edge of the workspace until a drop zone appears.

- To remove a panel, right-click (Windows) or Control-click (Mac) its tab and then select Close, or deselect it from the Window menu.
- To add a panel, select it from the Window menu and dock it wherever you want.

Manipulate panel groups

- To move a panel into a group, drag the panel's tab to the highlighted drop zone in the group.

- To rearrange panels in a group, drag a panel's tab to a new location in the group.
- To remove a panel from a group so that it floats freely, drag the panel by its tab outside the group.
- To move a group, drag the title bar (the area above the tabs).

Stack floating panels

When you drag a panel out of its dock but not into a drop zone, the panel floats freely. The floating panel allows you to position it anywhere in the workspace. You can stack floating panels or panel groups so that they move as a unit when you drag the topmost title bar.



- To stack floating panels, drag a panel by its tab to the drop zone at the bottom of another panel.

- To change the stacking order, drag a panel up or down by its tab.

Note: *Be sure to release the tab over the narrow drop zone between panels, rather than the broad drop zone in a title bar.*

- To remove a panel or panel group from the stack, so that it floats by itself, drag it out by its tab or title bar.

Resize panels

- To minimize or maximize a panel, panel group, or stack of panels, double-click a tab. You can also double-click the tab area (the empty space next to the tabs).
- To resize a panel, drag any side of the panel. Some panels, such as the Color panel cannot be resized by dragging.

Collapse and expand panel icons

You can collapse panels to icons to reduce clutter on the workspace. In some cases, panels are collapsed to icons in the default workspace.



- To collapse or expand all panel icons in a column, click the double arrow at the top of the dock.
- To expand a single panel icon, click it.
- To resize panel icons so that you see only the icons (and not the labels), adjust the width of the dock until the text disappears. To display the icon text again, make the dock wider.
- To collapse an expanded panel back to its icon, click its tab, its icon, or the double arrow in the panel's title bar.
- To add a floating panel or panel group to an icon dock, drag it in by its tab or title bar. (Panels are automatically collapsed to icons when added to an icon dock.)
- To move a panel icon (or panel icon group), drag the icon. You can drag panel icons up and down in the dock, into other docks (where they appear in the panel style of that dock), or outside the dock (where they appear as floating icons).

Save and switch workspaces

By saving the current size and position of panels as a named workspace, you can restore that workspace even if you move or close a panel. The names of saved workspaces appear in the workspace switcher in the Application bar.

Save a custom workspace

1 With the workspace in the configuration you want to save, choose Window > Workspace > New Workspace.

2 Type a name for the workspace.

3 Under Capture, select one or more options:

Keyboard shortcuts Saves the current set of keyboard shortcuts (Photoshop only).

Menus or Menu Customization Saves the current set of menus.

Display or switch workspaces

? Select a workspace from the workspace switcher in the Application bar.

In Photoshop, you can assign keyboard shortcuts to each workspace to navigate among them quickly.

Delete a custom workspace

- Select Manage Workspaces from the workspace switcher in the Application bar, select the workspace, and then click Delete.
- Select Delete Workspace from the workspace switcher.
- Choose Window > Workspace > Delete Workspace, select the workspace, and then click Delete.

Restore the default workspace

1 Select the Default or Essentials workspace from the workspace switcher in the application bar.

2 Select Window > Workspace > Reset [Workspace Name].

Restore a saved workspace arrangement

In Photoshop, workspaces automatically appear as you last arranged them, but you can restore the original, saved arrangement of panels.

- To restore an individual workspace, choose Window > Workspace > Reset [Workspace Name].
- To restore all the workspaces installed with Photoshop, click Restore Default Workspaces in the Interface preferences.

To rearrange the order of workspaces in the application bar, drag them.

Hide tool tips

When you position the pointer over most tools and options, descriptions appear in tool tips by default. If you find tool tips visually distracting, you can hide them.

? In the Interface preferences, deselect Show Tool Tips.

Note: *Tool tips are not available in some dialog boxes.*

(Windows-powered devices) Modifier Keys palette

The new Modifier Keys palette lets you access frequently-used keyboard modifiers—Shift, Ctrl, and Alt—on Windows-powered touch devices, such as the Surface Pro.

- Select Window > Modifier Keys.

Use tools

When you start Photoshop, the Tools panel appears at the left of the screen. Some tools in the Tools panel have options that appear in the context-sensitive options bar.

You can expand some tools to show hidden tools beneath them. A small triangle at the lower right of the tool icon signals the presence of hidden tools.

You can view information about any tool by positioning the pointer over it. The name of the tool appears in a tool tip below the pointer.

For a pictorial overview of the different tools in Photoshop, see .

With Photoshop Mix, you can perform non-destructive photo enhancements, make selections, cut out and mix images, and do much more right from your iPhone or iPad.

Read more and download Photoshop Mix.

Select and display tools

Select a tool

? Do one of the following:

- Click a tool in the Tools panel. If there is a small triangle at a tool's lower right corner, hold down the mouse button to view the hidden tools. Then click the tool you want to select.
- Press the tool's keyboard shortcut. The keyboard shortcut is displayed in its tool tip. For example, you can select the Move tool by pressing V.

Pressing and holding a keyboard shortcut key lets you temporarily switch to a tool. When you let go of the shortcut key, Photoshop returns to the tool you were using before the temporary switch.



***A** Tools panel **B** Active tool **C** Hidden tools **D** Tool name **E** Tool shortcut **F** Hidden tool triangle*

Cycle through hidden tools

By default, you cycle through a set of hidden tools by holding down Shift and repeatedly pressing a tool shortcut key.

If you prefer to cycle through tools without holding down Shift, you can disable this preference.

1 Choose Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS).

2 Deselect Use Shift Key For Tool Switch.

Change tool pointers

Each default pointer has a different hotspot, where an effect or action in the image begins. With most tools, you can switch to precise cursors, which appear as cross hairs centered around the hotspot.

In most cases, the pointer for a tool is the same as the icon for that tool; you see that pointer when you select the tool. The default pointer for the marquee tools is the cross-hair pointer ; for the text tool, the default pointer is the I-beam ; and for the painting tools, the default pointer is the Brush Size icon.

1 Choose Edit > Preferences > Cursors (Windows) or choose Photoshop > Preferences > Cursors (Mac OS).

2 Choose tool pointer settings under Painting Cursors or Other Cursors:

Standard Displays pointers as tool icons.

Precise Displays pointers as cross hairs.

Normal Brush Tip The pointer outline corresponds to approximately 50% of the area that the tool will affect. This option shows the pixels that would be most visibly affected.

Full Size Brush Tip The pointer outline corresponds to nearly 100% of the area that the tool will affect, or nearly all the pixels that would be affected.

Show Crosshair In Brush Tip Displays cross hairs in the center of the brush shape.

Show Only Crosshair While Painting Improves performance with large brushes.

3 Click OK.

The Painting Cursors options control the pointers for the following tools:

Eraser, Pencil, Paintbrush, Healing Brush, Clone Stamp, Pattern Stamp, Quick Selection, Smudge, Blur, Sharpen, Dodge, Burn, and Sponge

The Other Cursors options control the pointers for the following tools:

Marquee, Lasso, Polygonal Lasso, Magic Wand, Crop, Slice, Patch, Eyedropper, Pen, Gradient, Line, Paint Bucket, Magnetic Lasso, Magnetic Pen, Freeform Pen, Measure, and Color Sampler

To toggle between standard and precise cursors in some tool pointers, press Caps Lock.

Visually resize or change hardness of painting cursors

You can resize or change the hardness of a painting cursor by dragging in the image. As you drag, the painting cursor previews your changes. (Previews require OpenGL.)

? To resize a cursor, press Alt+right-click (Windows) or Control+Option (Mac OS), and drag left or right. To change hardness, drag up or down.

Use the options bar

The options bar appears below the menu bar at the top of the workspace. The options bar is context sensitive—it changes as you select different tools. Some settings in the options bar (such as painting modes and opacity) are common to several tools, and some are specific to one tool.

You can move the options bar in the workspace by using the gripper bar, and you can dock it at the top or bottom of the screen. Tool tips appear when you position the pointer over a tool. To show or hide the options bar, choose Window > Options.



***A** Gripper bar **B** Tool tip*

To return tools to their default settings, right-click (Windows) or Control-click (Mac OS) the tool icon in the options bar, and then choose Reset Tool or Reset All Tools from the context menu.

For more information on setting options for a specific tool, search for the tool's name in Photoshop Help.

Tool presets

Tool presets let you save and reuse tool settings. You can load, edit, and create libraries of tool presets using the Tool Preset picker in the options bar, the Tool Presets panel, and the Preset Manager.

To choose a tool preset, click the Tool Preset picker in the options bar, and select a preset from the pop-up panel. You can also choose Window > Tool Presets and select a preset in the Tools Presets panel.



A Click the Tool Preset picker in the options bar to show the Tool Preset pop-up panel. ***B*** *Select a preset to change the tool's options to the preset, which applies each time you select the tool until you choose Reset Tool from the panel menu.* ***C*** *Deselect to show all tool presets; select to show presets for only the tool selected in the toolbox.*

Create a tool preset

1 Choose a tool, and set the options you want to save as a tool preset in the options bar.

2 Do one of the following:

- Click the Tool Preset button next to the tool at the left of the options bar.
- Choose Window > Tool Presets to display the Tool Presets panel.

3 Do one of the following:

- Click the Create New Tool Preset button .
- Choose New Tool Preset from the panel menu.

4 Enter a name for the tool preset, and click OK.

Change the list of tool presets

? Click the triangle to open the Tool Presets pop-up panel menu and choose one of the following:

Show All Tool Presets Shows all loaded presets.

Sort By Tool Sorts the presets by tool.

Show Current Tool Presets Shows only the loaded presets for the active tool. You can also select the Current Tool Only option in the Tool Presets pop-up panel.

Text Only, Small List, or Large List Determines how presets are displayed in the pop-up panel.

Note: *To create, load, and manage libraries of tool presets, see Work with the Preset Manager.*

Touch gestures

Touch Gestures have been enabled in the 2014 release of Photoshop CC for Windows 8 systems. Touch input is recognized from any touch-capable device attached to the system, including opaque finger pads and indirect tablets as well as direct-touch devices integrated directly with a display. You can control Photoshop using devices which support two or more simultaneous touch points.

In Photoshop, two-fingered touch gestures are used to control the location, rotation, and scaling of the image canvas view. Users may alternate between touch view control and other interactions using the mouse or stylus, but touch may not be used simultaneously with other input. Touch control of the view is very convenient when painting on large monitors which are difficult to rotate physically and on tablets to avoid constantly shifting the device.

General considerations

- Photoshop constrains the freedom to view changes based on the motion at the beginning of the gesture so the user can control different aspects of the view independently.
  - When the user moves both touch points in parallel, the view pans without rotating or scaling.
  - When the initial motion is a pinch, scaling and pan will occur.
  - Rotation of touch points about a relatively motionless center enables rotation and pan but with no scaling.
  - Finally, by pinching and rotating at first, all three aspects may be adjusted. As a convenience, this latter free-transform gesture mode can also be chosen by simply holding initial touch points motionless for a moment.
- As expected, when not in the full-screen mode, Photoshop does not pan a canvas view that is smaller than its document window. To pan windowed views with touch, first use pinch to scale the view until it intersects a window edge. In full-screen mode, all view transforms are always available.
- The two-fingered double tap can be used to reset the image canvas view to show the entire canvas. A second two-fingered double tap will restore the user's previously selected view.

Gestures currently supported

See **Touch capabilities and customizable workspaces**.

Technology previews

Enable a technology preview feature

Photoshop ships with technology preview features that you can enable and try out. These features are not yet production-ready, so exercise discretion while using them. Do the following:

1. Select Preferences > Technology Previews.
2. Select the technology preview feature you want to enable. For example, select Design Space (Preview).
3. Click OK.

Note: *To enable Multitone 3D printing, you must restart Photoshop.*

Technology preview features in Photoshop CC 2015.1 release

Design Space (Preview)

Important: Design Space (Preview) requires Mac OS X 10.10 or Windows 8.1 64-bit OS or higher.

Design Space (Preview) is a companion experience to Photoshop for web and app designers. Technically, Design Space (Preview) is an HMTL5/CSS/JavaScript layer built on top of Photoshop. Separating this new experience from standard Photoshop in this manner facilitates a fresh UI, smarter interactions, and faster delivery of top-requested features.

For more information and a list of known issues, see Design Space (Preview).



A Toolbar *B Properties* *C Layers and Libraries* *D Collapse or expand columns*

Multitone 3D printing

This technology preview feature lets you print continuous tones using your Makerbot Replicator 2x 3D printer.

Do the following:

1 Select the Makerbot Replicator 2x printer in the 3D Print Settings panel.

2 Under Material, select Multitone Surface. If this option is not available for selection, ensure that the Multitone 3D Printing technology preview feature is already enabled .

3 Select other options relevant to the 3D object you're printing.

4 Select 3D > 3D Print to preview and print the 3D object.

For more information about 3D printing in Photoshop, see Print 3D objects.

Adobe welcomes your feedback on this feature. Visit **this feedback link.**

Customize keyboard shortcuts

Note: *For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.*

Photoshop lets you view a list of all shortcuts, and edit or create shortcuts. The Keyboard Shortcuts dialog box serves as a shortcut editor, and includes all commands that support shortcuts, some of which aren't addressed in the default shortcut set.

In addition to using keyboard shortcuts, you can access many commands using context-sensitive menus that are relevant to the active tool, selection, or panel. To display a context-sensitive menu, right-click in the document window or panel.

Define new keyboard shortcuts

1 Do one of the following:
   - Choose Edit > Keyboard Shortcuts.
   - Choose Window > Workspace > Keyboard Shortcuts & Menus and click the Keyboard Shortcuts tab.
2 Choose a set of shortcuts from the Set menu at the top of the Keyboard Shortcuts & Menus dialog box.
3 Choose a shortcut type from the Shortcuts For menu:

   Application Menus Lets you customize keyboard shortcuts for items in the menu bar.

   Panel Menus Lets you customize keyboard shortcuts for items in panel menus.

   Tools Lets you customize keyboard shortcuts for tools in the toolbox.
4 In the Shortcut column of the scroll list, select the shortcut you want to modify.
5 Type a new shortcut.

   If the keyboard shortcut is already assigned to another command or tool in the set, an alert appears. Click Accept to assign the shortcut to the new command or tool and erase the previously assigned shortcut. After you reassign a shortcut, you can click Undo Changes to undo the change, or click Accept and Go To Conflict to assign a new shortcut to the other command or tool.
6 When you're finished changing shortcuts, do one of the following:
   - To save all changes to the current set of keyboard shortcuts, click the Save Set button . Changes to a custom set are saved. If you're saving changes to the Photoshop Defaults set, the Save dialog box opens. Enter a name for the new set and click Save.
   - To create a new set based on the current set of shortcuts, click the Save Set As button . In the Save dialog box, enter a name for the new set in the Name text box, and click Save. The new keyboard shortcut set will appear in the pop-up menu under the new name.
   - To discard the last saved change without closing the dialog box, click Undo.
   - To return a new shortcut to the default, click Use Default.
   - To discard all changes and exit the dialog box, click Cancel.

Note: *If you haven't saved the current set of changes, you can click Cancel to discard all changes and exit the dialog box.*

Clear shortcuts from a command or tool

1 Choose Edit > Keyboard Shortcuts.
2 In the Keyboard Shortcuts dialog box, select the command or tool name whose shortcut you want to delete.
3 Click Delete Shortcut.

Delete a set of shortcuts

1 Choose Edit > Keyboard Shortcuts.

2 In the Set pop-up menu, choose the shortcut set that you want to delete.

3 Click the Delete icon and then click OK to exit the dialog box.

View a list of current shortcuts

To view a list of current shortcuts, export them to an HTML file, which you can display or print with a web browser.

1 Choose Edit > Keyboard Shortcuts.

2 From the Shortcuts For menu, choose a shortcut type: Application Menus, Panel Menus, or Tools.

3 Click Summarize.

Metadata and notes

About metadata

Metadata is a set of standardized information about a file, such as author name, resolution, color space, copyright, and keywords applied to it. For example, most digital cameras attach some basic information to an image file, such as height, width, file format, and time the image was taken. You can use metadata to streamline your workflow and organize your files.

About the XMP standard

Metadata information is stored using the Extensible Metadata Platform (XMP) standard, on which Adobe Bridge, Adobe Illustrator, Adobe InDesign, and Adobe Photoshop are built. Adjustments made to images with Photoshop® Camera Raw are stored as XMP metadata. XMP is built on XML, and in most cases the metadata is stored in the file. If it isn't possible to store the information in the file, metadata is stored in a separate file called a sidecar file. XMP facilitates the exchange of metadata between Adobe applications and across publishing workflows. For example, you can save metadata from one file as a template, and then import the metadata into other files.

Metadata that is stored in other formats, such as Exif, IPTC (IIM), GPS, and TIFF, is synchronized and described with XMP so that it can be more easily viewed and managed. Other applications and features (for example, Adobe Drive) also use XMP to communicate and store information such as version comments, which you can search using Adobe Bridge.

In most cases, the metadata remains with the file even when the file format changes (for example, from PSD to JPG). Metadata also remains when files are placed in an Adobe document or project.

If you're a C++ or Java developer, use the XMP Toolkit SDK to customize the processing and exchange of metadata. If you're an Adobe Flash or Flex developer, use the XMP File Info SDK to customize the File Info dialog box. For more information, visit the Adobe website.

Work with metadata in Adobe Bridge and Adobe Creative Suite components

Many of the powerful Adobe Bridge features that allow you to organize, search, and keep track of your files and versions depend on XMP metadata in your files. Adobe Bridge provides two ways of working with metadata: through the Metadata panel and through the File Info dialog box.

In some cases, multiple views exist for the same metadata property. For example, a property may be labeled Author in one view and Creator in another, but both refer to the same underlying property. Even if you customize these views for specific workflows, they remain standardized through XMP.

Notes

You can attach notes to an image in Photoshop. This is useful for associating review comments, production notes, or other information with the image. Notes appear as small non-printable icons on the image. They are associated with a location on the image rather than with a layer. You can hide or show notes, or open notes to view or edit their contents.

Add notes

You can add notes anywhere on your Photoshop image canvas. When you create a note, an icon appears on the image.

1. Select the Note tool in the toolbox. (If the tool isn't visible, hold down the Eyedropper.)
2. In the Options bar, enter or specify the following as needed:

   Author Specifies the note author's name.

   Color Selects the color for the note icon. Clicking the color box opens the Adobe Color Picker so you can select a color.
3. Click where you want to place the note.
4. The cursor will automatically be active

Show or hide notes

To show or hide notes, do one of the following:

- Choose View > Show > Notes.
- Choose View > Extras. This command also shows or hides grids, guides, selection edges, target paths, and slices.

Open and edit notes

- Using the Note tool, double-click the note icon in the image. The text editing area appears in the Notes panel.
- Choose Window > Notes to display the Notes panel, and click the back and forward arrows to toggle through all notes in the active image.

Import notes from a flattened PDF version of a multilayer image

When you open a PDF file, Photoshop automatically imports any notes it contains. You may want to import notes separately, however, if they were added to a flattened PDF version of a multilayer image. This approach lets reviewers who lack Photoshop provide comments, while letting you view comments in the context of the multilayer design.

1. Choose File > Import > Notes.
2. Select a PDF or FDF file that contains notes, and then click Load.

The annotations appear in the locations where they were saved in the source document.

Delete notes

? Select the Note tool, and then do either of the following:

- To delete an individual note, click it in the image, and then click the Delete Note icon in the Notes panel.
- To delete all notes, click Clear All in the options bar.

More Help topics

Add metadata using the File Info dialog box

Work with metadata templates

Import metadata into a document

Specify columns for an image

Specify columns for an image

Columns help you position images or elements precisely. The New, Image Size, and Canvas Size commands let you specify image width in terms of columns. Using columns is convenient when you plan to import an image into a page-layout program, such as Adobe InDesign, and you want the image to fit exactly within a certain number of columns.

1 Choose Edit > Preferences > Units & Rulers (Windows) or Photoshop > Preferences > Units & Rulers (Mac OS).

2 Enter values for Width and Gutter. (A gutter is the vertical whitespace between the columns.)

3 Use the File > New command to create a new image, select Columns for the Width value, and enter the number of columns you need for the new document. You can also resize an open image to the number of columns required by the page layout using the Image > Image Size or Image > Canvas Size commands.

More Help topics

Rulers

Grid and guides

Rulers

About rulers

Rulers help you position images or elements precisely. When visible, rulers appear along the top and left side of the active window. Markers in the ruler display the pointer's position when you move it. Changing the ruler origin (the (0, 0) mark on the top and left rulers) lets you measure from a specific point on the image. The ruler origin also determines the grid's point of origin.

To show or hide rulers, choose View > Rulers.

Change a ruler's zero origin

1 (Optional) Choose View > Snap To, then choose any combination of options from the submenu. This snaps the ruler origin to guides, slices, or document bounds. You can also snap to the grid.

2 Position the pointer over the intersection of the rulers in the upper-left corner of the window, and drag diagonally down onto the image. A set of cross hairs appears, marking the new origin on the rulers.

You can hold down Shift as you drag to make the ruler origin snap to the ruler ticks.

To reset a ruler's origin to its default value, double-click the upper-left corner of the ruler.



Change the unit of measurement

1 Do one of the following:
   - Double-click a ruler.
   - (Windows) Choose Edit > Preferences > Units & Rulers, or right-click the ruler and then choose a new unit from the context menu.
   - (Mac OS) Choose Photoshop > Preferences > Units & Rulers, or Control-click the ruler and then choose a new unit from the context menu.
2 For Rulers, choose a unit of measurement.

   Note: *Changing the units on the Info panel automatically changes the units on the rulers.*
3 For Point/Pica Size, choose from the following options:

   PostScript (72 points per inch) Sets a unit size compatible for printing to a PostScript device.

   Traditional Uses 72.27 points per inch, as traditionally used in printing.
4 Click OK.

More Help topics

Positioning elements with snapping

Show or hide non-printing Extras

Positioning with the Ruler tool

Specifying columns for an image

Grid and guides

Panels and menus

Enter values in panels, dialog boxes, and the options bar

? Do any of the following:

- Type a value in the text box, and press Enter (Windows) or Return (Mac OS).
- Drag the slider.
- Move the pointer over the title of a slider or pop-up slider. When the pointer turns to a Hand icon, drag the scrubby slider to the left or right. This feature is available only for selected sliders and pop-up sliders.
- Drag the dial.
- Click the arrow buttons in the panel to increase or decrease the value.
- (Windows) Click the text box and then use the Up Arrow key and the Down Arrow key on the keyboard to increase or decrease the value.
- Select a value from the menu associated with the text box.



***A** Menu arrow **B** Scrubby slider **C** Text box **D** Dial **E** Slider*

Work with sliders

About pop-up sliders

Some panels, dialog boxes, and options bars contain settings that use pop-up sliders (for example, the Opacity option in the Layers panel). If there is a triangle next to the text box, you can activate the pop-up slider by clicking the triangle. Position the pointer over the triangle next to the setting, hold down the mouse button, and drag the slider or angle radius to the desired value. Click outside the slider box or press Enter to close the slider box. To cancel changes, press the Esc key.

To increase or decrease values in 10% increments when the pop-up slider box is open, hold down Shift and press the Up Arrow or Down Arrow key.



***A** Click to open the pop-up slider box. **B** Drag slider or angle radius.*

You can also "scrub" some pop-up sliders. For example, if you hold the pointer over the word "Fill" or "Opacity" in the Layers panel, the pointer changes to the Hand icon. Then you can move the pointer left or right to change the fill or opacity percentage.

About scrubby sliders

In some panels, dialog boxes, and options bars, you can drag scrubby sliders to change option values. Scrubby sliders are hidden until you position the pointer over the title of sliders and pop-up sliders. When the pointer changes to a Hand icon, you drag to the left or right. Holding down the Shift key while dragging accelerates the scrubbing by a factor of 10.

Work with pop-up panels

Pop-up panels provide easy access to available options for brushes, swatches, gradients, styles, patterns, contours, and shapes. You can customize pop-up panels by renaming and deleting items and by loading, saving, and replacing libraries. You can also change the display of a pop-up panel to view items by their names, as thumbnail icons, or with both names and icons.

Click a tool thumbnail in the options bar to show its pop-up panel. Click an item in the pop-up panel to select it.



***A** Click to show the pop-up panel. **B** Click to view the pop-up panel menu.*

Rename or delete an item in a pop-up panel

? Select an item, click the triangle in the upper right corner of the pop-up panel, and choose one of the following:

Rename Tool Preset Lets you enter a new name for the item.

Delete Tool Preset Deletes an item in the pop-up panel.

***Note:** You can also delete an item in a pop-up panel by holding down Alt (Windows) or Option (Mac OS) and clicking the item.*

Customize the list of items in a pop-up panel

1 Click the triangle in the upper right corner of the pop-up panel to view the panel menu.

2 To return to the default library, choose the Reset Tool Presets command. You can either replace the current list or add the default library to the current list.

3 To load a different library, do one of the following:

- Choose the Load Tool Presets command to add a library to the current list. Then select the library file you want to use, and click Load.

- Choose the Replace Tool Presets command to replace the current list with a different library. Then select the library file you want to use, and click Load.
- Choose a library file (displayed at the bottom of the panel menu). Then click OK to replace the current list, or click Append to add it to the current list.

4 To save the current list as a library for later use, choose the Save Tool Presets command. Then enter a name for the library file, and click Save.

(Mac OS) Include the extension of the library file name so that you can easily share the libraries across operating systems. Select Append File Extension Always in the File Handling Preferences to append extensions to file names.

Change the display of items in a pop-up panel

1 Click the triangle in the upper right corner of the pop-up panel to view the panel menu.

2 Select a view option: Text Only, Small List, and Large List.

Display and define menus

Display context menus

Context menus display commands relevant to the active tool, selection, or panel. They are distinct from the menus across the top of the workspace.



1 Position the pointer over an image or panel item.

2 Right-click (Windows) or Control-click (Mac OS).

Define a set of menus

1 Do one of the following:

- Choose Edit > Menus.
- Choose Window > Workspace > Keyboard Shortcuts & Menus and click the Menus tab.

2 In the Keyboard Shortcuts and Menus dialog box, choose a set of menus from the Set drop-down menu. For information on creating a new set, see Customize keyboard shortcuts.

3 Choose a type from the Menu For menu:

Application Menus Lets you show, hide, or add color to items in the application menus.

Panel Menus Lets you show, hide, or add color to items in panel menus.

4 Click the triangle next to a menu or panel name.

5 Do one of the following:

- To hide a menu item, click the Visibility button .
- To show a menu item, click the empty Visibility button.
- To add color to a menu item, click the color swatch (if no color is assigned, it will say None) and choose a color.

6 When you finish changing the menus, do one of the following:

- To save all changes to the current set of menus, click the Save Set button . Changes to a custom set are saved. If you're saving changes to the Photoshop Defaults set, the Save dialog box opens. Enter a name for the new set and click Save.
- To create a new set based on the current set of menus, click the Save Set As button .

Note: *If you haven't saved the current set of changes, you can click Cancel to discard all changes and close the dialog box.*

7 In the Save dialog box, enter a name for the set and click Save.



Delete a set of menus

1 Do one of the following:

- Choose Edit > Menus.
- Choose Window > Workspace > Keyboard Shortcuts & Menus and click the Menu tab.

2 In the Keyboard Shortcuts & Menus dialog box, choose a set of menus from the Set menu.

3 Click the Delete Set icon .

Temporarily show hidden menu items

It's possible to temporarily show items that you've hidden in a menu. After the menu closes, the items return to their hidden state.

? Do one of the following:

- From a menu with hidden items, choose Show All Menu Items.
- Ctrl-click (Windows) or Command-click (Mac OS) a menu with hidden items.

To permanently reveal all menu items, choose Window > Workspace > Essentials.

Turn menu colors on or off

? In Interface preferences, select or deselect Show Menu Colors.

Place files

The Place command adds a photo, art, or any Photoshop-supported file as a Smart Object to your document. Smart Objects can be scaled, positioned, skewed, rotated, or warped without degrading the image.

Place a file in Photoshop

1 Open the Photoshop document that is the destination for the placed art or photo.

2 Do one of the following:

- (Photoshop) Choose File > Place, select the file you want to place, and click Place.

  You can also drag a file from Windows or Mac OS onto an open Photoshop image.

- (Bridge) Select the file and choose File > Place > In Photoshop.

3 If you are placing a PDF or Illustrator (AI) file, the Place PDF dialog box appears. Select the page or image you want to place, set the Crop options, and click OK. For more information on the Place PDF dialog box options, see Place PDF or Illustrator files in Photoshop.

The placed artwork appears inside a bounding box at the center of the Photoshop image. The artwork maintains its original aspect ratio; however, if the artwork is larger than the Photoshop image, it is resized to fit.

Note: *In addition to the Place command, you can also add Adobe Illustrator art as a Smart Object by copying and pasting the art from Illustrator into a Photoshop document. See Paste Adobe Illustrator art into Photoshop.*

4 (Optional) Reposition or transform the placed artwork by doing any of the following:

- To reposition the placed art, position the pointer inside the bounding box of the placed artwork and drag, or in the options bar, enter a value for X to specify the distance between the center point of the placed artwork and the left edge of the image. Enter a value for Y to specify the distance between the center point of the placed artwork and the top edge of the image.
- To scale the placed art, drag one of the corner handles of the bounding box or enter values for W and H in the options bar. When dragging, hold down the Shift key to constrain proportions.
- To rotate the placed art, position the pointer outside the bounding box (the pointer turns into a curved arrow) and drag, or enter a value (in degrees) for the Rotation option in the options bar. The artwork rotates around the center point of the placed artwork. To adjust the center point, drag it to a new location, or click a handle on the Center Point icon in the options bar.
- To skew the placed art, hold down Ctrl (Windows) or Command (Mac OS) and drag a side handle of the bounding box.
- To warp the placed art, choose Edit > Transform > Warp and then choose a warp from the Warp Style pop-up menu in the options bar.

  If you choose Custom from the Warp Style pop-up menu, drag the control points, a segment of the bounding box or mesh, or an area within the mesh to warp the image.

5 If you're placing a PDF, EPS, or Adobe Illustrator file, set the Anti-alias option in the options bar as desired. To blend edge pixels during rasterization, select the Anti-alias option. To produce a hard-edged transition between edge pixels during rasterization, deselect the Anti-alias option.

6 Do one of the following:

- Click Commit in the options bar or press Enter (Windows) or Return (Mac OS) to commit the placed artwork to a new layer.

- Click Cancel in the options bar, or press Esc to cancel the placement.

Place PDF or Illustrator files in Photoshop

When you place a PDF or Adobe Illustrator file, use the Place PDF dialog box to set options for placing the artwork.

1 With the destination Photoshop document open, place a PDF or Adobe Illustrator file.

2 Under Select in the Place PDF dialog box, select Page or Image, depending on what elements of the PDF document you want to import. If the PDF file has multiple pages or images, click the thumbnail of the page or file you want to place.

__Note:__ Use the Thumbnail Size menu to adjust the thumbnail view in the preview window. The Fit Page option fits one thumbnail in the preview window. A scroll bar appears if there are multiple items.

3 Under Options, choose from the Crop To menu to specify what part of the PDF or Illustrator (AI) document to include:

Bounding Box Crops to the smallest rectangular region that includes all the text and graphics of the page. This option eliminates extraneous white space.

Media Box Crops to the original size of the page.

Crop Box Crops to the clipping region (crop margins) of the PDF file.

Bleed Box Crops to the region specified in the PDF file for accommodating limitations inherent in production processes such as cutting, folding, and trimming.

Trim Box Crops to the region specified for the intended finished size of the page.

Art Box Crops to the region specified in the PDF file for placing the PDF data into another application.

4 Click OK to close the Place PDF dialog box.

5 If necessary, set any positioning, scaling, skewing, rotating, warping, or anti-aliasing options in the options bar.

6 Click Commit to place the artwork as a Smart Object on a new layer of the destination document.

Paste Adobe Illustrator art into Photoshop

You can copy art from Adobe Illustrator and paste it into a Photoshop document.

1 In Adobe Illustrator, specify preferences for the copy-and-paste behavior:

- To automatically rasterize the art when pasting it into a Photoshop document, turn off the PDF and the AICB (No Transparency Support) options in the File Handling & Clipboard preferences.
- To paste the art as a Smart Object, rasterized image, path, or shape layer, turn on the PDF and the AICB (No Transparency Support) options in the File Handling & Clipboard preferences.

2 Open a file in Adobe Illustrator, select the art you want to copy, and choose Edit > Copy.

3 In Photoshop, open the document that you want to paste the Adobe Illustrator art into and then choose Edit > Paste.

__Note:__ If the PDF and the AICB (No Transparency Support) options are turned off in the File Handling & Clipboard preferences of Adobe Illustrator, the art is automatically rasterized as it's pasted into the Photoshop document. You can skip the rest of the steps in this procedure.

4 In the Paste dialog box, select how you want to paste the Adobe Illustrator art and then click OK:

Smart Object Pastes the art as a Vector Smart Object that can be scaled, transformed, or moved without degrading the image. As the art is placed, its file data is embedded in the Photoshop document on a separate layer.

Pixels Pastes the art as pixels that can be scaled, transformed, or moved before it is rasterized and placed on its own layer in the Photoshop document.

Path Pastes the art as a path that can be edited with the pen tools, Path Selection tool, or Direct Selection tool. The path is pasted into the layer that's selected in the Layers panel.

Shape Layer Pastes the art as a new shape layer (a layer containing a path filled with the foreground color).

5 If you selected Smart Object or Pixels in the Paste dialog box, make any transformations you wish, and then click Enter or Return to place the art.

More Help topics

Adobe Bridge

Mini Bridge

Scale, rotate, skew, distort, apply perspective, or warp

Warp an item

Placing files

Understand Smart Objects

Path segments, components, and points

Create a shape on a shape layer

Place Photoshop images in other applications

Photoshop provides a number of features to help you use images in other applications. Because of the tight integration between Adobe products, many Adobe applications can directly import Photoshop (PSD) format files and use Photoshop features like layers, layer styles, masks, transparency, and effects.

Prepare images for page-layout programs

How you prepare an image for a page-layout program depends upon the file formats the program recognizes:

- Adobe InDesign 2.0 and later can place Photoshop PSD files. You do not need to save or export your Photoshop image to a different file format. Transparent areas are displayed and printed as expected.
- Most other page-layout programs require you to save the image as a TIFF or EPS file. However, if the image contains fully transparent areas, you must first define those areas using a clipping path. Check the documentation for your page-layout program to determine the best format for importing Photoshop images.

If the page-layout program cannot place Photoshop PSD files, follow these steps:

1 If your image contains a transparent background or areas that you want to be transparent, create a clipping path around the opaque areas of the image. Even if you have deleted the background around the image, you must define the area with a clipping path before converting the file to TIFF or EPS format. Otherwise, areas that are transparent may appear as white in the page-layout program.

2 Choose File > Save As.

3 In the Save As dialog box, choose the appropriate format from the Format menu. The format you choose depends on the final output for the document. For printing to non-PostScript printers, choose TIFF. For printing to PostScript printers, choose Photoshop EPS. Then click Save.

4 In the TIFF Options or EPS Options dialog box, set the following options. Leave any remaining options at their default settings, and click OK.
   - TIFF Options dialog box: set Image Compression to None.
   - EPS Options dialog box (Windows): set Preview to TIFF (8 bits/pixel) and Encoding to ASCII85.
   - EPS Options dialog box (Mac OS): set Preview to Mac (8 bits/pixel) and Encoding to ASCII85.

If the layout program displays transparent areas as white, try printing the document. Some layout programs do not display clipping paths properly but print them as expected.

Use Photoshop artwork in Adobe Illustrator

Adobe Illustrator can both open or place Photoshop files; you do not need to save or export your Photoshop image to a different file format. If you place an image into an open Illustrator file, you can incorporate the image as if it were any other element in the artwork, or you can maintain a link to the original file. Although you can't edit a linked image within Illustrator, you can jump back to Photoshop, using the Edit Original command, to revise it. Once saved, any changes you make are reflected in the version in Illustrator.

1 If the image file is open in Photoshop, save it as a Photoshop (PSD) file, and close the file.

2 In Adobe Illustrator, do one of the following:
   - To open the file directly in Illustrator, choose File > Open. Locate the image in the Open File dialog box, and click Open.
   - To incorporate the image into an existing Illustrator file, choose File > Place. Locate the file in the Place dialog box, make sure the Link option is not selected, and click Place.
   - To place the image into a file but maintain a link to the original, choose File > Place. In the Place dialog box, locate the file, select the Link option, and click Place. Illustrator centers the image in the open illustration. A red X through the image indicates it is linked and not editable.

3 If you opened or placed the image without linking, the Photoshop Import dialog box appears. Choose the appropriate option as follows, and click OK:
   - Convert Photoshop Layers To Objects to convert the layers to Illustrator objects. This option preserves masks, blending modes, transparency, and (optionally) slices and image maps. However, it does not support Photoshop adjustment layers and layer effects.
   - Flatten Photoshop Layers To A Single Image to merge all the layers into a single layer. This option preserves the look of the image, but you can no longer edit individual layers.

Create transparency using image clipping paths

You can use image clipping paths to define transparent areas in images you place in page-layout applications. In addition, Mac OS users can embed Photoshop images in many word-processor files.

You may want to use only part of a Photoshop image when printing it or placing it in another application. For example, you may want to use a foreground object and exclude the background. An *image clipping path* lets you isolate the foreground object and make everything else transparent when the image is printed or placed in another application.

Note: *Paths are vector-based; therefore, they have hard edges. You cannot preserve the softness of a feathered edge, such as in a shadow, when creating an image clipping path.*

1 Draw a work path that defines the area of the image you want to show.

If you've already selected the area of the image you want to show, you can convert the selection to a work path. See Convert a selection to a path for instructions.

2 In the Paths panel, save the work path as a path.

3 Choose Clipping Path from the Paths panel menu, set the following options, and click OK:

- For Path, choose the path you want to save.
- For Flatness, leave the flatness value blank to print the image using the printer's default value. If you experience printing errors, enter a flatness value to determine how the PostScript interpreter approximates the curve. The lower the flatness value, the greater the number of straight lines used to draw the curve and the more accurate the curve. Values can range from 0.2 to 100. In general, a flatness setting from 8 to 10 is recommended for high-resolution printing (1200 dpi to 2400 dpi), and a setting from 1 to 3 for low-resolution printing (300 dpi to 600 dpi).

4 If you plan to print the file using process colors, convert the file to CMYK mode.

5 Save the file by doing one of the following:

- To print the file using a PostScript printer, save in Photoshop EPS, DCS, or PDF format.
- To print the file using a non-PostScript printer, save in TIFF format and export to Adobe InDesign, or to Adobe PageMaker® 5.0 or later.

Print image clipping paths

Sometimes an imagesetter cannot interpret image clipping paths, or an image clipping path is too complex for a printer, resulting in a Limitcheck error or a general PostScript error. Sometimes you can print a complex path on a low-resolution printer without difficulty but run into problems when printing the same path on a high-resolution printer. This is because the lower-resolution printer simplifies the path, using fewer line segments to describe curves than the high-resolution printer does.

You can simplify an image clipping path in the following ways:

- Manually reduce the number of anchor points on the path.
- Increase the tolerance setting used to create the path. To do this, load the existing path as a selection, choose Make Work Path from the Paths panel menu, and increase the tolerance setting (4 to 6 pixels is a good starting value). Then re-create the image clipping path.

Export paths to Adobe Illustrator

The Paths To Illustrator command lets you export Photoshop paths as Adobe Illustrator files. Exporting paths in this way simplifies the task of combining Photoshop and Illustrator artwork or using Photoshop features with Illustrator artwork. For example, you may want to export a pen tool path and stroke it to use as a trap with a Photoshop clipping path you are printing in Illustrator. You can also use this feature to align Illustrator text or objects with Photoshop paths.

1. Draw and save a path or convert an existing selection into a path.
2. Choose File > Export > Paths To Illustrator.
3. Choose a location for the exported path, and enter a filename. Make sure Work Path is chosen from the Path menu to export the path.
4. Click Save.
5. Open the file in Adobe Illustrator. You can manipulate the path or use the path to align Illustrator objects that you add to the file.

   Note that the crop marks in Adobe Illustrator reflect the dimensions of the Photoshop image. The position of the path within the Photoshop image is maintained, provided you don't change the crop marks or move the path.

Link or embed an image using OLE (Windows only)

Photoshop is an OLE 2.0 server, which means it supports embedding or linking an image in an OLE container application (usually a word-processing or page-layout program). For example, you can insert Photoshop files and selections into other OLE applications, such as Adobe PageMaker, Adobe FrameMaker, and Microsoft Word, using copy and paste or other methods.

- Linking lets you place a link in the OLE container file that refers to the Photoshop file on the hard drive.
- Embedding lets you insert the Photoshop file into the OLE container file.

  After the image is in the container application, you can double-click it for editing in Photoshop. When you close the image in Photoshop, it is updated in the container application.

Link or embed a selection or image in an OLE application

? Do one of the following:

- Copy a selection in Photoshop, and insert it in your OLE container application using the application's Paste Special command. Refer to your word-processing or page-layout application documentation for more instructions. Pasted selections can only be embedded, not linked.
- Use your OLE container application's Insert Object command to insert a new Photoshop image or existing Photoshop file as an OLE-embedded or OLE-linked object. Refer to your word-processing or page-layout application documentation for instructions.

Insert an unlinked screen-resolution bitmap into an OLE application

? With the Move tool , drag a selection to the OLE container application. When you drop the object, it appears as a 72-ppi bitmap, which cannot be automatically updated in Photoshop.

Modify and update a linked or embedded image in an OLE application

1. Double-click the linked or embedded image in your word-processing or page-layout application to start Photoshop (if it is not already running), and open the image for editing.
2. Modify the image as desired.

3 Do one of the following:

- For embedded images, close the file, or choose File > Update or File > Close & Return to *[application name]*.
- For linked images, save and close the file.

Note: *You can also modify linked files without first opening the container document. The linked image is updated the next time you open the document in its OLE container application.*

More Help topics

Working with Photoshop and Flash

Working with Photoshop and Dreamweaver

Convert an image to another color mode

Understand shapes and paths

Convert a selection to a path

Add or deleteanchor points

Convert paths to selection borders

Plug-ins

About plug-in modules

Plug-in modules are software programs developed by Adobe Systems and by other software developers in conjunction with Adobe Systems to add features to Photoshop. A number of importing, exporting, and special-effects plug-ins come with your program. They are automatically installed in folders inside the Photoshop Plug-ins folder.

You can select an additional Plug-ins folder for compatible plug-ins stored with another application. You can also create a shortcut (Windows) or an alias (Mac OS) for a plug-in stored in another folder on your system. You can then add the shortcut or alias to the plug-ins folder and use that plug-in with Photoshop.

Once installed, plug-in modules appear as options in the Import or Export menu; as file formats in the Open, and Save As dialog boxes; or as filters in the Filter submenus. Photoshop can accommodate a large number of plug-ins. However, if the list of installed plug-in modules becomes too long, Photoshop may not be able to display all the plug-ins in their appropriate menus. If so, newly installed plug-ins appear in the Filter > Other submenu.

Install a plug-in module

In Mac OS, you cannot run Photoshop in the Classic environment. Plug-ins originally intended to work on Mac OS 9 won't appear.

? Do one of the following:

- To install an Adobe Systems plug-in module, use the plug-in installer, if provided. In Windows, you can also install or copy the module into the appropriate Plug-ins folder in the Photoshop program folder. In Mac OS, drag a copy of the module to the appropriate Plug-Ins folder in the Photoshop program folder. Make sure that the files are uncompressed.
- To install a third-party plug-in module, follow the installation instructions that came with the plug-in module. If you cannot run a third-party plug-in, it may require a legacy Photoshop serial number.

Select an additional plug-ins folder

1 Choose Edit > Preferences > Plug-ins (Windows) or choose Photoshop > Preferences > Plug-ins (Mac OS).
2 Select Additional Plug-ins Folder.
3 Click Choose, and select a folder or directory from the list. Make sure that you do not select a location inside the Plug-ins folder. To display the contents of a folder, double-click the directory (Windows) or click Open (Mac OS).
4 When you have highlighted the additional plug-ins folder, click OK (Windows) or Choose (Mac OS).
5 Restart Photoshop for the plug-ins to take effect.

Suppress the loading of plug-ins

? Add a tilde ~ character at the beginning of the plug-in name, folder, or directory. That file (or all files in the folder) will be ignored by the application.

View information about installed plug-ins

? Do one of the following:
- (Windows) Choose Help > About Plug-in and choose a plug-in from the submenu.
- (Mac OS) Choose Photoshop > About Plug-in, and then choose a plug-in from the submenu.

More Help topics

Presets

Preferences

Key shortcuts

This list covers some helpful shortcuts for some Photoshop features.

Print

To clear print settings, hold down the spacebar while selecting File > Print.

Blur gallery (Field, Iris, Tilt-Shift)

H: Temporarily hide on-canvas UI M: Temporarily show blur mask

Liquify

M: Load Last Mesh X: Mirror Tool

Crop tool

Double-click inside crop box, or press Enter or Return	Commit crop
Esc	Cancel crop
X	Switch crop box orientation between portrait and landscape
I	(Creative Cloud only) Front Image for Crop tool and Perspective Crop tool

Backspace or Delete	Reset crop box
O	Cycle overlay options
Shift + O	Cycle overlay orientation for Triangle and Golden Spiral overlays
Forward slash (/)	Hide and show cropped area
Shift + drag	Create new crop box
Shift + drag corner handle	Constrain proportions
Control (Windows) or Command (Mac OS)	Invoke Straighten tool
Control + rotate	Prevent crop box from shrinking
Shift + rotate	Restrict to 15-degree increments
Shift + drag image	Restrict to 45-degree axes
Control + drag	Temporarily disable snapping to edge

Adaptive Wide Angle

Tool shortcuts C: Constraint tool Y: Polygon Constraint tool M: Move tool H: Hand tool Z: Zoom tool

Control shortcuts P: Preview W: Show Constraint E: Show Mesh T: Correction S: Scale F: Focal Length R: Crop Factor A: As Shot

Hidden shortcuts not visible in interface L: Toggle transparent matte X: Temorary zoom E: Revert the last-added polygon corner

More Help topics

Default keyboard shortcuts

Presets

Migrate presets from earlier versions of Photoshop

You can migrate presets from earlier versions of Photoshop into newer versions. The Migrate Presets command lets you automatically migrate brushes, swatches, gradients, patterns, and more.

1. Choose Edit > Presets > Migrate Presets.
2. Click Yes when prompted to import presets from an earlier version of Photoshop.
3. Click OK.

Work with the Preset Manager

About the Preset Manager

The Preset Manager lets you manage the libraries of preset brushes, swatches, gradients, styles, patterns, contours, custom shapes, and preset tools that come with Photoshop. For example, you can use the Preset Manager to change the current set of preset items or create new libraries. After you load a library in the Preset Manager, you can access the library's items in locations such as the options bar, panels, dialog boxes, and so on.

In general, when you change a preset, Photoshop prompts you to save the changes as a new preset so that both the original and changed preset remain available.

Each type of library has its own file extension and default folder. Preset files are installed on your computer inside the Presets folder in the Adobe Photoshop application folder.

To open the Preset Manager, choose Edit > Presets > Preset Manager. Choose an option from the Preset Type menu to switch to a specific preset type.

You can adjust the configuration of presets by clicking the panel menu button and choosing a display mode from the top section of the menu:

Text Only Displays the name of each preset item.

Small Thumbnail or Large Thumbnail Displays a thumbnail of each preset item.

Small List or Large List Displays the name and thumbnail of each preset item.

Stroke Thumbnail Displays a sample brush stroke and brush thumbnail of each brush preset. (This option is available for brush presets only.)

To rearrange the list of items, drag an item up or down in the list.



Note: *To delete a preset in the Preset Manager, select the preset and click Delete. You can always use the Reset command to restore the default items in a library.*

Load a library of preset items

? Do one of the following:

- Click the triangle to the right of the Preset Type pop-up menu and then choose a library file from the bottom of the panel menu. Click OK to replace the current list, or click Append to add the current list.
- To add a library to the current list, click Load, select the library file you want to add, and click Load.
- To replace the current list with a different library, choose Replace *[Preset Type]* from the panel menu. Select the library file you want to use, and click Load.

Note: *Each type of library has its own file extension and default folder.*

Manage preset items

You can rename or delete preset items, as well as create or restore libraries of presets.

Rename preset items

1 Select a preset item. Shift-click to select multiple items.

2 Do one of the following:

- Click Rename, and then enter a new name for the brush, swatch, and so on.
- If the Preset Manager currently displays presets as thumbnails, double-click a preset, enter a new name, and click OK.
- If the Preset Manager currently displays presets as a list or text only, double-click a preset, enter a new name inline, and press Enter (Windows) or Return (Mac OS).

Delete preset items

? Do one of the following:

- Select a preset item, and click Delete.
- Alt-click (Windows) or Option-click (Mac OS) the items you want to delete.

Create a new library of presets

1 Do one of the following:

- To save all the presets in the list as a library, make sure that all items are selected.
- To save a subset of the current list as a library, hold down Shift, and select the items you want to save.

2 Click Save Set, choose a location for the library, enter a file name, and click Save.

You can save the library anywhere. However, if you place the library file in the appropriate Presets folder in the default preset location, the library name will appear at the bottom of the panel menu after you restart Photoshop.

Restore the default library of preset items

? Choose Reset from the panel menu. You can either replace the current list or append the default library to the current list.

Default preset locations

1 The default location for saving/loading/replacing presets depends on your operating system.

- Windows 7 and Windows Vista: [Drive]:\Users\<user>\AppData\Roaming\Adobe\Adobe Photoshop[version_number]\Presets.
- Mac: <User>/Library/Application Support/Adobe/AdobePhotoshop[version_number]/Presets.
- Windows XP: [Drive]:\Document and Settings\<user>\Application Data\Adobe\AdobePhotoshop [version_number]\Presets.

2 Presets that ship with Adobe Photoshop are stored in the Photoshop program folder.

Displaying hidden files in Windows

The default locations for saving/loading/replacing presets are hidden by default in Windows.

See Show hidden files and folders to learn how to view hidden items.

Memory and performance

Allocate RAM to Photoshop

Photoshop displays the RAM available to Photoshop and the ideal range of RAM for Photoshop (a percentage of the total available RAM) in Performance preferences.

? In the Performance preferences, enter the amount of RAM you want to allocate to Photoshop in the Let Photoshop Use text box. Alternatively, drag the slider.

For detailed information on improving Photoshop performance, including specifying RAM settings in preferences, see Optimize performance | Photoshop CS4, CS5 (kb404439) in the Adobe support knowledgebase.

Assigning scratch disks

When your system does not have enough RAM to perform an operation, Photoshop uses a proprietary virtual memory technology, also called scratch disks. A *scratch disk* is any drive or drive partition with free memory. By default, Photoshop uses the hard drive on which the operating system is installed as the primary scratch disk.

Photoshop detects and displays all available internal disks in the Preferences panel. Using the Preferences panel, you can enable other scratch disks to be used when the primary disk is full. Your primary scratch disk should be your fastest hard disk; make sure it has plenty of defragmented space available.

The following guidelines can help you assign scratch disks:

- For best performance, scratch disks should be on a different drive than any large files you are editing.
- Scratch disks should be on a different drive than the one your operating system uses for virtual memory.
- RAID disks/disk arrays are good choices for dedicated scratch disk volumes.
- Drives with scratch disks should be defragmented regularly.

Change the scratch disk assignment

1 Do any of the following in the Scratch Disks area of Performance preferences:
   - To change the scratch disk order, click the arrow buttons.
   - To enable or disable a scratch disk, select or deselect the Active checkbox.

   To ensure optimal performance, only local drives are available as scratch disks.

2 Click OK.

3 To apply the changes, restart Photoshop.

If Photoshop cannot launch because the scratch disk is full, hold down the Cmd + Opt keys (Mac) or Ctrl + Alt keys (Windows) on launch to set a new scratch disk.

Specify history and cache settings

? In the Performance preferences, do any of the following:
   - Specify the maximum number of History States that appear in the History panel.

- Specify the Cache Levels and Tile Size for image data. To quickly optimize these settings, click a preset for images with these characterstics:**Tall and Thin**Many layers and small dimensions.**Default**Moderate dimensions and layers.**Big and Flat**Large dimensions and few layers.

  You must restart Photoshop to apply new cache settings.

Free memory

The Purge command lets you free memory used by the Undo command, the History panel, or the clipboard.

? Choose Edit > Purge, and choose the item type or buffer you want to clear. If it is already empty, the item type or buffer is dimmed.

  Note: *The Purge command permanently clears from memory the operation stored by the command or buffer; Purge cannot be undone. For example, choosing Edit > Purge > Histories deletes all history states from the History panel. Use the Purge command when the amount of information in memory is so large that Photoshop performance is noticeably affected.*

Enable OpenGL and optimize GPU settings

OpenGL is a software and hardware standard that accelerates video processing when working with large or complex images such as 3D files. OpenGL requires a video adapter that supports the OpenGL standard. Your performance when opening, moving, and editing 3D models is significantly improved on a system with OpenGL. (If OpenGL is not available on your system, Photoshop uses software-based ray-trace rendering to display 3D files.)

If OpenGL is present on your system, you can enable it in the Preferences dialog box.

1. Do one of the following:
   - (Windows) Choose Edit > Preferences > Performance.
   - (Mac OS) Choose Photoshop > Preferences > Performance.
2. In the GPU Settings section, select Enable OpenGL Drawing.
3. Click OK. The preference affects subsequently opened images. No restart is necessary.

For more information, see:

- GPU and OpenGL support | Photoshop CS4, CS5(kb404898)
- GPU and OpenGL features and preferences | Photoshop and Bridge CS5, CS4(kb405745)
- Tested video cards | Photoshop CS5 (cpsid_83117)

Preferences

About preferences

In order for Photoshop to run as smoothly as possible, in a way that's customized for your particular workflow, you need to set up your Preferences to your liking.

Numerous program settings are stored in the Adobe Photoshop Prefs file, including general display options, file-saving options, performance options, cursor options, transparency options, type options, and options for plug-ins and scratch disks. Most of these options are set in the Preferences dialog box. Preference settings are saved each time you quit the application.

Unexpected behavior may indicate damaged preferences. If you suspect damage to preferences, restore preferences to their default settings.

Detailed information about specific preference settings appears in task-specific topics. For example, search Help for "Transparency preferences" to see those settings discussed in the context of related features such as layers.

Open a preferences dialog box

1 Do one of the following:
   - (Windows) Choose Edit > Preferences and choose the desired preference set from the submenu.
   - (Mac OS) Choose Photoshop > Preferences, and then choose the desired preference set from the submenu.
2 To switch to a different preference set, do one of the following:
   - Choose the preference set from the menu at the left of the dialog box.
   - Click Next to display the next preference set in the list; click Prev to display the previous set.

For information on a specific preference option, search Help.

To manually restore preferences to default:

- Find the preference file that you want to reset and move it to another location. When you restart Photoshop, a new preference file will be created in the original location. See Preference filenames and locations.

To restore preferences quickly using a keyboard shortcut:

- Press and hold Alt+Control+Shift (Windows) or Option+Command+Shift (Mac OS) as you start Photoshop. You are prompted to delete the current settings. The new preferences files are created the next time you start Photoshop.

Note: Using the keyboard shortcut, preference files for custom shortcuts, workspaces, and color settings will also be reset to default.

Disable and enable warning messages

Sometimes you will see messages containing warnings or prompts. You can suppress the display of these messages by selecting the Don't Show Again option in the message. You can also globally redisplay all messages that have been suppressed.

1 Do one of the following:
   - (Windows) Choose Edit > Preferences > General.
   - (Mac OS) Choose Photoshop > Preferences > General.
2 Click Reset All Warning Dialogs, and click OK.

More Help topics

Presets

Plug-ins

Show or hide non-printing Extras

Show or hide Extras

Guides, grids, selection edges, slices, and text baselines are examples of nonprinting *Extras* that help you select, move, or edit objects. You can enable or disable any combination of Extras without affecting the image. You can also show or hide enabled Extras to clean up the workspace.

? Do one of the following:

- To show or hide all enabled Extras, choose View > Extras. (A check mark appears next to enabled Extras in the Show submenu.)
- To enable and show an individual Extra, choose View > Show, and select the Extra from the submenu.
- To enable and show all available Extras, choose View > Show > All.
- To disable and hide all Extras, choose View > Show > None.
- To enable or disable groups of Extras, choose View > Show > Show Extra Options.

Note: *Color samplers are affected by the Extras, All, and None commands, though they are not an option in the Show submenu.*

More Help topics

Grid and guides

Rulers

Position with the Ruler tool

Position with the Ruler tool

The Ruler tool helps you position images or elements precisely. The Ruler tool calculates the distance between any two points in the workspace. When you measure from one point to another, a nonprinting line is drawn, and the options bar and Info panel show the following information:

- The starting location (X and Y)
- The horizontal (W) and vertical (H) distances traveled from the *x* and *y* axes
- The angle measured relative to the axis (A)
- The total length traveled (D1)
- The two lengths traveled (D1 and D2), when you use a protractor

  All measurements except the angle are calculated in the unit of measure currently set in the Units & Rulers preference dialog box.

  If your document has an existing measuring line, selecting the Ruler tool causes it to be displayed.

Measure between two points

1. Select the Ruler tool . (If the Ruler isn't visible, hold down the Eyedropper tool.)
2. Drag from the starting point to the ending point. Hold down the Shift key to constrain the tool to 45° increments.

3 To create a protractor from an existing measuring line, Alt-drag (Windows) or Option-drag (Mac OS) at an angle from one end of the measuring line, or double-click the line and drag. Hold down the Shift key to constrain the tool to multiples of 45°.

Edit a measuring line

1 Select the Ruler tool .

2 Do one of the following:

- To resize the line, drag one end of an existing measuring line.
- To move the line, place the pointer on the line away from either endpoint, and drag the line.
- To remove the line, place the pointer on the line away from either endpoint, and drag the line out of the image, or click Clear in the tool options bar.

Note: *You can drag out a measure line on an image feature that should be horizontal or vertical, and then choose Image > Image Rotation > Arbitrary. The correct angle of rotation required to straighten the image is automatically entered into the Rotate Canvas dialog box.*

More Help topics

Rulers

Grid and guides

Position elements with snapping

Use snapping

Snapping helps with precise placement of selection edges, cropping marquees, slices, shapes, and paths. However, if snapping prevents you from correctly placing elements, you can disable it.

Enable or disable snapping

? Choose View > Snap. A check mark indicates that snapping is enabled.

To temporarily disable snapping while using the Move tool, hold down Ctrl.

Specify what to snap to

? Choose View > Snap To, and choose one or more options from the submenu:

Guides Snaps to guides.

Grid Snaps to the grid. You cannot select this option when the grid is hidden.

Layer Snaps to the content in the layer.

Slices Snaps to slice boundaries. You cannot select this option when slices are hidden.

Document Bounds Snaps to the edges of the document.

All Selects all Snap To options.

None Deselects all Snap To options.

A check mark indicates that the option is selected and snapping is enabled.

If you want to enable snapping for only one option, make sure the Snap command is disabled, and then choose View > Snap To and choose an option. This automatically enables snapping for the selected option, and deselects all other Snap To options.

More Help topics

Grid and guides

Rulers

How to tune Photoshop for peak performance

How to tune Photoshop for peak performance

Chapter 4: Web, screen, and app design

Design Space (Preview)

Important: Design Space (Preview) requires Mac OS X 10.10 or Windows 8.1 64-bit OS or higher.

Get started

Design Space (Preview) is a companion experience to Photoshop for web and app designers. Technically, Design Space (Preview) is an HMTL5/CSS/JavaScript layer built on top of Photoshop. Separating this new experience from standard Photoshop in this manner facilitates a fresh UI, smarter interactions, and faster delivery of top-requested features.

Design Space is currently a Technology Preview. To help shape Design Space (Preview) into the experience you want, give us feedback @psdesign.

For a list of known issues in this release, see Top known issues in this release.

Note: *You can find Design Space (Preview) source code at github.*

Switch to Design Space (Preview)

In Photoshop, do one of the following:

- Select Window > Design Space (Preview).
- From the workspace selection pop-up menu in the upper-right corner of the screen, choose Design Space (Preview).

Note: *Design Space (Preview) is enabled by default. In the unlikely event that options to switch to the Design Space workspace are unavailable, ensure that Enable Design Space (Preview) under Preferences > Technology Previews is selected.*



After switching to Design Space (Preview) workspace, select Help > Design Space Introduction for a quick walkthrough of its features and functionality. The introduction is automatically displayed when you switch to Design Space (Preview) for the first time.

A first look at Design Space (Preview)



A Toolbar ***B*** *Properties* ***C*** *Layers and Libraries* ***D*** *Collapse or expand columns*

Cmd/Ctrl+click icons marked as ***D*** *to quickly toggle between the Properties and Layers & Libraries columns.*



Adjust the interface

- If necessary, you can maximize your working space and view properties, layers, and libraries in a single column. Select Window > Single-Column Mode.



- If you rely extensively on keyboard shortcuts, you can choose to hide the toolbar. Deselect Window > Pin Toolbar.

Create a document

There are multiple ways of creating a document using Design Space (Preview).

1 Select File > New or use the Cmd/Ctrl+N keyboard shortcut. Design Space (Preview) quickly creates a document with a single artboard that uses the iPhone 6 template.

2 Choose File > New... to open the New dialog box. Specify the necessary details and click OK. For more information, see Create an imageand Create an artboard document .

3 Choose File > New From Template and select one of the following templates:

Add an artboard to a Design Space (Preview) file

? In the Design Space (Preview) interface, do one of the following:

- Select Layer > Create New Artboard. Design Space (Preview) adds an artboard of default dimensions to the document.
- To add an artboard for a specific device, select Layer > New Artboard and then select a preset. For example, select Layer > New Artboard > iPad Pro.

? Add your design elements to the new artboard.

You can also add artboards to your document by clicking the + icons that appear alongside artboards currently in the document. These + icons appear wherever an existing artboard is selected and the canvas can accommodate additional artboards.

Tools

The following tools are available in Design Space (Preview):



Note: *The first letter indicates the shortcut to use the tool. For instance, the shortcut to use Rectangle tool is R.*

Select Aside from regular selection tasks, the new Select tool is special in allowing you to quickly navigate layer and artboard hierarchies.

- To drill down a nested group or layer hierarchy, double-click it with the Select tool enabled.
- Press Esc to step up one level in the hierarchy.

Rectangle & Ellipse Draw shapes. These tools work in much the same way as in standard Photoshop.

Type Creates a text layer.

Pen Works in much the same way as the Pen tool in standard Photoshop.

*While modifying the width, height, or other numeric properties of an object, you can enter math operations to get precise values. For example, 500/3 or 20*4.*

Sampler Advanced sampler tool. Lets you copy colors, effects, and other attributes. Follow these steps:

1. Select the object **to** which you want to copy an attribute. For example, select a rectangle.
2. Select the Sampler tool.
3. Perform the following action with the object **from** which you want to copy the attribute:Click: Copy the colorShift+Click: Copy effectsSpacebar: Invokes a heads-up display revealing the available attributes that you can sample. Whenever applicable, these attributes includes Typeface.



Search for documents, commands, and much more

Design Space (Preview) features comprehensive search functionality that lets you search across the following items among others:

- Menu commands
- Open documents
- Recent documents
- Layers, pixel layers, adjustment layers, group layers, vector layers, and text layers
- Artboards
- Libraries—all or a specific one
- Smart objects
- Styles
- Graphics
- Presets

While searching, you can filter your search results, so that they include only a specific type of items.

Follow these steps:

? Select Edit > Search to invoke the search functionality. Alternatively, press Ctrl/Cmd+F or click the Search icon at the left of the title bar.





Quickly create vector masks for layers

Design Space (Preview) makes creating masks for images in your project really straightforward.

1 Select a layer in the Layers panel.

2 Click the Mask Mode ( )icon in the Design Space top bar. Alternatively, press M to use the keyboard shortcut. While the Mask Mode is enabled, the Select tool arrow turns hollow ( ) and the Mask Mode icon turns blue.

3 Using tools such as the Pen tool and the Rectangle tool, draw a mask for your image.

4 When you're done creating the mask, exit the Mask Mode in one of the following ways:

- Click the Mask Mode icon ( ).
- Press Esc.
- Press the Mask Mode keyboard shortcut—M.

Manage and arrange objects

Create guides

Create guides in the Design Space (Preview) workspace to work acuurately with design elements.

1 Ensure that View > Show Guides is selected.

2 Click the Select tool and hover the mouse pointer over the edge of the work area. Notice the blue highlight indicating that guide creation is available.

3 Click and drag out a guide. If an artboard or a layer within an artboard is selected, an artboard-specific guide is created. Such a guide is displayed only when that artboard or its sub-layers are selected. If no artboard or a layer within an artboard is selected, a document-specific guide is created.

Distribute objects

1 Select three or more layers.

2 Choose Arrange > Distribute Objects and choose a command. Alternatively, select a distribution button from the Distribute and Alignment panel.

- **Horizontally** Spaces the layers evenly, starting from the horizontal center of each layer.
- **Vertically** Spaces the layers evenly, starting from the vertical center of each layer.

Align objects

1 Select two or more layers.

2 Choose Arrange > Align Objects and choose a command. Alternatively, select an alignment button from the Distribute and Alignment panel.

- **Left** Aligns the left pixel on the selected layers to the left pixel on the leftmost layer
- **Center** Aligns the horizontal center pixel on the selected layers to the horizontal center pixel of all the selected layers
- **Right** Aligns the right pixel on the linked layers to the rightmost pixel on all selected layers
- **Top** Aligns the top pixel on the selected layers to the topmost pixel on all selected layers
- **Middle** Aligns the vertical center pixel on each selected layers to the vertical center pixel of all the selected layers
- **Bottom** Aligns the bottom pixel on the selected layers to the bottommost pixel on selected layers

Transform objects

You can apply transformations to a single layer or multiple layers. To make a transformation, first select an item to transform and then choose a transformation command. While modifying the width, height, or other numeric properties of an object, you can enter math operations to get precise values. For example, 500/3 or 20*4.

Rotate

? Choose Layer > Transform and choose a command.

- **Rotate 180** Rotates the item by 180 degrees
- **Rotate Right** Rotates the item clockwise by 90 degrees

- **Rotate Left** Rotates the item counterclockwise by 90 degrees

? You can also rotate an object directly on canvas. With an object selected, hover over the corner and the widget changes to allow for rotation.



Flip

- Select a flip command from the Arrange menu.
  - **Flip Horizontal** Flips the item horizontally
  - **Flip Vertical** Flips the item vertically
  - **Swap Position** Swap the position of the two selected groups or layers

Change the appearance of objects

You can make changes to the object by modifying the options available in the Appearance panel.

Opacity

A layer's overall opacity determines to what degree it obscures or reveals the layer beneath it. A layer with 1% opacity appears nearly transparent, whereas one with 100% opacity appears completely opaque.

1 In the Layers panel, select one or more layers.

2 Specify a value for opacity in the Appearance panel.

Blending mode

A layer's blending mode determines how its pixels blend with underlying pixels in the image. You can create various special effects using blending modes.

1 In the Layers panel, select one or more layers.

2 Choose one of the following blending modes in the Appearance panel:

- Normal
- Dissolve
- Darken
- Lighten
- Screen

- Overlay
- Multiply
- Color Burn
- Linear Burn
- Darker Color

If you use any other blend mode in standard Photoshop, that blend mode is honored in Design Space (Preview) as well.

For more information about what each blending mode does, see Blending modes.

Type

1 In the Layers panel, select the text layer.

2 Specify the following settings in the Appearance panel:

- **Typeface** Set font from the drop-down.
- **Weight** Set weight based on the font you selected.
- **Text Color** Select the Text Color in one of the following ways:
  - Select the color from the color picker.
  - Specify a value for the color. See http://www.w3schools.com/cssref/css_colors_legal.asp for a ready reference of color values.
  - Specify a common name for color, such as tomato or magenta. For the supported list of names, see www.w3.org/TR/css3-color/#svg-color.
- **Size** Set size of the selected text.
- **Letter** Set letter spacing.
- **Line** Set line spacing.
- **Align** Align the text left, center, right, or justify.

Vector

With the help of vector tools, you can use Add, Subtract, Intersect, or Exclude options to modify the current shapes on a layer or combine one or more selected shape layers.

1 In the Layers panel, select the layers you want to combine.

2 Select Layers > Combine and then choose one of the following:

- **Unite Shape** Adds the new area to the existing shapes or path
- **Subtract Shape** Removes the overlapping area from the existing shapes or path
- **Intersect Shape** Restricts the area to the intersection of the new area and the existing shapes or path
- **Difference Shape** Excludes the overlap area in the consolidated new and existing areas

Fill

1 In the Layers panel, select one or more layers.

2 Open the fill color selector in the Appearance panel and then specify a color in one of the following ways:

- Click a color in the color picker.

- Specify a value for the color. See http://www.w3schools.com/cssref/css_colors_legal.asp for a ready reference of color values.
- Specify a common name for color, such as tomato or magenta. For the supported list of names, see www.w3.org/TR/css3-color/#svg-color.

? Specify the alpha value to set the opacity of the fill color.

Stroke

1 In the Layers panel, select one or more layers.

2 Open the stroke color selector in the Appearance panel and then specify a color in one of the following ways:

- Click a color in the color picker.
- Specify a value for the color. See http://www.w3schools.com/cssref/css_colors_legal.asp for a ready reference of color values.
- Specify a common name for color, such as tomato or magenta. For the supported list of names, see www.w3.org/TR/css3-color/#svg-color.

1 Specify the alpha value to set the opacity of the stroke color.

2 Specify the size of the stroke.

3 Specify the alignment of the stroke as Inside, Center, or Outside from the pop-up menu.

Apply layer effects

1 In the Layers panel, select one or more layers.

2 In the Effects panel, click the + icon to add a stroke, color overlay, drop shadow, or inner shadow.

Stroke Adds a stroke effect to the selected layer.

Color Overlay Fills the layer's content with a color.

Drop Shadow Adds a shadow that falls behind the contents on the layer.

Inner Shadow Adds a shadow that falls just inside the edges of the layer's content, giving the layer a recessed appearance.

? Specify the necessary settings for the effect.

- For color overlays, you can specify a blending mode. For information on what each blending mode does, see Blending modes.
- For inner shadows and drop shadows, you can specify the following settings:
  - Blending mode
  - The X and Y coordinates of the shadow
  - The extent to which you want the shadow to be blurred
  - The spread of the shadow. The Spread setting expands the boundaries of the shadow prior to blurring.

Creative Cloud Libraries integration

You can now use Creative Cloud Libraries to organize, access, and share your assets from right within the Design Space (Preview) interface. You work with libraries in Design Space (Preview) in much the same way as in standard Photoshop. For more information, see these resources:

- Creative Cloud Libraries in Photoshop
- Share files, libraries, and more

Export assets

You can export artboards, layers, layer groups, or entire documents as PNG, JPEG, SVG, or PDF assets from directly within the Design Space (Preview) interface.

1 In the Export panel, click + to specify export settings for the selected layers from which you want to generate assets.

2 Specify the Scale, Suffix, and Format for the asset you want to export.

3 If necessary, click + to specify settings for more assets.

4 Click the icon to save the generated assets to your computer.

Click the iOS icon to quickly add all available asset types relevant for iOS devices. Similarly, click the hdpi icon to quickly add all asset types relevant to HiDPI displays.

Note: *While exporting multiple objects as assets, for ease of use, Design Space follows the canvas order of objects instead of their Z-order in the Layers panel. You can also specify multiple export settings via different layer selections and export them all at once by selecting File > Export or clicking the Export icon on the top title bar.*

Top known issues in this release

- Entering a negative transform value for a Library-Linked Smart Object results in an error. Entering a negative number into the Width or Height field puts Design Space (Preview) into an internal error state where layer is no longer selectable or visible on-canvas and controls are unresponsive.Solution/workaround: Select Window > Return To Standard Photoshop and Step Backward In History until the layer becomes visible on canvas.
- Using the Sampler tool a second time on the same Library Linked Smart Object after Undo of the first attempt results in an error.Solution/workaround: Undo twice before attempting the second sample.
- Opening an Illustrator file (Import PDF) results in an error.Solution/workaround: Select Window > Return To Standard Photoshop. Now, return to Design Space (Preview).
- Sometimes a Library Linked Smart Object has the Swap functionality enabled when only one layer is selected.Solution/workaround: Clicking the Swap icon corrects the problem.
- Creating a shape in standard Photoshop and having it selected while entering Design Space (Preview) changes the shape Fill and Stroke settings.Solution/workaround: Either deselect the shape before entering Design Space or Undo after entering Design Space.
- Trying to export while in the Type edit mode fails and disables the Export panel icon.Solution/workaround: Use the menu command or the export icon in the doc header. Returning to standard Photoshop and back to Design Space (Preview) reenables the Export panel icon.
- When no layer is selected, creating a shape with the Pen tool places it outside the artboard in the Layers panel but inside the artboard on-canvas.Solution/workaround: After creating the shape, click the Select tool and nudge (hit an arrow key via the keyboard).

- Undo after creating a layer mask leaves a reveal an all-mask applied to the layer. This makes the layer appear as though there is no mask applied. However, the Layers panel icon still erroneously shows that the layer has a mask.Solution/workaround: Perform the Undo operation twice.
- Paths are created without the modifier keys after the first path. When you remove the first path drawn, the action acts like a subtraction.Solution/workaround: Hold down the Shift key before drawing.
- Layer highlighting issues. If no layers are selected, hovering the mouse pointer over layers does not highlight them. The Cmd/Ctrl modifier does not work either. If a layer is selected, the Cmd/Ctrl modifier only shows smart guides but not the Design Space (Preview) highlighting (blue).
- (Windows-only) You can't currently pan the canvas by scrolling with a trackpad on Windows.
- X and Y coordinates are incorrect after moving the artboard on the canvas.
- Moving a layer off the artboard and back on corrupts the X-Y coordinates for the layer.
- Deleting the first mask in a multiple mask situation results in an inverted/subtracted mask.
- Numbers are not correctly localized. The comma in the numbers display as a dot/period.
- Exporting assets from a modal tool state results in an error.

Tips and tricks

- You can quickly change the background color for the working area. Right-click outside the artboards/other content in the working area and then select a color.



- Use the following keyboard shortcuts to toggle between the standard Photoshop interface and Design Space (Preview):
  - Cmd+Ctrl+` (Mac)
  - Alt+Ctrl+` (Windows)
- Double-click a layer name in the Layers panel to rename it.
- Double-click the canvas to drill down into your layer hierarchy. Press Esc to back your layer selection out and deselect layers at the top level.
- Double-clicking a single layer on the canvas (Type or Vector) puts you in the Edit mode. Pressing Esc exits the Edit mode.
- Active layers/groups have a blue highlight around them.
- Click the + icon next to a selected artboard in the document to add a new artboard.
- Vector and pixel layers show transform handles to resize and rotate; type layers do not display handles.

More Help topics

Photoshop and design

Introduction to Design Space (Preview)

Artboards



If you are a web or UX designer, you increasingly find yourself designing websites or apps for multiple devices. Artboards help streamline your design process by giving you an infinite canvas on which you can lay out designs for different devices and screens. While creating artboards, you can choose from a wide variety of preset sizes or define your own custom artboard size.

Artboards are useful even if you normally design for just one screen size. For example, while designing a website, you can use artboards to view designs for different pages side-by-side and in context.

Note: *Artboards are optimized for the RGB color mode and advanced GPU drawing mode.*

So, what's an artboard?

You can think of an artboard as a special type of layer group. An artboard clips the contents of any contained elements to its boundaries. The hierarchy of elements in an artboard is displayed in the Layers panel, together with layers and layer groups. Artboards can contain layers and layer groups, but not other artboards.

Visually, artboards serve as individual canvases within a document. Any layers in the document not contained within an artboard are grouped at the top of the Layers panel and remain unclipped by any artboards.

Artboard preferences

To customize the look of your artboards select Preferences > Interface > Appearance > Artboards. You have the option to select the artboard matte color and to show or hide artboard borders.



Create an artboard document

1 In Photoshop, select File > New.

2 In the New dialog box, specify a name for the document. For example, iPhone website.

3 From the Document Type pop-up menu, select Artboard.

4 Select one of the 35+ Artboard Size presets.



? Begin adding your design elements to the artboard. You can add smart objects, layers, layer groups, etc. to the artboard.

Convert an existing document into an artboard document

If you have a standard Photoshop document, you can quickly convert it into an artboard document.

1 Select one or more layer groups or layers in the document.

2 Right-click the selection and then choose Artboard From Layers or Artboard From Group.

Add artboards to the current document

? In the Tools panel, click the icon to select the Artboard tool.

1 Draw the artboard on the canvas.

2 Resize the artboard if necessary. From the tool options bar, select a preset size from the Size pop-up menu. Alternatively, you can leave the artboard custom-sized.



1 Rename the artboard to your desired name. Do the following:

   1 With the artboard selected, select Layer > Rename Artboard.

   2 Type a new name for the artboard and press Return.

3 Begin adding your design elements to the artboard. You can add smart objects, layers, layer groups, etc. to the artboard.

Quickly add new artboards to a document

You can add artboards to your document by clicking the + icons that appear alongside artboards currently in the document. These + icons appear wherever the canvas can accommodate additional artboards. To duplicate an artboard, Option/Alt + click a + icon.

1 Select an artboard.

2 Click a + icon alongside the artboard. Photoshop adds an artboard to the document in the direction of the + icon.



Option/Alt + click a plus (+) icon to duplicate the currently-selected artboard. The new artboard is added in the direction of the + icon you clicked.

Work with artboards

Move elements between artboards Simply drag the elements from one artboard to another on the canvas. When you move an element between artboards, Photoshop tries to position it in the same location relative to the ruler origins located in the upper-left corners of the artboards.

When you add/move an element to an artboard, the new element moves to the top of the Layers panel Z-order for that artboard.

You can also group layers/elements not included in any artboard with existing artboards. Simply drag the element on the canvas to the target artboard. Alternatively, move it into the target artboard in the Layers panel.

Move With the Artboard or Move tool selected, click the label of an artboard to select it. Now, move it to its desired location on the canvas.

Resize With the Artboard or Move tool selected, click the label of an artboard to select it. Now, select a new preset Size for the artboard from the tool options bar.

If you want to resize the artboard to a custom size, simply resize its boundaries using the handles.

Grids Select an artboard and select View > Show > Grid to view grids in an artboard.

Guides With an artboard selected, drag guides from the ruler to the canvas. These guides now move with the artboard. You can also duplicate an artboard with the assigned guides to assign identical guides to the duplicated artboard. Alternatively, you can select View > New Guide Layout to target the desired artboards. To set the guide visibility options, select View > Show.





Inspect artboard properties Select an artboard and select Window > Properties to quickly inspect its key properties. You can also resize the artboard from within the Properties panel.

Artboard properties are also displayed in the tool options bar when an artboard is selected.

Show artboard names To show/hide artboard names select View > Show > Artboard Names. Artboard names are automatically truncated to the width of the artboard.



Filter layers by artboard In the Layers panel, from the Search pop-up menu, select Artboard. Select an artboard or any layer within an artboard. The Layers panel view is now restricted to just the selected artboard. To return to the full Layers panel view, either deselect all layers or select something outside the artboard.

Prevent auto-nesting into or out of Artboards Assign the lock in the illustration to an artboard to disallow auto-nesting into and out of the artboard, or to specific layers within an artboard to disallow auto-nesting of those particular layers. To revert to the normal auto-nesting behavior, remove any auto-nesting locks from artboards or layers.

Artboard positional lock Select an artboard and assign the positional lock. The artboard now remains fixed in its position on the canvas, but elements can still be added, moved within, or removed as usual.



Rename Double-click the artboard name in the Layers panel and enter a new name. Alternatively, use the Layer > Rename Artboard command.

Dissolve artboards You can quickly dissolve artboards into their constituent elements. With the artboards selected, select Layer > Ungroup Artboards. The artboards are dissolved and their constituent elements all move a level higher in the Layers panel. If the last remaining artboard in the document is dissolved or ungrouped, the document becomes a non-artboard document.

Export artboards

Export artboards as image assets

You can export artboards as JPEG, GIF, PNG, PNG-8, or SVG image assets directly from the Layers panel.

For more information, see Export artboards, layers, and more.

Export artboards as PDF

You can export artboards as a PDF presentation. Further, you can specify if the presentation should advance pages only on manual intervention or automatically after a defined time interval. Follow these steps:

1. In Photoshop, select File > Export > Artboards To PDF.
2. In the Artboards To PDF dialog, do the following:
   - Choose the destination/location where you want to save the generated PDF presentation.
   - Specify whether you want to export all artboards or only the ones currently selected.
   - Choose whether you want the slideshow to advance pages automatically after a defined time interval (seconds).
   - Choose whether you want the slideshow to loop automatically after the last page.
3. Click Run. Photoshop generates the PDF presentation.

Export artboards as files

You can export artboards as separate files. Follow these steps:

1. In Photoshop, select File > Export > Artboards To Files.
2. In the Artboards To Files dialog, do the following:
   - Choose the destination where you want to save the generated files.
   - Specify the filename.
   - Specify whether you want to export artboard content only or want to include overlapping areas as well.
   - Specify whether you want to export all artboards or only the ones currently selected.
   - Choose the file type you want to export. You have the option to export as BMP, JPEG, PDF, PSD, Targa, TIFF, PNG-8, or PNG-24.
   - Specify the export options for the file type you have selected.
3. Click Run. Photoshop exports the artboards as files.

Device Preview and the Preview CC companion app



Using the Device Preview feature in Photoshop and Preview CC, a companion app, you can quickly preview designs on their target iOS devices. Preview CC connects to Photoshop through a USB port or over Wi-Fi, and renders a live preview of your design. Any changes you make to your design are automatically sent to the device, so that you can preview them.

For documents with artboards, Device Preview attempts to show you the correct artboard by matching the size and position of the artboard with the size of the connected iOS device. You can also use the navigation bar to preview a specific artboard on the device or swipe through artboards in the order in which they're listed in the Photoshop Layers panel.

For more information about Device Preview and Preview CC, see:

- Device Preview
- Adobe Preview CC FAQ

FAQ

Can I add an artboard within an artboard?

No. Artboard nesting is currently not supported.

Is artboard a type of layer?

You can think of artboards as a special type of layer groups. Artboards are listed in the Photoshop Layers panel, just like layers and layer groups.

Can I make artboards out of a standard Photoshop document?

Yes. Use the Convert an existing document into an artboard document.

More Help topics

Photoshop and design

Design with artboards

Export artboards, layers, and more

Using Photoshop, you can export artboards, layers, layer groups, or Photoshop documents as PNG, JPEG, GIF, or SVG image assets.

Export artboards, layers, or documents using Quick Export

Export a Photoshop document or all artboards in it Select File > Export > Quick Export As[image format]. If prompted, choose a destination folder. Photoshop exports the current document as an image asset in the format specified in your Quick Export settings. If your document contains artboards, all artboards in it are exported individually when you select this option.

Export selected layers, layer groups, or artboards In the Layers panel, select the layers, layer groups, or artboards you want to export as image assets. Right-click your selection and select Quick Export As[image format] from the context menu. If prompted, choose a destination folder.

One image asset is generated per layer, layer group, or artboard selected.

Change Quick Export preferences

By default, Quick Export generates assets as PNG with transparency and prompts you every time to select an export location. You can change these settings by selecting either Preferences > Export or File > Export > Export Preferences and then specifying the following:

- Your preferred format for Quick Export: PNG, JPG, PNG-8, GIF, or SVG
- Format-specific parameters. For example, for PNG, you can specify if you want to export assets with Transparency enabled (32-bit) or export smaller-sized images (8-bit).
- Location for images exported using Quick Export. To do so, select one of the following:

Ask Where To Export Each Time: Prompts you to select a location every time you export assets**Export Files To An Assets Folder Next To The Current Document:** Places the image asset in a subfolder named Assets within the folder containing the source Photoshop document.

- Whether you want to include metadata—copyright and contact info—in the exported assets
- Whether you want to convert the assets to the sRGB color space

Export As dialog: Artboards, layers, or documents



Using the Export As dialog, you can fine-tune settings every time you export layers, layer groups, artboards, or Photoshop documents as images.

- Select File > Export > Export As to export the current Photoshop document. If your document contains artboards, all artboards in it are exported through this dialog.
- To bring up this dialog for layers, layer groups, or artboards, select them in the Layers panel. Right-click your selection and select Export As from the context menu. Each selected layer, layer group, or artboard is exported as a separate image asset.

Options in the Export As dialog

You can specify the following options in the Export As dialog:

Format Choose PNG, JPG, GIF, or SVG.

Format-specific setting For PNG, specify whether you want to export assets with Transparency enabled (32-bit) or export smaller-sized images (8-bit). For JPEG, specify the desired image quality (0–100%). GIF images are transparent by default.

While exporting PNG assets, remember the following:

•Selecting Transparency generates 32-bit PNG assets

- Selecting Smaller File generates 8-bit PNG assets

- Leaving the above options deselected generates 24-bit PNG assets

Size Specify the width and height of the image asset. Width and height are locked together by default. Changing the width automatically changes the height proportionately. If you want to specify the canvas bounds of the exported asset, see Canvas Size .

Scale Choose how big the exported image should be. This option is useful for exporting larger- or smaller-resolution assets. Changing the scale impacts the image size.

Resample Choose a resampling method. Resampling refers to changing the amount of image data as you change either the pixel dimensions or the resolution of an image, typically while resizing an image.

Bilinear: Adds pixels by averaging the color values of the surrounding pixels. This method produces medium-quality results.

Bicubic: Slower but more precise method based on an examination of the values of surrounding pixels. Using complex calculations, Bicubic produces smoother tonal gradations than the Bilinear or Nearest Neighbor resampling methods.

Bicubic Smoother: Good for enlarging images based on Bicubic interpolation, but designed to produce smoother results.

Bicubic Sharper: Good for reducing the size of an image based on Bicubic interpolation while enhancing sharpening. This method maintains the detail in a resampled image. If Bicubic Sharper oversharpens some areas of an image, try using Bicubic.

Bicubic Automatic: Automatically chooses the Bicubic sampling method appropriate for the image.

Nearest Neighbor: Fast but less precise method that replicates the pixels in an image. This method is for use with illustrations containing edges that are not anti-aliased. It preserves hard edges and produce a smaller file. However, this method can produce jagged effects, which become apparent when you scale an image or perform multiple manipulations on a selection.

Preserve Details: While resizing the image, this method places primary importance on the preservation of image details and sharpness.

Canvas Size If your asset needs to occupy a certain width and height, specify those values as the Canvas Size. The Export As dialog updates the preview to center the image within those bounds.

This option is useful in several scenarios, such as the following:

- You're exporting icons that have various sizes, but that need to be centered within 50x50 px boxes.
- You're exporting banner images that are smaller or larger than the required dimensions.

If the image is larger than the canvas size, it is clipped to the width and height values set for the canvas.

You can click Reset to revert the values to those set in Image Size.

Metadata Specify whether you want to embed metadata—copyright and contact information—in the exported assets.

Export assets at different sizes

You can export the selected layers, artboards, or documents as assets in multiple sizes using the Export As dialog. Follow these steps:

1. In the left pane, select a relative asset size—for example, 1.25x.
2. Choose a suffix for the asset exported at the relative asset size. For example, @1,25x. Suffixes help you easily manage the exported assets.
3. If necessary, click the + icon to specify more sizes and suffixes for the exported assets.

Note: *The scaling options you choose apply to all of your selected layers or artboards.*

Limitations and common errors

SVG export limitations

- Text may not render as expected. For best fidelity, convert the text layer to a shape before exporting it to SVG.
- Layer masks and clipping masks aren't rendered as expected. Consider using vector masks instead for SVG export.
- The background layer exports as transparent to SVG. Duplicate the background layer in the Layers panel to make it visible in the exported SVG image.

Common errors

Layer is empty

Layers that are empty or are not capable of rendering images cannot be rendered in the Export As dialog. These layers can be clipping masks, adjustment layers, or just layers that have no pixels in them.

Image is outside of the document bounds

The Export operation was unable to render the image, because it bleeds off the canvas. Move the image such that it fits within the canvas.

An unknown error has occurred

To fix this issue, click Done to close the Export As dialog, save the file, and then restart Photoshop.

More Help topics

Export options for design (tutorial video)

\[Legacy] Extract assets in Photoshop

Photoshop export options forum

Device Preview



Get real-time previews of your Photoshop designs on multiple iOS devices with the new Device Preview feature in Photoshop and the Adobe Preview CC mobile app. Changes you make in Photoshop CC are displayed in Preview CC in real time. You can reliably connect multiple iOS devices to Photoshop using USB or over Wi-Fi.

If you have a document with artboards, Device Preview attempts to show you the correct artboard by matching the size and position of the artboard with the size of the connected device. You can also use the navigation bar to preview a specific artboard on the device or swipe through artboards that have matching widths.

Connect Preview CC with Photoshop

Connect multiple iOS devices to Photoshop via USB or over WiFi. Creative Cloud seamlessly pairs your devices with Photoshop.

Wi-Fi



USB



Note: *If you're unable to see a device listed in the Device Preview dialog while connecting it, click Check For Devices.*

Having trouble connecting to your device? See Troubleshooting Device Preview connectivity

Once the connection has been successfully established, the Device Preview panel in Photoshop displays the name of the connected device. Any changes you now make to the design in Photoshop are reflected in the preview on the device.

Note: *While connecting to Photoshop for the first time, Preview CC requires that the Device Preview panel in Photoshop is open. Any subsequent connections don't require this panel to be open.*

Check for devices

If you're unable to see a device listed in the Device Preview dialog while connecting it, click Check For Devices.

Support for artboards

You can swipe to navigate between different artboards and preview them on actual devices. For example, you can preview an iPhone artboard on an iPhone while simultaneously previewing a larger version of that artboard on an iPad, reducing the time required to test designs on multiple screens.

Preview CC automatically selects and displays the appropriate artboard based on the device screen size.

Common questions

Is Preview CC available for Android?

Preview CC is not yet available for Android.

Which version of Photoshop CC does Preview CC work with?

Preview CC works with Photoshop CC 2015, which is available as a free update for Creative Cloud members. You can download Photoshop CC 2015 as an update via the Creative Cloud desktop app. See this Help article to learn how to install or upgrade to Photoshop CC 2015 .

Which devices does Preview CC support?

Preview CC works with iOS devices running iOS 8 or above.

Learn more about Preview CC

Adobe Preview CC FAQ answers several other frequently-asked questions about Preview CC.

Creative Commons Wi-Fi icon courtesy: Canopus49

More Help topics

Photoshop and design

Preview mobile apps and website designs

Copy CSS from layers

Copy CSS generates Cascading Style Sheet (CSS) properties from shape or text layers. The CSS is copied to the clipboard and can be pasted into a style sheet. For shapes it captures values for the following:

- size
- position
- stroke color
- fill color (including gradients)
- drop shadow

For text layers, **Copy CSS** also captures the following values:

- font family
- font size
- font weight
- line height
- underline
- strikethrough
- superscript
- subscript
- text alignment

Copying CSS from a layer group containing shapes or text creates a class for each layer as well as a Group class. The Group class represents a parent div containing child divs that correspond to the layers in the group. The top/left values for the child divs are in relation to the parent div.

Note: *The Copy CSS command does not work with Smart Objects or when selecting multiple shape/text layers that are not grouped.*

1 In the Layers panel, do one of the following:
   - Right-click a shape/text layer or layer group and choose Copy CSS from the context menu.
   - Select a shape/text layer or layer group and choose Copy CSS from the Layers panel menu.
2 Paste the code into your style sheet document.

For more information on creating web pages with Photoshop, see Slice web pages.

Work with web graphics

Note: *For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.*

The Photoshop web tools make it easy to build component pieces for your web pages or to output complete web pages in preset or customized formats.

- Use layers and slices to design web pages and web page interface elements. (See Layers and Slice web pages.)

- Use layer comps to experiment with different page compositions or to export variations of a page. (See Layer comps.)
- Create rollover text or button graphics to import into Dreamweaver or Flash.
- Create web animations with the Animation panel, then export them as animated GIF images or QuickTime files. See Create frame animations.
- Use Adobe Bridge to create a web photo gallery to quickly turn a set of images into an interactive web site, using a variety of professional-looking templates.

For a video on designing web sites with Photoshop and Dreamweaver, see Access Photoshop from Dreamweaver to enhance web image.

Creating rollover images

A *rollover* is a button or image on a web page that changes when the mouse is over it. To create a rollover, you need at least two images: a primary image for the normal state and a secondary image for the changed state.

Photoshop provides a number of useful tools for creating rollover images:

- Use layers to create primary and secondary images. Create content on one layer, then duplicate the layer and edit it to create similar content while maintaining alignment between layers. When creating a rollover effect, you can change the layer's style, visibility or position, make color or tonal adjustments, or apply filter effects. See Duplicate Photoshop layers.
- You can also use layer styles to apply effects, such as color overlays, drop shadows, glow, or emboss, to the primary layer. To create a rollover pair, turn the layer style on or off and save the image in each state. See Layer effects and styles .
- Use preset button styles from the Styles panel to quickly create rollover buttons with normal, mouseover, and mousedown states. Draw a basic shape with the rectangle tool and apply a style, such as Beveled Normal, to automatically turn the rectangle into a button. Then copy the layer and apply other preset styles, like Beveled Mouseover, to create additional button states. Save each layer as a separate image to create a finished rollover button set.
- Use the Save For Web & Devices dialog box to save rollover images in a web-compatible format and with an optimized file size. See Optimizing images.

When you save rollover images, use a naming convention to distinguish the primary (non-rollover state) image from the secondary (rollover state) image.

After creating a rollover image set in Photoshop, use Dreamweaver to place the images on a web page and automatically add the JavaScript code for the rollover action.

Export to Zoomify

You can post high-resolution images on the web that viewers can pan and zoom to see more detail. The basic-size image downloads in the same time as an equivalent size JPEG file. Photoshop exports the JPEG files and HTML file that you can upload to your web server.

1 Choose File > Export > Zoomify and set export options.

Template Sets the background and navigation for the image viewed in the browser.

Output Location Specifies the location and name of the file.

Image Tile Options Specifies the quality of the image.

Browser Options Sets the pixel width and height for the base image in the viewer's browser.

2 Upload the HTML and image files to your web server.

Working with hexadecimal color values

Photoshop can display the hexadecimal values of image colors or copy a color's hexadecimal value for use in an HTML file.

View hexadecimal color values in the Info panel

1 Choose Window > Info or click the Info panel tab to view the panel.

2 Choose Panel Options from the panel menu. Under First Color Readout or Second Color Readout, choose Web Color from the Mode menu and click OK.

3 Position the pointer over the color for which you want to view hexadecimal values.

Copy a color as a hexadecimal value

Photoshop copies colors either as an HTML COLOR attribute containing the hexadecimal value (color=#xxyyzz), or as the hexadecimal value alone.

1 Do one of the following:

- With the Eyedropper tool, move the pointer over the color that you want to copy. Right-click (Windows) or Control-click (Mac OS), and choose Copy Color As HTML or Copy Color's Hex Code.
- Set the foreground color using the Color panel, the Swatches panel, or the Adobe Color Picker. From the Color panel menu, choose Copy Color As HTML or Copy Color's Hex Code.
- In the Save For Web dialog box, click the color swatch or choose Matte > Other. In the Adobe Color Picker, right-click the hexadecimal value, and choose Copy.

2 Open the desired file in an HTML editing application, and choose Edit > Paste.

More Help topics

Choose web-safe colors

Tutorial: Extract PSD assets

Slicing web pages

Modify slice layout

Select one or more slices

Do one of the following:

- Select the Slice Select tool and click the slice in the image. When working with overlapping slices, click the visible section of an underlying slice to select it.
- Select the Slice Select tool, and Shift-click to add slices to the selection.
- Select the Slice Select tool in the Save for Web & Devices dialog box, and click in an auto slice or outside the image area, and drag across the slices you want to select. (Clicking in a user slice and dragging moves the slice.)

- Choose File > Save For Web & Devices. In the dialog box, use the Slice tool to select a slice.

When using either the Slice tool or the Slice Select tool, you can switch from one tool to the other by holding down Ctrl (Windows) or Command (Mac OS).

Move, resize, and snap user slices

You can move and resize user slices in Photoshop, but not in the Save For Web & Devices dialog box.

Move or resize a user slice

1 Select one or more user slices.

2 Do one of the following:

- To move a slice, move the pointer inside the slice selection border, and drag the slice to a new position. Press Shift to restrict movement to a vertical, horizontal, or 45° diagonal line.
- To resize a slice, grab a side or a corner handle of the slice, and drag. If you select and resize adjacent slices, common edges shared by the slices are resized together.

Resize or move a user slice using numeric coordinates

1 Select one or more user slices.

2 Click the Options button in the options bar. You can also double-click a slice to show the options.

3 In the Dimensions area of the Slice Options dialog box, change one or more of the following options:

X Specifies the distance in pixels between the left edge of the slice and the origin of the ruler in the document window.

Y Specifies the distance in pixels between the top edge of the slice and the origin of the ruler in the document window.

Note: *The default origin of the ruler is the upper-left corner of the image.*

W Specifies the width of the slice.

H Specifies the height of the slice.

Snap slices to a guide, user slice, or other object

1 Select the options you want from the View > Snap To submenu.

2 Choose View > Snap. A check mark indicates that the option is turned on.

3 Move your selected slices as desired. The slices snap to any of your chosen objects within 4 pixels.

Divide user slices and auto slices

Use the Divide Slice dialog box to divide slices horizontally, vertically, or both. Divided slices are always user slices, regardless of whether the original is a user slice or an auto slice.

Note: *You cannot divide layer-based slices.*

1 Select one or more slices.

2 With the Slice Select tool , click Divide in the options bar.

3 Select Preview in the Divide Slice dialog box to preview the changes.

4 In the Divide Slice dialog box, select one or both of the following options:

Divide Horizontally Into Divides the slice lengthwise.

Divide Vertically Into Divides the slice widthwise.

5 Define how you want to divide each selected slice:

- Select and enter a value for Slices Down or Slices Across to divide each slice evenly into the specified number of slices.
- Select and enter a value for Pixels Per Slice to create slices with the specified number of pixels. If the slice cannot be divided evenly by that number of pixels, the remainder is made into another slice. For example, if you divide a slice that is 100 pixels wide into three new slices each 30 pixels wide, the remaining 10-pixel-wide area becomes a new slice.

6 Click OK.

Duplicate slices

You can create a duplicate slice with the same dimensions and optimization settings as the original. If the original slice is a linked user slice, the duplicate is linked to the same collection of linked slices. Duplicate slices are always user slices, regardless of whether the original is a user slice, a layer-based slice, or an auto slice.

1 Select a slice or multiple slices.

2 Alt-drag (Windows) or Option-drag (Mac OS) from inside the selection.

Copy and paste a slice

You can copy and paste a selected slice within an image, into another image, or into another application such as Dreamweaver. Copying a slice copies all layers within the bounds of the slice (not just the active layer).

1 Select one or more slices with the Slice Select tool .

2 Choose Edit > Copy.

Note: *A slice can't be copied if there is an active selection in the document (a marquee pixel selection or a selected path).*

3 Do one of the following:

- If you want to paste the slice into another image, open and display that image.
- If pasting into Dreamweaver, make your Dreamweaver document the active window.

4 Choose Edit > Paste. A new layer is created when a slice is pasted into a Photoshop image.

Note: *A slice copied into Dreamweaver retains information about the filename and path of the original Photoshop source file. To view this information in Dreamweaver, right-click (Windows) or Ctrl+click (Mac OS) the image and choose Design Notes, then locate the FilePathSrc field on the All Info tab.*

Combine slices

You can combine two or more slices into a single slice. Photoshop determines the dimensions and position of the resulting slice from the rectangle created by joining the outer edges of the combined slices. If the combined slices are not adjacent or have different proportions or alignments, the newly combined slice may overlap other slices.

The combined slice takes the optimization settings of the first slice in the series of slices you select. A combined slice is always a user slice, regardless of whether the original slices include auto slices.

Note: *You cannot combine layer-based slices.*

1 Select two or more slices.

2 Right-click (Windows) or Ctrl-click (Mac OS) and choose Combine Slices.

Change the stacking order of slices

When slices overlap, the last slice you create is the top slice in the stacking order. You can change the stacking order to gain access to underlying slices. You can specify which slice is on the top and bottom of the stack and move slices up or down in the stacking order.

Note: *You cannot arrange the stacking order of auto slices.*

1 Select a slice or multiple slices.

2 Choose the Slice Select tool , and click a stacking order option in the options bar.



A *Bring To Front* ***B*** *Bring Forward* ***C*** *Send Backward* ***D*** *Send To Back*

Align and distribute user slices

You can align user slices along an edge or their centers, and distribute user slices evenly along the vertical or horizontal axis. By aligning and distributing user slices, you can eliminate unneeded auto slices and generate a smaller, more efficient HTML file.

Note: *To align or distribute layer-based slices, align or distribute the contents of the layers.*

1 Select the user slices you want to align.

2 Choose the Slice Select tool , and select an option in the options bar.



A *Top* ***B*** *Vertical Centers* ***C*** *Bottom* ***D*** *Left* ***E*** *Horizontal Centers* ***F*** *Right*



A *Top* ***B*** *Vertical Centers* ***C*** *Bottom* ***D*** *Left* ***E*** *Horizontal Centers* ***F*** *Right*

Delete a slice

When you delete a user slice or layer-based slice, auto slices are regenerated to fill the document area.

Deleting a layer-based slice does not delete the associated layer; however, deleting the layer associated with a layer-based slice does delete the layer-based slice.

Note: *You cannot delete auto slices. If you delete all user slices and layer-based slices in an image, one auto slice covering the entire image remains.*

1 Select one or more slices.

2 Choose the Slice or Slice Select tool and press the Backspace key or the Delete key.

3 To delete all user slices and layer-based slices, choose View > Clear Slices.

Lock all slices

Locking slices prevents you from resizing, moving, or otherwise changing them accidentally.

? Choose View > Lock Slice.

More Help topics

Work with slices in the Save For Web & Devices dialogbox

Align objects on different layers

HTML options for slices

Display the Slice Options dialog box

Do one of the following:

- Double-click a slice with the Slice Select tool . (If the tool isn't visible, hold down the Crop or Slice tool.)
- With the Slice Select tool active, click the Slice Options button in the options bar. This method is not in the Save For Web & Devices dialog box.

Specify a slice content type

You can specify how the slice data appears in a web browser when exported with an HTML file. The available options vary according to the slice type you select.

- Image slices contain image data. This is the default content type.
- No Image slices let you create empty table cells that can be populated with text or a solid color. You can enter HTML text in a No Image slice. If you set the Text Is HTML option in the Save for Web & Devices dialog box, the text is interpreted as HTML when viewed in a browser. Slices of type No Image aren't exported as images and can be previewed in a browser.

Note: *Setting options for an auto slice promotes the slice to a user slice.*

1 Select a slice. If you are working in Photoshop, double-click the slice with the Slice Select tool to display the Slice Options dialog box.

2 In the Slice Options dialog box, select a slice type from the Type pop-up menu.

Rename a slice

As you add slices to an image, you may find it helpful to rename slices based on their content. By default, user slices are named according to the settings in the Output Settings dialog box. (See Output settings for web graphics.)

? Select a slice and double-click the slice with the Slice Select tool to display the Slice Options dialog box. In the Slice Options dialog box, type a new name in the Name text box.

Note: *The Name text box is not available for No Image slice content.*

Choose a background color for a slice

You can select a background color to fill the transparent area (for Image slices) or entire area (for No Image slices) of the slice.

Photoshop does not display the selected background color—you must preview the image in a browser to view the effect of selecting a background color.

1 Select a slice. If you are working in the Photoshop Save For Web & Devices dialog box, double-click the slice with the Slice Select tool to display the Slice Options dialog box.

2 In the Slice Options dialog box, select a background color from the Background Color pop-up menu. Select None, Matte, White, Black, or Other (using the Adobe Color Picker).

Assign URL link information to an Image slice

Assigning a URL to a slice makes the entire slice area a link in the resulting web page. When a user clicks the link, the web browser navigates to the specified URL and target frame. This option is available only for Image slices.

1 Select a slice. If you are working in Photoshop, double-click the slice with the Slice Select tool to display the Slice Options dialog box.

2 In the Slice Options dialog box, enter a URL in the URL text box. You can enter a relative URL or absolute (full) URL. If you enter an absolute URL, be sure to include the proper protocol (for example, http://www.adobe.com, not www.adobe.com). For more information on using relative and full URLs, see an HTML reference.

3 If desired, enter the name of a target frame in the Target text box:

_blank Displays the linked file in a new window, leaving the original browser window open.

_self Displays the linked file in the same frame as the original file.

_parent Displays the linked file in its own original parent frameset. Use this option if the HTML document contains frames and the current frame is a child. The linked file appears in the current parent frame.

_top Replaces the entire browser window with the linked file, removing all current frames. The name must match a frame name previously defined in the HTML file for the document. When a user clicks the link, the specified file appears in the new frame.

Note: *For more information on frames, see an HTML reference.*

Specify browser messages and Alt text

You can specify what messages appear in the browser. These options are available only for Image slices and appear only in exported HTML files.

1 Select a slice. If you are working in Photoshop, double-click the slice with the Slice Select tool to display the Slice Options dialog box.

2 In the Slice Options dialog box, type the desired text.

Message Text Changes the default message in the browser's status area for a selected slice or slices. By default, the slice's URL, if any, is displayed.

Alt Tag/Alt Specifies an Alt tag for a selected slice or slices. The Alt text appears in place of the slice image in nongraphical browsers. It also appears in place of the image while the image is downloading and as a tool tip in some browsers.

Add HTML text to a slice

When you choose a slice of type No Image, you can enter text to be displayed in the slice area of the resulting web page. This can be plain text or text formatted with standard HTML tags. You can also select vertical and horizontal alignment options. For more information on specific HTML tags, see an HTML reference.

Photoshop does not display HTML text in the document window; you must use a web browser to preview the text. Be sure to preview HTML text in different browsers, with different browser settings, and on different operating systems to confirm that your text is displayed correctly on the web.

Note: *The amount of text in a No Image slice can affect the layout of an exported page.*

1. Select a slice. Double-click the slice with the Slice Select tool to display the Slice Options dialog box. You can double-click the slice in the Save For Web & Devices dialog box to set additional formatting options.
2. In the Slice Options dialog box, select No Image from the Slice Type menu.
3. Type the desired text in the text box.
4. (Save For Web & Devices dialog box only) If the text includes HTML formatting tags, select the Text Is HTML option. If you don't select this option, HTML tags are ignored and all text appears as unformatted plain text on the resulting web page.
5. (Save For Web & Devices dialog box only) If desired, select options in the Cell Alignment section of the dialog box:

   Default Uses the browser's default for horizontal alignment.

   Left Aligns the text to the left side of the slice area.

   Center Aligns the text to the center of the slice area.

   Right Aligns the text to the right side of the slice area.

   Default Uses the browser's default for vertical alignment.

   Top Aligns the text to the top of the slice area.

   Baseline Sets a common baseline for the first line of text in cells in the same row (of the resulting HTML table). Each cell in the row must use the Baseline option.

   Middle Centers the text vertically in the slice area.

   Bottom Aligns the text to the bottom of the slice area.

More Help topics

Preview optimized images in a web browser

Output settings for web graphics

Create web photo galleries

To create web galleries with Photoshop CS5, see Create a web photo gallery in Adobe Bridge Help. To use the older, optional Web Photo Gallery plug-in described in the topics below, first download and install it for Windows or Mac OS.

About web photo galleries

A web photo gallery is a web site that features a home page with thumbnail images and gallery pages with full-size images. Each page contains links that allow visitors to navigate the site. For example, when a visitor clicks a thumbnail image on the home page, the associated full-size image is loaded into a gallery page. You use the Web Photo Gallery command to automatically generate a web photo gallery from a set of images.



Photoshop provides a variety of styles for your gallery, which you can select using the Web Photo Gallery command. If you are an advanced user who knows HTML, you can create a new style or customize a style by editing a set of HTML template files.

Each template for gallery styles comes with different options. If you're using a preset style, some options may be dimmed, or unavailable in that particular style.

Create a web photo gallery

Create web galleries using Adobe Bridge

Adobe Bridge provides updated web gallery features. For instructions, see Create a web photo gallery in Adobe Bridge Help, or view the tutorials below.

Use the older, optional Photoshop plug-in

1 Download and install the older Web Photo Gallery plug-in for Windows or Mac OS.

2 Run Photoshop in 32-bit mode (64-bit Mac OS only) .

3 (Optional) Select the files or folder you want to use in Adobe Bridge.

   Your images will be presented in the order in which they're displayed in Bridge. If you'd rather use a different order, change the order in Bridge.

4 Do one of the following:

   - In Adobe Bridge, choose Tools > Photoshop > Web Photo Gallery.
   - In Photoshop, choose File > Automate > Web Photo Gallery.

5 Choose a style for the gallery from the Styles pop-up menu. A preview of the home page for the chosen style appears in the dialog box.

6 (Optional) Enter an e-mail address as the contact information for the gallery.

7 Choose the source files for your gallery from the Use menu.

Selected Images From Bridge Uses images you selected before opening the Web Photo Gallery dialog box.

Folder Uses images from folders you select using the Browse (Windows) or Choose (Mac OS) buttons. Select Include All Subfolders to include images inside any subfolders of the selected folder.

8 Click Destination, and then select a folder in which to store the images and HTML pages for the gallery. Then click OK (Windows) or Choose (Mac OS).

9 Select formatting options for the web gallery. Choose from the Options menu to display each set of options. See Web photo gallery options.

10 Click OK. Photoshop places the following HTML and JPEG files in your destination folder:

- A home page for your gallery named index.htm or index.html, depending on the Extension options. Open this file in any web browser to preview your gallery.
- JPEG images inside an images subfolder.
- HTML pages inside a pages subfolder.
- JPEG thumbnail images inside a thumbnails subfolder.

Making sure that your colors match

If you work with photos in a wide-gamut color working space such as ProPhoto RGB or Adobe RGB, image colors may change when viewed in a web gallery by a browser that doesn't read embedded color profiles. If this happens, try converting the image profiles to sRGB (which most browsers use as a default) before optimizing them or including them in a Web Photo Gallery. Convert them to sRGB in one of the following ways. It is a good idea to work with a copy of the images.

- To convert a single image, choose Edit >Convert To Profile and then choose sRGB. See Assign or remove a color profile (Illustrator, Photoshop) .
- To convert a folder of images, use the Image Processor. Choose File > Scripts > Image Processor. See Convert files with the Image Processor.

If you use the Image Processor, you can save the files directly to JPEG format in the size that you want them. If you do so, make sure to turn Resize Images off in the Large Image options.

Web photo gallery options

General Options for file extensions, encoding, and metadata.

Extension Uses either .htm or .html as the filename extension.

Use UTF 8 Encoding For URL Uses UTF-8 encoding.

Add Width And Height Attributes For Images Specifies dimensions, shortening download time.

Preserve All Metadata Maintains metadata info.

Banner Text options for the banner that appears on each page in the gallery. Enter text for each of these:

Site Name The name of the gallery.

Photographer The name of the person or organization receiving credit for the photos in the gallery.

Contact Info The contact information for the gallery, such as a telephone number or a business address.

Date The date appearing on each page of the gallery. By default, Photoshop uses the current date.

Font and Font Size (Available for some site styles) Options for the banner text.

Large Images Options for the main images that appear on each gallery page.

Add numeric links (Available for some site styles) Places a numeric sequence (starting at 1, ending with the total number of pages in the gallery) running horizontally at the top of each gallery page. Each number is a link to the respective page.

Resize Images Resizes the source images for placement on the gallery pages. Choose a size from the pop-up menu or enter a size in pixels. For Constrain, choose which dimensions of the image you want to constrain during resizing. For JPEG Quality, choose an option from the pop-up menu, enter a value between 0 and 12, or drag the slider. The higher the value, the better the image quality and the larger the file.

Note: *Photoshop uses the default image interpolation method set in preferences. Choose Bicubic Sharper as the default for best results when reducing image size.*

Border Size Specifies the width, in pixels, of the border around the image.

Titles Use (Available for some site styles) Specifies options for displaying captions under each image. Select Filename to display the filename, or select Description, Credits, Title, and Copyright to display description text drawn from the File Info dialog box.

Font and Font Size (Available for some site styles) Specify the font and size of the caption.

Thumbnails Options for the gallery home page, including the size of the thumbnail images.

Size Specifies the thumbnail size. Choose from the pop-up menu or enter a value in pixels for the width of each thumbnail.

Columns and Rows Specify the number of columns and rows in which to display thumbnails on the home page. This option doesn't apply to galleries that use the Horizontal Frame Style or Vertical Frame Style.

Border Size Specifies the width, in pixels, of the border around each thumbnail.

Titles Use (Available for some site styles) Specifies options for displaying captions under each thumbnail. Select Filename to display the filename, or select Description, Credits, Title, and Copyright to display description text drawn from the File Info dialog box.

Font and Font Size (Available for some site styles) Specify the font and size of the caption.

Custom Colors Options for colors of elements in the gallery. To change the color of an element, click its color swatch and then select a new color from the Adobe Color Picker. You can change the background color of each page (Background option) and of the banner (Banner option).

Security Displays text over each image as a theft deterrent.

Content Specifies the text to be displayed. Select Custom Text to enter customized text. Select Filename, Description, Credits, Title, or Copyright to display text drawn from the File Info dialog box.

Font, Color, and Position Specify the font, color, and alignment of the caption.

Rotate Place the text on the image at an angle.

Web photo gallery styles

To create web galleries with Photoshop CS5, see Create a web photo gallery in Adobe Bridge Help. To use the older, optional Web Photo Gallery plug-in described below, first download and install it for Windows or Mac OS.

Photoshop provides a variety of styles for your web photo gallery. If you are an advanced user who knows HTML, you can create a new style or customize a style by editing a set of HTML template files.

The web photo gallery styles provided by Photoshop are stored in individual folders in the following locations:

Windows Program Files/Adobe/Adobe Photoshop CS5/Presets/Web Photo Gallery.

Mac OS Adobe Photoshop CS5/Presets/Web Photo Gallery.

The name of each folder in this location appears as an option in the Styles menu in the Web Photo Gallery dialog box. Each folder contains the following HTML template files, which Photoshop uses to generate the gallery:

Caption.htm Determines the layout of the caption that appears below each thumbnail on the home page.

FrameSet.htm Determines the layout of the frame set for displaying pages.

IndexPage.htm Determines the layout of the home page.

SubPage.htm Determines the layout of the gallery pages with full-size images.

Thumbnail.htm Determines the layout of the thumbnails that appear on the home page.

Each template file contains HTML code and tokens. A *token* is a text string that is replaced by Photoshop when you set its corresponding option in the Web Photo Gallery dialog box. For example, a template file may contain the following TITLE element that uses a token as its enclosed text:

<TITLE>%TITLE%</TITLE>

When Photoshop generates the gallery using this template file, it replaces the token %TITLE% with the text that you entered for Site Name in the Web Photo Gallery dialog box.

To better understand an existing style, you can open and study its HTML template files using an HTML editor. Because only standard ASCII characters are required to create HTML documents, you can open, edit, and create these documents using a plain-text editor such as Notepad (Windows) or TextEdit (Mac OS).

About customizing web photo gallery styles

You can customize an existing web photo gallery style by editing one or more of its HTML template files. When customizing a style, you need to follow these guidelines so that Photoshop can generate the gallery correctly:

- The style folder must contain these files: Caption.htm, IndexPage.htm, SubPage.htm, Thumbnail.htm, and FrameSet.htm.
- You can rename the style folder but not the HTML template files in the folder.
- You can have an empty Caption.htm file, and place the HTML code and tokens determining the layout of the caption in the Thumbnail.htm file.
- You can replace a token in a template file with the appropriate text or HTML code, so that an option is set through the template file rather than through the Web Photo Gallery dialog box. For example, a template file may contain a BODY element with the following background color attribute that uses a token as its value:

  bgcolor=%BGCOLOR%

  To set the background color of the page to red, you can replace the token %BGCOLOR% with “FF0000.”
- You can add HTML code and tokens to the template files. All tokens must be in uppercase characters, and begin and end with the percent (%) symbol.

Customize or create a web photo gallery style

1 Locate the folder that stores the existing web photo gallery styles.

2 Do one of the following:

- To customize a style, create a copy of the style folder, and store it in the same location as the existing style folders.
- To create a new style, create a new folder for the new style, and store it in the same location as the existing style folders.

The new or customized style (named for its folder) appears in the Styles menu in the Web Photo Gallery dialog box.

3 Using an HTML editor, do one of the following:

- Customize the HTML template file.
- Create the necessary HTML template files and store them inside the style folder.

When creating the template files, make sure that you follow the guidelines for customization outlined in About customizing web photo gallery styles.

Note: *When customizing or creating a template for a gallery style, you should place each of the following tokens on a separate line in the HTML file: %CURRENTINDEX%, %NEXTIMAGE%, %NEXTINDEX%, %PAGE%, %PREVIMAGE%, and %PREVINDEX%. When generating specific pages of a gallery, Photoshop skips lines in a template that contain tokens that don't apply to those pages. For example, when Photoshop generates the first gallery page, it skips any line in the template that contains the %PREVIMAGE% token, which determines the link to the previous gallery page. By keeping the %PREVIMAGE% token on a separate line, you ensure that Photoshop doesn't ignore other tokens in the template.*

Web photo gallery style tokens

Photoshop uses tokens in the HTML template files to define a default web photo gallery style. Photoshop uses these tokens to generate a gallery based on user input in the Web Photo Gallery dialog box.

When customizing or creating a gallery style, you can add any token to any HTML template file, with the exception of %THUMBNAILS% and %THUMBNAILSROWS%, which can appear only in the IndexPage.htm file. When adding a token, keep in mind that you may also need to add HTML code to the file so that the token is used correctly.

You can use the following tokens in the HTML template files:

%ALINK% Determines the color of active links.

%ALT% Determines the name of an image file.

%ANCHOR% Provides the ability to return to the thumbnail of the image the user is viewing, rather than the beginning of the index. This takes effect when the user clicks the Home button.

%BANNERCOLOR% Determines the color of the banner.

%BANNERFONT% Determines the font of the banner text.

%BANNERFONTSIZE% Determines the font size of the banner text.

%BGCOLOR% Determines the background color.

%CAPTIONFONT% Determines the font of the caption below each thumbnail on the home page.

%CAPTIONFONTSIZE% Determines the font size of the caption.

%CAPTIONTITLE% Inserts the document title for a caption from the file information.

%CHARSET% Determines the character set used on each page.

%CONTACTINFO% Determines the contact information for the gallery, such as phone number and location.

%CONTENT_GENRATOR% Expands to "Adobe Photoshop CS5 Web Photo Gallery."

%COPYRIGHT% Inserts the copyright information for a caption from the file information.

%CREDITS% Inserts the credits for a caption from the file information.

%CURRENTINDEX% Determines the link for the current home page.

%CURRENTINDEXANCHOR% Resides in SubPage.htm and points to the first index page.

%DATE% Determines the date that appears on the banner.

%EMAIL% Determines the e-mail address contact information for the gallery.

%FILEINFO% Determines the image file information for a caption.

%FILENAME% Determines the filename of an image. Use this for metadata that appears as HTML text.

%FILENAME_URL% Determines the URL filename of an image. Use this for URL filenames only.

%FIRSTPAGE% Determines the link for the first gallery page that appears in the right frame of a frame set.

%FRAMEINDEX% Determines the link for the home page that appears in the left frame of a frame set.

%HEADER% Determines the title of the gallery.

%IMAGEBORDER% Determines the border size of the full-size image on a gallery page.

%IMAGE_HEIGHT% Enables the Add Width And Height Attributes For Images check box. This allows the user to download the attributes, reducing download time.

%IMAGE_HEIGHT_NUMBER% This token is replaced by a numeral (only) representing the width of the image.

%IMAGEPAGE% Determines the link to a gallery page.

%IMAGE_SIZE% If the Resize Images box is selected, this token contains the image pixel value used in the Large Images panel. If the box is not selected, this token contains an empty string. This is useful for JavaScript in the templates, because it can show the maximum height and width values for all images for the generated site.

%IMAGESRC% Determines the URL for a full-size image on a gallery page.

%IMAGE_WIDTH% Enables the Add Width And Height Attributes For Images check box. This allows the user to download the attributes, reducing download time.

%IMAGE_WIDTH_NUMBER% This token is replaced by a numeral (only) representing the width of the image.

%LINK% Determines the color of links.

%NEXTIMAGE% Determines the link for the next gallery page.

%NEXTIMAGE_CIRCULAR% Sets the link from large preview image to next large preview image.

%NEXTINDEX% Determines the link for the next home page.

%NUMERICLINKS% Inserts numbered links on subpages to all large preview images.

%PAGE% Determines the current page location (for example, page 1 of 3).

%PHOTOGRAPHER% Determines the name of the person or organization receiving credit for the photos in the gallery.

%PREVIMAGE% Determines the link for the previous gallery page.

%PREVINDEX% Determines the link for the previous home page.

%SUBPAGEHEADER% Determines the title of the gallery.

%SUBPAGETITLE% Determines the title of the gallery.

%TEXT% Determines the text color.

%THUMBBORDER% Determines the size of thumbnail borders.

%THUMBNAIL_HEIGHT% Enables the Add Width And Height Attributes For Images check box. This allows the user to download the attributes, reducing download time.

%THUMBNAIL_HEIGHT_NUMBER% This token is replaced with a numeral (only) representing the height of the thumbnail.

%THUMBNAILS% This token is replaced with thumbnails using the Thumbnail.htm file for the frame styles. You must place this token alone in a single, nonbreaking line in the HTML file.

%THUMBNAIL_SIZE% Contains the thumbnail pixel value in the Thumbnails panel. This is useful for JavaScript in the templates, as it can show the maximum height and width values for all thumbnails for the generated site.

%THUMBNAILSRC% Determines the link to a thumbnail.

%THUMBNAILSROWS% This token is replaced with rows of thumbnails using the Thumbnail.htm file for the nonframe styles. You must place this token alone in a single, nonbreaking line in the HTML file.

%THUMBNAIL_WIDTH% Enables the Add Width And Height Attributes For Images check box. This allows the user to download the attributes, reducing download time.

%THUMBNAIL_WIDTH_NUMBER% This token is replaced by a numeral (only) representing the width of the thumbnail.

%TITLE% Determines the title of the gallery.

%VLINK% Determines the color of visited links.

Slice web pages

Slices divide an image into smaller images that are reassembled on a web page using an HTML table or CSS layers. By dividing the image, you can assign different URL links to create page navigation, or optimize each part of an image using its own optimization settings.

You export and optimize a sliced image using the Save For Web & Devices command. Photoshop saves each slice as a separate file and generates the HTML or CSS code needed to display the sliced image.

When you work with slices, keep these basics in mind:

- You can create a slice by using the Slice tool or by creating layer-based slices.

- After you create a slice, you can select it using the Slice Select tool and then move, resize, or align it with other slices.
- You can set options for each slice—such as slice type, name, and URL—in the Slice Options dialog box.
- You can optimize each slice using different optimization settings in the Save For Web & Devices dialog box.

Slice types

Slices are categorized by their content type (Table, Image, No Image) and by the way they are created (user, layer-based, auto).

Slices created with the Slice tool are called *user slices*; slices created from a layer are called *layer-based slices*. When you create a new user slice or layer-based slice, additional *auto slices* are generated to account for the remaining areas of the image. In other words, auto slices fill the space in the image that is not defined by user slices or layer-based slices. Auto slices are regenerated every time you add or edit user slices or layer-based slices. You can convert auto slices to user slices.

User slices, layer-based slices, and auto slices look different—user slices and layer-based slices are defined by a solid line, whereas auto slices are defined by a dotted line. In addition, user slices and layer-based slices display a distinct icon. You can choose to show or hide auto slices, which can make your work with user-slices and layer-based slices easier to view.

A *subslice* is a type of auto slice that is generated when you create overlapping slices. Subslices indicate how the image is divided when you save the optimized file. Although subslices are numbered and display a slice symbol, you cannot select or edit them separately from the underlying slice. Subslices are regenerated every time you arrange the stacking order of slices.

Slices are created using different methods:

- Auto slices are automatically generated.
- User slices are created with the Slice tool.
- Layer-based slices are created with the Layers panel.

Slice a web page

You can use the slice tool to draw slice lines directly on an image, or design your graphic using layers, and then create slices based on the layers.

Create a slice with the Slice tool

1. Select the Slice tool . (Press the C key to cycle through tools grouped with the Crop too.)

   Any existing slices automatically appear in the document window.

2. Choose a style setting in the options bar:

   Normal Determines slice proportions as you drag.

   Fixed Aspect Ratio Sets a height-to-width ratio. Enter whole numbers or decimals for the aspect ratio. For example, to create a slice twice as wide as it is high, enter 2 for the width and 1 for the height.

   Fixed Size Specifies the slice's height and width. Enter pixel values in whole numbers.

3. Drag over the area where you want to create a slice. Shift-drag to constrain the slice to a square. Alt-drag (Windows) or Option-drag (Mac OS) to draw from the center. Use View > Snap To to align a new slice to a guide or another slice in the image. See Move, resize, and snap user slices.

Create slices from guides

1 Add guides to an image.

2 Select the Slice tool, and click Slices From Guides in the options bar.

When you create slices from guides, any existing slices are deleted.

Create a slice from a layer

A layer-based slice encompasses all the pixel data in the layer. If you move the layer or edit the layer's content, the slice area automatically adjusts to include the new pixels.



Layer-based slices are less flexible than user slices; however, you can convert ("promote") a layer-based slice to a user slice. See Convert auto and layer-based slices to user slices.

1 Select a layer in the Layers panel.

2 Choose Layer > New Layer-based Slice.

Don't use a layer-based slice when you plan to move the layer over a large area of the image during an animation, because the slice dimension may exceed a useful size.

Convert auto and layer-based slices to user slices

A layer-based slice is tied to the pixel content of a layer, so the only way to move, combine, divide, resize, and align it is to edit the layer—unless you convert it to a user slice.

All auto slices in an image are linked and share the same optimization settings. If you want to set different optimization settings for an auto slice, you need to promote it to a user slice.

1 Using the Slice Select tool , select one or more slices to convert.

2 Click Promote in the options bar.

You can promote an auto slice in the Save For Web & Devices dialog box by unlinking it. See Work with slices in the Save For Web & Devices dialog box

View slices and slice options

You can view slices in Photoshop and the Save For Web & Devices dialog box. The following characteristics can help you identify and differentiate between slices:

Slice lines Define the boundary of the slice. Solid lines indicate that the slice is a user slice or layer-based slice; dotted lines indicate that the slice is an auto slice.

Slice colors Differentiate user slices and layer-based slices from auto slices. By default, user slices and layer-based slices have blue symbols, and auto slices have gray symbols.

In addition, the Save For Web & Devices dialog box uses color adjustments to dim unselected slices. These adjustments are for display purposes only and do not affect the color of the final image. By default, the color adjustment for auto slices is twice the amount of that for user slices.

Slice numbers Slices are numbered 01 from left to right and top to bottom, beginning in the upper-left corner of the image. If you change the arrangement or total number of slices, slice numbers are updated to reflect the new order.

Slice badges The following *badges*, or icons, indicate certain conditions.

User slice has Image content.

User slice has No Image content.

Slice is layer-based.

Show or hide slice boundaries

? Choose View > Show > Slices. To hide and show slices along with other items, use the Extras command. See Show or hide Extras.

Show or hide auto slices

? Do one of the following:

- Select the Slice Select tool , and click Show Auto Slices or Hide Auto Slices in the options bar.
- Choose View > Show > Slices. Auto slices appear with the rest of your slices.

Show or hide slice numbers

1 Do one of the following:

- In Windows, choose Edit > Preferences > Guides, Grid & Slices.
- In Mac OS, choose Photoshop > Preferences > Guides, Grid & Slices.

2 Under Slices, click Show Slice Numbers.

Change the color of slice lines

1 In Windows, choose Edit > Preferences > Guides, Grid & Slices; in Mac OS, choose Photoshop > Preferences > Guides, Grid & Slices.

2 Under Slice Lines, choose a color from the Line Color menu.

After the color change, selected slice lines are automatically displayed in a contrasting color.

More Help topics

HTML options for slices

Work with slices in the Save For Web & Devices dialogbox

Specify a slice content type

Chapter 5: Image and color basics

Resize images

The Image Size command in Photoshop CC includes a method to preserve details and provide better sharpness while enlarging images.

Original uncropped image *Sharp resized image with details preservation*

In addition, the Photoshop CC Image Size dialog box has been updated for ease of use:

- A window displays the preview image from the resizing parameters.
- Resizing the dialog box resizes the preview window.
- The Scale Styles option is turned on and off from inside the gear menu in the upper right corner of the dialog box.
- From the Dimensions pop-up menu, choose different units of measurement to display the dimensions of the final output.
- Click the link icon to toggle the Constrain Proportions option on and off.

Resize images



1 Choose Image > Image Size.

2 Do any of the following to modify the image preview:

- To change the size of the preview window, drag a corner of the Image Size dialog box and resize it.
- To view a different area of the image, drag within the preview.
- To change the preview magnification, Ctrl-click (Windows) or Command-click (Mac OS) in the preview image to increase magnification. Alt-click (Windows) or Option-click (Mac OS) to reduce the magnification. After clicking, the percentage of magnification briefly appears near the bottom of the preview image.

3 To change the unit of measurement for the pixel dimension, click the triangle next to Dimensions and choose from the menu.

4 To maintain the original ratio of width to height measurement, make sure that the Constrain Proportions option is enabled. If you want to scale the width and height independently of each other, click the Constrain Proportions icon to unlink them.

Note: *You can change the unit of measurement for width and height by choosing from the menus to the right of the Width and Height text boxes.*

5 Do any of the following:

- To change the image size or resolution and allow the total number of pixels to adjust proportionately, make sure that Resample is selected, and if necessary, choose an interpolation method from the Resample menu.
- To change the image size or resolution without changing the total number of pixels in the image, deselect Resample.

6 (Optional) From the Fit To menu:

- Choose a preset to resize the image.
- Choose Auto Resolution to resize the image for a specific printing output. In the Auto Resolution dialog box, specify the Screen value and select a Quality. You can change the unit of measurement by choosing from the menu to the right of the Screen text box.

7 Enter values for Width and Height. To enter values in a different unit of measurement, choose from the menus next to the Width and Height text boxes.

The new image file size appears at the top of the Image Size dialog box, with the old file size in parentheses.

8 To change the Resolution, enter a new value. (Optional) You can also choose a different unit of measurement.

9 If your image has layers with styles applied to them, select Scale Styles from the gear icon to scale the effects in the resized image. This option is available only if you selected the Constrain Proportions option.

10 When you finish setting options, click OK.

To restore the initial values displayed in the Image Size dialog box, either choose Original Size from the Fit To menu, or hold down Alt (Windows) or Option (Mac OS), and click Reset.

Resampling options | Photoshop CC

Automatic Photoshop chooses the resampling method based on the document type and whether the document is scaling up or down.

Preserve Details (enlargement) When this method is chosen, a Noise reduction slider becomes available for smoothing out noise as you upscale the image.

Bicubic Smoother (enlargement) A good method for enlarging images based on Bicubic interpolation but designed to produce smoother results.

Bicubic Sharper (reduction) A good method for reducing the size of an image based on Bicubic interpolation with enhanced sharpening. This method maintains the detail in a resampled image. If Bicubic Sharper oversharpens some areas of an image, try using Bicubic.

Bicubic (smoother gradients) A slower but more precise method based on an examination of the values of surrounding pixels. Using more complex calculations, Bicubic produces smoother tonal gradations than Nearest Neighbor or Bilinear.

Nearest Neighbor (hard edges) A fast but less precise method that replicates the pixels in an image. This method preserves hard edges and produces a smaller file in illustrations containing edges that are not anti-aliased. However, this method can produce jagged effects, which become apparent when you distort or scale an image or perform multiple manipulations on a selection.

Bilinear A method that adds pixels by averaging the color values of surrounding pixels. It produces medium-quality results.

More Help topics

Image size and resolution

Image essentials

Note: *For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.*

About bitmap images

Bitmap images—technically called *raster images*—use a rectangular grid of picture elements (pixels) to represent images. Each pixel is assigned a specific location and color value. When working with bitmap images, you edit pixels rather than objects or shapes. Bitmap images are the most common electronic medium for continuous-tone images, such as photographs or digital paintings, because they can more efficiently represent subtle gradations of shades and color.

Bitmap images are resolution-dependent—that is, they contain a fixed number of pixels. As a result, they can lose detail and appear jagged if they are scaled to high magnifications on-screen or if they are printed at a lower resolution than they were created for.

Bitmap images sometimes require large amounts of storage space, and often need to be compressed to keep file sizes down when used in certain Creative Suite components. For instance, you compress an image file in its original application before you import it into a layout.

Note: *In Adobe Illustrator, you can create bitmap effects in your artwork using effects and graphic styles.*

About vector graphics

Vector graphics (sometimes called vector shapes or vector objects) are made up of lines and curves defined by mathematical objects called vectors, which describe an image according to its geometric characteristics.

You can freely move or modify vector graphics without losing detail or clarity, because they are resolution-independent—they maintain crisp edges when resized, printed to a PostScript printer, saved in a PDF file, or imported into a vector-based graphics application. As a result, vector graphics are the best choice for artwork, such as logos, that will be used at various sizes and in various output media.

The vector objects you create using the drawing and shape tools in Adobe Creative Suite are examples of vector graphics. You can use the Copy and Paste commands to duplicate vector graphics between Creative Suite components.

Combining vector graphics and bitmap images

When combining vector graphics and bitmap images in a document, it's important to remember that how your artwork looks on-screen isn't always how it will look in its final medium (whether commercially printed, printed on a desktop printer, or viewed on the web). The following factors influence the quality of your final artwork:

Transparency Many effects add partially transparent pixels to your artwork. When your artwork contains transparency, Photoshop performs a process called *flattening* before printing or exporting. In most cases, the default flattening process produces excellent results. However, if your artwork contains complex, overlapping areas and you require high-resolution output, you will probably want to preview the effects of flattening.

Image Resolution The number of pixels per inch (ppi) in a bitmap image. Using too low a resolution for a printed image results in *pixelation*—output with large, coarse-looking pixels. Using too high a resolution (pixels smaller than what the output device can produce) increases the file size without increasing the quality of the printed output, and slows the printing of the artwork.

Printer resolution and screen frequency The number of ink dots produced per inch (dpi) and the number of lines per inch (lpi) in a halftone screen. The relationship between image resolution, printer resolution, and screen frequency determines the quality of detail in the printed image.

Color channels

Every Photoshop image has one or more *channels,* each storing information about color elements in the image. The number of default color channels in an image depends on its color mode. By default, images in Bitmap, Grayscale, Duotone, and Indexed Color mode have one channel; RGB and Lab images have three; and CMYK images have four. You can add channels to all image types except Bitmap mode images. For more information, see Color modes.

Channels in color images are actually grayscale images that represent each of the color components of an image. For example, an RGB image has separate channels for red, green, and blues color values.

In addition to color channels, *alpha channels*, can be added to an image for storing and editing selections as masks, and spot color channels can be added to add spot color plates for printing. For more information, see Channel basics.

Bit depth

Bit depth specifies how much color information is available for each pixel in an image. The more bits of information per pixel, the more available colors and more accurate color representation. For example, an image with a bit depth of 1 has pixels with two possible values: black and white. An image with a bit depth of 8 has 2^8, or 256, possible values. Grayscale mode images with a bit depth of 8 have 256 possible gray values.

RGB images are made of three color channels. An 8-bit per pixel RGB image has 256 possible values for each channel which means it has over 16 million possible color values. RGB images with 8-bits per channel (bpc) are sometimes called 24-bit images (8 bits x 3 channels = 24 bits of data for each pixel).

In addition to 8-bpc images, Photoshop can also work with images that contain 16-bpc or 32-bpc. Images with 32-bpc are also known as high dynamic range (HDR) images.

Photoshop support for 16-bit images

Photoshop provides the following support for working with 16-bpc images:

- Working in Grayscale, RGB Color, CMYK Color, Lab Color, and Multichannel modes.
- All tools in the toolbox, except the Art History Brush tool, can be used with 16-bpc images.
- Color and tonal adjustment commands are available
- You can work with layers, including adjustment layers, in 16-bpc images.
- Many Photoshop filters can be used with 16-bpc images.

  To take advantage of certain Photoshop features, such as some filters, you can convert a 16-bpc image to an 8-bpc image. It's best if you do a Save As and convert a copy of the image file so the original file retains the full 16-bpc image data.

Convert between bit depths

? Do any of the following:

- To convert between 8 bpc and 16 bpc, Choose Image > Mode > 16 Bits/Channel or 8 Bits/Channel.
- To convert from 8 bpc or 16 bits to 32 bpc, choose Image > Mode > 32 Bits/Channel.

More Help topics

About masks and alpha channels

About spot colors

About high dynamic range images

Image size and resolution

For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.

Note: *Photoshop CC has an updated Image Size dialog box. See Resizing images for more information.*

About pixel dimensions and printed image resolution

Pixel dimensions measure the total number of pixels along an image's width and height. Resolution is the fineness of detail in a bitmap image and is measured in pixels per inch (ppi). The more pixels per inch, the greater the resolution. Generally, an image with a higher resolution produces a better printed image quality.



Unless an image is resampled (see Resampling), the amount of image data remains constant as you change either the print dimensions or resolution. For example, if you change the resolution of a file, its width and height change accordingly to maintain the same amount of image data.

In Photoshop, you can see the relationship between image size and resolution in the Image Size dialog box (choose Image > Image Size). Deselect Resample Image, because you don't want to change the amount of image data in your photo. Then change width, height, or resolution. As you change one value, the other two values change accordingly. With the Resample Image option selected, you can change the resolution, width, and height of the image to suit your printing or onscreen needs.



A Original dimensions and resolution ***B*** *Decreasing the resolution without changing pixel dimensions (no resampling)* ***C*** *Decreasing the resolution at same document size decreases pixel dimensions (resampling).*

Quickly display the current image size

If you want to quickly display a document's current image size, use the information box at the bottom of the document window.

? Position the pointer over the file information box, and hold down the mouse button.

File size

The file size of an image is the digital size of the image file, measured in kilobytes (K), megabytes (MB), or gigabytes (GB). File size is proportional to the pixel dimensions of the image. Images with more pixels may produce more detail at a given printed size, but they require more disk space to store and may be slower to edit and print. Image resolution thus becomes a compromise between image quality (capturing all the data you need) and file size.

Another factor that affects file size is file format. Because of the varying compression methods used by GIF, JPEG, PNG, and TIFF file formats, file sizes can vary considerably for the same pixel dimensions. Similarly, color bit-depth and the number of layers and channels in an image affect file size.

Photoshop supports a maximum pixel dimension of 300,000 by 300,000 pixels per image. This restriction places limits on the print size and resolution available to an image.

About monitor resolution

Your monitor's resolution is described in pixel dimensions. For example, if your monitor resolution and your photo's pixel dimensions are the same size, the photo will fill the screen when viewed at 100%. How large an image appears on-screen depends on a combination of factors—the pixel dimensions of the image, the monitor size, and the monitor resolution setting. In Photoshop, you can change the image magnification on-screen, so you can easily work with images of any pixel dimensions.



When preparing images for viewing on-screen, you should consider the lowest monitor resolution that your photo is likely to be viewed on.

About printer resolution

Printer resolution is measured in ink dots per inch, also known as dpi. Generally, the more dots per inch, the finer the printed output you'll get. Most inkjet printers have a resolution of approximately 720 to 2880 dpi. (Technically, inkjet printers produce a microscopic spray of ink, not actual dots like imagesetters or laser printers.)

Printer resolution is different from, but related to image resolution. To print a high quality photo on an inkjet printer, an image resolution of at least 220 ppi should provide good results.

Screen frequency is the number of printer dots or halftone cells per inch used to print grayscale images or color separations. Also known as *screen ruling* or *line screen*, screen frequency is measured in lines per inch (lpi)—or lines of cells per inch in a halftone screen. The higher the resolution of the output device, the finer (higher) a screen ruling you can use.

The relationship between image resolution and screen frequency determines the quality of detail in the printed image. To produce a halftone image of the highest quality, you generally use an image resolution that is from 1.5 to at most 2 times the screen frequency. But with some images and output devices, a lower resolution can produce good results. To determine your printer's screen frequency, check your printer documentation or consult your service provider.

Note: *Some imagesetters and 600-dpi laser printers use screening technologies other than halftoning. If you are printing an image on a nonhalftone printer, consult your service provider or your printer documentation for the recommended image resolutions.*

***A** 65 lpi: Coarse screen typically used to print newsletters and grocery coupons **B** 85 lpi: Average screen typically used to print newspapers **C** 133 lpi: High-quality screen typically used to print four-color magazines **D** 177 lpi: Very fine screen typically used for annual reports and images in art books*

Determine a suggested resolution for an image

If you plan to print your image using a halftone screen, the range of suitable image resolutions depends on the screen frequency of your output device. Photoshop can determine a recommended image resolution based on the screen frequency of your output device.

***Note:** If your image resolution is more than 2.5 times the screen ruling, an alert message appears when you try to print the image. This means that the image resolution is higher than necessary for the printer. Save a copy of the file, and then reduce the resolution.*

1. Choose Image > Image Size.
2. Click Auto.
3. For Screen, enter the screen frequency for the output device. If necessary, choose a different unit of measurement. Note that the screen value is used only to calculate the image resolution, not to set the screen for printing.
4. For Quality, select an option:

   Draft Produces a resolution that is the same as the screen frequency (no lower than 72 pixels per inch).

   Good Produces a resolution 1.5 times the screen frequency.

   Best Produces a resolution 2 times the screen frequency.

View the print size onscreen

? Do one of the following:

- Choose View > Print Size.
- Select the Hand tool or Zoom tool, and click Print Size in the options bar.

The image is redisplayed in its approximate printed size, as specified in the Document Size area of the Image Size dialog box. The size and resolution of your monitor affect the on-screen print size.

***Note:** The Print Size command is not available in the Creative Cloud version.*

Resampling

Resampling is changing the amount of image data as you change either the pixel dimensions or the resolution of an image. When you *downsample* (decrease the number of pixels), information is deleted from the image. When you *resample up* (increase the number of pixels, or *upsample*), new pixels are added. You specify an *interpolation* method to determine how pixels are added or deleted.



***A** Downsampled **B** Original **C** Resampled up (selected pixels displayed for each set of images)*

Keep in mind that resampling can result in poorer image quality. For example, when you resample an image to larger pixel dimensions, the image loses some detail and sharpness. Applying the Unsharp Mask filter to a resampled image can help refocus the image details.

You can avoid the need for resampling by scanning or creating the image at a sufficiently high resolution. If you want to preview the effects of changing pixel dimensions on-screen or to print proofs at different resolutions, resample a duplicate of your file.

Photoshop resamples images using an *interpolation method* to assign color values to any new pixels based on the color values of existing pixels. You can choose which method to use in the Image Size dialog box.

Nearest Neighbor A fast but less precise method that replicates the pixels in an image. This method is for use with illustrations containing edges that are not anti-aliased, to preserve hard edges and produce a smaller file. However, this method can produce jagged effects, which become apparent when you distort or scale an image or perform multiple manipulations on a selection.

Bilinear A method that adds pixels by averaging the color values of surrounding pixels. It produces medium-quality results.

Bicubic A slower but more precise method based on an examination of the values of surrounding pixels. Using more complex calculations, Bicubic produces smoother tonal gradations than Nearest Neighbor or Bilinear.

Bicubic Smoother A good method for enlarging images based on Bicubic interpolation but designed to produce smoother results.

Bicubic Sharper A good method for reducing the size of an image based on Bicubic interpolation with enhanced sharpening. This method maintains the detail in a resampled image. If Bicubic Sharper oversharpens some areas of an image, try using Bicubic.

You can specify a default interpolation method to use whenever Photoshop resamples image data. Choose Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS), and then choose a method from the Image Interpolation Methods menu.

Change pixel dimensions of an image

Changing an image's pixel dimensions affects not only its onscreen size but also its image quality and its printed characteristics—either its printed dimensions or its image resolution.

1. Choose Image > Image Size.
2. To maintain the current ratio of pixel width to pixel height, select Constrain Proportions. This option automatically updates the width as you change the height, and vice versa.
3. Under Pixel Dimensions, enter values for Width and Height. To enter values as percentages of the current dimensions, choose Percent as the unit of measurement. The new file size for the image appears at the top of the Image Size dialog box, with the old file size in parentheses.
4. Make sure that Resample Image is selected, and choose an interpolation method.
5. If your image has layers with styles applied to them, select Scale Styles to scale the effects in the resized image. This option is available only if you selected Constrain Proportions.
6. When you finish setting options, click OK.

   For best results when you produce a smaller image, downsample and apply the Unsharp Mask filter. To produce a larger image, rescan the image at a higher resolution.

Change the print dimensions and resolution

When creating an image for print media, it's useful to specify image size in terms of the printed dimensions and the image resolution. These two measurements, referred to as the *document size*, determine the total pixel count and therefore the file size of the image; document size also determines the base size at which an image is placed into another application. You can further manipulate the scale of the printed image using the Print command; however, changes you make using the Print command affect only the printed image, not the document size of the image file.

If you turn on resampling for the image, you can change print dimensions and resolution independently (and change the total number of pixels in the image). If you turn off resampling, you can change either the dimensions or the resolution—Photoshop adjusts the other value automatically to preserve the total pixel count. For the highest print quality, it's generally best to change the dimensions and resolution first, without resampling. Then resample only as necessary.

1. Choose Image > Image Size.
2. Change the print dimensions, image resolution, or both:
   - To change only the print dimensions or only the resolution and adjust the total number of pixels in the image proportionately, select Resample Image and then choose an interpolation method.
   - To change the print dimensions and resolution without changing the total number of pixels in the image, deselect Resample Image.
3. To maintain the current ratio of image width to image height, select Constrain Proportions. This option automatically changes the width as you change the height, and vice versa.

4 Under Document Size, enter new values for the height and width. If desired, choose a new unit of measurement. Note that for Width, the Columns option uses the width and gutter sizes specified in the Units & Rulers preferences.

5 For Resolution, enter a new value. If desired, choose a new unit of measurement.

To restore the initial values displayed in the Image Size dialog box, hold down Alt (Windows) or Option (Mac OS), and click Reset.

What affects file size?

File size depends on the pixel dimensions of an image and the number of layers it contains. Images with more pixels may produce more detail when printed, but they require more disk space to store and may be slower to edit and print. You should keep track of your file sizes to make sure the files are not becoming too large for your purposes. If the file is becoming too large, reduce the number of layers in the image or change the image size.

You can view the file size information for an image at the bottom of the application window.

More Help topics

Advanced cropping, resizing, and resampling

Resizing images

Display file information in the document window

About desktop printing

Preparing images for press

Sharpening recommendations

Position and scale images

Print images

Specify columns for an image

Managing layers

Image information

Acquire images from cameras and scanners

Acquiring digital images from cameras

You can copy images to your computer by connecting your camera or a media card reader to your computer.

- Use the Get Photos From Camera command in Adobe® Bridge® to download photos, and to organize, rename, and apply metadata to them.
- If your camera or the card reader appears as a drive on your computer, copy images directly to your hard disk or into Adobe Bridge.
- Use the software that came with your camera, Windows Image Acquisition (WIA), or Image Capture (Mac OS). For more information on using Windows Image Acquisition or Image Capture, see your computer documentation.

Import images from a digital camera using WIA (Windows only)

Certain digital cameras import images using Windows Image Acquisition (WIA) support. When you use WIA, Photoshop works with Windows and your digital camera or scanner software to import images directly into Photoshop.

1 Choose File > Import > WIA Support.

2 Select a destination in which to save your image files on your computer.

3 Make sure that Open Acquired Images in Photoshop is selected. If you are importing a large number of images, or if you want to edit the images later, deselect Open Acquired Images.

4 To save the imported images directly into a folder whose name is the current date, select Unique Subfolder.

5 Click Start.

6 Select the digital camera from which to import images.

   Note: *If the name of your camera does not appear in the submenu, verify that the software and drivers were properly installed and that the camera is connected.*

7 Choose the image or images you want to import:

   - Click the image from the list of thumbnails to import the image.
   - Hold down Shift and click multiple images to import them at the same time.
   - Click Select All to import all available images.

8 Click Get Picture to import the image.

Importing scanned images

Note: *See TWAIN plug-in for more information about scanning with Photoshop CS6 and later.*

To import scanned images, either open TIFF files saved from separate scanning software, or use a TWAIN or WIA interface directly in Photoshop. In either case, make sure to install the software necessary for your scanner. For installation instructions, see the documentation provided by the scanner manufacturer.

Note: *Scanner drivers are supported by the scanner manufacturer, not Adobe. If you have problems with scanning, make sure that you are using the latest version of the scanner driver and software.*

Import images from a separate scanning application

Most scanners come with software you can run outside of Photoshop, providing identical scanning options and quality. This method avoids issues caused by outdated TWAIN drivers. It can also improve efficiency, letting you edit images in Photoshop while scanning continues in the background.

1 Start the scanning software, and set options as desired. (In Mac OS, you can also use the Image Capture utility.)

2 Save scanned images in TIFF format.

3 In Photoshop, open the saved TIFF files.

Some scanner software lets you designate Photoshop as the external editor for an image after a scanning is completed.

Import images using a TWAIN interface

TWAIN is a cross-platform interface for acquiring images captured by certain scanners, digital cameras, and frame grabbers.

1 Install the TWAIN software provided by the device manufacturer.

2 Download the Photoshop TWAIN plug-in for Windows or Mac OS.

The plug-in supports 32-bit Windows and Mac OS. It also supports 64-bit Mac OS 10.6 if the scanner manufacturer provides 64-bit drivers. (Very few do, so most Mac OS users must run Photoshop in 32-bit mode.)

3 Choose File > Import, and select the device you want to use from the submenu.

Import images using a WIA interface (Windows only)

1 Choose File > Import > WIA Support.

2 Choose a destination on your computer for saving your image files.

3 Click Start.

4 Select Open Acquired Images In Photoshop (unless you have a large number of images to import, or if you want to edit the images at a later time).

5 Select Unique Subfolder if you want to save imported images in a folder named with the current date.

6 Select the scanner that you want to use.

Note: *If the name of your scanner does not appear in the submenu, verify that the software and drivers were properly installed and that the scanner is connected.*

7 Choose the kind of image you want to scan: Color Picture, Grayscale Picture, or Black And White Picture or Text.

To specify custom settings, select Adjust The Quality Of The Scanned Picture.

8 Click Preview. If necessary, drag the handles of the bounding box to adjust the size of the crop.

9 Click Scan.

The scanned image is saved in BMP format.

Create, open, and import images

Create an image

1 Choose File > New.

2 In the New dialog box, type a name for the image.

3 (Optional) Choose a document size from the Document Type menu.

Note: *To create a document with the pixel dimensions set for a specific device, click the Device Central button.*

4 Set the width and height by choosing a preset from the Size menu or entering values in the Width and Height text boxes.

To match the width, height, resolution, color mode, and bit depth of the new image to that of any open image, choose a filename from the bottom section of the Document Type menu.

5 Set the Resolution, Color Mode, and bit depth.

If you've copied a selection to the clipboard, the image dimensions and resolution are automatically based on that image data.

6 Select a Background Contents option:

White Fills the background layer with white, the default background color.

Background Color Fills the background layer with the current background color.

Transparent Makes the first layer transparent, with no color values. The resulting document has a single, transparent layer as its contents.

Other Opens the Color Picker dialog box to select a background color. For more information, see Adobe Color Picker overview.

7 (Optional) If necessary, click the Advanced button to display more options.

8 (Optional) Under Advanced, choose a color profile, or choose Don't Color Manage This Document. For Pixel Aspect Ratio, choose Square unless you're using the image for video. In that case, choose another option to use non-square pixels.

9 When you finish, you can save the settings as a preset by clicking Save Preset, or you can click OK to open the new file.

Duplicate an image

You can duplicate an entire image (including all layers, layer masks, and channels) into available memory without saving to disk.

1 Open the image you want to duplicate.

2 Choose Image > Duplicate.

3 Enter a name for the duplicated image.

4 If you want to duplicate the image and merge the layers, select Duplicate Merged Layers Only. To preserve the layers, make sure this option is deselected.

5 Click OK.

Open files

You can open files using the Open command and Open Recent command. You can also open files into Photoshop from Adobe Bridge or Adobe Photoshop Lightroom.

When opening certain files, such as camera raw and PDF, you specify settings and options in a dialog box before the files completely open in Photoshop.

In addition to still images, Photoshop users can open and edit 3D files, video and image sequence files. For more information, see Importing video files and image sequences .

Note: *Photoshop uses plug-in modules to open and import many file formats. If a file format does not appear in the Open dialog box or in the File > Import submenu, you may need to install the format's plug-in module.*

Sometimes Photoshop may not be able to determine the correct format for a file. This can happen, for example, because the file has been transferred between two operating systems. Sometimes a transfer between Mac OS and Windows can cause the file format to be mislabeled. In such cases, you must specify the correct format in which to open the file.

You can retain (where possible) layers, masks, transparency, compound shapes, slices, image maps, and editable type when bringing your Illustrator art into Photoshop. In Illustrator, export the art in the Photoshop (PSD) file format. If your Illustrator art contains elements that Photoshop doesn't support, the appearance of the artwork is preserved, but the layers are merged and the artwork is rasterized.

Open a file using the Open command

1 Choose File > Open.

2 Select the name of the file you want to open. If the file does not appear, select the option for showing all files from the Files Of Type (Windows) or Enable (Mac OS) pop-up menu.

3 Click Open. In some cases, a dialog box appears, letting you set format-specific options.

Note: *If a color profile warning message appears, specify whether to use embedded profile as the working space, convert the document color to working space, or reverse the embedded profile. For more information, see Color-managing imported images.*

Open a recently used file

? Choose File > Open Recent, and select a file from the submenu.

Note: *To specify the number of files listed in the Open Recent menu, change the Recent File List Contains option in the File Handling preferences. Choose Edit > Preferences > File Handling (Windows), or Photoshop > Preferences > File Handling (Mac OS).*

Specify the file format in which to open a file

If a file was saved with an extension that doesn't match its true format (for example, a PSD file saved with a .gif extension), or has no extension, Photoshop may not be able to open the file. Selecting the correct format will allow Photoshop to recognize and open the file.

? Do one of the following:

- (Windows) Choose File > Open As, and select the file you want to open. Then choose the desired format from the Open As pop-up menu, and click Open.
- (Mac OS) Choose File > Open, and choose All Documents from the Show pop-up menu. Then select the file you want to open, choose the desired file format from the Format pop-up menu, and click Open.

Note: *If the file does not open, then the chosen format may not match the file's true format, or the file may be damaged.*

Open PDF files

Adobe Portable Document Format (PDF) is a versatile file format that can represent both vector and bitmap data. It has electronic document search and navigation features. PDF is the primary format for Adobe Illustrator and Adobe Acrobat.

Some PDF files contain a single image, and others contain multiple pages and images. When you open a PDF file in Photoshop, you can choose which pages or images to open and specify rasterization options.

You can also import PDF data using the Place command, the Paste command, and the drag-and-drop feature. The page or image is placed on a separate layer as a Smart Object.

Note: *The following procedure is only for opening generic PDF files in Photoshop. You don't need to specify options in the Import PDF dialog box when opening Photoshop PDF files.*

1 Do one of the following:

- (Photoshop) Choose File > Open.

- (Bridge) Select the PDF file and choose File > Open With > Adobe Photoshop. Skip to step 3.

2 In the Open dialog box, select the name of the file, and click Open.

3 Under Select in the Import PDF dialog box, select Pages or Images, depending on what elements of the PDF document you want to import.

4 Click the thumbnails to select the pages or images you want to open. Shift-click to select more than one page or image. The number of selected items appears under the preview window. If you're importing images, skip to step 8.

Note: Use the Thumbnail Size menu to adjust the thumbnail view in the preview window. The Fit Page option fits one thumbnail in the preview window. A scroll bar appears if there are multiple items.

5 To give the new document a name, type it in the Name text box. If you're importing more than one page or image, multiple documents open with the base name followed by a number.

6 Under Page Options, choose from the Crop To menu to specify what part of the PDF document to include:

Bounding Box Crops to the smallest rectangular region that includes all the text and graphics of the page. This option eliminates extraneous white space and any document elements outside the Trim Box.

Note: Bounding Box will not crop white space that is part of a background created by the source application.

Media Box Crops to the original size of the page.

Crop Box Crops to the clipping region (crop margins) of the PDF file.

Bleed Box Crops to the region specified in the PDF file for accommodating limitations inherent in production processes such as cutting, folding, and trimming.

Trim Box Crops to the region specified for the intended finished size of the page.

Art Box Crops to the region specified in the PDF file for placing the PDF data into another application.

7 Under Image Size, enter values (if necessary) for Width and Height:

- To preserve the aspect ratio of the pages as they're scaled to fit within the rectangle defined by the Width and Height values, select Constrain Proportions.
- To scale the pages exactly to the Width and Height values, deselect Constrain Proportions. Some distortion might occur when the pages are scaled.

When more than one page is selected, the Width and Height text boxes display the maximum width and height values of the selected pages. All pages are rendered at their original size if Constrain Proportions is selected and you don't change the Width and Height values. Changing the values will scale all pages proportionately as they're rasterized.

8 Specify the following options under Image Size:

Resolution Sets the resolution for the new document. See also About pixel dimensions and printed image resolution.

Mode Sets the color mode for the new document. See also Color modes.

Bit Depth Sets the bit depth for the new document. See also Bit depth.

The Width and Height values plus the Resolution determine the final pixel dimension of resulting document.

9 To suppress color profile warnings, select Suppress Warning.

10 Click OK.

Open an EPS file

Encapsulated PostScript (EPS) can represent both vector and bitmap data and is supported by virtually all graphic, illustration, and page-layout programs. The Adobe application that primarily produces PostScript artwork is Adobe Illustrator. When you open an EPS file containing vector art, it is *rasterized*—the mathematically defined lines and curves of the vector artwork are converted into the pixels or bits of a bitmap image.

You can also bring PostScript artwork into Photoshop using the Place command, the Paste command, and the drag-and-drop feature.

1 Choose File > Open.
2 Select the file you want to open, and click Open.
3 Indicate the desired dimensions, resolution, and mode. To maintain the same height-to-width ratio, select Constrain Proportions.
4 To minimize jagged lines at the edges of artwork, select Anti-aliased.

More Help topics

Adobe Bridge

Mini Bridge

Color modes

About creating images for video

About foreground and background colors

About plug-in modules

Processing images with Camera Raw

PDF

Understand Smart Objects

Place files

Copy and paste between applications

Viewing images

Change the screen mode

You can use the screen mode options to view images on your entire screen. You can show or hide the menu bar, title bar, and scroll bars.

Press the F key to quickly cycle through screen modes.

? Do one of the following:

- To display the default mode (menu bar at the top and scroll bars on the side), choose View > Screen Mode > Standard Screen Mode. Or, click the Screen Mode button in the Application bar, and select Standard Screen Mode from the pop-up menu.
- To display a full-screen window with a menu bar and a 50% gray background, but no title bar or scroll bars, choose View > Screen Mode > Full Screen Mode With Menu Bar. Or, click the Screen Mode button in the Application bar, and select Full Screen Mode With Menu Bar from the pop-up menu.
- To display a full-screen window with only a black background (no title bar, menu bar, or scroll bars), choose View > Screen Mode > Full Screen Mode. Or, click the Screen Mode button in the Application bar, and select Full Screen Mode from the pop-up menu.

View another area of an image

? Do one of the following:

- Use the window scroll bars.
- Select the Hand tool and drag to pan over the image. To use the Hand tool while another tool is selected, hold down the spacebar as you drag in the image.

If your computer has OpenGL, you can use the Hand tool to flick the image in the direction you want to view. After a quick mouse gesture, the image will move as if you were continuously dragging. Enable this feature by choosing Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS) and then select Enable Flick Panning.



- Drag the colored box (proxy view area) in the Navigator panel.

Use the Rotate View tool

You use the Rotate View tool to rotate the canvas non-destructively; it does not transform the image. Rotating the canvas can be useful for any number of reasons, including facilitating easier painting or drawing. (OpenGL is required.)

You can also use rotate gestures on MacBook computers with multi-touch trackpads.

1 In the toolbox, select the Rotate View tool . (If the tool isn't visible, hold down the Hand tool.)

2 Do any of the following:

- Drag in the image. A compass will indicate north in the image, regardless of the current canvas angle.

- In the options bar, enter degrees in the Rotation Angle field.
- Click or drag the circular Set Angle of Rotation control.

3 To restore the canvas to the original angle, click Reset View.

For a video on the Rotate View tool and other workspace tips, see www.adobe.com/go/lrvid4001_ps. (Discussion of the Rotate View tool begins at the 5:10 mark.)

Disable trackpad gestures (Mac OS)

If you have a MacBook computer with a multi-touch trackpad, you can use the trackpad to flick, rotate, or zoom images. This functionality can greatly increase your efficiency, but you can disable it if inadvertent changes occur.

1 Choose Photoshop > Preferences > Interface (Mac OS).

2 In the General section, deselect Enable Gestures.

Use the Navigator panel

You use the Navigator panel to quickly change the view of your artwork using a thumbnail display. The colored box in the Navigator (called the *proxy view area*) corresponds to the currently viewable area in the window.

? Do one or more of the following:

- To display the Navigator panel, select Window > Navigator.
- To change the magnification, type a value in the text box, click the Zoom Out or Zoom In button, or drag the zoom slider.
- To move the view of an image, drag the proxy view area in the image thumbnail. You can also click the image thumbnail to designate the viewable area.

  ***Tip**: To simultaneously set the size and position of the proxy area, Control-drag (Windows) or Command-drag (Mac OS) in the image thumbnail.*

- To change the color of the proxy view area, select Panel Options from the panel menu. Select a preset color from the Color pop-up menu, or click the color box to choose a custom color.



***A** Panel menu button **B** Thumbnail display of artwork **C** Proxy preview area **D** Zoom text box **E** Zoom Outbutton **F** Zoom slider **G** Zoom Inbutton*

Zoom in or out

Use the Zoom tool or the View menu commands to zoom in or zoom out of an image. When you use the Zoom tool, each click magnifies or reduces the image to the next preset percentage and centers the display around the point you click. When the image has reached its maximum magnification level of 3200% or minimum size of 1 pixel, the magnifying glass appears empty.

To view images most accurately, precisely revealing sharpening, layer effects, and other adjustments, see Display images at 100%.

Set Zoom tool preferences

1 Choose Edit > Preferences > Performance (Windows) or Photoshop > Preferences > Performance (Mac OS). In the GPU Settings section, select Enable OpenGL Drawing.

Note: *Some Zoom tool preferences require OpenGL. If Enable OpenGL Drawing is unavailable, your video card does not support this technology.*

2 In the General preferences, select any of the following:

Animated Zoom Enables continuous zooming while holding down the Zoom tool

Zoom Resizes Windows See Automatically resize the window when zooming.

Zoom With Scroll Wheel Enables zooming with the scroll wheel on your mouse.

Zoom Clicked Point To Center Centers the zoom view on the clicked location.

Zoom a preset amount

? Do any of the following:

- Select the Zoom tool , and click either the Zoom In orZoom Out button in the options bar. Then, click the area you want to zoom in or out.

  Tip*: To quickly switch to zoom out mode, hold down Alt (Windows) or Option (Mac OS).*

- Choose View > Zoom In or View >Zoom Out. The Zoom In or Zoom Out command becomes unavailable when the maximum image magnification or reduction is reached.
- Set the zoom level at the lower left corner of the document window or in the Navigator panel.

Display images at 100%

A zoom setting of 100% provides the most accurate view, because each image pixel is displayed by one monitor pixel. (At other zoom settings, image pixels are interpolated to a different amount of monitor pixels.)

? Do one of the following:

- Double-click the Zoom tool in the toolbox.
- (Creative Cloud) Choose View > 100% or, click 100% in either the Zoom tool or Hand tool options bar.
- Choose View > Actual Pixels or, click Actual Pixels in either the Zoom tool or Hand tool options bar.
- Enter 100% in the Status Bar and press Enter (Windows) or Return (Mac OS).

The 100% view of an image displays an image as it will appear in a web browser (at the current monitor resolution).

Zoom continuously

To zoom continuously, your video card must support OpenGL, and Animated Zoom must be selected in the General preferences.

? Select the Zoom tool, and then do any of the following:

- Click and hold in the image to zoom in. Press Alt (Windows) or Option (Mac OS) to zoom out.
- In the options bar, select Scrubby Zoom. Then drag to the left in the image to zoom out, or to the right to zoom in.

Magnify a specific area

1 Select the Zoom tool.

2 Drag over the part of the image that you want to magnify.



The area inside the zoom marquee is displayed at the highest possible magnification. To move the marquee around the artwork in Photoshop, begin dragging a marquee and then hold down the spacebar.

Temporarily zoom an image

1 Hold down the H key, and then click in the image and hold down the mouse button.

The current tool changes to the Hand tool, and the image magnification changes as follows:

- If the entire image originally fit within the document window, the image zooms in to fit the window.
- If only a portion of the image was originally visible, the image zooms out. Drag the zoom marquee to magnify a different part of the image.

2 Release the mouse button and then the H key.

The image returns to the previous magnification and tool.

Automatically resize the window when zooming

? With the Zoom tool active, select Resize Windows To Fit in the options bar. The window is resized when you magnify or reduce the view of the image.

When Resize Windows To Fit is deselected (the default), the window maintains a constant size regardless of the image magnification. This can be helpful when using smaller monitors or working with tiled views.

Note: *To automatically resize the window when using keyboard shortcuts for zooming, choose Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS). Then select the Zoom Resizes Windows.*

Fit an image to the screen

? Do one of the following:

- Double-click the Hand tool in the toolbox.
- Choose View > Fit On Screen.
- Select a zoom tool or the Hand tool, and click the Fit On Screen button in the options bar.

  These options scale both the zoom level and the window size to fit the available screen space.

Hide the pixel grid

Over 500% magnification, the image's pixel grid becomes visible by default. To hide the grid, do the following.

? Choose View > Show, and deselect Pixel Grid.

More Help topics

Viewing multiple images

Match zoom and location in multiple images

Color modes

Different color modes:

1 RGB mode (millions of colors)

2 CMYK mode (four-printed colors)

3 Index mode (256 colors)

4 Grayscale mode (256 grays)

5 Bitmap mode (2 colors)

The color mode or image mode determines how colors combine based on the number of channels in a color model. Different color modes result in different levels of color detail and file size. For instance, use CMYK color mode for images in a full-color print brochure, and use RGB color mode for images in web or e-mail to reduce file size while maintaining color integrity.

RGB Color mode

Photoshop RGB Color mode uses the RGB model, assigning an intensity value to each pixel. In 8-bits-per-channel images, the intensity values range from 0 (black) to 255 (white) for each of the RGB (red, green, blue) components in a color image. For example, a bright red color has an R value of 246, a G value of 20, and a B value of 50. When the values of all three components are equal, the result is a shade of neutral gray. When the values of all components are 255, the result is pure white; when the values are 0, pure black.

RGB images use three colors, or *channels*, to reproduce colors on screen. In 8-bits-per-channel images, the three channels translate to 24 (8 bits x 3 channels) bits of color information per pixel. With 24-bit images, the three channels can reproduce up to 16.7 million colors per pixel. With 48-bit (16-bits-per-channel) and 96-bit (32-bits-per-channel) images, even more colors can be reproduced per pixel. In addition to being the default mode for new Photoshop images, the RGB model is used by computer monitors to display colors. This means that when working in color modes other than RGB, such as CMYK, Photoshop converts the CMYK image to RGB for display on screen.

Although RGB is a standard color model, the exact range of colors represented can vary, depending on the application or display device. The RGB Color mode in Photoshop varies according to the working space setting that you specify in the Color Settings dialog box.

CMYK Color mode

In the CMYK mode, each pixel is assigned a percentage value for each of the process inks. The lightest (highlight) colors are assigned small percentages of process ink colors; the darker (shadow) colors higher percentages. For example, a bright red might contain 2% cyan, 93% magenta, 90% yellow, and 0% black. In CMYK images, pure white is generated when all four components have values of 0%.

Use the CMYK mode when preparing an image to be printed using process colors. Converting an RGB image into CMYK creates a *color separation*. If you start with an RGB image, it's best to edit first in RGB and then convert to CMYK at the end of your editing process. In RGB mode, you can use the Proof Setup commands to simulate the effects of a CMYK conversion without changing the actual image data. You can also use CMYK mode to work directly with CMYK images scanned or imported from high-end systems.

Although CMYK is a standard color model, the exact range of colors represented can vary, depending on the press and printing conditions. The CMYK Color mode in Photoshop varies according to the working space setting that you specify in the Color Settings dialog box.

Lab Color mode

The CIE L*a*b* color model (Lab) is based on the human perception of color. The numeric values in Lab describe all the colors that a person with normal vision sees. Because Lab describes how a color looks rather than how much of a particular colorant is needed for a device (such as a monitor, desktop printer, or digital camera) to produce colors, Lab is considered to be a *device-independent* color model. Color management systems use Lab as a color reference to predictably transform a color from one color space to another color space.

The Lab Color mode has a lightness component (L) that can range from 0 to 100. In the Adobe Color Picker and Color panel, the *a* component (green-red axis) and the *b* component (blue-yellow axis) can range from +127 to –128.

Lab images can be saved in Photoshop, Photoshop EPS, Large Document Format (PSB), Photoshop PDF, Photoshop Raw, TIFF, Photoshop DCS 1.0, or Photoshop DCS 2.0 formats. You can save 48-bit (16-bits-per-channel) Lab images in Photoshop, Large Document Format (PSB), Photoshop PDF, Photoshop Raw, or TIFF formats.

Note: *The DCS 1.0 and DCS 2.0 formats convert the file to CMYK when opened.*

Grayscale mode

Grayscale mode uses different shades of gray in an image. In 8-bit images, there can be up to 256 shades of gray. Every pixel of a grayscale image has a brightness value ranging from 0 (black) to 255 (white). In 16-and 32-bit images, the number of shades in an image is much greater than in 8-bit images.

Grayscale values can also be measured as percentages of black ink coverage (0% is equal to white, 100% to black).

Grayscale mode uses the range defined by the working space setting that you specify in the Color Settings dialog box.

Bitmap mode

Bitmap mode uses one of two color values (black or white) to represent the pixels in an image. Images in Bitmap mode are called bitmapped 1-bit images because they have a bit depth of 1.

Duotone mode

Duotone mode creates monotone, duotone (two-color), tritone (three-color), and quadtone (four-color) grayscale images using one to four custom inks.

Indexed Color mode

Indexed Color mode produces 8-bit image files with up to 256 colors. When converting to indexed color, Photoshop builds a *color lookup table (CLUT)*, which stores and indexes the colors in the image. If a color in the original image does not appear in the table, the program chooses the closest one or uses *dithering* to simulate the color using available colors.

Although its palette of colors is limited, indexed color can reduce file size yet maintain the visual quality needed for multimedia presentations, web pages, and the like. Limited editing is available in this mode. For extensive editing, you should convert temporarily to RGB mode. Indexed color files can be saved in Photoshop, BMP, DICOM (Digital Imaging and Communications in Medicine), GIF, Photoshop EPS, Large Document Format (PSB), PCX, Photoshop PDF, Photoshop Raw, Photoshop 2.0, PICT, PNG, Targa®, or TIFF formats.

Multichannel mode

Multichannel mode images contain 256 levels of gray in each channel and are useful for specialized printing. Multichannel mode images can be saved in Photoshop, Large Document Format (PSB), Photoshop 2.0, Photoshop Raw, or Photoshop DCS 2.0 formats.

These guidelines apply when converting images to Multichannel mode:

- Layers are unsupported and therefore flattened.
- Color channels in the original image become spot color channels in the converted image.
- Converting a CMYK image to Multichannel mode creates cyan, magenta, yellow, and black spot channels.
- Converting an RGB image to Multichannel mode creates cyan, magenta, and yellow spot channels.
- Deleting a channel from an RGB, CMYK, or Lab image automatically converts the image to Multichannel mode, flattening layers.
- To export a multichannel image, save it in Photoshop DCS 2.0 format.

Note: *Indexed Color and 32-bit images cannot be converted to Multichannel mode.*

More Help topics

About color working spaces

Soft-proof colors

About duotones

Match, replace, and mix colors

Match colors

Match the color in different images

The Match Color command matches colors between multiple images, between multiple layers, or between multiple selections. It also lets you adjust the colors in an image by changing the luminance, changing the color range, and neutralizing a color cast. The Match Color command works only in RGB mode.

When you use the Match Color command, the pointer becomes the Eyedropper tool. Use the Eyedropper tool while adjusting the image to view the color pixel values in the Info panel. This panel gives you feedback about changes in color values as you use the Match Color command. See View color values in an image.

The Match Color command matches the colors in one image (the source image) with colors in another image (the target image). Match Color is useful when you're trying to make the colors in different photos consistent, or when certain colors (such as skin tones) in one image must match the colors in another image.

In addition to matching the color between two images, the Match Color command can match the color between different layers in the same image.

Match the color between two images

1 (Optional) Make a selection in the source and target images.

   If you don't make a selection, then the Match Color command matches the overall image statistics between images.

2 Make the image that you want to change active, and then choose Image > Adjustments > Match Color.

   If you're applying the Match Color command to a specific layer in the target image, make sure that layer is active when you choose the Match Color command.

3 From the Source menu in the Image Statistics area of the Match Color dialog box, choose the source image whose colors you'll be matching in the target image. Choose None when you don't want to reference a different image to calculate the color adjustment. With None chosen, the target image and the source image are the same.

   If necessary, use the Layer menu to choose the layer from the source image whose colors you want to match. You can also choose Merged from the Layer menu to match the colors from all the layers in the source image.

4 If you made a selection in the image, do one or more of the following:

   - In the Destination Image area, select Ignore Selection When Applying Adjustment if you're applying the adjustment to the entire target image. This option ignores the selection in the target image and applies the adjustment to the entire target image.

- In the Image Statistics area, select Use Selection In Source To Calculate Colors if you made a selection in the source image and want to use the colors in the selection to compute the adjustment. Deselect this option to ignore the selection in the source image, and use the colors from the entire source image to compute the adjustment.
- In the Image Statistics area, select Use Selection In Target To Calculate Adjustment if you made a selection in the target image and want to use the colors in the selection to calculate the adjustment. Deselect this option to ignore the selection in the target image and compute the adjustment by using the colors of the entire target image.

5 To automatically remove a color cast in the target image, select the Neutralize option. Make sure that the Preview option is selected so that your image is updated as you make adjustments.

6 To increase or decrease the brightness in the target image, move the Luminance slider. Alternatively, enter a value in the Luminance box. The maximum value is 200, the minimum is 1, and the default is 100.

7 To adjust the color saturation in the target image, adjust the Color Intensity slider. Alternatively, enter a value in the Color Intensity box. The maximum value is 200, the minimum is 1 (which produces a grayscale image), and the default is 100.

8 To control the amount of adjustment applied to the image, move the Fade slider. Moving the slider to the right reduces the adjustment.

9 Click OK.

Match the color of two layers in the same image

1 (Optional) Make a selection in the layer you want to match. Use this method when matching a color region (for example, facial skin tones) in one layer with a region in another.

If you don't make a selection, then the Match Color matches the colors of the entire source layer.

2 Make sure that the layer you want to target (apply the color adjustment to) is active, and then choose Image > Adjustments > Match Color.

3 From the Source menu in the Image Statistics area of the Match Color dialog box, make sure that the image in the Source menu is the same as the target image.

4 Use the Layer menu to choose the layer whose colors you want to match. You can also choose Merged from the Layer menu to match the colors from all the layers.

5 If you made a selection in the image, do one or more of the following:

- In the Destination Image area, select Ignore Selection When Applying Adjustment if you're applying the adjustment to the entire target layer. This option ignores the selection in the target layer and applies the adjustment to the entire target layer.
- In the Image Statistics area, select Use Selection In Source To Calculate Colors if you made a selection in the source image and want to use the color in the selection to compute the adjustment. Deselect this option to ignore the selection in the source layer and use the colors in the entire source layer to compute the adjustment.
- In the Image Statistics area, select Use Selection In Target To Calculate Adjustment if you want to use only the colors in the selected area of the target layer to compute the adjustment. Deselect this option to ignore the selection and use the colors of the entire target layer to compute the adjustment.

6 To automatically remove a color cast in the target layer, select the Neutralize option. Make sure that the Preview option is selected so that your image is updated as you make adjustments.

7 To increase or decrease the brightness in the target layer, move the Luminance slider. Alternatively, enter a value in the Luminance box. The maximum value is 200, the minimum is 1, and the default is 100.

8 To adjust the range of color pixel values in the target layer, adjust the Color Intensity slider. Alternatively, enter a value in the Color Intensity box. The maximum value is 200, the minimum is 1 (which produces a grayscale image), and the default is 100.

9 To control the amount of adjustment applied to the image, adjust the Fade slider. Moving the slider to the right reduces the amount of adjustment.

10 Click OK.

Save and apply settings in the Match Color command

- In the Image Statistics area of the Match Color dialog box, click the Save Statistics button. Name and save the settings.
- In the Image Statistics area of the Match Color dialog box, click the Load Statistics button. Locate and load the saved settings file.

Replace colors

Replace the color of objects in an image

Photoshop provides several techniques that let you replace the colors of objects. For great flexibility and results, apply a Hue/Saturation adjustment to selected objects. For less flexibility but a convenient grouping of options, use the Replace Color dialog box. For speed but less precision, try the Color Replacement tool.

Apply a Hue/Saturation adjustment to selected objects

In most cases, this flexible technique best replaces colors. Because masks and adjustment layers are non-destructive, you can later fine-tune the results with complete freedom. A unique Colorize option makes absolute, rather than relative, color changes (avoiding tinting from original colors).

1 Select the object you want to change. The Quick Selection tool often produces good results. For additional techniques, see Select a color range in an imageand Refine selection edges.

2 In the Adjustments panel, click the Hue/Saturation icon.

The selection becomes a mask on the adjustment layer.

3 In the Properties panel, change Hue and Saturation settings to replace the object's color. If the original color tints the new color, select Colorize, and readjust settings. (See Adjust hue and saturation .)

Leave the Lightness setting at zero to maintain contrast. To maintain both contrast and saturation, select the Hue blending mode for the adjustment layer.

4 If necessary, enlarge or reduce the affected area by painting on the mask with white or black. (See Edit layer masks.)

For more information, see Adjustments panel overview.

Use the Replace Color dialog box

The Replace Color dialog box combines tools for selecting a color range with HSL sliders for replacing that color. You can also choose the replacement color in the Color Picker.

Replace Color lacks the Colorize option from the Hue/Saturation adjustment, which may be needed for a complete color change. You may also find the adjustment layer technique easier for changing specific objects. However, the Replace Color command is good for global color changes—especially changing out-of-gamut colors for printing.

1 Choose Image > Adjustments > Replace Color.

2 (Optional) If you are selecting similar, contiguuous colors in the image, select Localized Color Clusters to build a more accurate mask.

3 Select a preview option:

Selection Displays the mask in the preview box. Masked areas are black, and unmasked areas are white. Partially masked areas (areas covered with a semitransparent mask) appear as varying levels of gray according to their opacity.

Image Displays the image in the preview box. This option is useful when you are working with a magnified image or have limited screen space.

4 To select the colors that you want to replace, use the Eyedropper tool to click in the image or in the preview box to select the areas exposed by the mask.

5 To refine the selection, do any of the following:

- Shift-click or use the Add To Sample Eyedropper tool to add areas.
- Alt-click (Windows), Option-click (Mac OS), or use the Subtract From Sample Eyedropper tool to remove areas.
- Click the Selection Color swatch to open the Color Picker. Use the Color Picker to target the color you want replaced. As you select a color in the Color Picker, the mask in the preview box is updated.

6 Drag the Fuzziness slider or enter a Fuzziness value to control the degree to which related colors are included in the selection.

7 Specify a Replacement color by doing either of the following:

- Drag the Hue, Saturation, and Lightness sliders (or enter values in the text boxes).
- Double-click the Result swatch and use the Color Picker to select the replacement color.

Note: *You cannot replace pure gray, black, or white with a color. However, you can change the Lightness setting. (The Hue and Saturation settings are relative to existing color, so they have no effect.)*

8 (Optional) Click Save to store settings you will later load for other images.

Use the Color Replacement tool

The Color Replacement tool paints over a targeted color with a replacement color. While this tool is good for quick edits, it often proves unsatisfactory, particularly with dark colors and black. If you don't get good results after experimenting with tool options, see Adjust hue and saturation.

The Color Replacement tool doesn't work in Bitmap, Indexed, or Multichannel color mode.

1 Select the Color Replacement tool . (If the tool isn't visible, access it by holding down the Brush tool.)

2 In the options bar, choose a brush tip. Generally, you should keep the blending mode set to Color.

3 For the Sampling option, choose one of the following:

Continuous Samples colors continuously as you drag.

Once Replaces the targeted color only in areas containing the color that you first click.

Background Swatch Replaces only areas containing the current background color.

4 From the Limits menu, select one of the following:

Discontiguous Replaces the sampled color wherever it occurs under the pointer.

Contiguous Replaces colors that are contiguous with the color immediately under the pointer.

Find Edges Replaces connected areas containing the sampled color while better preserving the sharpness of shape edges.

5 For Tolerance, choose a low percentage to replace colors very similar to the pixel you click, or raise the percentage to replace a broader range of colors.

6 To produce a smooth edge in the corrected areas, select Anti-aliased.

7 Choose a foreground color to replace the unwanted color. (See Choose colors in the toolbox.)

8 Click the color you want to replace in the image.

9 Drag in the image to replace the targeted color.

If the range of replaced colors is too small, increase the Tolerance setting in the options bar.

Mix colors selectively

Make selective color adjustments

Selective color correction is a technique used by high-end scanners and separation programs to change the amount of process colors in each of the primary color components in an image. You can modify the amount of a process color in any primary color *selectively*—without affecting the other primary colors. For example, you can use selective color correction to dramatically decrease the cyan in the green component of an image while leaving the cyan in the blue component unaltered.

Even though Selective Color uses CMYK colors to correct an image, you can use it on RGB images.

1 Make sure that the composite channel is selected in the Channels panel. The Selective Color adjustment is available only when you're viewing the composite channel.

2 Do one of the following:

- Click the Selective Color icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Selective Color. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Selective Color. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

3 Do one of the following:

- Choose the color you want to adjust from the Colors menu in the Properties panel. You can also choose a Preset that you've saved.
- In the Properties panel, choose a Selective Color preset from the Preset menu.

4 Select a method in the Properties panel:

Relative Changes the existing amount of cyan, magenta, yellow, or black by its percentage of the total. For example, if you start with a pixel that is 50% magenta and add 10%, 5% is added to the magenta (10% of 50% = 5%) for a total of 55% magenta. (This option cannot adjust pure specular white, which contains no color components.)

Absolute Adjusts the color in absolute values. For example, if you start with a pixel that is 50% magenta and add 10%, the magenta ink is set to a total of 60%.

Note: *The adjustment is based on how close a color is to one of the options in the Colors menu. For example, 50% magenta is midway between white and pure magenta and receives a proportionate mix of corrections defined for the two colors.*

5 Drag the sliders to increase or decrease the components in the selected color.

You can also save the settings you make for the Selective Color adjustment and reuse the settings on other images.

More Help topics

Blending mode examples

Save adjustment settings

Reapply adjustment settings

Distort filters are unavailable

Issue

When you try to use the Pinch, Spherize, Twirl, or Zigzag distort filters on a large image in Adobe Photoshop, they are dimmed (unavailable).

Solution

Reduce the pixel dimensions of the image.

Additional Information

There are maximum image pixel dimensions for each of these filters:

ZigZag: 8000 X 8000 Pinch: 11500 X 11500 Spherize: 11500 X 11500 Twirl: 11500 X 11500

Invalid JPEG Marker error | Opening images

Issue

When you open an image in Photoshop, one of the following errors occurs:

- Could not complete your request because it is not a valid Photoshop document.
- Could not complete your request because an unknown or invalid JPEG marker type is found.
- Could not complete your request because the file-format module cannot parse the file.
- This is not a valid Portable Document File (PDF) document. It cannot be opened.



Solutions

Solution 1: Make sure that the filename extension matches the actual file type.

It's important that the extension you add to the filename is the appropriate one for the actual file type of the image. When you choose a format from the Format pop-up menu in the Save As dialog box, the appropriate extension is added automatically. If you entered the extension manually, you could have typed in an extension that doesn't match the file format of your file.

Filename extensions are hidden by default. To turn them on, perform the following steps:

Mac OS

1 In Finder, choose Finder > Finder Preferences > Advanced.

2 Select Show all filename extensions.

Windows

1 Open Windows Explorer.

2 If you don't see your menus, choose Organize > Layout > Menu Bar.



3 Choose Tools > Folder Options > View.



4 Deselect Hide Extensions for Known File Types.



5 Click Apply, then click OK.

Solution 2: Make sure that the file has only one filename extension.

Turn on filename extensions as in Solution 1, and view your images in Finder or Windows Explorer. Then, check to see of there are two extensions on your files. If your images have two extensions, such as:

filename.pdf.jpg

Remove the last extension so the file is named:

filename.pdf

Solution 3: Make sure that your hardware isn't damaged.

Validate your hardware to make sure that there are no hardware failures, such as with an external hard disk or network.

More Help topics

Error: "[Filename].psd could not be opened" occurs opening images in Photoshop | Mac OS

Image information

Work with the Info panel

The Info panel shows the color values beneath the pointer and, depending on the tool in use, gives other useful information. The Info panel also displays a hint on using the selected tool, gives document status information, and can display 8-bit, 16-bit, or 32-bit values.

The Info panel displays the following information:

- Depending on the option you specify, the Info panel displays 8-bit, 16-bit, or 32-bit values.
- When displaying CMYK values, the Info panel displays an exclamation point next to the CMYK values if the color beneath the pointer or color sampler is out of the printable CMYK color gamut.
- When a marquee tool is being used, the Info panel displays the *x* and *y* coordinates of the pointer position and the width (W) and height (H) of the marquee as you drag.
- When the Crop tool or Zoom tool is being used, the Info panel displays the width (W) and height (H) of the marquee as you drag. The panel also shows the angle of rotation of the crop marquee.
- When the Line tool, the Pen tool, or Gradient tool is being used, or when a selection is being moved, the Info panel displays the *x* and *y* coordinates of your starting position, the change in X (DX), the change in Y (DY), the angle (A), and the length (D) as you drag.
- When a two-dimensional transformation command is being used, the Info panel displays the percentage change in width (W) and height (H), the angle of rotation (A), and the angle of horizontal skew (H) or vertical skew (V).
- When any color adjustment dialog box (for example, Curves) is being used, the Info panel displays before-and-after color values for the pixels beneath the pointer and beneath color samplers.
- If the Show Tool Hints option is enabled, you see hints for using the tool selected in the toolbox.
- Depending on the options selected, the Info panel displays status information, such as document size, document profile, document dimensions, scratch sizes, efficiency, timing, and current tool.

Use the Info panel

The Info panel displays file information about an image and also provides feedback about the color values as you move a tool pointer over an image. Make sure the Info panel is visible in your workspace if you want to view information while dragging in the image.

1 (Optional) Do one of the following if you need to display the Info panel:
   - Click the Info panel tab if it's docked with other panels.
   - Choose Window > Info. File information about the image is displayed at the bottom of the Info panel. You can change the information displayed by clicking the triangle in the upper right corner of the panel and choosing Panel Options from the panel menu.
2 Set the options for the information you want displayed in the Info Panel by doing any of the following:
   - Choose Panel Options from the Info panel menu and specify options in the Info Panel Options dialog box.
   - Click an eyedropper icon and choose display options from the pop-up menu. You can also use the pop-up menu to specify whether the Info panel displays 8-bit, 16-bit, or 32-bit values.
   - Click the cursor coordinates icon and choose a unit of measurement.
3 Select a tool.
4 Move the pointer in the image, or drag in the image to use the tool. The following information may appear, depending on which tool you're using:

   Displays the numeric values for the color beneath the pointer.

Displays the *x* and *y* coordinates of the pointer.

Displays the width (W) and height (H) of a marquee or shape as you drag, or the width and height of an active selection.

Change the Info panel options

1 Click the triangle in the upper right corner to open the Info panel menu and choose Panel Options.

2 In the Info Panel Options dialog box, for First Color Readout, choose one of the following display options:

Actual Color Displays values in the current color mode of the image.

Proof Color Displays values for the output color space of the image.

\[Color mode] Displays the color values in that color mode.

Total Ink Displays the total percentage of all CMYK ink at the pointer's current location, based on the values set in the CMYK Setup dialog box.

Opacity Displays the opacity of the current layer. This option does not apply to the background.

You can also set the readout options by clicking the eyedropper icon in the Info panel. In addition to the First Color Readout options, you can also display 8-bit, 16-bit, or 32-bit values.

3 For Second Color Readout, choose a display option from the list in step 2. For the second readout, you can also click the eyedropper icon in the Info panel and choose readout options from the pop-up menu.



4 For Ruler Units, choose a unit of measurement.

5 Under Status information, select from the following to display file information in the Info panel:

Document Sizes Displays information on the amount of data in the image. The number on the left represents the printing size of the image—approximately the size of the saved, flattened file in Adobe Photoshop format. The number on the right indicates the file's approximate size including layers and channels.

Document Profile Displays the name of the color profile used by the image.

Document Dimensions Displays the dimensions of the image.

Scratch Sizes Displays information on the amount of RAM and the scratch disk used to process the image. The number on the left represents the amount of memory that is currently being used by the program to display all open images. The number on the right represents the total amount of RAM available for processing images.

Efficiency Displays the percentage of time spent performing an operation instead of reading or writing to the scratch disk. If the value is below 100%, Photoshop is using the scratch disk and is therefore operating more slowly.

Timing Displays the amount of time it took to complete the last operation.

Current Tool Displays the name of the active tool.

Measurement Scale Displays the scale of the document.

6 (Optional) Select Show Tool Hints to display a hint for using a selected tool at the bottom of the Info panel.

7 Click OK.

To change measurement units, click the crosshair icon in the Info panel and choose from the menu.

Display file information in the document window

The status bar is located at the bottom of every document window and displays useful information—such as the current magnification and file size of the active image, and brief instructions for using the active tool.

Note: *You can also view copyright and authorship information that has been added to the file. This information includes standard file information and Digimarc watermarks. Photoshop automatically scans opened images for watermarks using the Digimarc Detect Watermark plug-in. If a watermark is detected, Photoshop displays a copyright symbol in the image window's title bar and updates the Copyright fields of the File Info dialog box.*

1 Click the triangle in the bottom border of the document window.



2 Choose a view option from the pop-up menu:

Note: *If you have Version Cue enabled, choose from the Show submenu.*

Version Cue Displays the Version Cue workgroup status of your document, such as open, unmanaged, unsaved, and so forth. This option is available only if you have Version Cue enabled.

Document Sizes Information on the amount of data in the image.

Document Profile The name of the color profile used by the image.

Document Dimensions The dimensions of the image.

Measurement Scale The scale of the document.

Scratch Sizes Information on the amount of RAM and the scratch disk used to process the image.

Efficiency The percentage of time actually spent performing an operation instead of reading or writing to the scratch disk.

Timing The time it took to complete the last operation.

Current Tool The name of the active tool.

32-bit Exposure Option for adjusting the preview image for viewing 32-bits-per-channel high dynamic range (HDR) images on your computer monitor. The slider is available only when the document window displays an HDR image.

Click the file information area of the status bar to display document width, height, channels, and resolution. Control-click (Windows) or Command-click (Mac OS), to display tile width and height.

More Help topics

Adjust displayed dynamic range for 32-bit HDR images

High dynamic range images

About high dynamic range images

The dynamic range (ratio between dark and bright regions) in the visible world far exceeds the range of human vision and of images that are displayed on a monitor or printed. But whereas human eyes can adapt to very different brightness levels, most cameras and computer monitors can reproduce only a fixed dynamic range. Photographers, motion picture artists, and others working with digital images must be selective about what's important in a scene because they are working with a limited dynamic range.

High dynamic range (HDR) images open up a world of possibilities because they can represent the entire dynamic range of the visible world. Because all the luminance values in a real-world scene are represented proportionately and stored in an HDR image, adjusting the exposure of an HDR image is like adjusting the exposure when photographing a scene in the real world.

A Image with shadow detail but highlights clipped ***B*** *Image with highlight detail but shadows clipped* ***C*** *HDR image containing the dynamic range of the scene*

In Photoshop, the luminance values of an HDR image are stored using a floating-point numeric representation that's 32 bits long (32-bits-per-channel). The luminance values in an HDR image are directly related to the amount of light in a scene. By contrast, non-floating point 16- and 8-bpc image files store luminance values only from black to paper white, reflecting an extremely small segment of dynamic range in the real world.

In Photoshop, the Merge To HDR Pro command lets you create HDR images by combining multiple photographs captured at different exposures. Because an HDR image contains brightness levels that far exceed the display capabilities of a standard 24-bit monitor, Photoshop lets you adjust the HDR preview. If you need to print or use tools and filters that don't work with HDR images, you can convert them to 16- or 8-bpc images.

Take photos for HDR images

Keep the following tips in mind when you take photos to be combined with the Merge To HDR Pro command:

- Secure the camera to a tripod.
- Take enough photos to cover the full dynamic range of the scene. You can try taking at least five to seven photos, but you might need to take more exposures depending on the dynamic range of the scene. The minimum number of photos should be three.

- Vary the shutter speed to create different exposures. Changing the aperture changes the depth of field in each exposure and can produce lower-quality results. Changing the ISO or aperture may also cause noise or vignetting in the image.
- In general, don't use your camera's auto-bracket feature, because the exposure changes are usually too small.
- The exposure differences between the photos should be one or two EV (exposure value) steps apart (equivalent to about one or two f-stops apart).
- Don't vary the lighting; for instance, don't use a flash in one exposure but not the next.
- Make sure that nothing is moving in the scene. Exposure Merge works only with differently exposed images of the identical scene.

Features that support 32-bpc HDR images

You can use the following tools, adjustments, and filters with 32-bpc HDR images. (To work with more Photoshop features, convert a 32-bpc image to a 16-bpc or an 8-bpc image. To preserve the original image, create a copy with the Save As command.)

Adjustments Levels, Exposure, Hue/Saturation, Channel Mixer, Photo Filter.

Note: *Although the Exposure command can be used with 8- and 16-bpc images, it is designed for making exposure adjustments to 32-bpc HDR images.*

Blend Modes Normal, Dissolve, Darken, Multiply, Lighten, Darker Color, Linear Dodge (Add), Lighter Color, Difference, Subtract, Divide, Hue, Saturation, Color, and Luminosity.

Create new 32-bpc documents In the New dialog box, 32 bit is an option in the bit depth pop-up menu to the right of the Color Mode pop-up menu.

Edit menu commands All commands including Fill, Stroke, Free Transform, and Transform.

File Formats Photoshop (PSD, PSB), Radiance (HDR), Portable Bit Map (PBM), OpenEXR, and TIFF.

Note: *Although Photoshop cannot save an HDR image in the LogLuv TIFF file format, it can open and read a LogLuv TIFF file.*

Filters Average, Box Blur, Gaussian Blur, Motion Blur, Radial Blur, Shape Blur, Surface Blur, Add Noise, Clouds, Difference Clouds, Lens Flare, Smart Sharpen, Unsharp Mask, Emboss, De-Interlace, NTSC Colors, High Pass, Maximum, Minimum, and Offset.

Image commands Image Size, Canvas Size, Image Rotation, Crop, Trim, Duplicate, Apply Image, Calculations, and Variables.

View Pixel Aspect Ratio (Custom Pixel Aspect Ratio, Delete Pixel Aspect Ratio, Reset Pixel Aspect Ratio, etc.)

Layers New layers, duplicate layers, adjustment layers (Levels, Vibrance, Hue/Saturation, Channel Mixer, Photo Filter, and Exposure), fill layers, layer masks, layer styles, supported blending modes, and Smart Objects.

Modes RGB Color, Grayscale, conversion to 8 Bits/Channel or 16 Bits/Channel.

Pixel Aspect Ratio Support for square and non-square documents.

Selections Invert, Modify Border, Transform Selection, Save Selection and Load Selection.

Tools All tools in the toolbox except: Magnetic Lasso, Magic Wand, Spot Healing Brush, Healing Brush, Red Eye, Color Replacement, Art History Brush, Magic Eraser, Background Eraser, Paint Bucket, Dodge, Burn, and Sponge. Some tools work with supported blend modes only.

Merge images to HDR

The Merge To HDR Pro command combines multiple images with different exposures of the same scene, capturing the full dynamic range in a single HDR image. You can output the merged image as a 32-, 16-, or 8-bpc file. However, only a 32-bpc file can store all the HDR image data.

HDR merging works best when photos are optimized for the process. For recommendations, see Take photos for HDR images.

1 Do one of the following:
   - (Photoshop) Choose File > Automate > Merge To HDR Pro.
   - (Bridge) Select the images you want to use and choose Tools > Photoshop > Merge To HDR Pro. Skip to step 5.
2 In the Merge To HDR Pro dialog box, click Browse to select specific images, click Add Open Files, or choose Use > Folder. (To remove a particular item, select it in files list, and click Remove.)
3 (Optional) Select Attempt To Automatically Align Source Images if you held the camera in your hands when you photographed the images.
4 Click OK.

   Note: *If images lack exposure metadata, enter values in the Manually Set EV dialog box.*

   A second Merge To HDR Pro dialog box displays thumbnails of the source images, and a preview of the merged result.
5 To the upper right of the preview, choose a bit depth for the merged image.

   Choose 32 Bit if you want the merged image to store the entire dynamic range of the HDR image. 8-bit and (non-floating point) 16-bit image files cannot store the entire range of luminance values in an HDR image.
6 To adjust the tonal range, see Options for 32-bit imagesor Options for 16- or 8-bit images.
7 (Optional) To save your tonal settings for future use, choose Preset > Save Preset. (To later reapply the settings, choose Load Preset.)

Options for 32-bit images

Move the slider below the histogram to adjust the white point preview of the merged image. Moving the slider adjusts the image preview only; all HDR image data remains in the merged file.

The preview adjustment is stored in the HDR file and applied whenever you open the file in Photoshop. To readjust the white point preview at any time, choose View > 32-Bit Preview Options.

Options for 16- or 8-bit images

HDR images contain luminance levels that far exceed the dynamic range that 16- or 8-bpc images can store. To produce an image with the dynamic range you want, adjust exposure and contrast when converting from 32-bpc to lower bit depths.

Choose one of the following tone-mapping methods:

Local Adaptation Adjusts HDR tonality by adjusting local brightness regions throughout the image.

Edge Glow Radius specifies the size of the local brightness regions. Strength specifies how far apart two pixels' tonal values must be before they're no longer part of the same brightness region.

Tone and Detail Dynamic range is maximized at a Gamma setting of 1.0; lower settings emphasize midtones, while higher settings emphasize highlights and shadows. Exposure values reflect f-stops. Drag the Detail slider to adjust sharpness and the Shadow and Highlight sliders to brighten or darken these regions.

Color Vibrance adjusts the intensity of subtle colors, while minimizing clipping of highly saturated colors. Saturation adjusts the intensity of all colors from –100 (monochrome) to +100 (double saturation).

Toning Curve Displays an adjustable curve over a histogram showing luminance values in the original, 32-bit HDR image. The red tick marks along the horizontal axis are in one EV (approximately one f-stop) increments.

Note: *By default, the Toning Curve and Histogram limit and equalize your changes from point to point. To remove the limit and apply more extreme adjustments, select the Corner option after inserting a point on the curve. When you insert and move a second point, the curve becomes angular.*



A *Inserting a point and selecting the Corner option.* ***B*** *Adjusting new point makes the curve angular at the point where the Corner option is used.*

Equalize Histogram Compresses the dynamic range of the HDR image while trying to preserve some contrast. No further adjustments are necessary; this method is automatic.

Exposure and Gamma Lets you manually adjust the brightness and contrast of the HDR image. Move the Exposure slider to adjust gain and the Gamma slider to adjust contrast.

Highlight Compression Compresses the highlight values in the HDR image so they fall within the luminance values range of the 8- or 16-bpc image file. No further adjustments are necessary; this method is automatic.

Compensate for moving objects

If images have different content due to moving objects like cars, people, or foliage, select Remove Ghosts in the Merge To HDR Pro dialog box.

Photoshop displays a green outline around the thumbnail with the best tonal balance, identifying the base image. Moving objects found in other images are removed. (If movement occurs in very light or dark areas, click a different thumbnail where moving objects are better exposed to improve results.)

For a tutorial on the Remove Ghosts option, see this video. (Discussion of Remove Ghosts begins at 3:00.)

Save or load camera response curves

Response curves indicate how camera sensors interpret different levels of incoming light. By default, the Merge To HDR Pro dialog box automatically calculates a camera response curve based on the tonal range of images you are merging. You can save the current response curve and later apply it to another group of merged images.

? In the upper-right corner of the Merge to HDR Pro dialog box, click the response curve menu ▾≡, and then choose Save Response Curve. (To later reapply the curve, choose Load Response Curve.)

Convert from 32 bits to 16 or 8 bpc

If you originally created a 32-bit image during the Merge to HDR Pro process, you can later convert it to a 16- or 8-bit image.

1 Open a 32-bpc image in Photoshop, and choose Image > Mode > 16 Bits/Channel or 8 Bits/Channel.

2 Adjust exposure and contrast to produce an image with the dynamic range you want. (See Options for 16- or 8-bit images.)

3 Click OK to convert the 32-bit image.

Adjust displayed dynamic range for 32-bit HDR images

The dynamic range of HDR images exceeds the display capabilities of standard computer monitors. When you open an HDR image in Photoshop, it can look very dark or washed out. Photoshop lets you adjust the preview so that the monitor displays an HDR image whose highlights and shadows aren't washed out or too dark. The preview settings are stored in the HDR image file (PSD, PSB, and TIFF only) and are applied whenever the file is opened in Photoshop. Preview adjustments don't edit the HDR image file; all the HDR image information remains intact. Use the Exposure adjustment (Image > Adjustments > Exposure) to make exposure edits to the 32-bpc HDR image.

To view 32-bit readouts in the Info panel, click the Eyedropper icon in the Info panel and choose 32-Bit from the pop-up menu.

1 Open a 32-bpc HDR image in Photoshop, and choose View > 32-Bit Preview Options.

2 In the 32-bit Preview Options dialog box, choose an option from the Method menu:

Exposure And Gamma Adjusts the brightness and contrast.

Highlight Compression Compresses the highlight values in the HDR image so they fall within the luminance values range of the 8- or 16-bpc image file.

3 If you chose Exposure And Gamma, move the Exposure and Gamma sliders to adjust the brightness and contrast of the image preview.

4 Click OK.

You can also adjust the preview of an HDR image open in Photoshop by clicking the triangle in the status bar of the document window and choosing 32-Bit Exposure from the pop-up menu. Move the slider to set the white point for viewing the HDR image. Double-click the slider to return to the default exposure setting. Since the adjustment is made per view, you can have the same HDR image open in multiple windows, each with a different preview adjustment. Preview adjustments made with this method are not stored in the HDR image file.

About the HDR Color Picker

The HDR Color Picker allows you to accurately view and select colors for use in 32-bit HDR images. As in the regular Adobe Color Picker, you select a color by clicking a color field and adjusting the color slider. The Intensity slider allows you to adjust the brightness of a color to match the intensity of the colors in the HDR image you're working with. A Preview area lets you view swatches of a selected color to see how it will display at different exposures and intensities.



A Preview area ***B*** *Adjusted color* ***C*** *Original color* ***D*** *32-bit floating point values* ***E*** *Intensity slider* ***F*** *Picked color* ***G*** *Color slider* ***H*** *Color values*

Display the HDR Color Picker

? With a 32-bpc image open, do one of the following:

- In the toolbox, click the foreground or background color selection box.
- In the Color panel, click the Set Foreground Coloror Set Background Color selection box.

The Color Picker is also available when features let you choose a color. For example, by clicking the color swatch in the options bar for some tools, or the eyedroppers in some color adjustment dialog boxes.

Choose colors for HDR images

The lower part of the HDR Color Picker functions like the regular Color Picker does with 8- or 16-bit images. Click in the color field to select a color and move the color slider to change hues, or use the HSB or RGB fields to enter numeric values for a particular color. In the color field, brightness increases as you move from bottom to top, and saturation increases as you move from left to right.

Use the Intensity slider to adjust the brightness of the color. The color value plus the intensity value are converted to 32-bit floating point number values in your HDR document.

1 Select a color by clicking in the color field and moving the color slider, or by entering HSB or RGB numeric values, as in the Adobe Color Picker.

2 Adjust the Intensity slider to boost or reduce the color's brightness. The new color swatch in the Preview scale at the top of the Color Picker shows the effect of increasing or decreasing stops for the selected color.

The Intensity Stops correspond inversely to exposure setting stops. If you boost the Exposure setting of the HDR image two stops, reducing the Intensity stops by two will maintain the same color appearance as if the HDR image exposure and the color intensity were both set to 0.

If you know the exact 32-bit RGB values for the color you want, you can enter them directly in the 32-bit value RGB fields.

3 (Optional) Adjust settings for the Preview area.

Preview Stop Size Sets the stop increments for each preview swatch. For example, a setting of 3 results in swatches of -9, -6, -3, +3, +6, +9. These swatches let you preview the appearance of your selected color at different exposure settings.

Relative to Document Select to adjust the preview swatches to reflect the current exposure setting for the image. For example, if the document exposure is set higher, the new preview swatch will be lighter than the color selected in the Color Picker's color field, to show the effect of the higher exposure on the selected color. If the current exposure is set to 0 (the default), checking or unchecking this option will not change the new swatch.

4 (Optional) Click Add to Swatches to add the selected color to the Swatches panel.

5 Click OK.

Paint on HDR images

You can edit and add effects to HDR/32-bpc images using any of the following Photoshop tools: Brush, Pencil, Pen, Shape, Clone Stamp, Pattern Stamp, Eraser, Gradient, Blur, Sharpen, Smudge, and History Brush. You can also use the Text tool to add 32-bpc text layers to an HDR image.

When editing or painting on HDR images, you can preview your work at different exposure settings using either the 32-Bit Exposure slider in the document info area or the 32-Bit Preview Options dialog box (View > 32-Bit Preview Options). The HDR Color Picker also lets you preview your selected foreground color at different intensity settings, to match different exposure settings in an HDR image.

1 Open an HDR image.

2 (Optional) Set the exposure for the image. See Adjust displayed dynamic range for 32-bit HDR images.

3 For the Brush or Pencil tools, click the foreground color to open the HDR Color Picker and select a color. For the Text tool, click the color chip in the Text tool options bar to set the text color.

The Preview area of the HDR Color Picker helps you select and adjust a foreground color in relation to different exposure settings in the HDR image. See About the HDR Color Picker.

By default, the Toning Curve and Histogram limit and equalize your changes from point to point. To remove the limit and apply more extreme adjustments, select the Corner option after inserting a point on the curve. When you insert and move a second point, the curve becomes angular.

More Help topics

Adjust HDR exposure and toning

Curves overview

Adobe Color Picker overview

Customize indexed color tables

Customize indexed color tables

The Color Table command lets you make changes to the color table of an indexed-color image. These customization features are particularly useful with *pseudocolor images*—images displaying variations in gray levels with color rather than shades of gray, often used in scientific and medical applications. However, customizing the color table can also produce special effects with indexed-color images that have a limited number of colors.

Note: *To shift colors simply in a pseudocolor image, choose Image > Adjustments, and use the color adjustment commands in the submenu.*

Edit colors and assign transparency with a color table

You can edit colors in the color table to produce special effects, or assign transparency in the image to a single color in the table.

1. Open the indexed-color image.
2. Choose Image > Mode > Color Table.
3. To change a single color, click the color and choose a new color in the Color Picker.
4. To change a range of colors, drag in the table to choose the range of colors you want to change. In the Color Picker, choose the first color you want in the range and click OK. When the Color Picker redisplays, choose the last color you want in the range and click OK.

   The colors you selected in the Color Picker are placed in the range you selected in the Color Table dialog box.
5. To assign transparency to a color, select the Eyedropper tool in the Color Table dialog box, and click the color in the table or in the image. The sampled color is replaced with transparency in the image.
6. Click OK in the Color Table dialog box to apply the new colors to the indexed-color image.

Choose a predefined color table

1. Open the indexed-color image.
2. Do one of the following:
   - Choose Image > Mode > Color Table.
   - Choose Image > Mode > Indexed Color. In the Indexed Color dialog box, choose Custom from the Panel pop-up menu. This opens the Color Table dialog box.
3. In the Color Table dialog box, choose a predefined table from the Table menu.

   Custom Creates a palette you specify.

   Black Body Displays a palette based on the different colors a black body radiator emits as it is heated—from black to red, orange, yellow, and white.

   Grayscale Displays a palette based on 256 levels of gray—from black to white.

   Spectrum Displays a palette based on the colors produced as white light passes through a prism—from violet, blue, and green to yellow, orange, and red.

   System (Mac OS) Displays the standard Mac OS 256-color system palette.

   System (Windows) Displays the standard Windows 256-color system palette.

Save and load color tables

You use the Save and Load buttons in the Color Table dialog box to save your indexed color tables for use with other Adobe Photoshop images. After you load a color table into an image, the colors in the image change to reflect the color positions they reference in the new color table.

Note: *You can also load saved color tables into the Swatches panel.*

More Help topics

Converting between color modes

Customize color pickers and swatches

Change the Color Picker

Instead of using the Adobe Color Picker, you can choose colors from your computer operating system's standard Color Picker or from a third party Color Picker.

1. Choose Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS).
2. Choose a Color Picker from the Color Picker menu, and click OK.

   For more information, see your operating system documentation.

Add and delete color swatches

You can add or delete color swatches from the Swatches panel.

You can also add a color swatch from the Color Picker by clicking the Add To Swatches button.

Add a color to the Swatches panel

1. Decide which color you want to add and make it the foreground color.
2. Do one of the following:
   - Click the New Swatch button in the Swatches panel. Alternatively, choose New Swatch from the Swatches panel menu.
   - Position the pointer over an empty space in the bottom row of the Swatches panel (the pointer turns into the Paint Bucket tool), and click to add the color. Enter a name for the new color and click OK.

- (Creative Cloud only) Choose Load Swatches from the panel menu. Then, in the Load window, navigate to an HTML, CSS, or SVG file and click OK. Photoshop will read the color values specified in the documents. This feature recognizes the following HTML/CSS color syntax: #112233, #123, rgb(1,2,3), rgba(1,2,3,4), hsb(1,2,3), and hsba(1,2,3,4).

Note: *New colors are saved in the Photoshop preferences file so that they persist between editing sessions. To permanently save a color, save it in a library.*

Delete a color from the Swatches panel

? Do one of the following:

- Drag a swatch to the Delete icon .
- Hold down Alt (Windows) or Option (Mac OS), position the pointer over a swatch (the pointer turns into scissors), and click.

Manage swatch libraries

Swatch libraries provide an easy way to access different sets of colors. You can save custom sets of swatches as a library for reuse. You can also save swatches in a format for sharing in other applications.

Load or replace a library of swatches

? Choose one of the following from the Swatches panel menu:

Load Swatches Adds a library to the current set of swatches. Select the library file you want to use, and click Load.

Replace Swatches Replaces the current list with a different library. Select the library file you want to use, and click Load. Photoshop gives your the option of saving the current set of swatches before replacing them.

Name of a color library Loads a specific color system listed in the lower part of the Swatches panel menu. You can either replace or append the current set of colors with the library you're loading.

Save a set of swatches as a library

1 Choose Save Swatches from the Swatches panel menu.

2 Choose a location for the swatch library, enter a filename, and click Save.

You can save the library anywhere. However, if you place the library file in the Presets/Swatches folder in the default presets location, the library name will appear at the bottom of the Swatches panel menu after you restart the application.

Return to the default library of swatches

? Choose Reset Swatches from the Swatches panel menu. You can either replace or append the current set of colors with the default swatch library.

Share swatches between applications

You can share the solid swatches you create in Photoshop, Illustrator, and InDesign by saving a swatch library for exchange. The colors appear exactly the same across applications as long as your color settings are synchronized.

1 In the Swatches panel, create the process and spot-color swatches you want to share, and remove any swatches you don't want to share.

   Note: *You cannot share the following types of swatches between applications: patterns, gradients, and the Registration swatch from Illustrator or InDesign; and book color references, HSB, XYZ, duotone, monitorRGB, opacity, total ink, and webRGB swatches from Photoshop. These types of swatches are automatically excluded when you save swatches for exchange.*

2 Select Save Swatches For Exchange from the Swatches panel menu, and save the swatch libraries in an easily accessible location.

3 Load the swatch library into the Swatches panel for Photoshop, Illustrator, or InDesign.

More Help topics

Add swatches from HTML, CSS, and SVG files

Work with the Preset Manager

Convert between color modes

In Photoshop you can easily create an image in one color mode and convert it to another, perhaps to get it ready for a specific print job.

Convert an image to another color mode

You can change an image from its original mode (source mode) to a different mode (target mode). When you choose a different color mode for an image, you permanently change the color values in the image. For example, when you convert an RGB image to CMYK mode, RGB color values outside the CMYK gamut (defined by the CMYK working space setting in the Color Settings dialog box) are adjusted to fall within gamut. As a result, some image data may be lost and can't be recovered if you convert the image from CMYK back to RGB.

Before converting images, it's best to do the following:

- Do as much editing as possible in the original image mode (usually RGB for images from most scanners or digital cameras, or CMYK for images from traditional drum scanners or imported from a Scitex system).
- Save a backup copy before converting. Be sure to save a copy of your image that includes all layers so that you can edit the original version of the image after the conversion.
- Flatten the file before converting it. The interaction of colors between layer blending modes changes when the mode changes.

Note: *In most cases, you'll want to flatten a file before converting it. However, it isn't required and, in some cases, it isn't desirable (for example, when the file has vector text layers).*

? Choose Image > Mode and the mode you want from the submenu. Modes not available for the active image appear dimmed in the menu.

   Images are flattened when converted to Multichannel, Bitmap, or Indexed Color mode, because these modes do not support layers.

Convert an image to Bitmap mode

Converting an image to Bitmap mode reduces the image to two colors, greatly simplifying the color information in the image and reducing its file size.

When converting a color image to Bitmap mode, first convert it to Grayscale mode. This removes the hue and saturation information from the pixels and leaves just the brightness values. However, because only a few editing options are available for Bitmap mode images, it's usually best to edit the image in Grayscale mode and then convert it to Bitmap mode.

Note: *Images in Bitmap mode are 1 bit per channel. You must convert a 16- or 32-bits-per-channel image to 8-bit Grayscale mode before converting it to Bitmap mode.*

1 Do one of the following:

- If the image is in color, choose Image > Mode > Grayscale. Then choose Image > Mode > Bitmap.
- If the image is grayscale, choose Image > Mode > Bitmap.

2 For Output, enter a value for the output resolution of the Bitmap mode image, and choose a unit of measurement. By default, the current image resolution appears as both the input and the output resolutions.

3 Choose one of the following bitmap conversion methods from the Use pop-up menu:

50% Threshold Converts pixels with gray values above the middle gray level (128) to white and pixels with gray values below that level to black. The result is a very high-contrast, black-and-white representation of the image.

Pattern Dither Converts an image by organizing the gray levels into geometric configurations of black and white dots.

Diffusion Dither Converts an image by using an error-diffusion process, starting at the pixel in the upper-left corner of the image. If the pixel's value is above middle gray (128), the pixel is changed to white—if below it, to black. Because the original pixel is rarely pure white or pure black, error is inevitably introduced. This error is transferred to surrounding pixels and diffused throughout the image, resulting in a grainy, film-like texture.

Halftone Screen Simulates the appearance of halftone dots in the converted image. Enter values in the Halftone Screen dialog box:

- For Frequency, enter a value for the screen frequency, and choose a unit of measurement. Values can range from 1.000 to 999.999 for lines per inch and from 0.400 to 400.00 for lines per centimeter. You can enter decimal values. The screen frequency specifies the ruling of the halftone screen in lines per inch (lpi). The frequency depends on the paper stock and type of press used for printing. Newspapers commonly use an 85-line screen. Magazines use higher resolution screens, such as 133-lpi and 150-lpi. Check with your print shop for correct screen frequencies.
- Enter a value for the screen angle in degrees from -180 to +180. The screen angle refers to the orientation of the screen. Continuous-tone and black-and-white halftone screens commonly use a 45° angle.
- For Shape, choose the dot shape you want.

Note: *The halftone screen becomes part of the image. If you print the image on a halftone printer, the printer will use its own halftone screen as well as the halftone screen that is part of the image. On some printers, the result is a moiré pattern.*

Custom Pattern Simulates the appearance of a custom halftone screen in the converted image. Choose a pattern that lends itself to thickness variations, typically one with a variety of gray shades.

To use this option, you first define a pattern and then screen the grayscale image to apply the texture. To cover the entire image, the pattern must be as large as the image. Otherwise, the pattern is tiled. Photoshop comes with several self-tiling patterns that can be used as halftone screen patterns.

To prepare a black-and-white pattern for conversion, first convert the image to grayscale and then apply the Blur More filter several times. This blurring technique creates thick lines tapering from dark gray to white.



Convert a color photo to Grayscale mode

1 Open the photo you want to convert to black-and-white.

2 Choose Image > Mode > Grayscale.

3 Click Discard. Photoshop converts the colors in the image to black, white, and shades of gray.

Note: *The technique above minimizes file size but discards color information and can convert adjacent colors to the exact same shade of gray. Using a Black & White adjustment layer increases file size but retains color information, letting you map colors to shades of gray.*

Convert a Bitmap mode image to Grayscale mode

You can convert a Bitmap mode image to Grayscale mode in order to edit it. Keep in mind that a Bitmap mode image edited in Grayscale mode may not look the same when you convert it back to Bitmap mode. For example, suppose a pixel that is black in Bitmap mode is edited to a shade of gray in Grayscale mode. When the image is converted back to Bitmap mode, that pixel is rendered as white if its gray value is above the middle gray value of 128.

1 Choose Image > Mode > Grayscale.

2 Enter a value between 1 and 16 for the size ratio.

The size ratio is the factor for scaling down the image. For example, to reduce a grayscale image by 50%, enter 2 for the size ratio. If you enter a number greater than 1, the program averages multiple pixels in the Bitmap mode image to produce a single pixel in the grayscale image. This process lets you generate multiple shades of gray from an image scanned on a 1-bit scanner.

Convert a grayscale or RGB image to indexed color

Converting to indexed color reduces the number of colors in the image to at most 256—the standard number of colors supported by the GIF and PNG-8 formats and many multimedia applications. This conversion reduces file size by deleting color information from the image.

To convert to indexed color, you must start with an image that is 8 bits per channel and in either Grayscale or RGB mode.

1 Choose Image > Mode > Indexed Color.

   Note: *All visible layers will be flattened; any hidden layers will be discarded.*

   For grayscale images, the conversion happens automatically. For RGB images, the Indexed Color dialog box appears.

2 Select Preview in the Indexed Color dialog box to display a preview of the changes.

3 Specify conversion options.

Conversion options for indexed-color images

When converting an RGB image to indexed color, you can specify a number of conversion options in the Indexed Color dialog box.

Palette Type A number of palette types are available for converting an image to indexed color. For the Perceptual, Selective, and Adaptive options, you can choose using a local palette based on the current image's colors. These are the available palette types:

Exact Creates a palette using the exact colors appearing in the RGB image—an option available only if the image uses 256 or fewer colors. Because the image's palette contains all colors in the image, there is no dithering.

System (Mac OS) Uses the Mac OS default 8-bit palette, which is based on a uniform sampling of RGB colors.

System (Windows) Uses the Windows system's default 8-bit palette, which is based on a uniform sampling of RGB colors.

Web Uses the 216-color palette that web browsers, regardless of platform, use to display images on a monitor limited to 256 colors. This palette is a subset of the Mac OS 8-bit palette. Use this option to avoid browser dither when viewing images on a monitor display limited to 256 colors.

Uniform Creates a palette by uniformly sampling colors from the RGB color cube. For example, if Photoshop takes six evenly-spaced color levels each of red, green, and blue, the combination produces a uniform palette of 216 colors (6 cubed = 6 x 6 x 6 = 216). The total number of colors displayed in an image corresponds to the nearest perfect cube (8, 27, 64, 125, or 216) that is less than the value in the Colors text box.

Local (Perceptual) Creates a custom palette by giving priority to colors for which the human eye has greater sensitivity.

Local (Selective) Creates a color table similar to the Perceptual color table, but favoring broad areas of color and the preservation of web colors. This option usually produces images with the greatest color integrity.

Local (Adaptive) Creates a palette by sampling the colors from the spectrum appearing most commonly in the image. For example, an RGB image with only the colors green and blue produces a palette made primarily of greens and blues. Most images concentrate colors in particular areas of the spectrum. To control a palette more precisely, first select a part of the image containing the colors you want to emphasize. Photoshop weights the conversion toward these colors.

Master (Perceptual) Creates a custom palette by giving priority to colors for which the human eye has greater sensitivity. Applies when you have multiple documents open; takes all open documents into account.

Master (Selective) Creates a color table similar to the Perceptual color table, but favoring broad areas of color and the preservation of web colors. This option usually produces images with the greatest color integrity. Applies when you have multiple documents open; takes all open documents into account.

Master (Adaptive) Creates a palette by sampling the colors from the spectrum appearing most commonly in the image. For example, an RGB image with only the colors green and blue produces a palette made primarily of greens and blues. Most images concentrate colors in particular areas of the spectrum. To control a palette more precisely, first select a part of the image containing the colors you want to emphasize. Photoshop weights the conversion toward these colors. Applies when you have multiple documents open; takes all open documents into account.

Custom Creates a custom palette using the Color Table dialog box. Either edit the color table and save it for later use or click Load to load a previously created color table. This option also displays the current Adaptive palette, which is useful for previewing the colors most often used in the image.

Previous Uses the custom palette from the previous conversion, making it easy to convert several images with the same custom palette.

Number Of Colors For the Uniform, Perceptual, Selective, or Adaptive palette, you can specify the exact number of colors to be displayed (up to 256) by entering a value for Colors. The Colors text box controls only how the indexed color table is created. Adobe Photoshop still treats the image as an 8-bit, 256-color image.

Color Inclusion And Transparency To specify colors to be included in the indexed color table or to specify transparency in the image, choose from the following options:

Forced Provides options to force the inclusion of certain colors in the color table. Black And White adds a pure black and a pure white to the color table; Primaries adds red, green, blue, cyan, magenta, yellow, black, and white; Web adds the 216 web-safe colors; and Custom lets you define custom colors to add.

Transparency Specifies whether to preserve transparent areas of the image during conversion. Selecting this option adds a special index entry in the color table for transparent colors. Deselecting this option fills transparent areas with the matte color, or with white if no matte color is chosen.

Matte Specifies the background color used to fill anti-aliased edges that lie adjacent to transparent areas of the image. When Transparency is selected, the matte is applied to edge areas to help blend the edges with a web background of the same color. When Transparency is deselected, the matte is applied to transparent areas. Choosing None for the matte creates hard-edged transparency if Transparency is selected; otherwise, all transparent areas are filled with 100% white. The image must have transparency for the Matte options to be available.

Dithering Unless you're using the Exact color table option, the color table may not contain all the colors used in the image. To simulate colors not in the color table, you can dither the colors. Dithering mixes the pixels of the available colors to simulate the missing colors. Choose a dither option from the menu, and enter a percentage value for the dither amount. A higher amount dithers more colors but may increase file size. You can choose from the following dither options:

None Does not dither colors but instead uses the color closest to the missing color. This tends to result in sharp transitions between shades of color in the image, creating a posterized effect.

Diffusion Uses an error-diffusion method that produces a less-structured dither than the Pattern option. To protect colors in the image that contain entries in the color table from being dithered, select Preserve Exact Colors. This is useful for preserving fine lines and text for web images.

Pattern Uses a halftone-like square pattern to simulate any colors not in the color table.

Noise Helps to reduce seam patterns along the edges of image slices. Choose this option if you plan to slice the image for placement in an HTML table.

More Help topics

Color modes

Customize indexed color tables

Adding a conditional mode change to an action

About color

Note: *For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.*

Understanding color

Knowing how colors are created and how they relate to each other lets you work more effectively in Photoshop. Instead of achieving an effect by accident, you'll produce consistent results thanks to an understanding of basic color theory.

Primary colors

Additive primaries are the three colors of light (red, green, and blue) that produce all the colors in the visible spectrum when added together in different combinations. Adding equal parts of red, blue, and green light produces white. The complete absence of red, blue, and green light results in black. Computer monitors are devices that use the additive primaries to create color.



A *Red* ***B*** *Green* ***C*** *Blue*

Subtractive primaries are pigments, which create a spectrum of colors in different combinations. Unlike monitors, printers use subtractive primaries (cyan, magenta, yellow, and black pigments) to produce colors through subtractive mixing. The term "subtractive" is used because the primary colors are pure until you begin mixing them together, resulting in colors that are less pure versions of the primaries. For example, orange is created through the subtractive mixing of magenta and yellow together.



A Cyan *B Magenta* *C Yellow* *D Black*

The color wheel

If you're new to adjusting color components, it helps to keep a standard color wheel diagram on hand when you work on color balance. You can use the color wheel to predict how a change in one color component affects other colors and also how changes translate between RGB and CMYK color models.



A Red *B Yellow* *C Green* *D Cyan* *E Blue* *F Magenta*

For example, you can decrease the amount of any color in an image by increasing the amount of its opposite on the color wheel—and vice versa. Colors that lie opposite each other on the standard color wheel are known as *complementary* colors. Similarly, you can increase and decrease a color by adjusting the two adjacent colors on the wheel, or even by adjusting the two colors adjacent to its opposite.

In a CMYK image, you can decrease magenta either by decreasing the amount of magenta or by increasing its complement, which is green (the color on the opposite side of the color wheel from magenta). In an RGB image, you can decrease magenta by removing red and blue or by adding green. All of these adjustments result in an overall color balance containing less magenta.

Color models, spaces, and modes

A color model describes the colors we see and work with in digital images. Each color model, such as RGB, CMYK, or HSB, represents a different method (usually numeric) for describing color.

A color space is a variant of a color model and has a specific gamut (range) of colors. For example, within the RGB color model are a number of color spaces: Adobe RGB, sRGB, ProPhoto RGB, and so on.

Each device, like your monitor or printer, has its own color space and can only reproduce colors in its gamut. When an image moves from one device to another, image colors may change because each device interprets the RGB or CMYK values according to its own color space. You can use color management when moving images to ensure that most colors are the same or similar enough so they appear consistent. See Why colors sometimes don't match.

In Photoshop, a document's color mode determines which color model is used to display and print the image you're working on. Photoshop bases its color modes on the color models that are useful for images used in publishing. You can choose from RGB (Red, Green, Blue), CMYK (Cyan, Magenta, Yellow, Black), Lab Color (based on CIE L* a* b*), and Grayscale. Photoshop also includes modes for specialized color output such as Indexed Color and Duotone. Color modes determine the number of colors, the number of channels, and the file size of an image. Choosing a color mode also determines which tools and file formats are available. See Color modes.

When you work with the colors in an image, you are adjusting numerical values in the file. It's easy to think of a number as a color, but these numerical values are not absolute colors in themselves—they only have a color meaning within the color space of the device that is producing the color.

Adjust color hue, saturation, and brightness

Based on the human perception of color, the HSB model describes three fundamental characteristics of color:

Hue Color reflected from or transmitted through an object. It is measured as a location on the standard color wheel, expressed as a degree between 0° and 360°. In common use, hue is identified by the name of the color, such as red, orange, or green.

Saturation Strength or purity of the color (sometimes called *chroma*). Saturation represents the amount of gray in proportion to the hue, measured as a percentage from 0% (gray) to 100% (fully saturated). On the standard color wheel, saturation increases from the center to the edge.

Brightness Relative lightness or darkness of the color, usually measured as a percentage from 0% (black) to 100% (white).



***A** Hue **B** Saturation **C** Brightness*

More Help topics

Understanding color management

Choose a color with the Adobe Color Picker

Color and monochrome adjustments using channels

Mix color channels

Using the Channel Mixer adjustment, you can create high-quality grayscale, sepia tone, or other tinted images. You can also make creative color adjustments to an image. To create high-quality grayscale images, choose the percentage for each color channel in the Channel Mixer adjustment. To convert a color image to grayscale and add tinting to the image, use the Black & White command (see Convert a color image to black and white).

The Channel Mixer adjustment options modify a targeted (output) color channel using a mix of the existing (source) color channels in the image. Color channels are grayscale images representing the tonal values of the color components in an image (RGB or CMYK). When you use the Channel Mixer, you are adding or subtracting grayscale data from a source channel to the targeted channel. You are not adding or subtracting colors to a specific color component as you do with the Selective Color adjustment.

Channel Mixer presets are available from the Preset menu in the Properties panel. Use the default Channel Mixer presets to create, save, and load custom presets.

Mix color channels

1 In the Channels panel, select the composite color channel.

2 To access the Channel Mixer adjustment, do one of the following:

- Click the Channel Mixer icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Channel Mixer. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Channel Mixer. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

3 Do one of the following:

- In the Properties panel, choose a channel from the Output Channel menu in which to blend one or more existing channels.
- In the Properties panel, choose a Channel Mixer preset from the Preset menu.

Choosing an output channel sets the source slider for that channel to 100% and all other channels to 0%. For example, choosing Red as the output channel sets the Source Channels sliders to 100% for Red, and to 0% for Green and Blue (in an RGB image).

4 To decrease the channel's contribution to the output channel, drag a source channel slider to the left. To increase the channel's contribution, drag a source channel slider to the right or enter a value between -200% and +200% in the box. Using a negative value inverts the source channel before adding it to the output channel.

Photoshop displays the total value of the source channels in the Total field. If the combined channel values are above 100%, Photoshop displays a warning icon next to the total.

5 Drag the slider or enter a value for the Constant option.

This option adjusts the grayscale value of the output channel. Negative values add more black, and positive values add more white. A -200% value makes the output channel black, and a +200% value makes the output channel white.

You can save Channel Mixer dialog box settings for reuse on other images. See Save adjustment settingsand Reapply adjustment settings.

Create monochrome images from RGB or CMYK images

Monochrome images display color channels as gray values. Adjust the percentage of each source channel to fine-tune the overall grayscale image.

1 In the Channels panel, select the composite color channel.

2 Apply a Channel Mixer adjustment.

3 In the Properties panel, do one of the following:

- Select Monochrome.
- Select one of the default presets from the Channel Mixer menu:**Black & White Infrared (RGB)**Red=-70%, Green=200%, Blue=-30%**Black & White With Blue Filter (RGB)**Red=0%, Green=0%, Blue=100%**Black & White With Green Filter (RGB)**Red=0%, Green=100%, Blue=0%**Black & White With Orange Filter (RGB)**Red=50%, Green=50%, Blue=0%**Black & White With Red Filter (RGB)**Red=100%, Green=0%, Blue=0%**Black & White With Yellow Filter (RGB)**Red=34%, Green=66%, Blue=0%

4 To control the amount of detail and contrast in the images before you convert them to grayscale, use the source channel sliders.

Before adjusting the percentages of the source channels, view how each source channel affects the monochrome image. For example, in RGB, view the image with the Red channel set to +100% and the Green and Blue source channels set to 0%. Then, view the image with the Green source channel set to +100% and the other two channels set to 0%. Finally, view the image with Blue source channel set to +100% and the other channels set to 0%.

The Total value displays the total percentage of the source channels. For best results, adjust the source channels so the combined values equal 100%. If the combined values are above 100%, a warning icon appears next to the total, indicating that the processed image will be brighter than the original, possibly removing highlight detail.

5 (Optional) Drag the slider or enter a value for the Constant option.

This option adjusts the grayscale value of the output channel. Negative values add more black, and positive values add more white. A -200% value makes the output channel black; a +200% value makes the output channel white.

Create a hand-tinted appearance for specific image elements

1 In the Channels panel, select the composite color channel.

2 Apply a Channel Mixer adjustment.

3 In the Properties panel, select and then deselect Monochrome.

4 Choose an Output Channel option, and adjust the source channel sliders. (Repeat this step as desired for each output channel.)



***A** Original color image **B** Selecting Monochrome creates grayscale image **C** Deselecting Monochrome and mixing channels tints elements of grayscale image*

More Help topics

Save adjustment settings

Reapply adjustment settings

Erase parts of an image



Erase with the Eraser tool

The Eraser tool changes pixels to either the background color or to transparent. If you're working on a background or in a layer with transparency locked, the pixels change to the background color; otherwise, the pixels are erased to transparency.

You can also use the eraser to return the affected area to a state selected in the History panel.

1 Select the Eraser tool .

2 Set the background color you want to apply if you are erasing in the background or a layer with locked transparency.

3 In the options bar, choose a Mode setting. Brush and Pencil set the eraser to act like those tools. Block is a hard-edged, fixed-sized square with no options for changing the opacity or flow.

4 For Brush and Pencil modes, choose a brush preset, and set Opacity and Flow in the options bar.

An opacity of 100% erases pixels completely. A lower opacity erases pixels partially. See Paint tool options.

5 To erase to a saved state or snapshot of the image, click the left column of the state or snapshot in the History panel, and then select Erase To History in the options bar.

To temporarily use the Eraser tool in Erase To History mode, hold down Alt (Windows) or Option (Mac OS) as you drag in the image.

6 Drag through the area you want to erase.

Change similar pixels with the Magic Eraser tool

When you click in a layer with the Magic Eraser tool, the tool changes all similar pixels to transparent. If you're working in a layer with locked transparency, the pixels change to the background color. If you click in the background, it is converted to a layer and all similar pixels change to transparent.

You can choose to erase contiguous pixels only or all similar pixels on the current layer.



1 Select the Magic Eraser tool .

2 Do the following in the options bar:

- Enter a tolerance value to define the range of colors that can be erased. A low tolerance erases pixels within a range of color values very similar to the pixel you click. A high tolerance extends the range of colors that will be erased.
- Select Anti-aliased to smooth the edges of the area you erase.
- Select Contiguous to erase only pixels contiguous to the one you click, or deselect to erase all similar pixels in the image.
- Select Sample All Layers to sample the erased color using combined data from all visible layers.
- Specify an opacity to define the strength of the erasure. An opacity of 100% erases pixels completely. A lower opacity erases pixels partially.

3 Click in the part of the layer you want to erase.

Change pixels to transparent with the Background Eraser tool

The Background Eraser tool erases pixels on a layer to transparency as you drag. You can erase the background while maintaining the edges of an object in the foreground. By specifying different sampling and tolerance options, you can control the range of the transparency and the sharpness of the boundaries.

If you want to erase the background of an object with intricate or wispy edges, use QuickSelect.

The background eraser samples the color in the center of the brush, also called the hotspot, and deletes that color wherever it appears inside the brush. It also performs color extraction at the edges of any foreground objects, so that color halos are not visible if the foreground object is later pasted into another image.

Note: *The background eraser overrides the lock transparency setting of a layer.*

1 In the Layers panel, select the layer containing the areas you want to erase.

2 Select the Background Eraser tool . (If the tool isn't visible, hold down the Eraser tool , and choose the Background Eraser from the pop-up menu.)

3 Click the brush sample in the options bar, and set brush options in the pop-up panel:

- Choose settings for the Diameter, Hardness, Spacing, Angle, and Roundness options (see Standard brush tip shape options).
- If you're using a pressure-sensitive digitizing tablet, choose options from the Size and Tolerance menus to vary the size and tolerance of the background eraser over the course of a stroke. Choose Pen Pressure to base the variation on the pen pressure. Choose Stylus Wheel to base the variation on the position of the pen thumbwheel. Choose Off if you don't want to vary the size or tolerance.

4 Do the following in the options bar:

- Choose a Limits mode for erasing: Discontiguous to erase the sampled color wherever it occurs under the brush; Contiguous to erase areas that contain the sampled color and are connected to one another; and Find Edges to erase connected areas containing the sampled color while better preserving the sharpness of shape edges.
- For Tolerance, enter a value or drag the slider. A low tolerance limits erasure to areas that are very similar to the sampled color. A high tolerance erases a broader range of colors.
- Select Protect Foreground Color to prevent the erasure of areas that match the foreground color in the toolbox.
- Choose a Sampling option: Continuous to sample colors continuously as you drag; Once to erase only areas containing the color you first click; and Background Swatch to erase only areas containing the current background color.

5 Drag through the area you want to erase. The Background Eraser tool pointer appears as a brush shape with a cross hair indicating the tool's hot spot .

Auto Erase with the Pencil tool

The Auto Erase option for the Pencil tool lets you paint the background color over areas containing the foreground color.

1 Specify foreground and background colors.

2 Select the Pencil tool .

3 Select Auto Erase in the options bar.

4 Drag over the image.

If the center of the cursor is over the foreground color when you begin dragging, the area is erased to the background color. If the center of the cursor is over an area that doesn't contain the foreground color when you begin dragging, the area is painted with the foreground color.

More Help topics

Painting tools

Standard brush tip shape options

Bristle tip shape options

Create patterns

Visually resize or change hardness of painting cursors

Choose colors

About foreground and background colors

Photoshop uses the *foreground* color to paint, fill, and stroke selections and the *background* color to make gradient fills and fill in the erased areas of an image. The foreground and background colors are also used by some special effects filters.

You can designate a new foreground or background color using the Eyedropper tool, the Color panel, the Swatches panel, or the Adobe Color Picker.

The default foreground color is black, and the default background color is white. (In an alpha channel, the default foreground is white, and the background is black.)

Choose colors in the toolbox

The current foreground color appears in the upper color selection box in the toolbox; the current background color appears in the lower box.



***A** Default Colors icon **B** Switch Colors icon **C** Foreground color box **D** Background color box*

- To change the foreground color, click the upper color selection box in the toolbox, and then choose a color in the Adobe Color Picker.
- To change the background color, click the lower color selection box in the toolbox, and then choose a color in the Adobe Color Picker.
- To reverse the foreground and background colors, click the Switch Colors icon in the toolbox.
- To restore the default foreground and background colors, click the Default Colors icon in the toolbox.

Choose colors with the Eyedropper tool

The Eyedropper tool samples color to designate a new foreground or background color. You can sample from the active image or from anywhere else on the screen.

1 Select the Eyedropper tool .

2 In the options bar, change the sample size of the eyedropper by choosing an option from the Sample Size menu:

Point Sample Reads the precise value of the pixel you click.

3 by 3 Average, 5 by 5 Average, 11 by 11 Average, 31 by 31 Average, 51 by 51 Average, 101 by 101 Average Reads the average value of the specified number of pixels within the area you click.



3 Choose one of the following from the Sample menu:

All Layers Samples color from all layers in the document.

Current Layer Samples color from the currently active layer.

4 To circle the Eyedropper tool with a ring that previews the sampled color above the current foreground color, select Show Sampling Ring. (This option requires OpenGL. See Enable OpenGL and optimize GPU settings.)

5 Do one of the following:

- To select a new foreground color, click in the image. Alternatively, position the pointer over the image, press the mouse button, and drag anywhere on the screen. The foreground color selection box changes dynamically as you drag. Release the mouse button to pick the new color.
- To select a new background color, Alt-click (Windows) or Option-click (Mac OS) in the image. Alternatively, position the pointer over the image, press Alt (Windows) or Options (Mac OS), press the mouse button, and drag anywhere on the screen. The background color selection box changes dynamically as you drag. Release the mouse button to pick the new color.

To use the Eyedropper tool temporarily to select a foreground color while using any painting tool, hold down Alt (Windows) or Option (Mac OS).

Adobe Color Picker overview

In the Adobe Color Picker, you choose colors using four color models: HSB, RGB, Lab, and CMYK. Use the Adobe Color Picker to set the foreground color, background color, and text color. You can also set target colors for different tools, commands, and options.

You can configure the Adobe Color Picker to let you choose only colors that are part of the web-safe palette or choose from specific color systems. You can also access an HDR (high dynamic range) picker to choose colors for use in HDR images.

The Color field in the Adobe Color Picker displays color components in HSB color mode, RGB color mode, and Lab color mode. If you know the numeric value of the color you want, you can enter it into the text fields. You can also use the color slider and the color field to preview a color to choose. As you adjust the color using the color field and color slider, the numeric values are adjusted accordingly. The color box to the right of the color slider displays the adjusted color in the top section and the original color in the bottom section. Alerts appear if the color is not a web-safe color or is out of gamut for printing (non-printable) .



***A** Picked color **B** Original color **C** Adjusted color **D** Out-of-gamut alert icon **E** Alert icon for color that is not web-safe **F** Displays only web-safe colors **G** Color field **H** Color slider **I** Color values*

When you select a color in the Adobe Color Picker, it simultaneously displays the numeric values for HSB, RGB, Lab, CMYK, and hexadecimal numbers. This is useful for viewing how the different color models describe a color.

Although Photoshop uses the Adobe Color Picker by default, you can use a different color picker than the Adobe Color Picker by setting a preference. For example, you can use the built-in color picker of your computer's operating system or a third-party plug-in color picker.

Display the Color Picker

- In the toolbox, click the foreground or background color selection box.
- In the Color panel, click the Set Foreground Color or Set Background Color selection box.

  The Color Picker is also available when features let you choose a color. For example, by clicking the color swatch in the options bar for some tools, or the eyedroppers in some color adjustment dialog boxes.

Choose a color with the Adobe Color Picker

You can choose a color by entering color component values in HSB, RGB, and Lab text boxes, or by using the color slider and the color field.

To choose a color with the color slider and color field, click in the color slider or move the color slider triangle to set one color component. Then move the circular marker or click in the color field. This sets the other two color components.

As you adjust the color using the color field and color slider, the numeric values for the different color models adjust accordingly. The rectangle to the right of the color slider displays the new color in the top half and the original color in the bottom. Alerts appear if the color is not a web-safe color or is out of gamut .

You can choose a color outside the Adobe Color Picker window. Moving the pointer over the document window changes it to the Eyedropper tool. You can then select a color by clicking in the image. The selected color is displayed in the Adobe Color Picker. You can move the Eyedropper tool anywhere on your desktop by clicking in the image and then holding down the mouse button. You can select a color by releasing the mouse button.

Choose a color using the HSB model

Using the HSB color model, the hue is specified in the color field, as an angle from 0° to 360° that corresponds to a location on the color wheel. Saturation and brightness are specified as percentages. In the color field, the hue saturation increases from left to right and the brightness increases from the bottom to top.

1 In the Adobe Color Picker, select the H option and then enter a numeric value in the H text box or select a hue in the color slider.

2 Adjust the saturation and brightness by clicking in the color field, moving the circular maker, or entering numeric values in the S and B text boxes.

3 (Optional) Select either the S option or B option to display the color's saturation or brightness in the color field for making further adjustments.

Choose a color using the RGB model

Choose a color by specifying its red, green, and blue components.

1 In the Adobe Color Picker, enter numeric values in the R, G, and B text boxes. Specify component values from 0 to 255 (0 is no color, and 255 is the pure color).

2 To visually select a color using the color slider and color field, click either R, G, or B and then adjust the slider and color field.

   The color you click appears in the color slider with 0 (none of that color) at the bottom and 255 (maximum amount of that color) at the top. The color field displays the range of the other two components, one on the horizontal axis and one on the vertical axis.

Choose a color using the Lab model

When choosing a color based on the Lab color model, the L value specifies the luminance of a color. The A value specifies how red or green a color is. The B value specifies how blue or yellow a color is.

1 In the Adobe Color Picker, enter values for L (from 0 to 100), and for A and B (from -128 to +127).

2 (Optional) Use the color slider or color field to adjust the color.

Choose a color using the CMYK model

You can choose a color by specifying each component value as a percentage of cyan, magenta, yellow, and black.

? In the Adobe Color Picker, enter percentage values for C, M, Y, and K, or use the color slider and color field to choose a color.

Choose a color by specifying a hexadecimal value

You can choose a color by specifying a hexadecimal value that defines the R, G, and B components in a color. The three pairs of numbers are expressed in values from 00 (minimum luminance) to ff (maximum luminance). For example, 000000 is black, ffffff is white, and ff0000 is red.

? In the Adobe Color Picker, enter a hexadecimal value in the # text box.

Choose a color while painting

The heads-up-display (HUD) color picker lets you quickly choose colors while painting in the document window, where image colors provide helpful context.

Note: *The HUD color picker requires OpenGL. (See Enable OpenGL and optimize GPU settings.)*

Choose the type of HUD color picker

1 Choose Edit > Preferences > General (Windows) or Photoshop > Preferences > General (Mac OS).

2 From the HUD Color Picker menu, choose Hue Strip to display a vertical picker or Hue Wheel to display a circular one.

Choose a color from the HUD color picker

1 Select a painting tool.

2 Press Shift + Alt + right-click (Windows) or Control + Option + Command (Mac OS).

3 Click in the document window to display the picker. Then drag to select a color hue and shade.

After clicking in the document window, you can release the pressed keys. Temporarily press the spacebar to maintain the selected shade while you select another hue, or vice versa.



***A** Shade **B** Hue*

To instead select a color from the image, hold down Alt (Windows) or Option (Mac OS) to access the Eyedropper tool.

Choose web-safe colors

The *web-safe colors* are the 216 colors used by browsers regardless of the platform. The browser changes all colors in the image to these colors when displaying the image on an 8-bit screen. The 216 colors are a subset of the Mac OS 8-bit color palettes. By working only with these colors, you can be sure that art you prepare for the web will not dither on a system set to display 256 colors.

Select web-safe colors in the Adobe Color Picker

? Select the Only Web Colors option in the lower left corner of the Adobe Color Picker. Any color you pick with this option selected is web-safe.

Change a non-web color to a web-safe color

If you select a non-web color, an alert cube appears next to the color rectangle in the Adobe Color Picker.

? Click the alert cube to select the closest web color. (If no alert cube appears, the color you chose is web-safe.)

Select a web-safe color using the Color panel

1 Click the Color panel tab, or choose Window > Color to view the Color panel.

2 Choose an option for selecting a web-safe color:

- Choose Make Ramp Web Safe from the Color panel menu. Any color you pick with this option selected is web-safe.

- Choose Web Color Sliders from the Color panel menu. By default, web color sliders snap to web-safe colors (indicated by tick marks) when you drag them. To override web-safe color selection, Alt-drag (Windows) or Option-drag (Mac OS) the sliders.

If you choose a non-web color, an alert cube appears above the color ramp on the left side of the Color panel. Click the alert cube to select the closest web color.

Choose a CMYK equivalent for a non-printable color

Some colors in the RGB, HSB, and Lab color models cannot be printed because they are out-of-gamut and have no equivalents in the CMYK model. When you choose a non-printable color in either the Adobe Color Picker or the Color panel, a warning alert triangle appears. A swatch below the triangle displays the closest CMYK equivalent.

Note: *In the Color panel, the alert triangle is not available if you are using Web Color Sliders.*

? To choose the closest CMYK equivalent, click the alert triangle in the Color Picker dialog box or the Color panel.

Printable colors are determined by the current CMYK working space defined in the Color Settings dialog box.

Choose a spot color

The Adobe Color Picker lets you choose colors from the PANTONE MATCHING SYSTEM®, the Trumatch® Swatching System™, the Focoltone® Colour System, the Toyo Color Finder™ 1050 system, the ANPA-Color™ system, the HKS® color system, and the DIC Color Guide.

To ensure that the final printed output is the color you want, consult your printer or service bureau and choose your color based on a printed color swatch. Manufacturers recommend that you get a new swatch book each year to compensate for fading inks and other damage.

Note: *Photoshop prints spot colors to CMYK (process color) plates in every image mode except Duotone. To print true spot color plates, create spot color channels.*

1. Open the Adobe Color Picker, and click Color Libraries.

   The Custom Colors dialog box displays the color closest to the color currently selected in the Adobe Color Picker.

2. For Book, choose a color library. See below for descriptions of the color libraries.
3. Locate the color you want by entering the ink number or by dragging the triangles along the scroll bar.
4. Click the desired color patch in the list.

Spot color libraries

The Adobe Color Picker supports the following color systems:

ANPA-COLOR Commonly used for newspaper applications. The *ANPA-COLOR ROP Newspaper Color Ink Book* contains samples of the ANPA colors.

DIC Color Guide Commonly used for printing projects in Japan. For more information, contact Dainippon Ink & Chemicals, Inc., in Tokyo, Japan.

FOCOLTONE Consists of 763 CMYK colors. Focoltone colors help avoid prepress trapping and registration problems by showing the overprints that make up the colors. A swatch book with specifications for process and spot colors, overprint charts, and a chip book for marking up layouts are available from Focoltone. For more information, contact Focoltone International, Ltd., in Stafford, United Kingdom.

HKS swatches Used for printing projects in Europe. Each color has a specified CMYK equivalent. You can select from HKS E (for continuous stationery), HKS K (for gloss art paper), HKS N (for natural paper), and HKS Z (for newsprint). Color samplers for each scale are available. HKS Process books and swatches have been added to the color system menu.

PANTONE® Colors used for spot-color reproduction. The PANTONE MATCHING SYSTEM can render 1,114 colors. PANTONE color guides and chip books are printed on coated, uncoated, and matte paper stocks to ensure accurate visualization of the printed result and better on-press control. You can print a solid PANTONE color in CMYK. To compare a solid PANTONE color to its closest process color match, use the *PANTONE solid to process* guide. The CMYK screen tint percentages are printed under each color. For more information, contact Pantone, Inc., Carlstadt, NJ (www.pantone.com).

TOYO Color Finder 1050 Consists of more than 1,000 colors based on the most common printing inks used in Japan. The TOYO Process Color Finder book and swatches have been added to the color system menu. The TOYO Color Finder 1050 Book contains printed samples of Toyo colors and is available from printers and graphic arts supply stores. For more information, contact Toyo Ink Manufacturing Co., Ltd., in Tokyo, Japan.

TRUMATCH Provides predictable CMYK color matching with more than 2,000 achievable, computer-generated colors. Trumatch colors cover the visible spectrum of the CMYK gamut in even steps. The Trumatch Color displays up to 40 tints and shades of each hue, each originally created in four-color process and each reproducible in four colors on electronic imagesetters. In addition, four-color grays using different hues are included. For more information, contact Trumatch Inc., in New York City, New York.

More Help topics

Customize color pickers and swatches

Match, replace, and mix colors

Improving tonal quality with Levels

Choose colors in the Color and Swatches panels

Identify out-of-gamut colors

About the HDR Color Picker

About spot colors

Viewing multiple images

View images in multiple windows

The document window is where your images appear. You can open multiple windows to display different images or different views of the same one. A list of open windows appears in the Window menu. To bring an open image to the front, choose the file name from the bottom of the Window menu. Available memory may limit the number of windows per image.

1 Choose Window > Arrange > New Window For *[Image File Name]*.

2 If you want to arrange the windows, choose Window > Arrange and then choose one of the following:

Cascade Displays undocked windows stacked and cascading from the upper-left to the lower right of the screen.

Tile Displays windows edge to edge. As you close images, the open windows are resized to fill the available space.

Float in Window Allows image to float freely.

Float All in Windows Floats all images.

Consolidate All to Tabs Shows one image in full screen and minimizes the other images to tabs.

You can use the Hand tool's Scroll All Windows option to scroll through all open images. Select it in the options bar and drag in one image to scroll through all visible images.

Match zoom and location in multiple images

Match only zoom

1 Open one or more images, or open one image in multiple windows.

2 Choose Window > Arrange > Tile to display the images edge to edge.

3 Select the Zoom tool, and then do one of the following:

- Select Zoom All Windows in the options bar, and then click one of the images. The other images zoom in or out the same relative amount.
- Choose Window > Arrange > Match Zoom. Hold down the Shift key and click one of the images. The other images zoom in or out at the same magnification.

Match only location

1 Open one or more images, or open one image in multiple windows.

2 Choose Window > Arrange > Tile.

3 Do either of the following:

- Choose Window > Arrange > Match Location.
- Select the Hand tool, select Scroll All Windows in the options bar, and then drag to view another area in one of the images. (To temporarily enable this option, hold down the Shift key while dragging with the Hand tool.)

Note: *Photoshop automatically scrolls to the same relative location on the horizontal and vertical axes. You may need to manually scroll to reveal the edges of images.*

Match zoom and location

1 Open one or more images, or open one image in multiple windows.

2 Choose Window > Arrange > Tile.

3 Choose Window > Arrange > Match All.



4 Select the Zoom tool or the Hand tool.

5 Select one of the images, hold down the Shift key, and click in or drag an area of an image. The other images are magnified to the same percentage and snap to the area you clicked.

More Help topics

Viewing images

Combining multiple images into a group portrait

Placing Photoshop images in other applications

Use Camera Raw for photo correction

Blending modes

The blending mode specified in the options bar controls how pixels in the image are affected by a painting or editing tool. Think in terms of the following colors when visualizing a blending mode's effect:

- The *base color* is the original color in the image.
- The *blend color* is the color being applied with the painting or editing tool.
- The *result color* is the color resulting from the blend.

Blending mode descriptions

Choose from the Mode pop-up menu in the options bar.

Note: *Only the Normal, Dissolve, Darken, Multiply, Lighten, Linear Dodge (Add), Difference, Hue, Saturation, Color, Luminosity, Lighter Color, and Darker Color blending modes are available for 32-bit images.*

Normal Edits or paints each pixel to make it the result color. This is the default mode. (Normal mode is called *Threshold* when you're working with a bitmapped or indexed-color image.)

Dissolve Edits or paints each pixel to make it the result color. However, the result color is a random replacement of the pixels with the base color or the blend color, depending on the opacity at any pixel location.

Behind Edits or paints only on the transparent part of a layer. This mode works only in layers with Lock Transparency deselected and is analogous to painting on the back of transparent areas on a sheet of acetate.

Clear Edits or paints each pixel and makes it transparent. This mode is available for the Shape tools (when fill region ☐ is selected), Paint Bucket tool , Brush tool , Pencil tool , Fill command, and Stroke command. You must be in a layer with Lock Transparency deselected to use this mode.

Darken Looks at the color information in each channel and selects the base or blend color—whichever is darker—as the result color. Pixels lighter than the blend color are replaced, and pixels darker than the blend color do not change.

Multiply Looks at the color information in each channel and multiplies the base color by the blend color. The result color is always a darker color. Multiplying any color with black produces black. Multiplying any color with white leaves the color unchanged. When you're painting with a color other than black or white, successive strokes with a painting tool produce progressively darker colors. The effect is similar to drawing on the image with multiple marking pens.

Color Burn Looks at the color information in each channel and darkens the base color to reflect the blend color by increasing the contrast between the two. Blending with white produces no change.

Linear Burn Looks at the color information in each channel and darkens the base color to reflect the blend color by decreasing the brightness. Blending with white produces no change.

Lighten Looks at the color information in each channel and selects the base or blend color—whichever is lighter—as the result color. Pixels darker than the blend color are replaced, and pixels lighter than the blend color do not change.

Screen Looks at each channel's color information and multiplies the inverse of the blend and base colors. The result color is always a lighter color. Screening with black leaves the color unchanged. Screening with white produces white. The effect is similar to projecting multiple photographic slides on top of each other.

Color Dodge Looks at the color information in each channel and brightens the base color to reflect the blend color by decreasing contrast between the two. Blending with black produces no change.

Linear Dodge (Add) Looks at the color information in each channel and brightens the base color to reflect the blend color by increasing the brightness. Blending with black produces no change.

Overlay Multiplies or screens the colors, depending on the base color. Patterns or colors overlay the existing pixels while preserving the highlights and shadows of the base color. The base color is not replaced, but mixed with the blend color to reflect the lightness or darkness of the original color.

Soft Light Darkens or lightens the colors, depending on the blend color. The effect is similar to shining a diffused spotlight on the image. If the blend color (light source) is lighter than 50% gray, the image is lightened as if it were dodged. If the blend color is darker than 50% gray, the image is darkened as if it were burned in. Painting with pure black or white produces a distinctly darker or lighter area, but does not result in pure black or white.

Hard Light Multiplies or screens the colors, depending on the blend color. The effect is similar to shining a harsh spotlight on the image. If the blend color (light source) is lighter than 50% gray, the image is lightened, as if it were screened. This is useful for adding highlights to an image. If the blend color is darker than 50% gray, the image is darkened, as if it were multiplied. This is useful for adding shadows to an image. Painting with pure black or white results in pure black or white.

Vivid Light Burns or dodges the colors by increasing or decreasing the contrast, depending on the blend color. If the blend color (light source) is lighter than 50% gray, the image is lightened by decreasing the contrast. If the blend color is darker than 50% gray, the image is darkened by increasing the contrast.

Linear Light Burns or dodges the colors by decreasing or increasing the brightness, depending on the blend color. If the blend color (light source) is lighter than 50% gray, the image is lightened by increasing the brightness. If the blend color is darker than 50% gray, the image is darkened by decreasing the brightness.

Pin Light Replaces the colors, depending on the blend color. If the blend color (light source) is lighter than 50% gray, pixels darker than the blend color are replaced, and pixels lighter than the blend color do not change. If the blend color is darker than 50% gray, pixels lighter than the blend color are replaced, and pixels darker than the blend color do not change. This is useful for adding special effects to an image.

Hard Mix Adds the red, green and blue channel values of the blend color to the RGB values of the base color. If the resulting sum for a channel is 255 or greater, it receives a value of 255; if less than 255, a value of 0. Therefore, all blended pixels have red, green, and blue channel values of either 0 or 255. This changes all pixels to primary additive colors (red, green, or blue), white, or black.

Note: *For CMYK images, Hard Mix changes all pixels to the primary subtractive colors (cyan, yellow, or magenta), white, or black. The maximum color value is 100.*

Difference Looks at the color information in each channel and subtracts either the blend color from the base color or the base color from the blend color, depending on which has the greater brightness value. Blending with white inverts the base color values; blending with black produces no change.

Exclusion Creates an effect similar to but lower in contrast than the Difference mode. Blending with white inverts the base color values. Blending with black produces no change.

Subtract Looks at the color information in each channel and subtracts the blend color from the base color. In 8- and 16-bit images, any resulting negative values are clipped to zero.

Divide Looks at the color information in each channel and divides the blend color from the base color.

Hue Creates a result color with the luminance and saturation of the base color and the hue of the blend color.

Saturation Creates a result color with the luminance and hue of the base color and the saturation of the blend color. Painting with this mode in an area with no (0) saturation (gray) causes no change.

Color Creates a result color with the luminance of the base color and the hue and saturation of the blend color. This preserves the gray levels in the image and is useful for coloring monochrome images and for tinting color images.

Luminosity Creates a result color with the hue and saturation of the base color and the luminance of the blend color. This mode creates the inverse effect of Color mode.

Lighter Color Compares the total of all channel values for the blend and base color and displays the higher value color. Lighter Color does not produce a third color, which can result from the Lighten blend, because it chooses the highest channel values from both the base and blend color to create the result color.

Darker Color Compares the total of all channel values for the blend and base color and displays the lower value color. Darker Color does not produce a third color, which can result from the Darken blend, because it chooses the lowest channel values from both the base and the blend color to create the result color.

Blending mode examples

These examples show the result of painting part of the image's face using each blending mode.

Original Image	*Normal, 100% opacity*	*Normal, 50% opacity*	*Dissolve, 50% opacity*
Behind	*Clear*	*Darken*	*Multiply*
Color Burn	*Linear Burn*	*Lighten*	*Screen*
Color Dodge	*Linear Dodge (Add)*	*Overlay*	*Soft Light*
Hard Light	*Vivid Light*	*Linear Light*	*Pin Light*

Hard Mix	*Difference*	*Exclusion*	*Subtract*
Divide	*Hue*	*Saturation*	*Color*
Luminosity, 80% opacity	*Lighter Color*	*Darker Color*	

Choose colors in the Color and Swatches panels

Color panel overview

The Color panel (Window > Color) displays the color values for the current foreground and background colors. Using the sliders in the Color panel, you can edit the foreground and background colors using different color models. You can also choose a foreground or background color from the spectrum of colors displayed in the color ramp at the bottom of the panel.



***A** Foreground color **B** Background color **C** Slider **D** Color ramp*

The Color panel may display the following alerts when you select a color:

- An exclamation point inside a triangle appears above the left side of the color ramp when you choose a color that cannot be printed using CMYK inks.
- A square appears above the left side of the color ramp when you choose a color that is not web-safe.

Change the color model of the Color panel sliders

? Choose a Sliders option from the Color panel menu.

Change the spectrum displayed in the Color panel

1 Choose an option from the Color panel menu:
   - RGB Spectrum, CMYK Spectrum, or Grayscale Ramp to display the spectrum of the specified color model.
   - Current Colors to display the spectrum of colors between the current foreground color and the current background color.
2 To display only web-safe colors, choose Make Ramp Web Safe.

To change the spectrum of the color ramp quickly, Shift-click in the color ramp until you see the spectrum you want.

Select a color in the Color panel

1 In the Color panel, click the foreground or background color box to make it active (outlined in black).

When the background color box is active in the Color panel, the Eyedropper tool changes the background color by default.

2 Do one of the following:
   - Drag the color sliders. By default, the slider colors change as you drag. You can turn off this feature to improve performance by deselecting Dynamic Color Sliders in the General section of the Preferences dialog box.
   - Enter values next to the color sliders.
   - Click the color selection box, choose a color using the Color Picker, and click OK.
   - Position the pointer over the color ramp (the pointer becomes the eyedropper), and click to sample a color. Alt-click to apply the sample to the non-active color selection box.

Select a color in the Swatches panel

The Swatches panel (Window > Swatches) stores colors that you use often. You can add or delete colors from the panel or display different libraries of colors for different projects.

- To choose a foreground color, click a color in the Swatches panel.
- To choose a background color, Ctrl-click (Windows) or Command-click (Mac OS) a color in the Swatches panel.

Note: *Change how swatches are displayed by choosing an option from the Swatches panel menu.*

More Help topics

Identify out-of-gamut colors

Color modes

Adobe Color Picker overview

Choose colors with the Eyedropper tool

Choose colors

Add a conditional mode change to an action

Add a conditional mode change to an action

You can specify conditions for a mode change so that the conversion can occur during an *action*, which is a series of commands applied sequentially to a single file or a batch of files. When a mode change is part of an action, an error can occur if the file being opened is not in the source mode specified in the action. For example, suppose one step in an action is to convert an image with a source mode of RGB to a target mode of CMYK. Applying this action to an image in Grayscale mode, or any other source mode besides RGB, results in an error.

When you record an action, you can use the Conditional Mode Change command to specify one or more modes for the source mode and a mode for the target mode.

1 Start recording an action.

2 Choose File > Automate > Conditional Mode Change.

3 In the Conditional Mode Change dialog box, select one or more modes for the source mode. Use the All or None buttons to select all possible modes or no mode.

4 Choose a target mode from the Mode pop-up menu.

5 Click OK. The conditional mode change appears as a new step in the Actions panel.

More Help topics

Playing and managing actions

Converting between color modes

Adding conditional actions | Creative Cloud

Add swatches from HTML CSS and SVG

Note: *This feature was introduced in the Creative Cloud release for Photoshop CS6.*

You can add all colors specified in an HTML, CSS, or SVG document to the **Swatches** panel. If a color value is repeated in a document, only one instance of the color is added not duplicates. This feature recognizes the following HTML/CSS color syntax: #112233, #123, rgb(1,2,3), rgba(1,2,3,4), hsb(1,2,3), and hsba(1,2,3,4).

1 In the **Swatches** panel, do one of the following:

- Choose **Load Swatches** from the panel menu.
- Choose **Replace Swatches** from the panel menu.

2 In the **Load** window, navigate to the HTML, CSS, or SVG file, select it, and then, click **Load**.

For more information, see Customizing color pickers and swatches.

Chapter 6: Layers

Layer basics

About Photoshop layers

Photoshop layers are like sheets of stacked acetate. You can see through transparent areas of a layer to the layers below. You move a layer to position the content on the layer, like sliding a sheet of acetate in a stack. You can also change the opacity of a layer to make content partially transparent.



You use layers to perform tasks such as compositing multiple images, adding text to an image, or adding vector graphic shapes. You can apply a layer style to add a special effect such as a drop shadow or a glow.

Organizing Photoshop layers

A new image has a single layer. The number of additional layers, layer effects, and layer sets you can add to an image is limited only by your computer's memory.

You work with layers in the Layers panel. *Layer groups* help you organize and manage layers. You can use groups to arrange your layers in a logical order and to reduce clutter in the Layers panel. You can nest groups within other groups. You can also use groups to apply attributes and masks to multiple layers simultaneously.

For some great tips for working with layers, see the tutorial video Organize with layers and layer groups .

Photoshop layers for non-destructive editing

Sometimes layers don't contain any apparent content. For example, an adjustment layer holds color or tonal adjustments that affect the layers below it. Rather than edit image pixels directly, you can edit an adjustment layer and leave the underlying pixels unchanged.

A special type of layer, called a Smart Object, contains one or more layers of content. You can transform (scale, skew, or reshape) a Smart Object without directly editing image pixels. Or, you can edit the Smart Object as a separate image even after placing it in a Photoshop image. Smart Objects can also contain smart filter effects, which allow you to apply filters non-destructively to images so that you can later tweak or remove the filter effect. See Nondestructive editingand Work with Smart Objects.

Video layers

You can use video layers to add video to an image. After importing a video clip into an image as a video layer, you can mask the layer, transform it, apply layer effects, paint on individual frames, or rasterize an individual frame and convert it to a standard layer. Use the Timeline panel to play the video within the image or to access individual frames. See Supported video and image sequence formats.

Photoshop Layers panel overview

The Layers panel in Photoshop lists all layers, layer groups, and layer effects in an image. You can use the Layers panel to show and hide layers, create new layers, and work with groups of layers. You can access additional commands and options in the Layers panel menu.



A Layers panel menu B Filter C Layer Group D Layer E Expand/Collapse Layer effects F Layer effect G Layer thumbnail

Display the Photoshop Layers panel

? Choose Window > Layers.

Choose a command from the Photoshop Layers panel menu

? Click the triangle in the upper-right corner of the panel.

Change the size of Photoshop layer thumbnails

? Choose Panel Options from the Layers panel menu, and select a thumbnail size.

Change thumbnail contents

? Choose Panel Options from the Layers panel menu, and select Entire Document to display the contents of the entire document. Select Layer Bounds to restrict the thumbnail to the object's pixels on the layer.

Turn off thumbnails to improve performance and save monitor space.

Expand and collapse groups

? Click the triangle to the left of a group folder. See View layers and groups within a group.

Filter Photoshop layers

At the top of the Layers panel, the filtering options help you find key layers in complex documents quickly. You can display a subset of layers based on name, kind, effect, mode, attribute, or color label.



1 Choose a filter type from the pop-up menu.
2 Select or enter the filter criteria.
3 Click the toggle switch to switch layer filtering on or off.

Convert background and Photoshop layers

When you create a new image with a white background or a colored background, the bottommost image in the Layers panel is called *Background*. An image can have only one background layer. You cannot change the stacking order of a background layer, its blending mode, or its opacity. However, you can convert a background into a regular layer, and then change any of these attributes.

When you create a new image with transparent content, the image does not have a background layer. The bottommost layer is not constrained like the background layer; you can move it anywhere in the Layers panel and change its opacity and blending mode.

Convert a background into a Photoshop layer

1 Double-click Background in the Layers panel, or choose Layer > New > Layer From Background.
2 Set layer options. (See Create layers and groups.)
3 Click OK.

Convert a Photoshop layer into a background

1 Select a Photoshop layer in the Layers panel.
2 Choose Layer > New > Background From Layer.

   Any transparent pixels in the layer are converted to the background color, and the layer drops to the bottom of the layer stack.

   Note: *You cannot create a background by giving a regular layer the name, Background—you must use the Background From Layer command.*

Duplicate Photoshop layers

You can duplicate layers within an image or into another or a new image.

Duplicate a Photoshop layer or group within an image

1 Select a layer or group in the Layers panel.
2 Do one of the following:
   - Drag the layer or group to the Create a New Layer button .

- Choose Duplicate Layer or Duplicate Group from the Layers menu or the Layers panel menu. Enter a name for the layer or group, and click OK.

Duplicate a Photoshop layer or group in another image

1 Open the source and destination images.

2 From the Layers panel of the source image, select one or more layers or a layer group.

3 Do one of the following:

- Drag the layer or group from the Layers panel to the destination image.
- Select the Move tool , and drag from the source image to the destination image. The duplicate layer or group appears above the active layer in the Layers panel of the destination image. Shift-drag to move the image content to the same location it occupied in the source image (if the source and destination images have the same pixel dimensions) or to the center of the document window (if the source and destination images have different pixel dimensions).
- Choose Duplicate Layer or Duplicate Group from the Layers menu or the Layers panel menu. Choose the destination document from the Document pop-up menu, and click OK.
- Choose Select > All to select all the pixels on the layer, and choose Edit > Copy. Then choose Edit > Paste in the destination image. (This method copies only pixels, excluding layer properties such as blending mode.)

Create a new document from a Photoshop layer or group

1 Select a layer or group from the Layers panel.

2 Choose Duplicate Layer or Duplicate Group from the Layers menu or the Layers panel menu.

3 Choose New from the Document pop-up menu, and click OK.

Sample from all visible Photoshop layers

The default behavior of the Mixer Brush, Magic Wand, Smudge, Blur, Sharpen, Paint Bucket, Clone Stamp, and Healing Brush tools is to sample color only from pixels on the active layer. This means you can smudge or sample in a single layer.

? To smudge or sample pixels from all visible layers with these tools, select Sample All Layers from the options bar.

Change transparency preferences

1 In Windows, choose Edit > Preferences > Transparency & Gamut; in Mac OS, choose Photoshop > Preferences > Transparency & Gamut.

2 Choose a size and color for the transparency checkerboard, or choose None for Grid Size to hide the transparency checkerboard.

3 Click OK.

More Help topics

Create and manage layers and groups

Select, group, and link layers

Work with Smart Objects

Nondestructive editing

Techniques for nondestructive editing

Nondestructive editing allows you to make changes to an image without overwriting the original image data, which remains available in case you want to revert to it. Because nondestructive editing doesn't remove data from an image, the image quality doesn't degrade when you make edits. You can perform nondestructive editing in Photoshop in several ways:

Working with adjustment layers Adjustment layers apply color and tonal adjustments to an image without permanently changing pixel values.

Transforming with Smart Objects Smart Objects enable nondestructive scaling, rotating, and warping.

Filtering with Smart Filters Filters applied to Smart Objects become Smart Filters and allow for nondestructive filter effects.

Adjusting variations, shadows, and highlights with Smart Objects Shadow/Highlight and Variations commands can be applied to a Smart Object as Smart Filters.

Retouching on a separate layer Clone Stamp, Healing Brush, and Spot Healing Brush tools let you retouch nondestructively on a separate layer. Be sure to select Sample All Layers from the options bar (select Ignore Adjustment Layers to ensure that adjustment layers won't affect the separate layer twice). You can discard unsatisfactory retouching, if necessary.

Editing in Camera Raw Adjustments to batches of raw, JPEG, or TIFF images preserve the original image data. Camera Raw stores adjustment settings on a per-image basis separately from the original image files.

Opening Camera Raw files as Smart Objects Before you can edit Camera Raw files in Photoshop, you must configure settings for them with Camera Raw. Once you edit a Camera Raw file in Photoshop, you can't reconfigure Camera Raw settings without losing the changes. Opening Camera Raw files in Photoshop as Smart Objects enables you to reconfigure Camera Raw settings at any time, even after you edit the file.

Cropping nondestructively After you create a cropping rectangle with the Crop tool, select Hide from the options bar to preserve the cropped area in a layer. Restore the cropped area anytime by choosing Image > Reveal All or by dragging the Crop tool beyond the edge of the image. The Hide option is unavailable for images that contain only a background layer.

Masking Layer and vector masks are nondestructive because you can re-edit the masks without losing the pixels they hide. Filter masks let you mask out the effects of Smart Filters on Smart Object layers.

More Help topics

About Camera Raw

About adjustment and fill layers

Work with Smart Objects

Apply Smart Filters

Understand color adjustments

Adjusting image color and tone

Crop images

About layer and vector masks

Retouch with the Clone Stamp tool

Retouch with the Healing Brush tool

Retouch with the Spot Healing Brush tool

Create and manage layers and groups

Create layers and groups

A new layer appears either above the selected layer or within the selected group in the Layers panel.

Create a new layer or group

1 Do one of the following:

- To create a new layer or group using default options, click the Create A New Layer button or New Group button in the Layers panel.
- Choose Layer > New > Layer or choose Layer > New > Group.
- Choose New Layer or New Group from the Layers panel menu.
- Alt-click (Windows) or Option-click (Mac OS) the Create A New Layer button or New Group button in the Layers panel to display the New Layer dialog box and set layer options.
- Ctrl-click (Windows) or Command-click (Mac OS) the Create A New Layer button or New Group button in the Layers panel to add a layer below the currently selected layer.

2 Set layer options, and click OK:

Name Specifies a name for the layer or group.

Use Previous Layer to Create Clipping Mask This option is not available for groups. (See Mask layers with clipping masks .)

Color Assigns a color to the layer or group in the Layers panel.

Mode Specifies a blending mode for the layer or group. (See Blending modes.)

Opacity Specifies an opacity level for the layer or group.

Fill With Mode-Neutral Color Fills the layer with a preset, neutral color.

Note: *To add currently selected layers to a new group, choose Layer > Group Layers, or Shift-click the New Group button at the bottom of the Layers panel.*

Create a layer from an existing file

1 Drag the file icon from Windows or Mac OS onto an open image in Photoshop.

2 Move, scale, or rotate the imported image. (See Place a file in Photoshop.)

3 Press Enter or Return.

By default, Photoshop creates a Smart Object layer. To create standard layers from dragged files, deselect Place Or Drag Raster Images As Smart Objects in the General preferences.

If the placed file is a multilayer image, a flattened version appears on the new layer. To instead copy separate layers, duplicate them in another image. (See Duplicate Photoshop layers.)

Create a layer with effects from another layer

1 Select the existing layer in the Layers panel.

2 Drag the layer to the Create A New Layer button at the bottom of the Layers panel. The newly created layer contains all the effects of the existing one.

Convert a selection into a new layer

1 Make a selection.

2 Do one of the following:

- Choose Layer > New > Layer Via Copy to copy the selection into a new layer.
- Choose Layer > New > Layer Via Cut to cut the selection and paste it into a new layer.

Note: *You must rasterize Smart Objects or shape layers to enable these commands.*

View layers and groups within a group

? Do one of the following to open the group:

- Click the triangle to the left of the folder icon .
- Right-click (Windows) or Control-click (Mac OS) the triangle to the left of the folder icon and choose Open This Group.
- Alt-click (Windows) or Option-click (Mac OS) the triangle to open or close a group and the groups nested within it.

Show or hide a layer, group, or style

Showing or hiding layers, groups, or styles lets you isolate or view only certain portions of your image for easy editing.

? Do one of the following in the Layers panel:

- Click the eye icon next to a layer, group, or layer effect to hide its content in the document window. Click in the column again to redisplay the content. To view the eye icon for styles and effects, click the Reveal Effects In panel icon .
- Choose Show Layers or Hide Layers from the Layers menu.
- Alt-click (Windows) or Option-click (Mac OS) an eye icon to display only the contents of that layer or group. Photoshop remembers the visibility states of all layers before hiding them. If you don't change the visibility of any other layer, Alt-clicking (Windows) or Option-clicking (Mac OS) the same eye icon restores the original visibility settings.
- Drag through the eye column to change the visibility of multiple items in the Layers panel.

Note: *Only visible layers are printed.*

More Help topics

Layer basics

Select, group, and link layers

Select layers

You can select one or more layers to work on them. For some activities, such as painting or making color and tonal adjustments, you can work on only one layer at a time. A single selected layer is called the *active layer*. The name of the active layer appears in the title bar of the document window.

For other activities, such as moving, aligning, transforming, or applying styles from the Styles panel, you can select and work on multiple layers at a time. You can select layers in the Layers panel or with the Move tool .

You can also link layers. Unlike multiple layers selected at the same time, linked layers stay linked when you change the selection in the Layers panel. See Link and unlink layers.

If you don't see the desired results when using a tool or applying a command, you may not have the correct layer selected. Check the Layers panel to make sure that you're working on the correct layer.

Select layers in the Layers panel

? Do one of the following:

- Click a layer in the Layers panel.
- To select multiple contiguous layers, click the first layer and then Shift-click the last layer.
- To select multiple noncontiguous layers, Ctrl-click (Windows) or Command-click (Mac OS) them in the Layers panel.

Note: *When selecting, Ctrl-click (Windows) or Command-click (Mac OS) the area outside the layer thumbnail. Ctrl-clicking or Command-clicking the layer thumbnail selects the nontransparent areas of the layer.*

- To select all layers, choose Select > All Layers.
- To select all layers of a similar type (for example all type layers), select one of the layers, and choose Select > Similar Layers.
- To deselect a layer, Ctrl-click (Windows) or Command-click (Mac OS) the layer.
- To have no layer selected, click in the Layers panel below the background or bottom layer, or choose Select > Deselect Layers.

Select layers in the document window

You can also select a layer or layers directly from the document window.

1 Select the Move tool .

2 Do one of the following:

- In the options bar, select Auto Select, then choose Layer from the drop-down menu, and click in the document on the layer you want to select. The top layer containing pixels under the cursor is selected.
- In the options bar, select Auto Select, then choose Group from the drop-down menu, and click in the document on the content you want to select. The top group containing pixels under the cursor is selected. If you click an ungrouped layer, it becomes selected.
- Right-click (Windows) or Control-click (Mac OS) in the image, and choose a layer from the context menu. The context menu lists all the layers that contain pixels under the current pointer location.

Select a layer in a group

You can open a group and then select an individual layer within that group.

1 Click the group in the Layers panel.

2 Click the triangle to the left of the folder icon .

3 Click the individual layer in the group.

Group and link layers

Grouping layers helps organize your projects and keeps your Layers panel uncluttered. By linking layers, you establish a relationship between them, even if they aren't next to each other in your layer order.

Group and ungroup layers

1 Select multiple layers in the Layers panel.

2 Do one of the following:

- Choose Layer > Group Layers.
- Alt-drag (Windows) or Option-drag (Mac OS) layers to the folder icon at the bottom of the Layers panel to group the layers.

3 To Ungroup the layers, select the group and choose Layer > Ungroup Layers.

Add layers to a group

? Do one of the following:

- Select the group in the Layers panel and click the Create a New Layer button .
- Drag a layer to the group folder.
- Drag a group folder into another group folder. The group and all of its layers move.
- Drag an existing group to the New Group button .

Link and unlink layers

You can link two or more layers or groups. Unlike multiple layers selected at the same time, linked layers retain their relationship until you unlink them. You can move or apply transformations to linked layers.

1 Select the layers or groups in the Layers panel.

2 Click the link icon at the bottom of the Layers panel.

3 To unlink layers do one of the following:

- Select a linked layer, and click the link icon.
- To temporarily disable the linked layer, Shift-click the Link icon for the linked layer. A red X appears. Shift-click the link icon to enable the link again.
- Select the linked layers and click the Link icon. To select all linked layers, select one of the layers and then choose Layer > Select Linked Layers.

Show layer edges and handles

Showing the boundary or edges of the content in a layer can help you move and align the content. You can also display the transform handles for selected layers and groups so that you can resize or rotate them.

Display the edges of content in a selected layer

? Choose View > Show > Layer Edges.

Display transform handles in a selected layer

1 Select the Move tool .

2 From the options bar, select Show Transform Controls.

You can resize and rotate layer content using the transform handles. See Transform freely.

More Help topics

Move, stack, and lock layers

Mask layers

You can add a mask to a layer and use the mask to hide portions of the layer and reveal the layers below. Masking layers is a valuable compositing technique for combining multiple photos into a single image or for removing a person or object from a photo.

About layer and vector masks

You can use masks to hide portions of a layer and reveal portions of the layers below. You can create two types of masks:

- Layer masks are resolution-dependent bitmap images that are edited with the painting or selection tools.
- Vector masks are resolution independent and are created with a pen or shape tool.

Layer and vector masks are nondestructive, which means you can go back and re-edit the masks later without losing the pixels they hide.

In the Layers panel, both the layer and vector masks appear as an additional thumbnail to the right of the layer thumbnail. For the layer mask, this thumbnail represents the grayscale channel that is created when you add the layer mask. The vector mask thumbnail represents a path that clips out the contents of the layer.

Note: *To create a layer or vector mask on the Background layer, first convert it to a regular layer (Layer > New > Layer from Background).*



A Layer mask thumbnail *B Vector mask thumbnail* *C Vector Mask Link icon* *D Add Mask*

You can edit a layer mask to add or subtract from the masked region. A layer mask is a grayscale image, so areas you paint in black are hidden, areas you paint in white are visible, and areas you paint in shades of gray appear in various levels of transparency.



A vector mask creates a sharp-edged shape on a layer and is useful anytime you want to add a design element with clean, defined edges. After you create a layer with a vector mask, you can apply one or more layer styles to it, edit them if needed, and instantly have a usable button, panel, or other web-design element.

The Properties panel provides additional controls to adjust a mask. You can change the opacity of a mask to let more or less of the masked content show through, invert the mask, or refine the mask borders, as with a selection area.



A Layer mask *B Vector mask*

Add layer masks

When you add a layer mask, you can hide or show all of the layer, or base the mask on a selection or transparency. Later, you'll paint on the mask to precisely hide portions of the layer, revealing the layers beneath.

Add a mask that shows or hides the entire layer

1 Make sure that no part of your image is selected. Choose Select > Deselect.

2 In the Layers panel, select the layer or group.

3 Do one of the following:

- To create a mask that reveals the entire layer, click the Add Layer Mask button in the Layers panel, or choose Layer > Layer Mask > Reveal All.
- To create a mask that hides the entire layer, Alt-click (Windows) or Option-click (Mac OS) the Add Layer Mask button, or choose Layer > Layer Mask > Hide All.

Add a layer mask that hides part of a layer

1 In the Layers panel, select the layer or group.

2 Select the area in the image, and do one of the following:

- Click the New Layer Mask button in the Layers panel to create a mask that reveals the selection.
- Alt-click (Windows) or Option-click (Mac OS) the Add Layer Mask button in the Layers panel to create a mask that hides the selection.
- Choose Layer > Layer Mask > Reveal Selection or Hide Selection.

Create a mask from layer transparency

If you want to directly edit layer transparency, create a mask from this data. This technique is helpful for video and 3D workflows.

1 In the Layers panel, select the layer.

2 Choose Layer > Layer Mask > From Transparency.

Photoshop converts transparency into an opaque color, hidden by the newly created mask. The opaque color varies greatly, depending upon the filters and other processing previously applied to the layer.

Apply a layer mask from another layer

? Do one of the following:

- To move the mask to another layer, drag the mask to the other layer.
- To duplicate the mask, Alt-drag (Windows) or Option-drag (Mac OS) the mask to the other layer.

Unlink layers and masks

By default, a layer or group is linked to its layer mask or vector mask, as indicated by the link icon between the thumbnails in the Layers panel. The layer and its mask move together in the image when you move either one with the Move tool . Unlinking them lets you move them independently and shift the mask's boundaries separately from the layer.

- To unlink a layer from its mask, click the link icon in the Layers panel.
- To reestablish the link between a layer and its mask, click between the layer and mask path thumbnails in the Layers panel.

Disable or enable a layer mask

? Do one of the following:

- Select the layer containing the layer mask you want to disable or enable, and click the Disable/Enable Mask button in the Properties panel.
- Shift-click the layer mask thumbnail in the Layers panel.
- Select the layer containing the layer mask you want to disable or enable, and choose Layer > Layer Mask > Disable or Layer > Layer Mask > Enable.

A red X appears over the mask thumbnail in the Layers panel when the mask is disabled, and the layer's content appears without masking effects.

Apply or delete a layer mask

You can apply a layer mask to permanently delete the hidden portions of a layer. Layer masks are stored as alpha channels, so applying and deleting layer masks can help reduce file size. You can also delete a layer mask without applying the changes.

1 In the Layers panel, select the layer containing the layer mask.

2 Do one of the following:

- To remove the layer mask after applying it permanently to the layer, click the Apply Mask icon at the bottom of the Properties panel.
- To remove the layer mask without applying it to the layer, click the Delete button at the bottom of the Properties panel, and then click Delete.

You can also apply or delete layer masks using the Layer menu.

Note: *You cannot apply a layer mask permanently to a Smart Object layer when deleting the layer mask.*

Select and display the layer mask channel

For easier editing of a layer mask, you can display the grayscale mask by itself or as a rubylith overlay on the layer.

? In the Layers panel, do one of the following:

- Alt-click (Windows) or Option-click (Mac OS) the layer mask thumbnail to view only the grayscale mask. To redisplay the layers, Alt-click or Option-click the layer mask thumbnail. Alternatively, click the eye icon in the Properties panel.
- Hold down Alt+Shift (Windows) or Option+Shift (Mac OS), and click the layer mask thumbnail to view the mask on top of the layer in a rubylith masking color. Hold down Alt+Shift or Option+Shift, and click the thumbnail again to turn off the color display.

Change the layer mask rubylith color or opacity

1 Double-click the layer mask channel in the Channels panel.

2 To choose a new mask color, in the Layer Mask Display Options dialog box, click the color swatch and choose a new color.

3 To change the opacity, enter a value between 0% and 100%.

Both the color and opacity settings affect only the appearance of the mask and have no effect on how underlying areas are protected. For example, you may want to change these settings to make the mask more easily visible against the colors in the image.

4 Click OK.

Adjust mask opacity and edges

Use the Properties panel to adjust the opacity of a selected layer or vector mask. The Density slider controls mask opacity. Feather lets you soften mask edges.

Additional options are specific to layer masks. The Invert option reverses masked and unmasked areas. The Mask Edge option gives you various controls to modify the mask edges, such as Smooth and Contract/Expand. For information on the Color Range option, see Create and confine adjustment and fill layers.

Change mask density

1 In the Layers panel, select the layer containing the mask you want to edit.

2 In the Layers panel, click the Mask thumbnail. A border appears around the thumbnail.

3 In the Properties panel, drag the Density slider to adjust the mask opacity.

At 100% density, the mask is completely opaque and blocks out any underlying area of the layer. As you lower the density, more of the area under the mask becomes visible.

Feather mask edges

1 In the Layers panel, select the layer containing the mask you want to edit.

2 In the Layers panel, click the Mask thumbnail. A border appears around the thumbnail.

3 Drag the Feather slider to apply feathering to the mask edges.

Feathering blurs the edges of the mask to create a softer transition between the masked and unmasked areas. Feathering is applied from the edges of the mask outward, within the range of pixels you set with the slider.

Refine mask edges

1 In the Layers panel, select the layer containing the mask you want to edit.

2 In the Layers panel, click the Mask thumbnail. A border appears around the thumbnail.

3 Click Mask Edge. You can modify mask edges with the options in the Refine Mask dialog box and view the mask against different backgrounds. For a description of options, see Refine selection edges.

4 Click OK to close the Refine Mask dialog box and apply your changes to the layer mask.

More Help topics

About masks and alpha channels

Merging layers

Combine multiple images into a group portrait

Load selections from a layer or layer mask's boundaries

Layer opacity and blending

A layer's blending mode determines how its pixels blend with underlying pixels in the image. You can create a variety of special effects using blending modes.

Specify overall and fill opacity for selected layers

A layer's overall opacity determines to what degree it obscures or reveals the layer beneath it. A layer with 1% opacity appears nearly transparent, whereas one with 100% opacity appears completely opaque.

In addition to overall opacity, which affects layer styles and blending modes applied to a layer, you can specify fill opacity. Fill opacity affects only pixels, shapes, or text on a layer without affecting the opacity of layer effects such as drop shadows.

Note: *You cannot change the opacity of a background layer or a locked layer. To convert a background layer into a regular layer that supports transparency, see Convert background and Photoshop layers.*

1 In the Layers panel, select one or more layers or groups.

2 Change the Opacity and Fill values. (If you selected a group, only Opacity is available.)

To view all blending options, choose Blending Options from the Add A Layer Style icon fx at the bottom of the Layers panel.

Specify a blending mode for a layer or group

By default, the blending mode of a layer group is Pass Through, which means that the group has no blending properties of its own. When you choose a different blending mode for a group, you effectively change the order in which the image components are put together. All of the layers in the group are put together first. The composite group is then treated as a single image and blended with the rest of the image using the selected blending mode. Thus, if you choose a blending mode other than Pass Through for the group, none of the adjustment layers or layer blending modes inside the group will apply to layers outside the group.

Note: *There is no Clear blending mode for layers. For Lab images, the Color Dodge, Color Burn, Darken, Lighten, Difference, Exclusion, Subtract, and Divide modes are unavailable. For HDR images, see Features that support 32-bpc HDR images.*

1 Select a layer or group from the Layers panel.

2 Choose a blending mode:

- From the Layers panel, choose an option from the Blend Mode pop-up menu.
- Choose Layer > Layer Style > Blending Options, and then choose an option from the Blend Mode pop-up menu.

For descriptions and examples of each mode, see Blending modes.

Group blend effects

By default, layers in a clipping mask are blended with the underlying layers using the blending mode of the bottommost layer in the group. However, you can choose to have the blending mode of the bottommost layer apply only to that layer, allowing you to preserve the original blending appearance of the clipped layers. (See Reveal layers with clipping masks.)

You can also apply the blending mode of a layer to layer effects that modify opaque pixels, such as Inner Glow or Color Overlay, without changing layer effects that modify only transparent pixels, such as Outer Glow or Drop Shadow.

1 Select the layer that you want to affect.

2 Double-click a layer thumbnail, choose Blending Options from the Layers panel menu, or choose Layer > Layer Style > Blending Options.

Note: To view blending options for a text layer, choose Layer > Layer Style > Blending Options, or choose Blending Options from the Add A Layer Style button at the bottom of the Layers panel menu.

3 Specify the scope of blending options:

- Select Blend Interior Effects As Group to apply the blending mode of the layer to layer effects that modify opaque pixels, such as Inner Glow, Satin, Color Overlay, and Gradient Overlay.
- Select Blend Clipped Layers As Group to apply the blending mode of the base layer to all layers in the clipping mask. Deselecting this option, which is always selected by default, maintains the original blending mode and appearance of each layer in the group.



- Select Transparency Shapes Layers to restrict layer effects and knockouts to opaque areas of the layer. Deselecting this option, which is always selected by default, applies these effects throughout the layer.
- Select Layer Mask Hides Effects to restrict layer effects to the area defined by the layer mask.
- Select Vector Mask Hides Effects to restrict layer effects to the area defined by the vector mask.

4 Click OK.

Exclude channels from blending

You can restrict blending effects to a specified channel when you blend a layer or group. By default, all channels are included. When using an RGB image, for example, you can choose to exclude the red channel from blending; in the composite image, only the information in the green and blue channels is affected.

1 Do one of the following:

- Double-click a layer thumbnail.

- Choose Layer > Layer Style > Blending Options.
- Choose Blending Options from the Add A Layer Style icon fx at the bottom of the Layers panel.

Note: *To view blending options for a text layer, choose Layer > Layer Style > Blending Options, or choose Blending Options from the Add A Layer Style button at the bottom of the Layers panel menu.*

2 From the Advanced Blending area of the Layer Style dialog box, deselect any channels you do not want to include when the layer is blended.

Specify a tonal range for blending layers

The sliders in the Blending Options dialog box control which pixels from the active layer and the underlying visible layers appear in the final image. For example, you can drop dark pixels out of the active layer or force bright pixels from the underlying layers to show through. You can also define a range of partially blended pixels to produce a smooth transition between blended and unblended areas.

1 Double-click a layer thumbnail, choose Layer > Layer Style > Blending Options, or choose Add A Layer Style > Blending Options from the Layers panel menu.

Note: *To view blending options for a text layer, choose Layer > Layer Style > Blending Options, or choose Blending Options from the Add A Layer Style button at the bottom of the Layers panel menu.*

2 In the Advanced Blending area of the Layer Style dialog box, choose an option from the Blend If pop-up menu.

- Choose Gray to specify a blending range for all channels.
- Select an individual color channel (for example, red, green, or blue in an RGB image) to specify blending in that channel.

3 Use the This Layer and Underlying Layer sliders to set the brightness range of the blended pixels—measured on a scale from 0 (black) to 255 (white). Drag the white slider to set the high value of the range. Drag the black slider to set the low value of the range.

To define a range of partially blended pixels, hold down Alt (Windows) or Option (Mac OS), and drag one half of a slider triangle. The two values that appear above the divided slider indicate the partial blending range.

Keep the following guidelines in mind when specifying blending ranges:

- Use the This Layer sliders to specify the range of pixels on the active layer that will blend, and therefore appear, in the final image. For example, if you drag the white slider to 235, pixels with brightness values higher than 235 will remain unblended and will be excluded from the final image.
- Use the Underlying Layer sliders to specify the range of pixels in the underlying visible layers that will blend in the final image. Blended pixels are combined with pixels in the active layer to produce composite pixels, whereas unblended pixels show through overlying areas of the active layer. For example, if you drag the black slider to 19, pixels with brightness values lower than 19 will remain unblended and will show through the active layer in the final image.

Fill new layers with a neutral color

You can't apply certain filters (such as the Lighting Effects filter) to layers with no pixels. Selecting Fill With (Mode)-Neutral Color in the New Layer dialog box resolves this problem by first filling the layer with a preset, neutral color. This invisible, neutral color is assigned according to the layer's blending mode. If no effect is applied, filling with a neutral color has no effect on the remaining layers. The Fill With Neutral Color option is not available for layers that use the Normal, Dissolve, Hard Mix, Hue, Saturation, Color, or Luminosity modes.

More Help topics

Knockout to reveal content from other layers

Add Lighting Effects

Move, stack, and lock layers

You can easily rearrange an image's layers in the Layers panel or directly in the document window. You can also lock layers to protect them.

Change the stack order of layers and groups

? Do one of the following:

- Drag the layer or group up or down in the Layers panel. Release the mouse button when the highlighted line appears where you want to place the layer or group.
- To move a layer into a group, drag a layer to the group folder . If the group is closed, the layer is placed at the bottom of the group.
- Select a layer or group, choose Layer > Arrange, and choose a command from the submenu. If the selected item is in a group, the command applies to the stacking order within the group. If the selected item is not in a group, the command applies to the stacking order within the Layers panel.
- To reverse the order of selected layers, choose Layer > Arrange > Reverse. These options appear dimmed if you do not have at least two layers selected.

Note: *By definition, the background layer is always at the bottom of the stacking order. Therefore, the Send To Back command places the selected item directly above the background layer.*

Move the content of layers

1 From the Layers panel, select the layers containing the objects you want to move.

2 Select the Move tool .

You can select the layers that you want to move directly in the document window. In the Move tool's options bar, select Auto Select, then choose Layer from the drop-down menu. Shift-click to select multiple layers. Select Auto Select, then choose Group, to select the entire group when you select one layer in the group.

3 Do one of the following:

- In the document window, drag any object onto one of the selected layers. (All objects on the layer will move together.)
- Press an arrow key on the keyboard to nudge the objects by 1 pixel.
- Hold down Shift and press an arrow key on the keyboard to nudge the objects by 10 pixels.

Rotate a layer

1 From the Layers panel, select the layer you want to rotate.

2 If anything is currently selected in the image, choose Select > Deselect.

3 Choose Edit > Transform > Rotate. A box defining the boundaries of the layer (called a bounding box) appears.

4 Move the pointer outside of the bounding box (the pointer becomes a curved, two-sided arrow), and then drag. Press Shift to constrain the rotation to 15° increments.

5 When you're satisfied with the results, press Enter (Windows) or Return (Mac OS), or click the check mark in the options bar. To cancel the rotation, press Esc, or click the Cancel Transform icon on the options bar.

Lock layers

You can lock layers fully or partially to protect their contents. For instance, you may want to lock a layer fully when you finish with it. You may want to lock a layer partially if it has the correct transparency and styles, but you are still deciding on positioning. When a layer is locked, a lock icon appears to the right of the layer name. The lock icon is solid when the layer is fully locked and hollow when the layer is partially locked.

Lock all properties of a layer or group

1 Select a layer or group.

2 Click the Lock All option in the Layers panel.

Note: Layers in a locked group display a dimmed lock icon .

Partially lock a layer

1 Select a layer.

2 Click one or more lock options in the Layers panel.

Lock Transparent Pixels Confines editing to the opaque portions of the layer. This option is equivalent to the Preserve Transparency option in earlier versions of Photoshop.

Lock Image Pixels Prevents modification of the layer's pixels using the painting tools.

Lock Position Prevents the layer's pixels from being moved.

Note: For type and shape layers, Lock Transparency and Lock Image are selected by default and cannot be deselected.

Apply lock options to selected layers or a group

1 Select multiple layers or a group.

2 Choose Lock Layers or Lock All Layers In Group from the Layers menu or the Layers panel menu.

3 Select lock options, and click OK.

More Help topics

Rotate or flip an entire image

Scale, rotate, skew, distort, apply perspective, or warp

Combine images with Auto-Blend Layers

Layer comps

Designers often create multiple compositions (or comps) of a page layout to show clients. Using layer comps, you can create, manage, and view multiple versions of a layout in a single Photoshop file.

A layer comp is a snapshot of a state of the Layers panel. Layer comps record three types of layer options:

- Layer visibility—whether a layer is showing or hidden.
- Layer position in the document.
- Layer appearance—whether a layer style is applied to the layer and the layer's blending mode.

Note: *Unlike layer effects, Smart Filter settings cannot be changed across layer comps. Once a Smart Filter is applied to a layer, it appears in all layer comps for the image.*



A *Apply Layer Comp icon* ***B*** *Last Document State* ***C*** *Selected comps*

Create a layer comp

1 Choose Window > Layer Comps to display the Layer Comps panel.

2 Click the Create New Layer Comp button at the bottom of the Layer Comps panel. The new comp reflects the current state of layers in the Layers panel.

3 In the New Layer Comp dialog box, name the comp, add descriptive comments, and choose options to apply to layers: Visibility, Position, and Appearance.

4 Click OK. The options you chose are stored as defaults for your next comp.

To duplicate a comp, select a comp in the Layer Comps panel and drag the comp to the New Comps button.

Apply and view layer comps

? In the Layer Comp panel, do any of the following:

- To view a layer comp, you first need to apply it. Click the Apply Layer Comp icon next to a selected comp.
- To cycle through a view of all layer comps, use the Previous and Next buttons at the bottom of the panel. (To cycle through specific comps, first select them.)
- To restore the document to its state before you chose a layer comp, click the Apply Layer Comp icon next to Last Document State at the top of the panel.

Change and update a layer comp

If you change the configuration of a layer comp, you need to update it.

1 Select the layer comp in the Layer Comps panel.

2 Make changes to the layer's visibility, position, or style. You may need to change the layer comp's options to record these changes.

3 To change your comp options, select Layer Comp Options from the panel menu and select additional options to record layer position and style.

4 Click the Update Layer Comp button at the bottom of the panel.

Layer comps in Smart Objects

Consider a document with layer comps placed as a Smart Object within another document. When you select the Smart Object in the containing document, the Properties panel gives you access to the layer comps that were defined in the source file.

This feature lets you change the state of the Smart Object at a layer level without editing the Smart Object.



Clear layer comp warnings

Certain actions create a state where the layer comp can no longer be fully restored. This happens when you delete a layer, merge a layer, or convert a layer to a background. In such instances, a caution icon appears next to the layer comp name.

? Do one of the following:

- Ignore the warning, which may result in the loss of one or more layers. Other saved parameters may be preserved.
- Update the comp, which results in the loss of the previously captured parameters, but brings the comp up to date.
- Click the caution icon to see the message explaining that the layer comp can't be restored properly. Choose Clear to remove the alert icon and leave the remaining layers unchanged.
- Right-click (Windows) or Control-click (Mac OS) the caution icon to see the pop-up menu that lets you choose either the Clear Layer Comp Warning or the Clear All Layer Comp Warnings command.

Delete a layer comp

? Do one of the following:

- Select the layer comp in the Layer Comps panel and click the Delete icon in the panel, or choose Delete Layer Comp from the panel menu.
- Drag it to the Delete icon in the panel.

Export layer comps

You can export layer comps to individual files.

? Choose File > Scripts > Layer Comps To Files and then choose the file type and set the destination.

Work with Smart Objects

Understand Smart Objects

Smart Objects are layers that contain image data from raster or vector images, such as Photoshop or Illustrator files. Smart Objects preserve an image's source content with all its original characteristics, enabling you to perform nondestructive editing to the layer.

In Photoshop CC and CS6, you can embed the contents of an image into a Photoshop document. In Photoshop CC, you can also create Linked Smart Objects whose contents are referenced from external image files. The contents of a Linked Smart Object are updated when its source image file changes.

Linked Smart Objects are distinct from duplicated instances of a Smart Object within a Photoshop document. With Linked Smart Objects, you can use a shared source file across multiple Photoshop documents which is a familiar and welcome concept for web designers.

Smart Object benefits

With Smart Objects, you can:

- Perform nondestructive transforms. You can scale, rotate, skew, distort, perspective transform, or warp a layer without losing original image data or quality because the transforms don't affect the original data.
- Work with vector data, such as vector artwork from Illustrator, that otherwise would be rasterized in Photoshop.
- Perform nondestructive filtering. You can edit filters applied to Smart Objects at any time.
- Edit one Smart Object and automatically update all its linked instances.
- Apply a layer mask that's either linked or unlinked to the Smart Object layer.
- Try various designs with low-resolution placeholder images that you later replace with final versions.

You can't perform operations that alter pixel data—such as painting, dodging, burning, or cloning—directly to a Smart Object layer, unless it is first converted into a regular layer, which will be rasterized. To perform operations that alter pixel data, you can edit the contents of a Smart Object, clone a new layer above the Smart Object layer, edit duplicates of the Smart Object, or create a new layer.

Note: *When you transform a Smart Object that has a Smart Filter applied to it, Photoshop turns off filter effects while the transform is being performed. Filter effects are applied again after the transform is complete. See Apply Smart Filters.*





Create embedded Smart Objects

You can create embedded Smart Objects using several methods: by using the Open As Smart Object command; placing a file (CS6) or placing a file as embedded (CC, CS6), pasting data from Illustrator; or converting one or more Photoshop layers to Smart Objects.

? Do any of the following:

- (CC) Choose File > Place Embedded to import files as Smart Objects into an open Photoshop document.
- Choose File > Open As Smart Object, select a file, and click Open.
- (CS6) Choose File> Place to import files as Smart Objects into an open Photoshop document.

Although you can place JPEG files, it's better to place PSD, TIFF, or PSB files because you can add layers, modify pixels, and resave the file without loss. (Saving a modified JPEG file requires you to flatten new layers and recompress the image, causing image quality degradation).

- Choose Layer > Smart Object > Convert to Smart Object to convert a selected layer into a Smart Object.
- In Bridge, choose File > Place > In Photoshop to import a file as a Smart Object into an open Photoshop document.

An easy way to work with camera raw files is to open them as Smart Objects. You can double-click the Smart Object layer containing the raw file at any time to adjust the Camera Raw settings.See the video Open an image as a Smart Object to learn how.

- Select one or more layers and choose Layer > Smart Objects > Convert To Smart Object. The layers are bundled into one Smart Object.
- Drag PDF or Adobe Illustrator layers or objects into a Photoshop document.
- Paste artwork from Illustrator into a Photoshop document, and choose Smart Object in the Paste dialog box. For the greatest flexibility, enable both PDF and AICB (No Transparency Support) in the File Handling & Clipboard section of the Preferences dialog box in Adobe Illustrator.

Create Linked Smart Objects | Photoshop CC

Note: *The Linked Smart Object feature is available in Photoshop versions 14.2 (Photoshop CC | January 2014) and later.*

In Photoshop CC, you can create Linked Smart Objects. The contents of Linked Smart Objects are updated when the source image file changes. Linked Smart Objects are particularly useful for teams or in cases where assets must be reused across designs.

Follow these steps to create a Linked Smart Object:

1 Choose File > Place Linked.

2 Select an appropriate file and click Place.

The Linked Smart Object is created and is displayed in the Layers panel with a link icon ( ).

You can also create a Linked Smart Object in an open document by dragging and dropping the appropriate file while keeping the following key pressed:(Windows) Alt key(Mac OS) Option keyTo change this default behavior, turn off Preferences > General > Always Create Smart Objects While Placing.

File size savings using Linked Smart Objects

Since Linked Smart Objects maintain a dependency on an external file rather than embedding a source file within the containing document, they often result in significantly smaller file sizes. While Linked Smart Objects do not store the original file in the containing document, they still store a flattened and scaled version of the image data from the original file. In some cases, the size of this data may be much larger than the size of the original file, making the file size savings seem negligible.

Update Linked Smart Objects

If an external source file changes while a Photoshop document referencing it is open, the relevant Linked Smart Object is automatically updated. However, when you open a Photoshop document containing out-of-synch Linked Smart Objects, you can update the Smart Objects:

- Right-click a Linked Smart Object layer and choose Update Modified Content.
- Choose Layer > Smart Objects > Update Modified Content.

Linked Smart Objects whose source images have changed are visually highlighted in the Layers panel:

You can update all linked Smart Objects in the current Photoshop document by choosing Layer > Smart Objects > Update All Modified Content.

Note: *While detecting changes to Linked Smart Objects or updating a Linked Smart Object, Photoshop looks only at the immediate linked file. Links nested inside Smart Objects are not updated.*

Resolve a broken Smart Object link

To resolve a Linked Smart Object with a missing external source, follow these steps:

1 Right-click the Linked Smart Object layer icon and choose Resolve Broken Link.

2 Navigate to the new location of the missing object.

3 Click Place.

View Linked Smart Object properties

With a Linked Smart Object layer selected in the Layers panel, choose Window > Properties.

The following properties are displayed:

- The path of the external source file for the Linked Smart Object
- The Linked Smart Object size and positional coordinates (X, Y)

You can perform the following actions directly from within the Properties panel:

- Edit the contents of the external image file. If necessary, Photoshop opens an external application that can handle the source image file. For example, Photoshop opens Adobe Illustrator if the external source image is a .ai file.
- Embed the Linked Smart Object within the current document.

Embed Linked Smart Objects

Do one of the following:

- Right-click a Linked Smart Object layer in the Layers panel and choose Embed Linked.
- Choose Layer > Smart Objects > Embed Linked.
- In the Properties panel, click Embed.

Choose Layer > Smart Objects > Embed All Linked to embed all Linked Smart Objects in the Photoshop document.

Package Linked Smart Objects

You can package the Linked Smart Objects in a Photoshop document, such that their source files are saved to a folder on your computer. A copy of the Photoshop document is saved along with the source files in the folder.

1. Choose File > Package.
2. Select a location where you want to place the source files and a copy of the Photoshop document.

Any audio or video Linked Smart Objects in the document are packaged as well.

Note: *You must save a file before packaging the Linked Smart Objects that it contains.*

How Photoshop locates linked files

Photoshop always looks for linked files in the last-known relative location. If the linked file is not found in that location, Photoshop looks for it:

- In the last-known absolute location
- Using a saved alias (Mac OS only)
- In the same folder as the containing document

This behavior allows you to move, copy, and share project folders and files with minimal risk of encountering broken links.

Note: *The Resolve Missing Assets dialog always displays the last-known absolute path of missing source files.*

Convert an embedded Smart Object to a Linked Smart Object

You can convert an embedded Smart Object to a Linked Smart Object. Transforms, filters, and other effects applied to the embedded Smart Object are preserved when it is converted.

Do the following:

1 Select an embedded Smart Object layer in the Photoshop document.

2 Choose Layer > Smart Object > Convert To Linked.

3 Select the location on your computer where you want to save the source file. Enter a name for the file, including a supported extension. For example, link_file.jpg.

Filter the Layers panel by Smart Objects | Photoshop CC

? In the Layers panel, select Smart Object from the filtering pop-up menu.

? Click one of the following icons:

- Filter for up-to-date Linked Smart Objects
- Filter for out-of-synch Linked Smart Objects
- Filter for missing Linked Smart Objects
- Filter for embedded Smart Objects

You can use the toggle switch ( ) to turn off layer filtering.

Duplicate an embedded Smart Object

? In the Layers panel, select a Smart Object layer, and do one of the following:

- To create a duplicate Smart Object that is linked to the original, choose Layer > New > Layer Via Copy, or drag the Smart Object layer to the Create A New Layer icon at the bottom of the Layers panel. Edits you make to the original affect the copy and vice versa.
- To create a duplicate Smart Object that isn't linked to the original, choose Layer > Smart Objects > New Smart Object Via Copy. Edits you make to the original don't affect the copy.

A new Smart Object appears in the Layers panel with the same name as the original and "copy" as a suffix.

Edit the contents of a Smart Object

When you edit a Smart Object, the source content is opened in either Photoshop (if the content is raster data or a camera raw file) or the application that handles the placed format by default (for example, Adobe Illustrator or Adobe Acrobat). When you save changes to the source content, the edits appear in all linked instances of the Smart Object in the Photoshop document.

1 Select the Smart Object from the Layers panel, and do one of the following:

- Choose Layer > Smart Objects > Edit Contents.

- Double-click the Smart Objects thumbnail in the Layers panel.
- In the Properties panel, click Edit Contents.

2 Click OK to close the dialog box.

3 Make edits to the source content file, then choose File > Save.

Photoshop updates the Smart Object to reflect the changes you made. (If you don't see the changes, make the Photoshop document containing the Smart Object active.)

Replace the contents of a Smart Object

You can replace the image data in one Smart Object or multiple linked instances. This feature lets you quickly update a visual design, or replace low-resolution placeholder images with final versions.

Note: *When you replace a Smart Object, any scaling, warping, or effects that you applied to the first Smart Object are maintained.*

1 Select the Smart Object, and choose Layer > Smart Objects > Replace Contents.

2 Navigate to the file you want to use, and click Place.

3 Click OK.

The new content is placed in the Smart Object.

Convert an embedded or linked Smart Object to a layer

Converting a Smart Object to a regular layer rasterizes the content at the current size. Convert a Smart Object to a regular layer only if you no longer need to edit the Smart Object data. Transforms, warps, and filters applied to a Smart Object are no longer editable after the Smart Object is rasterized.

- Select the Smart Object, and choose Layer > Smart Objects > Rasterize.

If you want to re-create the Smart Object, reselect its original layers and start from scratch. The new Smart Object won't retain transforms you applied to the original Smart Object.

Export the contents of an embedded Smart Object

1 Select the Smart Object from the Layers panel, and choose Layer > Smart Objects > Export Contents.

2 Choose a location for the contents of the Smart Object, then click Save.

Photoshop exports the Smart Object in its original placed format (JPEG, AI, TIF, PDF, or other formats). If the Smart Object was created from layers, it is exported in PSB format.

More Help topics

Linked Smart Objects

Place a file in Photoshop

Paste Adobe Illustrator art into Photoshop

Nondestructive editing

Apply Smart Filters

Any filter applied to a Smart Object is a Smart Filter. Smart Filters appear in the Layers panel below the Smart Object layer to which they are applied. Because you can adjust, remove, or hide Smart Filters, they are nondestructive.

You can apply any Photoshop filter (that has been enabled to work with Smart Filters)—except for Extract, Liquify, Pattern Maker, and Vanishing Point—as a Smart Filter. In addition, you can apply Shadow/Highlight as Smart Filters.

To work with Smart Filters, select a Smart Object layer, choose a filter, and then set filter options. After you apply a Smart Filter, you can adjust, reorder, or delete it.

To expand or collapse the view of Smart Filters, click the triangle next to the Smart Filter icon, displayed to the right of the Smart Object layer in the Layers panel. (This technique also shows or hides Layer Style.) Or, choose Layers panel Options from the Layers panel menu, then select Expand New Effects in the dialog box.

Use filter masks to selectively mask Smart Filter effects.

Apply a Smart Filter

1 Do one of the following:

- To apply a Smart Filter to an entire Smart Object layer, select the layer in the Layers panel.
- To constrain the effects of the Smart Filter to a selected area of a Smart Object layer, make a selection.
- To apply a Smart Filter to a regular layer, select the layer, and choose Filter > Convert For Smart Filters, and click OK.

2 Do one of the following:

- Choose a filter from the Filter menu. You can choose any filter, including third-party filters that support Smart Filters, except Extract, Liquify, Pattern Maker, and Vanishing Point.
- Choose Image > Adjustments > Shadows/Highlight.

Note: *If you apply one or more filters using the Filter Gallery, they appear as a group in the Layers panel named "Filter Gallery." You can edit individual filters by double-clicking a Filter Gallery entry.*

3 Set filter options and click OK.

The Smart Filter appears under the Smart Filters line in the Layers panel beneath the Smart Object layer. If you see a warning icon next to a Smart Filter in the Layers panel, the filter doesn't support the image's color mode or depth.

After you apply a Smart Filter, you can drag it (or an entire group of Smart Filters) onto another Smart Object layer in the Layers panel; press Alt-drag (Windows) or Option-drag (Mac OS) Smart Filters. You can't drag Smart Filters onto regular layers.

Edit a Smart Filter

If a Smart Filter contains editable settings, you can edit it at any time. You can also edit blending options for Smart Filters.

Note: *When you edit a Smart Filter, you can't preview filters stacked above it. After you finish editing the Smart Filter, Photoshop again displays the filters stacked above it.*

Edit Smart Filter settings

1 Double-click the Smart Filter in the Layers panel.

2 Set filter options, and click OK.

Edit Smart Filter blending options

Editing Smart Filter blending options is similar to using the Fade command when applying a filter to a traditional layer.

1 Double-click the Edit Blending Options icon next to the Filter in the Layers panel.

2 Set blending options, and click OK.

Hide Smart Filters

? Do one of the following:

- To hide a single Smart Filter, click the eye icon next to the Smart Filter in the Layers panel. To show the Smart Filter, click in the column again.
- To hide all Smart Filters applied to a Smart Object layer, click the eye icon next to the Smart Filters line in the Layers panel. To show the Smart Filters, click in the column again.

Reorder, duplicate, or delete Smart Filters

You can reorder Smart Filters in the Layers panel, duplicate them, or delete Smart Filters if you no longer want to apply them to a Smart Object.

Reorder Smart Filters

? In the Layers panel, drag a Smart Filter up or down in the list. (Double-click Filter Gallery to reorder any gallery filters.)

Photoshop applies Smart Filters from the bottom up.

Duplicate Smart Filters

? In the Layers panel, Alt-drag (Windows) or Option-drag (Mac OS) the Smart Filter from one Smart Object to another, or to a new location in the Smart Filters list.

Note: *To duplicate all Smart Filters, Alt-drag (Windows) or Option-drag (Mac OS) the Smart Filters icon that appears next to the Smart Object layer.*

Delete Smart Filters

- To delete an individual Smart Filter, drag it to the Delete icon at the bottom of the Layers panel.
- To delete all Smart Filters applied to a Smart Object layer, select the Smart Object layer and choose Layer > Smart Filter > Clear Smart Filters.

Mask Smart Filters

When you apply a Smart Filter to a Smart Object, Photoshop displays an empty (white) mask thumbnail on the Smart Filters line in the Layers panel under the Smart Object. By default, this mask shows the entire filter effect. (If you made a selection before applying the Smart Filter, Photoshop displays the appropriate mask instead of an empty mask on the Smart Filters line in the Layers panel.)

Use filter masks to selectively mask Smart Filters. When you mask Smart Filters, the masking applies to all Smart Filters—you can't mask individual Smart Filters.

Filter masks work much like layer masks, and you can use many of the same techniques with them. Like layer masks, filter masks are stored as alpha channels in the Channels panel, and you can load their boundaries as a selection.

Like layer masks, you can paint on a filter mask. Areas of the filter that you paint in black are hidden; areas you paint in white are visible; and areas you paint in shades of gray appear in various levels of transparency.

Use the controls in the Masks panel to change the filter mask density, add feathering to the edges of the mask, or invert the mask.

Note: *By default, layer masks are linked to regular layers or Smart Object layers. When you move the layer mask or the layer using the Move tool, they move as a unit.*

Mask Smart Filter effects

1 Click the filter mask thumbnail in the Layers panel to make it active.

   A border appears around the mask thumbnail.

2 Select any of the editing or painting tools.

3 Do one of the following:

   - To hide portions of the filter, paint the mask with black.
   - To show portions of the filter, paint the mask with white.
   - To make the filter partially visible, paint the mask with gray.

   You can also apply image adjustments and filters to filter masks.

Change filter mask opacity or feather mask edges

1 Click the filter mask thumbnail or select the Smart Object layer in the Layers panel, and then click the Filter Mask button in the Masks panel.

2 In the Masks panel, drag the Density slider to adjust the mask opacity, and the Feathering slider to apply feathering to the mask edges. See Adjust mask opacity and edges.

   Note: *The Mask Edge option is not available for filter masks.*

Invert a filter mask

? Click the filter mask thumbnail in the Layers panel, then click Invert in the Masks panel.

Display only the filter mask

? Alt-click (Windows) or Option-click (Mac OS) the filter mask thumbnail in the Layers panel. To show the Smart Object layer, Alt-click or Option-click the filter mask thumbnail again.

Move or copy filter masks

- To move the mask to another Smart Filter Effect, drag the mask to the other Smart Filter Effect.
- To copy the mask, Alt-drag (Windows) or Option-drag (Mac OS) the mask to another Smart Filter Effect.

Disable a filter mask

? Do one of the following:

   - Shift-click the filter mask thumbnail in the Layers panel.
   - Click the filter mask thumbnail in the Layers panel, then click the Disable/Enable Mask button in the Masks panel.

- Choose Layer > Smart Filter > Disable Filter Mask.

A red X appears over the filter mask thumbnail when the mask is disabled, and the Smart Filter appears without masking. To re-enable the mask, Shift-click the Smart Filter mask thumbnail again.

Delete a Smart Filter mask

- Click the filter mask thumbnail in the Layers panel, then click the Delete icon in the Masks panel.
- Drag the filter mask thumbnail in the Layers panel to the Delete icon.
- Select the Smart Filter Effect, and choose Layer > Smart Filters > Delete Filter Mask.

Add a filter mask

If you delete a filter mask, you can subsequently add another mask.

- To add an empty mask, select the Smart Object layer, and then click the Filter Mask button in the Masks panel.
- To add a mask based on a selection, make a selection, and then right-click (Windows) or Control-click (Mac OS) the Smart Filters line in the Layers panel, and choose Add Filter Mask.

More Help topics

Nondestructive editing

Blending modes

Specify overall and fill opacity for selected layers

Select and display the layer mask channel

Load a layer or layer mask's boundaries as a selection

Align and distribute layers

In Photoshop you can use the Align and Distribute options to easily line up and properly space your image layers, used frequently for creating panoramic images.

Align objects on different layers

You can align the content of layers and groups using the Move tool . (See Move the content of layers.)

1 Do one of the following:
   - To align multiple layers, select the layers with the Move tool or in the Layers panel, or select a group.
   - To align the content of one or more layers to a selection border, make a selection in the image, and then select the layers in the Layers panel. Use this method to align to any specified point in the image.

2 Choose Layer > Align or Layer > Align Layers To Selection, and choose a command from the submenu. These same commands are available as Alignment buttons in the Move tool options bar.

   Top Edges Aligns the top pixel on the selected layers to the topmost pixel on all selected layers, or to the top edge of the selection border.

   Vertical Centers Aligns the vertical center pixel on each selected layers to the vertical center pixel of all the selected layers, or to the vertical center of the selection border.

Bottom Edges Aligns the bottom pixel on the selected layers to the bottommost pixel on selected layers, or to the bottom edge of the selection border.

Left Edges Aligns the left pixel on the selected layers to the left pixel on the leftmost layer, or to the left edge of the selection border.

Horizontal Centers Aligns the horizontal center pixel on the selected layers to the horizontal center pixel of all the selected layers, or to the horizontal center of the selection border.

Right Edges Aligns the right pixel on the linked layers to the rightmost pixel on all selected layers, or to the right edge of the selection border.

Distribute layers and groups evenly

1 Select three or more layers.

2 Choose Layer > Distribute and choose a command. Alternatively, select the Move tool and click a distribution button in the options bar.

Top Edges Spaces the layers evenly, starting from the top pixel of each layer.

Vertical Centers Spaces the layers evenly, starting from the vertical center pixel of each layer.

Bottom Edges Spaces the layers evenly, starting from the bottom pixel of each layer.

Left Edges Spaces the layers evenly, starting from the left pixel of each layer.

Horizontal Centers Spaces the layers evenly, starting from the horizontal center of each layer.

Right Edges Spaces the layers evenly, starting from the right pixel on each layer.

Automatically align image layers

The Auto-Align Layers command can automatically align layers based on similar content in different layers, such as corners and edges. You assign one layer as a reference layer, or let Photoshop automatically choose the reference layer. Other layers are aligned to the reference layer so that matching content overlays itself.

Using the Auto-Align Layers command, you can combine images in several ways:

- Replace or delete parts of images that have the same background. After aligning the images, use masking or blending effects to combine parts of each image into one image.

  See Combine images with Auto-Blend Layers.

- Stitch images together that share overlapping content.
- For video frames shot against a static background, you can convert frames into layers, then add or delete content across multiple frames.

1 Copy or place the images you want to align into the same document.

  Each image will be in a separate layer. See Duplicate Photoshop layers.

  You can load multiple images into layers using a script. Choose File > Scripts > Load Files into Stack.

2 (Optional) In the Layers panel, create a reference layer by locking it. See Lock layers. If you do not set a reference layer, Photoshop will analyze all the layers and select the one at the center of the final composition as the reference.

3 Select the remaining layers you want to align.

To select multiple adjacent layers from the panel, Shift-click; To select noncontiguous layers, Ctrl-Click (Windows) or Command-click (Mac OS).

Note: *Do not select adjustment layers, vector layers, or Smart Objects that do not contain information needed for alignment.*

4 Choose Edit > Auto-Align Layers, and choose an alignment option. For stitching together multiple images that share overlapping areas—for example, to create a panorama—use the Auto, Perspective, or Cylindrical options. To align scanned images with offset content, use the Reposition Only option.

Auto Photoshop analyzes the source images and applies either a Perspective or Cylindrical layout, depending on which produces a better composite.

Perspective Creates a consistent composition by designating one of the source images (by default, the middle image) as the reference image. The other images are then transformed (repositioned, stretched, or skewed, as necessary) so that overlapping content across layers is matched.

Cylindrical Reduces the "bow-tie" distortion that can occur with the Perspective layout by displaying individual images as on an unfolded cylinder. Overlapping content across layers is still matched. The reference image is placed at the center. Best suited for creating wide panoramas.

Spherical Aligns images with wide fields of view (vertical and horizontal). Designates one of the sources images (the middle image, by default) as the reference image and spherically transforms the other images so that overlapping content is matched.

Scene Collage Aligns layers and matches overlapping content, without changing the shape of the objects in the image (for example, a circle will still be a circle).

Reposition Only Aligns the layers and matches overlapping content, but does not transform (stretch or skew) any of the source layers.

Lens Correction Automatically corrects for lens defects:

Vignette Removal Compensates for a lens defect that causes the edges, especially the corners, of an image to be darker than the center.

Geometric Distortion Compensates for barrel, pincushion, or fisheye distortion.

Note: *Geometric Distortion will try to take into account the radical distortion to improve the result of the alignment, except with fish eye lens; when fish eye metadata is detected, Geometric Distortion will align the images for fish eye*

After auto-aligning, you can use Edit > Free Transform to fine tune the alignment or make tonal adjustments to even out exposure differences between layers, then combine the layers into one composite image.

For a video on using Photoshop's alignment tools and automatic features to create panoramas, see Create a panoramic photo .

More Help topics

Move, stack, and lock layers

Create panoramic images with Photomerge

Combine multiple images intoa group portrait

Combine multiple images into a group portrait

You can use the Auto-Align Layers command to make a composite photo from a pair of nearly identical images that may contain some unwanted areas. For example, one shot of a group portrait is ideal except that one of the subjects has her eyes closed. In another shot her eyes are open. Using Auto-Align Layers and layer masking, you can combine these shots and eliminate the flaw in the final image.

1. Open the two images you want to combine.
2. Create a new image (File > New) with the same dimensions as the two source images.
3. In the Layers panel for each source image, select the layer that contains the image content, and drag it to the new image window. The Layers panel for the new image now contains two new layers, one for each source image.
4. In the Layers panel of the new image, arrange the new layers so the layer that contains the content you want to correct (portrait with eyes closed) is on top of the layer that contains the correct content (portrait with eyes open).
5. Select the two new layers, and choose Edit > Auto-Align Layers.
6. Select Reposition Only, then click OK. Photoshop finds the common areas in each layer and aligns them so that identical areas overlap.
7. Click the top layer to select only that layer.
8. Add a blank layer mask to the layer:
   - Click Add Layer Mask in the Layers panel.
   - Choose Layer > Layer Mask > Reveal All.
9. Set the foreground color to black, choose a brush tip and size, and zoom in if necessary to focus on the part of the image you want to correct.
10. Using the brush tool, add to the layer mask by painting over the top layer. Painting with black completely masks out the top layer, while grayscale creates partial transparency to the layer below, and white restores the top layer. See Masking layers . Continue editing the layer mask until you successfully blend the two layers to create one unified image.

    Note: *Make sure that the layer mask thumbnail, not the image thumbnail, is selected in the Layers panel during the masking operation.*
11. To allow further editing, save the layered and masked version of the image, and make another copy that you can flatten to produce a single-layer version with a smaller file size.

More Help topics

About masks and alpha channels

Masking layers

Merging layers

Automatically align image layers

Manage layers and groups

Managing layers and groups keeps your project organized. You can rename layers, color-code to easily locate similar layers, and delete and export layers as needed.

Rename a layer or layer group

As you add layers or layer groups to an image, it's helpful to give them names that reflect their content. Descriptive names make layers easy to identify in the Layers panel.

? Do one of the following:

- Double-click the layer name or group name in the Layers panel and enter a new name. Press Enter (Windows) or Return (Mac OS).
- Select the layer/group and then follow these steps:
  - Choose Layer > Rename Layer or Layer > Rename Group.
  - Enter a new name for the layer/group in the Layers panel.
  - Press Enter (Windows) or Return (Mac OS).

Assign a color to a layer or group

Color coding layers and groups helps you locate related layers in the Layers panel. Simply right-click the layer or group and select a color.

Rasterize layers

You cannot use the painting tools or filters on layers that contain vector data (such as type layers, shape layers, vector masks, or Smart Objects) and generated data (such as fill layers). However, you can rasterize these layers to convert their contents into a flat, raster image.

? Select the layers you want to rasterize, choose Layer > Rasterize, and then choose an option from the submenu:

Type Rasterizes the type on a type layer. It does not rasterize any other vector data on the layer.

Shape Rasterizes a shape layer.

Fill Content Rasterizes the fill of a shape layer, leaving the vector mask.

Vector Mask Rasterizes the vector mask on a layer, turning it into a layer mask.

Smart Object Converts a Smart Object into a raster layer.

Video Rasterizes the current video frame to an image layer.

3D (Extended only) Rasterizes the current view of 3D data into a flat raster layer.

Layer Rasterizes all vector data on the selected layers.

All Layers Rasterizes all layers that contain vector and generated data.

Note: *To rasterize linked layers, select a linked layer, choose Layer > Select Linked Layers, and then rasterize the selected layers.*

Delete a layer or group

Deleting layers you no longer need reduces the size of your image file.

To quickly delete empty layers, choose File > Scripts > Delete All Empty Layers.

1 Select one or more layers or groups from the Layers panel.

2 Do one of the following:

- To delete with a confirmation message, click the Delete icon . Alternatively, choose Layers > Delete > Layer or Delete Layer or Delete Group from the Layers panel menu.
- To delete the layer or group without confirmation, drag it to the Delete icon , Alt-click (Windows) or Option-click (Mac OS) the Delete icon, or press the Delete key.
- To delete hidden layers, choose Layers > Delete > Hidden Layers.

To delete linked layers, select a linked layer, choose Layer > Select Linked Layers, and then delete the layers.

Export layers

You can export all layers or visible layers to separate files.

? Choose File > Scripts > Export Layers To Files.

Merging layers

When you have finalized the content of layers, you can merge them to reduce the size of your image files. When you merge layers, the data on the top layers replaces any data it overlaps on the lower layers. The intersection of all transparent areas in the merged layers remains transparent.

Note: *You cannot use an adjustment or fill layer as the target layer for a merge.*

In addition to merging layers, you can stamp them. Stamping allows you to merge the contents of more than one layer into a target layer while leaving the other layers intact.

Note: *When you save a merged document, you cannot revert back to the unmerged state; the layers are permanently merged.*

Merge two layers or groups

1 Make sure that the layers and groups you want to merge are visible.

2 Select the layers and groups you want to merge.

3 Choose Layer > Merge Layers.

Note: *You can merge two adjacent layers or groups by selecting the top item and then choosing Layer > Merge Layers. You can merge linked layers by choosing Layer > Select Linked Layers, and then merging the selected layers. You can merge two 3D layers by choosing Layer > Merge Layers; they will share the same scene and the top layer will inherit the bottom layer 3D properties (the camera views must be the same for this to be enabled).*

Merge layers in a clipping mask

1 Hide any layers that you do not want to merge.

2 Select the base layer in the clipping mask. The base layer must be a raster layer.

3 Choose Merge Clipping Mask from the Layers menu or the Layers panel menu.

For more information on clipping masks, see Mask layers with clipping masks .

Merge all visible layers and groups in an image

? Choose Merge Visible from the Layers panel or the Layers panel menu. All layers showing an eye icon are merged.

Note: *A visible layer must be selected to enable the Merge Visible command.*

Stamp multiple layers or linked layers

When you stamp multiple selected layers or linked layers, Photoshop creates a new layer containing the merged content.

1 Select multiple layers.

2 Press Ctrl+Alt+E (Windows) or Command+Option+E (Mac OS).

To stamp all visible layers, do the following:

1 Turn visibility on for the layers you want to merge.

2 Press Shift+Ctrl+Alt+E (Windows) or Shift+Command+Option+E (Mac OS).

Photoshop creates a new layer containing the merged content.

Flatten all layers

Flattening reduces file size by merging all visible layers into the background and discarding hidden layers. Any transparent areas that remain are filled with white. When you save a flattened image, you cannot revert back to the unflattened state; the layers are permanently merged.

Note: *Converting an image between some color modes flattens the file. Save a copy of your file with all layers intact if you want to edit the original image after the conversion.*

1 Make sure that all the layers you want to keep are visible.

2 Choose Layer > Flatten Image, or choose Flatten Image from the Layers panel menu.

More Help topics

Display file information in the document window

Generate image assets from layers

You can generate JPEG, PNG, or GIF image assets from the contents of a layer or layer group in a PSD file. Assets are automatically generated when you append a supported image format extension to a layer name or a layer group name. Optionally, you can also specify quality and size parameters for the generated image assets.

Generating image assets from a PSD file is particularly useful for multidevice web design.

How to create and generate web graphics with Adobe Generator, see Extract Assets for the web .

Generate image assets from layers or layer groups

To understand the image asset generator better, consider a simple PSD file **(download from this link)** with the following layer hierarchy:



The layer hierarchy for this file has two layer groups—Rounded_rectangles and Ellipses. Each of these layer groups contains five layers.

Follow these steps to generate image assets from this PSD file:

1 With the PSD file open, select File > Generate > Image Assets.

2 Append appropriate file format extensions (.jpg, .png, or .gif) to the names of the layers or layer groups from which you want to generate image assets. For example, rename the layer groups, Rounded_rectangles and Ellipses, as Rounded_rectangles.jpg and Ellipses.png; and the layer, Ellipse_4 as Ellipse_4.gif.

Note: *The special characters : and * are not supported in layer names.*

Photoshop generates the image assets and saves them in a subfolder alongside the source PSD file. If the source PSD file is not saved yet, Photoshop saves the generated assets in a new folder on your Desktop.



Image asset generation is enabled for the current document. Once enabled, the feature remains available whenever the document is opened next. In order to disable image asset generation for the current document, deselect File > Generate > Image Assets.

Generate multiple assets from a layer or layer group

To generate multiple assets from a layer/layer group, separate the asset names with commas. For example, the following layer name generates three assets:

Ellipse_4.jpg, Ellipse_4b.png, Ellipse_4c.png

Save assets to a subfolder

You can choose to save image assets generated from particular layers/layer groups in a subfolder directly under the document's asset folder. Include the subfolder name in the layer/layer group name; for example:

[subfolder]/Ellipse_4.jpg

A web design use case

Generating image assets from a PSD file is particularly useful for multidevice web design. Consider the following web design and its layer structure:



Let's extract the icon on top and the top row of the Global Hotspots image grid as image assets:

- Append image format extensions to the appropriate layer names.





Rename the appropriate layers/layer groups

Note: *A single image asset is generated from the contents of a layer/layer group. For example, the AdventureCo Logo layer group in the screenshot above contains a shape layer and a live text layer. These layers are flattened when an image asset is generated from the layer group.*

Photoshop generates the assets and saves them in the same location as the source PSD file.



Specify quality and size parameters

JPEG assets are generated at 90% quality by default. PNG assets are generated as 32-bit images by default. GIF assets are generated with basic alpha transparency.

While renaming layers or layer groups in preparation for asset generation, you can customize quality and size.

Parameters for JPEG assets

- Add the desired output quality as a suffix to the asset name—.jpg(1-10) or .jpg(1-100%). For example:
  - Ellipse_4.jpg5
  - Ellipse_4.jpg50%
- Add the desired output image size (relative or in supported formats—px, in, cm, and mm) as a prefix to the asset name. Photoshop scales the image accordingly. For example:
  - 200% Ellipse_4.jpg

- 300 x 200 Rounded_rectangle_3.jpg
- 10in x 200mm Rounded_rectangle_3.jpg

Note: Remember to add a space character between the prefix and the asset name. If you're specifying the size in pixels, you can omit the unit. For example, 300 x 200.

As illustrated, you can mix different units and pixels while specifying the desired output image size. For example, 4in x 100 Rounded_rectangle_3.jpg is a valid layer name for asset generation.

Parameters for PNG assets

- Add the desired output quality as a suffix to the asset name—8, 24, or 32. For example:
  - Ellipse_4.png24
- Add the desired output image size (relative or in supported formats—px, in, cm, and mm) as a prefix to the asset name. Photoshop scales the image accordingly. For example:
  - 42% Ellipse_4.png
  - 300mm x 20cm Rounded_rectangle_3.png
  - 10in x 50cm Rounded_rectangle_3.png

Note: Remember to add a space character between the prefix and the asset name. If you're specifying the size in pixels, you can omit the unit. For example, 300 x 200.

As illustrated, you can mix different units and pixels while specifying the desired output image size. For example, 4in x 100 Rounded_rectangle_3.png is a valid layer name for asset generation.

Parameters for GIF assets

- Add the desired output image size (relative or in supported formats—px, in, cm, and mm) as a prefix to the asset name. For example:
  - 42% Ellipse_4.gif
  - 300mm x 20cm Rounded_rectangle_3.gif
  - 20in x 50cm Rounded_rectangle_3.gif

Note: Remember to add a space character between the prefix and the asset name. If you're specifying the size in pixels, you can omit the unit. For example, 300 x 200.

As illustrated, you can mix different units and pixels while specifying the desired output image size. For example, 4in x 100 Rounded_rectangle_3.gif is a valid layer name for asset generation.

Quality parameters are not available for GIF assets.

Construct complex layer names

You can specify multiple asset names with parameters while naming a layer for asset generation. For example:

120% Delicious.jpg, 42% Delicious.png24, 100x100 Delicious_2.jpg90%, 250% Delicious.gif

Photoshop generates the following assets from this layer:

- Delicious.jpg (an 8-quality JPG image scaled 120%)
- Delicious.png (a 24-bit PNG image scaled 42%)
- Delicious_2.jpg (a 90%-quality JPG image that has an absolute size of 100x100 px)
- Delicious.gif (a GIF image scaled 250%)

Specify default settings for assets

You can specify document-wide default settings for the generated assets. Follow these steps:

1 Create an empty layer in the document.

2 Begin the name of the layer with the keyword default. Now, enter the settings that you want to apply to all image assets generated from the document. For example:

default hi-res/ Generates all image assets in a subfolder named hi-res. For example, [asset_folder]/hi-res/Delicious.jpg.

default hi-res/@2x Generates all image assets in a subfolder named hi-res. Additionally, suffixes the asset names with @2x. For example, [asset_folder]/hi-res/Delicious@2x.jpg.

default 50% lo-res/ Saves image assets scaled down by 50% in the subfolder lo-res under the document's asset folder

default hi-res/@2x + 50% lo-res/ Generates two image assets from a layer:

- In the hi-res subfolder, an image asset whose name is suffixed with @2x
- In the lo-res subfolder, an image asset scaled down by 50%

Note: *Default scaling factors are overriden by scaling factors specified for individual layers.*

Disable image asset generation for all documents

You can disable image asset generation globally for all Photoshop documents by modifying your Preferences.

1 Select Edit > Preferences > Plug-Ins.

2 Deselect Enable Generator.

3 Click OK.

Note: *The File > Generate menu command is unavailable when you disable image asset generation from Preferences. The feature can be enabled again only in the Preferences dialog box.*

FAQ

- **Do I need to specify unique asset names?**

  Asset names must be unique at a document level.

- **What is the default quality level at which image assets are generated?**

  JPG assets are generated at 90% quality by default. PNG assets are generated as 32-bit images by default. GIF assets are generated with basic alpha transparency.

- **Does Photoshop generate image assets from layers with transparency and other effects?**

  Yes. Transparency and other effects applied to a layer are reflected in the assets generated from that layer. However, such effects may be flattened in the generated assets.

- **How are image assets generated from layers that bleed off the canvas?**

  Assets are clipped to the document boundaries. If an image does not fall within the document boundaries, Generator does not create the associated image assets.

- **Is the comma the only permitted separator between image asset names?**

  In addition to the comma (,), you can use the plus (+) symbol as a separator between image asset names. For example:

  42% Rounded_rectangle_1.png24 + 100x100 Rounded_rectangle_1.jpg90%

is the same as:

42% Rounded_rectangle_1.png24, 100x100 Rounded_rectangle_1.jpg90%

More Help topics

A closer look at the Photoshop Generator syntax

Extract assets

Layer effects and styles

Photoshop provides a variety of effects—such as shadows, glows, and bevels—that change the appearance of a layer's contents in a non-distructive way. Layer effects are linked to the layer contents. When you move or edit the contents of the layer, the same effects are applied to the modified contents. For example, if you apply a drop shadow to a text layer and then add new text, the shadow is added automatically to the new text.

A layer style is one or more effects applied to a layer or layer group. You can apply one of the preset styles provided with Photoshop or create a custom style using the Layer Style dialog box. The layer effects icon fx appears to the right of the layer's name in the Layers panel. You can expand the style in the Layers panel to view or edit the effects that compose the style.

You can apply multiple effects in a single layer style. Also, more than one instance of some effects can comprise a layer style.



***A** Layer effects icon **B** Click to expand and show layer effects **C** Layer effects*

When you save a custom style, it becomes a preset style. Preset styles appear in the Styles panel and can be applied to a layer or group with a single click.

Apply preset styles

You can apply preset styles from the Styles panel. The layer styles that come with Photoshop are grouped into libraries by function. For example, one library contains styles for creating web buttons; another library contains styles for adding effects to text. To access these styles, you need to load the appropriate library. For information on loading and saving styles, see Create and manage preset styles.

***Note:** You cannot apply layer styles to a background, locked layer, or group.*

Display the Styles panel

? Choose Window > Styles.

Apply a preset style to a layer

Normally, applying a preset style replaces the current layer style. However, you can add the attributes of a second style to those of the current style.

? Do one of the following:

- Click a style in the Styles panel to apply it to the currently selected layers.
- Drag a style from the Styles panel onto a layer in the Layers panel.
- Drag a style from the Styles panel to the document window, and release the mouse button when the pointer is over the layer content to which you want to apply the style.

  ***Note**: Hold down Shift as you click or drag to add (rather than replace) the style to any existing effects on the destination layer.*

- Choose Layer > Layer Style > Blending Options, and click the word *Styles* in the Layer Style dialog box (top item in the list on the left side of the dialog box). Click the style you want to apply, and click OK.
- When using a Shape tool or Pen tool in shape layers mode, select a style from the pop-up panel in the options bar before drawing the shape.

***Note:** Some effects have a + icon, indicating that they can be applied more than once in a layer style.*

Apply a style from another layer

- In the Layers panel, Alt-drag (Windows) or Option-drag (Mac OS) the style from a layer's effect list to copy it to another layer.
- In the Layers panel, click-drag the style from a layer's effect list to move it to another layer.

Change how preset styles are displayed

1 Click the triangle in the Styles panel, Layer Style dialog box, or Layer Style pop-up panel in the options bar.

2 Choose a display option from the panel menu:

- Text Only to view the layer styles as a list.
- Small Thumbnail or Large Thumbnail to view the layer styles as thumbnails.
- Small List or Large List to view the layer styles as a list, with a thumbnail of the selected layer style displayed.

Layer Style dialog box overview

You can edit styles applied to a layer or create new styles using the Layer Style dialog box.



You can create custom styles using one or more of the following effects:

Drop Shadow

Adds a shadow that falls behind the contents on the layer.

Inner Shadow

Adds a shadow that falls just inside the edges of the layer's content, giving the layer a recessed appearance.

Outer Glow and Inner Glow

Add glows that emanate from the outside or inside edges of the layer's content.

Bevel and Emboss

Add various combinations of highlights and shadows to a layer.

Satin

Applies interior shading that creates a satiny finish.

Color, Gradient, and Pattern Overlay

Fills the layer's content with a color, gradient, or pattern.

Stroke

Outlines the object on the current layer using color, a gradient, or a pattern. It is particularly useful on hard-edged shapes such as type.

Apply or edit a custom layer style

Note: *You cannot apply layer styles to a background layer, a locked layer, or a group. To apply a layer style to a background layer, first convert it into a regular layer.*

1 Select a single layer from the Layers panel.

2 Do one of the following:

- Double-click the layer, outside the layer name or thumbnail.
- Click the Add A Layer Style icon *fx* at the bottom of the Layers panel and choose an effect from the list.
- Choose an effect from the Layer > Layer Style submenu.
- To edit an existing style, double-click an effect displayed below the layer name in the Layers panel. (Click the triangle next to the Add A Layer Style icon *fx* to display the effects contained in the style.)

3 Set effect options in the Layer Style dialog box. See Layer style options.

4 Add other effects to the style, if desired. In the Layer Style dialog box, click the check box to the left of the effect name to add the effect without selecting it.

You can edit multiple effects without closing the Layer Style dialog box. Click the name of an effect on the left side of the dialog box to display its options.

Change style defaults to custom values

1 In the Layer Style dialog box, customize settings as desired.

2 Click Make Default.

When you next open the dialog box, your custom defaults are automatically applied. If you adjust settings and want to return to your custom defaults, click Reset To Default.

To return to Photoshop's original defaults, see Restore preferences to default .

Layer style options

Altitude For the Bevel and Emboss effect, sets the height of the light source. A setting of 0 is equivalent to ground level, 90 is directly above the layer.

Angle Determines the lighting angle at which the effect is applied to the layer. You can drag in the document window to adjust the angle of a Drop Shadow, Inner Shadow, or Satin effect.

Anti-alias Blends the edge pixels of a contour or gloss contour. This option is most useful on small shadows with complicated contours.

Blend Mode Determines how the layer style blends with the underlying layers, which may or may not include the active layer. For example, an inner shadow blends with the active layer because the effect is drawn on top of that layer, but a drop shadow blends only with the layers beneath the active layer. In most cases, the default mode for each effect produces the best results. See Blending modes.

Choke Shrinks the boundaries of the matte of an Inner Shadow or Inner Glow prior to blurring.

Color Specifies the color of a shadow, glow, or highlight. You can click the color box and choose a color.

Contour With solid-color glows, Contour allows you to create rings of transparency. With gradient-filled glows, Contour allows you to create variations in the repetition of the gradient color and opacity. In beveling and embossing, Contour allows you to sculpt the ridges, valleys, and bumps that are shaded in the embossing process. With shadows, Contour allows you to specify the fade. For more information, see Modify layer effects with contours.

Distance Specifies the offset distance for a shadow or satin effect. You can drag in the document window to adjust the offset distance.

Depth Specifies the depth of a bevel. It also specifies the depth of a pattern.

Use Global Light This setting allows you to set one "master" lighting angle that is then available in all the layer effects that use shading: Drop Shadow, Inner Shadow, and Bevel and Emboss. In any of these effects, if Use Global Light is selected and you set a lighting angle, that angle becomes the global lighting angle. Any other effect that has Use Global Light selected automatically inherits the same angle setting. If Use Global Light is deselected, the lighting angle you set is "local" and applies only to that effect. You can also set the global lighting angle by choosing Layer Style > Global Light.

Gloss Contour Creates a glossy, metallic appearance. Gloss Contour is applied after shading a bevel or emboss.

Gradient Specifies the gradient of a layer effect. Click the gradient to display the Gradient Editor, or click the inverted arrow and choose a gradient from the pop-up panel. You can edit a gradient or create a new gradient using the Gradient Editor. You can edit the color or opacity in the Gradient Overlay panel the same way you edit them in the Gradient

Editor. For some effects, you can specify additional gradient options. Reverse flips the orientation of the gradient, Align With Layer uses the bounding box of the layer to calculate the gradient fill, and Scale scales the application of the gradient. You can also move the center of the gradient by clicking and dragging in the image window. Style specifies the shape of the gradient.

Highlight or Shadow Mode Specifies the blending mode of a bevel or emboss highlight or shadow.

Jitter Varies the application of a gradient's color and opacity.

Layer Knocks Out Drop Shadow Controls the drop shadow's visibility in a semitransparent layer.

Noise Specifies the number of random elements in the opacity of a glow or shadow. Enter a value or drag the slider.

Opacity Sets the opacity of the layer effect. Enter a value or drag the slider.

Pattern Specifies the pattern of a layer effect. Click the pop-up panel and choose a pattern. Click the New Preset button to create a new preset pattern based on the current settings. Click Snap To Origin to make the origin of the pattern the same as the origin of the document (when Link With Layer is selected), or to place the origin at the upper-left corner of the layer (if Link With Layer is deselected). Select Link With Layer if you want the pattern to move along with the layer as the layer moves. Drag the Scale slider or enter a value to specify the size of the pattern. Drag a pattern to position it in the layer; reset the position by using the Snap To Origin button. The Pattern option is not available if no patterns are loaded.

Position Specifies the position of a stroke effect as Outside, Inside, or Center.

Range Controls which portion or range of the glow is targeted for the contour.

Size Specifies the radius and size of blur or the size of the shadow.

Soften Blurs the results of shading to reduce unwanted artifacts.

Source Specifies the source for an inner glow. Choose Center to apply a glow that emanates from the center of the layer's content, or Edge to apply a glow that emanates from the inside edges of the layer's content.

Spread Expands the boundaries of the matte prior to blurring.

Style Specifies the style of a bevel: Inner Bevel creates a bevel on the inside edges of the layer contents; Outer Bevel creates a bevel on the outside edges of the layer contents; Emboss simulates the effect of embossing the layer contents against the underlying layers; Pillow Emboss simulates the effect of stamping the edges of the layer contents into the underlying layers; and Stroke Emboss confines embossing to the boundaries of a stroke effect applied to the layer. (The Stroke Emboss effect is not visible if no stroke is applied to the layer.)

Technique Smooth, Chisel Hard, and Chisel Soft are available for bevel and emboss effects; Softer and Precise apply to Inner Glow and Outer Glow effects.**Smooth**Blurs the edges of a matte slightly and is useful for all types of mattes, whether their edges are soft or hard. It does not preserve detailed features at larger sizes.**Chisel Hard**Uses a distance measurement technique and is primarily useful on hard-edged mattes from anti-aliased shapes such as type. It preserves detailed features better than the Smooth technique.**Chisel Soft**Uses a modified distance measurement technique and, although not as accurate as Chisel Hard, is more useful on a larger range of mattes. It preserves features better than the Smooth technique.**Softer**Applies a blur and is useful on all types of mattes, whether their edges are soft or hard. At larger sizes, Softer does not preserve detailed features.**Precise**Uses a distance measurement technique to create a glow and is primarily useful on hard-edged mattes from anti-aliased shapes such as type. It preserves features better than the Softer technique.

Texture Applies a texture. Use Scale to scale the size of the texture. Select Link With Layer if you want the texture to move along with the layer as the layer moves. Invert inverts the texture. Depth varies the degree and direction (up/down) to which the texturing is applied. Snap To Origin makes the origin of the pattern the same as the origin of the document (if Link With Layer is deselected) or places the origin in the upper-left corner of the layer (if Link With Layer is selected). Drag the texture to position it in the layer.

Modify layer effects with contours

When you create custom layer styles, you can use contours to control the shape of Drop Shadow, Inner Shadow, Inner Glow, Outer Glow, Bevel and Emboss, and Satin effects over a given range. For example, a Linear contour on a Drop Shadow causes the opacity to drop off in a linear transition. Use a Custom contour to create a unique shadow transition.

You can select, reset, delete, or change the preview of contours in the Contour pop-up panel and Preset Manager.



***A** Click to display the Contour Editor dialog box.* ***B** Click to display the pop-up panel.*

Create a custom contour

1. Select the Drop Shadow, Inner Shadow, Inner Glow, Outer Glow, Bevel and Emboss, Contour, or Satin effect in the Layer Style dialog box.
2. Click the contour thumbnail in the Layer Style dialog box.
3. Click the contour to add points, and drag to adjust the contour. Or enter values for Input and Output.
4. To create a sharp corner instead of a smooth curve, select a point and click Corner.
5. To save the contour to a file, click Save and name the contour.
6. To store a contour as a preset, choose New.
7. Click OK. New contours are added at the bottom of the pop-up panel.

Load a contour

? Click the contour in the Layer Style dialog box, and in the Contour Editor dialog box, and then choose Load. Go to the folder containing the contour library you want to load and click Open.

Delete a contour

? Click the inverted arrow next to the currently selected contour to view the pop-up panel. Press Alt (Windows) or Option (Mac OS), and click the contour you want to delete.

Set a global lighting angle for all layers

Using global light gives the appearance of a common light source shining on the image.

? Do one of the following:

- Choose Layer > Layer Style > Global Light. In the Global Light dialog box, enter a value or drag the angle radius to set the angle and altitude, and click OK.
- In the Layer Style dialog box for Drop Shadow, Inner Shadow, or Bevel, select Use Global Light. For Angle, enter a value or drag the radius, and click OK.

The global lighting applies to each layer effect that uses the global lighting angle.

Display or hide layer styles

When a layer has a style, an "fx" icon fx appears to the right of the layer's name in the Layers panel.

Hide or show all layer styles in an image

? Choose Layer > Layer Style > Hide All Effects or Show All Effects.

Expand or collapse layer styles in the Layers panel

? Do one of the following:

- Click the triangle ▼ next to the Add A Layer Style icon fx to expand the list of layer effects applied to that layer.
- Click the triangle to collapse the layer effects.
- To expand or collapse all of the layer styles applied within a group, hold down Alt (Windows) or Option (Mac OS), and click the triangle or inverted triangle for the group. The layer styles applied to all layers within the group expand or collapse correspondingly.

Copy layer styles

Copying and pasting styles is an easy way to apply the same effects to multiple layers.

Copy layer styles between layers

1. From the Layers panel, select the layer containing the style you want to copy.
2. Choose Layer > Layer Style > Copy Layer Style.
3. Select the destination layer from the panel, and choose Layer > Layer Style > Paste Layer Style.

   The pasted layer style replaces the existing layer style on the destination layer or layers.

Copy layer styles between layers by dragging

? Do one of the following:

- In the Layers panel, Alt-drag (Windows) or Option-drag (Mac OS) a single layer effect from one layer to another to duplicate the layer effect, or drag the Effects bar from one layer to another to duplicate the layer style.
- Drag one or more layer effects from the Layers panel to the image to apply the resulting layer style to the highest layer in the Layers panel that contains pixels at the drop point.

Scale a layer effect

A layer style may have been fine-tuned for a target resolution and features of a given size. Using Scale Effects allows you to scale the effects in the layer style without scaling the object to which the layer style is applied.

1. Select the layer in the Layers panel.
2. Choose Layer > Layer Style > Scale Effects.
3. Enter a percentage or drag the slider.
4. Select Preview to preview the changes in the image.
5. Click OK.

Remove layer effects

You can remove an individual effect from a style applied to a layer, or remove the entire style from the layer.

Remove an effect from a style

1 In the Layers panel, expand the layer style to see its effects.

2 Drag the effect to the Delete icon .

Remove a style from a layer

1 In the Layers panel, select the layer containing the style you want to remove.

2 Do one of the following:

- In the Layers panel, drag the Effects bar to the Delete icon .
- Choose Layer > Layer Style > Clear Layer Style.
- Select the layer, and then click the Clear Style button at the bottom of the Styles panel.

Convert a layer style to image layers

To customize or fine-tune the appearance of layer styles, you can convert the layer styles to regular image layers. After you convert a layer style to image layers, you can enhance the result by painting or applying commands and filters. However, you can no longer edit the layer style on the original layer, and the layer style no longer updates as you change the original image layer.

Note: *The layers produced by this process may not result in artwork that exactly matches the version using layer styles. You may see an alert when you create the new layers.*

1 In the Layers panel, select the layer containing the layer style that you want to convert.

2 Choose Layer > Layer Style > Create Layers.

You can now modify and restack the new layers in the same way as regular layers. Some effects—for example, Inner Glow—convert to layers within a clipping mask.

Create and manage preset styles

You can create a custom style and save it as a preset, which is then available from the Styles panel. You can save preset styles in a library and load or remove them from the Styles panel as you need them.

Create a new preset style

1 From the Layers panel, select the layer containing the style that you want to save as a preset.

2 Do one of the following:

- Click an empty area of the Styles panel.
- Click the Create New Style button at the bottom of the Styles panel.
- Choose New Style from the Styles panel menu.
- Choose Layer > Layer Style > Blending Options, and click New Style in the Layer Style dialog box.

3 Enter a name for the preset style, set style options, and click OK.

Rename a preset style

? Do one of the following:

- Double-click a style in the Styles panel. If the Styles panel is set to display styles as thumbnails, enter a new name in the dialog box and click OK. Otherwise, type a new name directly in the Styles panel and press Enter (Windows) or Return (Mac OS).

- Select a style in the Styles area of the Layer Style dialog box. Then choose Rename Style from the pop-up menu, enter a new name, and click OK.
- When using a shape or Pen tool, select a style from the Style pop-up panel in the options bar. Then choose Rename Style from the pop-up panel menu.

Delete a preset style

? Do one of the following:

- Drag a style to the Delete icon at the bottom of the Styles panel.
- Press Alt (Windows) or Option (Mac OS), and click the layer style in the Styles panel.
- Select a style in the Styles area of the Layer Style dialog box. (See Apply preset styles.) Then choose Delete Style from the pop-up menu.
- When using a shape or Pen tool, select a style from the Layer Style pop-up panel in the options bar. Then choose Delete Style from the pop-up panel menu.

Save a set of preset styles as a library

1 Do one of the following:

- Choose Save Styles from the Styles panel menu.
- Select Styles on the left side of the Layer Style dialog box. Then choose Save Styles from the pop-up menu.
- When using a shape or Pen tool, click the layer style thumbnail in the options bar. Then choose Save Styles from the pop-up panel menu.

2 Choose a location for the style library, enter a file name, and click Save.

You can save the library anywhere. However, if you place the library file in the Presets/Styles folder inside the default presets location, the library name will appear at the bottom of the Styles panel menu when you restart the application.

Note: *You can also use the Preset Manager to rename, delete, and save libraries of preset styles.*

Load a library of preset styles

1 Click the triangle in the Styles panel, Layer Style dialog box, or Layer Style pop-up panel in the options bar.

2 Do one of the following:

- Choose Load Styles to add a library to the current list. Then select the library file you want to use, and click Load.
- Choose Replace Styles to replace the current list with a different library. Then select the library file you want to use, and click Load.
- Choose a library file (displayed at the bottom of the panel menu). Then click OK to replace the current list, or click Append to append the current list.

3 To return to the default library of preset styles, choose Reset Styles. You can either replace the current list or append the default library to the current list.

Note: *You can also use the Preset Manager to load and reset style libraries. See Work with the Preset Manager.*

Extract assets

As of the 2015 release of Photoshop CC, extract assets functionality is no longer available in the form described in this article. More intuitive functionality to export artboards, layers, layer groups, and documents as image assets has been introduced in Photoshop.

For details of these newer export options, see Export artboards, layers, and more.

s is a feature in Photoshop CC (2014) and earlier that provides an interface on top of Adobe Generator ets quickly for web and screen design from Photoshop files. You can select layers or layer groups in nd use a graphical user interface to extract them as JPG, PNG, SVG, or GIF image assets.

Assets you can:

a layer or a layer group from a PSD into one or more image assets

mage assets that are PNG, JPG, GIF, or SVG

x, 2x, or more versions of all image assets

each image asset

xtract assets into your preferred folder

- Ensure that the extracted assets are updated whenever the PSD changes

Extract layers or layer groups

When multiple layers or layer groups are selected for extraction, you are presented with options to generate a separate asset from each of the selected items.

1 Select one or more layers or layer groups.

2 Do one of the following:

- Right-click the selected items and then select Extract Assets from the context menu.
- Press the Cmd+Opt+Shift+W (Mac) or Ctrl+Alt+Shift+W (Windows) keyboard shortcut.
- Select File > Extract Assets.

Note: *Extract Assets honors layer names that conform with the Specify quality and size parameters. For example, if you try to extract an asset from a layer named layer.gif, the Extract Assets dialog displays GIF as the default format for the image asset.*

? In the Extract Assets dialog, specify the following settings for each asset that you want to generate: Asset format: Select PNG-8, PNG-24, PNG-32, GIF, JPG, or SVG. Quality scaling: For JPEG assets, you can specify a value from 0–100% to scale the quality of the asset. Adjust the slider in the appropriate direction.

1 To extract more than one version of the asset, click the + icon next to the asset in the Extract Assets dialog. You can specify different format, quality, and scaling parameters for each asset.

2 Click Extract.

3 Photoshop notifies you that it requires a change in layer name to continue with the asset extraction. This is because Photoshop uses the underlying Generator framework to create assets through the Generator syntax. Click OK to continue with extracting assets.

4 Navigate to the folder where you want to save the generated assets.

5 Click Extract. Photoshop creates the image assets and opens their containing folder in the Finder (Mac) or Windows Explorer. In the process of creating the assets, the relevant layers are automatically renamed in accordance with the Specify quality and size parameters.

Note: *Layers/layer groups that you extract as image assets are displayed in the Extract Assets dialog the next time you invoke image asset extraction functionality.*

Specify asset resolutions

You can specify extraction settings and create assets for different purposes using a number of pre-populated setting combinations. For example, you can generate assets for Retina displays. Any settings that you specify are applied document-wide.

1 Specify one or more resolutions you want in the Extract Assets section on the right.

2 If you want a resolution that is not listed, or to change the destination subfolder for assets to be extracted at different resolutions, click Settings.

3 You can either use the default suffixes for each resolution or add your own.

4 You can also choose to use the default subfolders for each resolution or specify a different subfolder name that you prefer.

5 Clicking Done in the Extract Assets dialog saves these settings to the document. Whenever you next create assets, the same settings are used. All future assets are created for the resolutions you have chosen when the document is opened in any instance of Photoshop CC.

Automatically generate assets

If necessary, you can select the Automatically Generate Assets While Updating Document option. This option is synchronized with the Generate > Image Assets option for Photoshop Generator. When you enable the Extract Assets option, the Generator option is also automatically enabled.

Share with developers

1 Save your PSD file to the Creative Cloud folder you synchronized with Creative Cloud.

2 Open Extract Assets (File > Extract Assets) and add the assets you want. Click Extract and choose the default folder to save to.

3 When you open the PSD in Creative Cloud, you will now be able to view your Photoshop file along with a list of assets you have extracted.

4 You can now share your PSD and the assets you have created with developers you want to collaborate with through Creative Cloud .

Common errors

Layer is empty in the Extract Assets dialog

Layers that are empty or are not capable of rendering images cannot be rendered in Extract Assets dialog. These layers can be Clipping Masks, Adjustment Layers, or just layers that have no pixels in them.

Asset names are in conflict

If you have layers with the same name but split across different groups, they are likely to overwrite each other because assets are usually rendered into one single directory. To prevent this, Photoshop automatically rename a layer when we detect a conflict.

If you override the renaming, you receive this error to prevent you from overwriting an existing asset with the name you have chosen.

If your asset names contain invalid characters, you also receive this error. Rename the file without the invalid characters to resolve the issue.

Image is outside of the document bounds

Extract was unable to render the image because it bleeds off the canvas. Move the image so that it fits within the canvas.

An unknown error has occured

This error occurs if Adobe Generator stops responding while the Extract Assets dialog box is open. To fix it, click Done to close the Extract Assets dialog, save your file, and then restart Photoshop.

Adobe also recommends

- Extract Assets forum
- Generate image assets from layers
- Extract for PSD to web workflows (preview)

Mask layers with vector masks

A vector mask is a resolution independent path that clips out the contents of the layer. Vector masks are usually more accurate than those created with pixel-based tools. You create vector masks with the pen or shapes tools. For more information on working with the pen or shapes tools, see About drawing.

Add a vector mask that shows or hides the entire layer

1 In the Layers panel, select the layer to which you want to add a vector mask.

2 Do one of the following:

- To create a vector mask that reveals the entire layer, choose Layer > Vector Mask > Reveal All.
- To create a vector mask that hides the entire layer, choose Layer > Vector Mask > Hide All.

Add a vector mask that shows the contents of a shape

1 In the Layers panel, select the layer to which you want to add a vector mask.

2 Select a path, or use one of the shape or Pen tools to draw a work path.

__Note:__ To create a path with a Shape tool, click the Paths icon in the Shape tool options bar.

3 Click the Vector Mask button in the Masks panel, or choose Layer > Vector Mask > Current Path.

Edit a vector mask

1 In the Layers panel, select the layer containing the vector mask you want to edit.

2 Click the Vector Mask button in the Properties panel or the thumbnail in the Paths panel. Then change the shape using the shape, pen, or Direct Selection tools. See Editing paths.

Change vector mask opacity or feather mask edges

1 In the Layers panel, select the layer containing the vector mask.

2 In the Properties panel, click the Vector Mask button.

3 Drag the Density slider to adjust mask opacity, or the Feathering slider to feather mask edges. For more information, see Adjust mask opacity and edges.

Remove a vector mask

1 In the Layers panel, select the layer containing the vector mask.

2 In the Properties panel, click the Delete Mask button .

Disable or enable a vector mask

? Do one of the following:

- Select the layer containing the vector mask you want to disable or enable, and click the Disable/Enable Mask button in the Properties panel.
- Shift-click the vector mask thumbnail in the Layers panel.
- Select the layer containing the vector mask you want to disable or enable, and choose Layer > Vector Mask > Disable or Layer > Vector Mask > Enable.

A red X appears over the mask thumbnail in the Layers panel when the mask is disabled, and the layer's content appears without masking effects.

Convert a vector mask to a layer mask

? Select the layer containing the vector mask you want to convert, and choose Layer > Rasterize > Vector Mask.

Note: *After you rasterize a vector mask, you can't change it back into a vector object.*

More Help topics

About masks and alpha channels

Mask layers

Merging layers

Combine multiple images into a group portrait

Combine images with Auto-Blend Layers

The Auto-Blend Layers command

Use the Auto-Blend Layers command to stitch or combine images with smooth transitions in the final composite image. Auto-Blend Layers applies layer masks as needed to each layer to mask out over or underexposed areas or content differences. Auto-Blend layers is available only for RGB or Grayscale images. It does not work with Smart Objects, video layers, 3D layers, or background layers.

Among the many uses of the Auto-Blend Layers command, you can blend multiple images of a scene with different areas in focus to achieve a composite image with an extended depth of field. Similarly, you can create a composite by blending multiple images of a scene with different illuminations. In addition to combining images of a scene, you can stitch together images into a panorama. (Although, it might be better to use the Photomerge command to produce panoramas from multiple images.)

Auto-Blend Layers applies layer masks as needed to each layer to mask out over or underexposed areas or content differences and create a seamless composite.

Depth of field blending

1 Copy or place the images you want to combine into the same document.

   Each image will be in a separate layer. See Duplicate Photoshop layers.

2 Select the layers you want to blend.

3 (Optional) Align the layers.

   You can align layers manually or by using the Auto-Align Layers command. See Automatically align image layers.

4 With the layers still selected, choose Edit > Auto-Blend Layers.

5 Select the Auto-Blend Objective:

   Panorama Blends overlapping layers into a panorama image.

   Stack Images Blends the best details in each corresponding area. This options works best with aligned layers.

   Note: *Stack Images lets you blend multiple images of a scene with different areas in focus or different illuminations, to achieve the best results of all the images (you must auto-align the images first).*

6 Select Seamless Tones And Colors to adjust the color and tonality for blending.

7 Click OK.

More Help topics

Move, stack, and lock layers

Combine multiple images into a group portrait

Create panoramic images with Photomerge

Reveal layers with clipping masks

A *clipping mask* lets you use the content of a layer to mask the layers above it. The masking is determined by the content of the bottom or *base layer*. The non-transparent content of the base layer clips (reveals), the content of the layers above it in the clipping mask. All other content in the clipped layers is masked out.





You can use multiple layers in a clipping mask, but they must be successive layers. The name of the base layer in the mask is underlined, and the thumbnails for the overlying layers are indented. The overlying layers display a clipping mask icon.

The Blend Clipped Layers As Group option in the Layer Style dialog box determines whether the blending mode of the base affects the whole group or just the base. (See Group blend effects.)

Create a clipping mask

1 Arrange the layers in the Layers panel so that the base layer with the mask is below the layers that you want to mask.

2 Do one of the following:

- Hold down Alt (Windows) or Option (Mac OS), position the pointer over the line in the Layers panel dividing the base layer and the first layer above it that you want to include in the clipping mask (the pointer changes to two overlapping circles), and click.
- Select the first layer above the base layer in the Layers panel, and choose Layer > Create Clipping Mask.

3 To add additional layers to the clipping mask, use either method in step 2, and work your way upward one level at a time in the Layers panel.

Note: *If you create a new layer between layers in a clipping mask, or drag an unclipped layer between layers in a clipping mask, the layer becomes part of the clipping mask.*

Layers in the clipping mask are assigned the opacity and mode attributes of the base layer.

Remove a layer from a clipping mask

? Do one of the following:

- Hold down Alt (Windows) or Option (Mac OS), position the pointer over the line separating two grouped layers in the Layers panel (the pointer changes to two overlapping circles), and click.
- In the Layers panel, select a layer in the clipping mask, and choose Layer > Release Clipping Mask. This command removes the selected layer and any layers above it from the clipping mask.

Release all layers in a clipping mask

1 In the Layers panel, select the clipping mask layer just above the base layer.

2 Choose Layer > Release Clipping Mask.

More Help topics

About masks and alpha channels

Mask layers

Merging layers

Combine multiple images into a group portrait

Load selections from a layer or layer mask's boundaries

You can select all the nontransparent areas on a layer, or, if a layer mask exists, all the unmasked areas. Selecting these areas is useful when you want to select text or image content that is surrounded by or contains transparent areas, or to create a selection that excludes masked areas on a layer.

1 Do one of the following:
   - To select only the nontransparent areas on an unmasked layer, Ctrl-click (Windows) or Command-click (Mac OS) the layer thumbnail in the Layers panel.
   - To select the unmasked areas on a layer that has a layer mask, Ctrl-click (Windows) or Command-click (Mac OS) the layer mask thumbnail in the Layers panel.
2 If a selection already exists, you can do any of the following:
   - To add the pixels to an existing selection, press Ctrl+Shift (Windows) or Command+Shift (Mac OS), and click the layer thumbnail or layer mask thumbnail in the Layers panel.
   - To subtract the pixels from an existing selection, press Ctrl+Alt (Windows) or Command+Option (Mac OS), and click the layer thumbnail or layer mask thumbnail in the Layers panel.
   - To load the intersection of the pixels and an existing selection, press Ctrl+Alt+Shift (Windows) or Command+Option+Shift (Mac OS), and click the layer thumbnail or layer mask thumbnail in the Layers panel.

If you want to move all the contents of a layer, use the Move tool without loading a transparency mask.

More Help topics

About masks and alpha channels

Mask layers

Edit layer masks

Merging layers

Combine multiple images into a group portrait

Knockout to reveal content from other layers

Create a knockout

Knockout options let you specify which layers “punch through” to reveal content from other layers. For example, you can use a text layer to knock out a color adjustment layer and reveal a portion of the image using the original colors.

As you plan your knockout effect, you need to decide which layer will create the shape of the knockout, which layers will be punched through, and which layer will be revealed. If you want to reveal a layer other than the Background, you can place the layers you want to use in a group or clipping mask.



1 Do one of the following in the Layers panel:

- To reveal the background, position the layer that will create the knockout above the layers that will be punched through, and make sure the bottom layer in the image is a Background layer. (Choose Layer > New > Background From Layer to convert a regular layer into a Background layer.)
- To reveal a layer above the background, place the layers you want to punch through in a group. The top layer in the group will punch through the grouped layers to the next layer below the group.
- To reveal the base layer of a clipping mask, place the layers you want to use in a clipping mask. (See Reveal layers with clipping masks.) Make sure that the Blend Clipped Layers As Group option is selected for the base layer. (See Group blend effects.)

2 Select the top layer (the layer that will create the knockout).

3 To display blending options, either double-click the layer (anywhere outside the layer name or thumbnail), choose Layer > Layer Style > Blending Options, or choose Blending Options from the Layers panel menu.

Note: *To view blending options for a text layer, choose Layer > Layer Style > Blending Options, or choose Blending Options from the Add A Layer Style button at the bottom of the Layers panel menu.*

4 Choose an option from the Knockout pop-up menu:

- Select Shallow to knock out to the first possible stopping point, such as the first layer after the layer group or the base layer of the clipping mask.
- Select Deep to knock out to the background. If there is no background, Deep knocks out to transparency.

Note: *If you are not using a layer group or clipping mask, either Shallow or Deep creates a knockout that reveals the background layer (or transparency, if the bottom layer is not a background layer).*

5 To create the knockout effect, do one of the following:

- Lower the fill opacity.
- Using the choices in the Blend Mode menu, change the blending mode to reveal the underlying pixels.

6 Click OK.

More Help topics

Layer opacity and blending

Edit layer masks

You can easily edit and refine existing layer masks.

1 In the Layers panel, select the layer containing the mask you want to edit.

2 Click the Mask thumbnail in the Layers panel.

3 Select any of the editing or painting tools.

Note: *The foreground and background colors assume default grayscale values when the mask is active.*

4 Do one of the following:

- To subtract from the mask and reveal the layer, paint the mask with white.
- To make the layer partially visible, paint the mask with gray. Darker grays make the level more transparent; lighter grays make it more opaque.
- To add to the mask and hide the layer or group, paint the mask with black. The layers below become visible.

To edit the layer instead of the layer mask, select it by clicking its thumbnail in the Layers panel. A border appears around the layer thumbnail.

To paste a copied selection into a layer mask, Alt-click (Windows) or Option-click (Mac OS) the layer mask thumbnail in the Layers panel to select and display the mask channel. Choose Edit > Paste, then Select > Deselect. The selection is converted to grayscale and added to the mask. Click the layer thumbnail in the Layers panel to deselect the mask channel.

More Help topics

About masks and alpha channels

Mask layers

Merge and stamp layers

Combine multiple images into a group portrait

Load selections from a layer or layer mask's boundaries

Layers 101

Introduction to layers and the Layers panel

Layers 101

Chapter 7: Selecting

Make quick selections

Select with the Quick Selection tool

You can use the Quick Selection tool to quickly "paint" a selection using an adjustable round brush tip. As you drag, the selection expands outward and automatically finds and follows defined edges in the image.

1 Select the Quick Selection tool . (If the tool isn't visible, hold down the Magic Wand tool .)

2 In the options bar, click one of the selection options: New, Add To, or Subtract From.

New is the default option if nothing is selected. After making the initial selection, the option changes automatically to Add To.

3 To change the brush tip size, click the Brush pop-up menu in the options bar, and type in a pixel size or drag the slider. Use the Size pop-up menu options to make the brush tip size sensitive to pen pressure or a stylus wheel.

When creating a selection, press the right bracket (]) to increase the Quick Selection tool brush tip size; press the left bracket ([) to decrease the brush tip size.

4 Choose Quick Selection options.

Sample All Layers Creates a selection based on all layers instead of just the currently selected layer.

Auto-Enhance Reduces roughness and blockiness in the selection boundary. Auto-Enhance automatically flows the selection further toward image edges and applies some of the edge refinement you can apply manually in the Refine Edge dialog with the Contrast and Radius options.

5 Paint inside the part of the image you want to select.

The selection grows as you paint. If updating is slow, continue to drag to allow time to complete work on the selection. As you paint near the edges of a shape, the selection area extends to follow the contours of the shape edge.



If you stop dragging and then click or drag in a nearby area, the selection will grow to include the new area.

- To subtract from a selection, click the Subtract From option in the options bar, then drag over the existing selection.
- To temporarily switch between add and subtract modes, hold down the Alt (Windows) or Option (Mac OS) key.
- To change the tool cursor, choose Edit > Preferences > Cursors > Painting Cursors (Windows) or Photoshop > Preferences > Cursors > Painting Cursors (Mac OS). Normal Brush Tip displays the standard Quick Selection cursor with a plus or minus sign to show the selection mode.

6 (Optional) Click Refine Edge to further adjust the selection boundary. See Refine selection edges.

Select with the Magic Wand tool

The Magic Wand tool lets you select a consistently colored area (for example, a red flower) without having to trace its outline. You specify the selected color range, or *tolerance*, relative to the original color you click.

You cannot use the Magic Wand tool on an image in Bitmap mode or on 32-bits-per-channel images.

1 Select the Magic Wand tool . (If the tool isn't visible, access it by holding down the Quick Selection tool .)

2 Specify one of the selection options in the options bar. The Magic Wand tool's pointer changes depending on which option is selected.



***A** New **B** Add To **C** Subtract From **D** Intersect With*

3 In the options bar, specify any of the following:

Tolerance Determines the color range of selected pixels. Enter a value in pixels, ranging from 0 to 255. A low value selects the few colors very similar to the pixel you click. A higher value selects a broader range of colors.

Anti-aliased Creates a smoother-edged selection.

Contiguous Selects only adjacent areas using the same colors. Otherwise, all pixels in the entire image using the same colors are selected.

Sample All Layers Selects colors using data from all the visible layers. Otherwise, the Magic Wand tool selects colors from the active layer only.

4 In the image, click the color you want to select. If Contiguous is selected, all adjacent pixels within the tolerance range are selected. Otherwise, all pixels in the tolerance range are selected.

5 (Optional) Click Refine Edge to further adjust the selection boundary or view the selection against different backgrounds or as a mask. See Refine selection edges.

More Help topics

Make selections

Save selections and alpha channel masks

Convert paths to selection borders

Selection tools gallery

Make selections

About selecting pixels

A selection isolates one or more parts of your image. By selecting specific areas, you can edit and apply effects and filters to portions of your image while leaving the unselected areas untouched.

The easiest way to select pixels in your image is to use the Make quick selections. You can also select areas of a certain shape with the Select with the marquee toolsor use the Select with the lasso toolsto make a selection by tracing an element in your image. It's also possible to make selections based on a Select a color range in an imagein an image. There are commands in the Select menu to select, deselect, or reselect all pixels.

In addition to pixels, vector data can be used to make selections. Use the pen or shape tools to produce precise outlines called paths. Paths can be converted to selections.

Selections can be copied, moved, and pasted, or saved and stored in an alpha channel. Alpha channels store selections as grayscale images called masks. A mask is like the inverse of a selection: it covers the unselected part of the image and protects it from any editing or manipulations you apply. You can convert a stored mask back into a selection by loading the alpha channel into an image.

Note: *While paths can be converted to selections, selections can also be converted to paths.*

Select single or multiple objects or paths for quick editing. See the tutorial on Path selection and editing.

Select, deselect, and reselect pixels

If a tool is not working as expected, you may have a hidden selection. Use the Deselect command and try the tool again.

Select all pixels on a layer within the canvas boundaries

1 Select the layer in the Layers panel.

2 Choose Select > All.

Deselect selections

? Do one of the following:

- Choose Select > Deselect.
- If you are using the Rectangle Marquee tool, the Elliptical Marquee tool, or the Lasso tool, click anywhere in the image outside the selected area.

Reselect the most recent selection

? Choose Select > Reselect.

More Help topics

Make quick selections

Select with the marquee tools

Select with the lasso tools

Select a color range in an image

Convert paths to selection borders

Save selections and alpha channel masks

Selection tools gallery

Select with the marquee tools

The marquee tools let you select rectangles, ellipses, and 1-pixel rows and columns.

1 Select a marquee tool:

Rectangular Marquee Makes a rectangular selection (or a square, when used with the Shift key).

Elliptical Marquee Makes an elliptical selection (or a circle, when used with the Shift key).

Single Row or Single Column Marquee Defines the border as a 1-pixel-wide row or column.

2 Specify one of the selection options in the options bar.

***A** New **B** Add To **C** Subtract From **D** Intersect With*

3 Specify a feathering setting in the options bar. Turn anti-aliasing on or off for the Elliptical Marquee tool. See Soften the edges of selections.

4 For the Rectangular Marquee tool or the Elliptical Marquee tool, choose a style in the options bar:

Normal Determines marquee proportions by dragging.

Fixed Ratio Sets a height-to-width ratio. Enter values (decimal values are valid) for the aspect ratio. For example, to draw a marquee twice as wide as it is high, enter 2 for the width and 1 for the height.

Fixed Size Specifies set values for the marquee's height and width. Enter pixel values in whole numbers.

In addition to pixels (px) you can also use specific units such as inches (in) or centimeters (cm) in height and width values.

5 For aligning your selection to guides, a grid, slices, or document bounds, do one of the following to snap your selection:

- Choose View > Snap, or choose View > Snap To and choose a command from the submenu. The marquee selection can snap to a document boundary or to a variety of Photoshop Extras, controlled in the Snap To submenu.

6 Do one of the following to make a selection:

- With the Rectangular Marquee tool or the Elliptical Marquee tool, drag over the area you want to select.
- Hold down Shift as you drag to constrain the marquee to a square or circle (release the mouse button before you release Shift to keep the selection shape constrained).
- To drag a marquee from its center, hold down Alt (Windows) or Option (Mac OS) after you begin dragging.



- With the Single Row or Single Column Marquee tool, click near the area you want to select, and then drag the marquee to the exact location. If no marquee is visible, increase the magnification of your image view.

To reposition a rectangular or elliptical marquee, first drag to create the selection border, keeping the mouse button depressed. Then hold down the spacebar and continue to drag. Release the spacebar, but keep the mouse button depressed, if you need to continue adjusting the selection border.

More Help topics

Make selections

Save selections and alpha channel masks

Convert paths to selection borders

Selection tools gallery

Select with the lasso tools

Select with the Lasso tool

The Lasso tool is useful for drawing freeform segments of a selection border.

1 Select the Lasso tool , and set feathering and anti-aliasing in the options bar. (See Soften the edges of selections.)

2 To add to, subtract from, or intersect with an existing selection, click the corresponding button in the options bar.

***A** New **B** Add To **C** Subtract From **D** Intersect With*

3 Do either of the following:

- Drag to draw a freehand selection border.
- To switch between freehand and straight-edged segments, press Alt (Windows) or Option (Mac OS), and click where segments should begin and end. (To erase recently drawn straight segments, hold down the Delete key.)

4 To close the selection border, release the mouse without holding down Alt or Option.

5 (Optional) Click Refine Edge to further adjust the selection boundary. See Refine selection edges.

Select with the Polygonal Lasso tool

The Polygonal Lasso tool is useful for drawing straight-edged segments of a selection border.

1 Select the Polygonal Lasso tool , and select options.

2 Specify one of the selection options in the options bar.

***A** New **B** Add To **C** Subtract From **D** Intersect With*

3 (Optional) Set feathering and anti-aliasing in the options bar. See Soften the edges of selections.

4 Click in the image to set the starting point.

5 Do one or more of the following:

- To draw a straight segment, position the pointer where you want the first straight segment to end, and click. Continue clicking to set endpoints for subsequent segments.
- To draw a straight line at a multiple of 45°, hold down Shift as you move to click the next segment.
- To draw a freehand segment, hold down Alt (Windows) or Option (Mac OS), and drag. When you finish, release Alt or Option and the mouse button.
- To erase recently drawn straight segments, press the Delete key.

6 Close the selection border:

- Position the Polygonal Lasso tool pointer over the starting point (a closed circle appears next to the pointer), and click.
- If the pointer is not over the starting point, double-click the Polygonal Lasso tool pointer, or Ctrl-click (Windows) or Command-click (Mac OS).

7 (Optional) Click Refine Edge to further adjust the selection boundary. See Refine selection edges.

Select with the Magnetic Lasso tool

When you use the Magnetic Lasso tool , the border snaps to the edges of defined areas in the image. The Magnetic Lasso tool is not available for 32-bits-per-channel images.

The Magnetic Lasso tool is especially useful for quickly selecting objects with complex edges set against high-contrast backgrounds.

1 Select the Magnetic Lasso tool.

2 Specify one of the selection options in the options bar.



***A** New **B** Add To **C** Subtract From **D** Intersect With*

3 (Optional) Set feathering and anti-aliasing in the options bar. See Soften the edges of selections.

4 Set any of these options:

Width To specify a detection width, enter a pixel value for Width. The Magnetic Lasso tool detects edges only within the specified distance from the pointer.

To change the lasso pointer so that it indicates the lasso width, press the Caps Lock key. You can change the pointer while the tool is selected but not in use. Press the right bracket (]) to increase the Magnetic Lasso edge width by 1 pixel; press the left bracket ([) to decrease the width by 1 pixel.

Contrast To specify the lasso's sensitivity to edges in the image, enter a value between 1% and 100% for Contrast. A higher value detects only edges that contrast sharply with their surroundings; a lower value detects lower-contrast edges.

Frequency To specify the rate at which the lasso sets fastening points, enter a value between 0 and 100 for Frequency. A higher value anchors the selection border in place more quickly.

On an image with well-defined edges, try a higher width and higher edge contrast, and trace the border roughly. On an image with softer edges, try a lower width and lower edge contrast, and trace the border more precisely.

Stylus Pressure If you are working with a stylus tablet, select or deselect the Stylus Pressure option. When the option is selected, an increase in stylus pressure decreases the edge width.

5 Click in the image to set the first fastening point. Fastening points anchor the selection border in place.

6 Release the mouse button or keep it pressed, and then move the pointer along the edge you want to trace.

The most recent segment of the selection border remains active. As you move the pointer, the active segment snaps to the strongest edge in the image, based on the detection width set in the options bar. Periodically, the Magnetic Lasso tool adds fastening points to the selection border to anchor previous segments.

7 If the border doesn't snap to the desired edge, click once to add a fastening point manually. Continue to trace the edge, and add fastening points as needed.



8 To switch temporarily to the other lasso tools, do one of the following:

- To activate the Lasso tool, hold down Alt (Windows) or Option (Mac OS), and drag while pressing the mouse button.
- To activate the Polygonal Lasso tool, hold down Alt (Windows) or Option (Mac OS), and click.

9 To erase recently drawn segments and fastening points, press the Delete key until you've erased the fastening points for the desired segment.

10 Close the selection border:

- To close the border with a magnetic segment, double-click, or press Enter or Return. (To manually close the border, drag over the starting point and click.)
- To close the border with a straight segment, hold down Alt (Windows) or Option (Mac OS), and double-click.

11 (Optional) Click Refine Edge to further adjust the selection boundary. See Refine selection edges.

More Help topics

Make selections

Save selections and alpha channel masks

Convert paths to selection borders

Selection tools gallery

Select a color range in an image

Select a range of colors

The Color Range command selects a specified color or color range within an existing selection or an entire image. If you want to replace a selection, be sure to deselect everything before applying this command. The Color Range command is not available for 32-bits-per-channel images.

To refine an existing selection, use the Color Range command repeatedly to select a subset of colors. For example, to select the green areas in a cyan selection, select Cyans in the Color Range dialog box, and click OK. Then reopen the Color Range dialog box, and select Greens. (The results are subtle because this technique selects parts of colors within a color mix.)

You can also select skin tones and automatically detect faces to select them. To create a selection that preserves skin tones while you adjust the color of everything else, select Invert below the eyedropper samplers.

1 Choose Select > Color Range.

You can also use Color Range to refine a layer mask. See Adjust mask opacity and edges.

2 From the Select menu, choose one of the following:

Skin Tones To select colors that resemble common skin tones. Enable Detect Faces for more accurate skin tone selection.

Sampled Colors To enable the Eyedropper tool and pick sample colors from the image. If you are selecting multiple color ranges in the image, select Localized Color Clusters to build a more accurate selection.

- A color or tonal range. You won't be able to adjust the selection if you use this option.

3 Select one of the display options:

Selection Previews the selection that will result from the colors you sample in the image. By default, white areas are selected pixels, black areas are unselected, and gray areas are partially selected.

Image Previews the entire image. For example, you might want to sample from a part of the image that isn't on-screen.

To toggle between the Image and Selection previews in the Color Range dialog box, press Ctrl (Windows) or Command (Mac OS).

4 For sampled colors, position the Eyedropper pointer over the image or preview area, and click to sample the colors you want included.



To adjust the selection:

- To add colors, select the plus eyedropper, and click in the preview area or image.
- To remove colors, select the minus eyedropper, and click in the preview area or image.

To activate the plus eyedropper temporarily, hold down Shift. Hold down Alt (Windows) or Option (Mac OS) to activate the minus eyedropper.

5 Adjust the range of colors selected using the Fuzziness slider or by entering a value. The Fuzziness setting controls how wide a range of colors is in the selection, and increases or decreases the amount of partially selected pixels (gray areas in the selection preview). Set a low Fuzziness value to restrict the color range, a higher value to increase the range.

If you selected Localized Color Clusters, use the Range slider to control how far or near a color must be from the sample points to be included in the selection. For example, your image contains a patch of yellow flowers in both the foreground and the background, but you want to select just the foreground flowers. Sample the colors in the foreground flowers and reduce the Range so that the similarly colored flowers in the background are not selected.

6 To preview the selection in the image window, choose a Selection Preview option:

None Shows the original image.

Grayscale Shows white for completely selected pixels, gray for partially selected ones, and black for unselected ones.

Black Matte Shows the original image for selected pixels, and black for unselected ones. This option is good for bright images.

White Matte Shows the original image for selected pixels, and white for unselected ones. This option is good for dark images.

Quick Mask Shows unselected areas as a rubylith overlay (or a custom color you've specified in the Quick Mask Options dialog box).

7 To revert to the original selection, hold down Alt (Windows) or Option (Mac OS), and click Reset.

8 To save and load color range settings, use the Save and Load buttons in the Color Range dialog box to save and reuse the current settings.

You can save Skin Tones selection settings as a preset.

Note: *If you see the message "No pixels are more than 50% selected," the selection border will not be visible. You may have picked a color choice from the Select menu, such as Reds, when the image didn't contain any red hues with high enough saturation.*

Save Skin Tones settings as a preset

The Color Range selections command saves Skin Tones selections as a preset. It can also save the setting for the Detect Faces option when you select Skin Tones or Sampled Colors.

To save Skin Tones settings as a preset:

1 Choose Select > Color Range.

2 In the Color Range dialog box, choose Skin Tones from the Select menu.

3 For more accurate skin tone selection, select Detect Faces and then adjust the Fuzziness slider or enter a value. To help you make your selections, make sure the display option is set to Selection and choose a Selection Preview to view your selections in the document window.

4 Click the Save button and in the Save window, type a file name for the skin tone preset, and then click Save.

To load a skin tones preset:

1 In the Color Range dialog box, click the Load button.

2 In the Load window, select the preset file you want, and then click Load.

More Help topics

Make selections

Save selections and alpha channel masks

Convert paths to selection borders

Selection tools gallery

Adjust pixel selections

Move, hide, or invert a selection

You can move a selection border around an image, hide a selection border, and invert a selection so that the previously unselected part of the image is selected.

Note: *To move the selection itself, not the selection border, use the Move tool. See Move a selection.*

Move a selection border

1 Using any selection tool, select New Selection from the options bar, and position the pointer inside the selection border. The pointer changes to indicate that you can move the selection.

2 Drag the border to enclose a different area of the image. You can drag a selection border partly beyond the canvas boundaries. When you drag it back, the original border reappears intact. You can also drag the selection border to another image window.



You can apply geometric transformations to change the shape of a selection border. (See Apply transformations.)

Control the movement of a selection

- To constrain the direction to multiples of 45°, begin dragging, and then hold down Shift as you continue to drag.
- To move the selection in 1-pixel increments, use an arrow key.
- To move the selection in 10-pixel increments, hold down Shift, and use an arrow key.

Hide or show selection edges

Do one of the following:

- Choose View > Extras. This command shows or hides selection edges, grids, guides, target paths, slices, annotations, layer borders, count, and Smart Guides.
- Choose View > Show > Selection Edges. This toggles the view of the selection edges and affects the current selection only. The selection edges reappear when you make a different selection.

Select the unselected parts of an image

? Choose Select > Inverse.

You can use this option to select an object placed against a solid-colored background. Select the background using the Magic Wand tool and then invert the selection.

Adjust selections manually

You can use the selection tools to add to or subtract from existing pixel selections.

Before manually adding to or subtracting from a selection, you may want to set the feather and anti-aliasing values in the options bar to the same settings used in the original selection.

Add to a selection or select an additional area

1 Make a selection.

2 Using any selection tool, do one of the following:

- Select the Add To Selection option in the options bar, and drag to add to the selection.
- Hold down Shift, and drag to add to the selection.

A plus sign appears next to the pointer when you're adding to a selection.

Subtract from a selection

1 Make a selection.

2 Using any selection tool, do one of the following:

- Select the Subtract From Selection option in the options bar, and drag to intersect with other selections.
- Hold down Alt (Windows) or Option (Mac OS), and drag to subtract another selection.

A minus sign appears next to the pointer when you're subtracting from a selection.

Select only an area intersected by other selections

1 Make a selection.

2 Using any selection tool, do one of the following:

- Select the Intersect With Selection option in the options bar, and drag.
- Hold down Alt+Shift (Windows) or Option+Shift (Mac OS) and drag over the portion of the original selection you want to select.

An "x" appears next to the pointer when you're selecting an intersected area.



Expand or contract a selection by a specific number of pixels

1 Use a selection tool to make a selection.

2 Choose Select > Modify > Expand or Contract.

3 For Expand By or Contract By, enter a pixel value between 1 and 100, and click OK.

The border is increased or decreased by the specified number of pixels. (Any portion of the selection border running along the canvas's edge is unaffected by the Expand command.)

Create a selection around a selection border

The Border command lets you select a width of pixels inside and outside an existing selection border. This can be useful when you need to select a border or band of pixels around an image area, rather than the area itself, for example to clean up a halo effect around a pasted object.



1 Use a selection tool to make a selection.
2 Choose Select > Modify > Border.
3 Enter a value between 1 and 200 pixels for the border width of the new selection, and click OK.

   The new selection frames the original selected area, and is centered on the original selection border. For example, a border width of 20 pixels creates a new, soft-edged selection that extends 10 pixels inside the original selection border and 10 pixels outside it.

Expand a selection to include areas with similar color

Do one of the following:

- Choose Select > Grow to include all adjacent pixels falling within the tolerance range specified in the Magic Wand options.
- Choose Select > Similar to include pixels throughout the image, not just adjacent ones, falling within the tolerance range.

  To increase the selection in increments, choose either command more than once.

Note: *You cannot use the Grow and Similar commands on Bitmap mode images or 32-bits-per-channel images.*

Clean up stray pixels in a color-based selection

1 Choose Select > Modify > Smooth.
2 For Sample Radius, enter a pixel value between 1 and 100, and click OK.

   For each pixel in the selection, Photoshop examines the pixels around it, to the distance you specify in the radius setting. If more than half of these surrounding pixels are selected, the pixel remains in the selection, and the unselected pixels around it are added to the selection. If less than half the surrounding pixels are selected, the pixel is removed from the selection. The overall effect is to reduce patchiness and smooth sharp corners and jagged lines in the selection.

Refine selection edges

The Refine Edge option improves the quality of selection edges, letting you extract objects with ease. You can also use Refine Edge options to refine a layer mask. (See Adjust mask opacity and edges.)

- Click Refine Edge in the options bar, or choose Select > Refine Edge. Then set the following options:

View Mode From the pop-up menu, choose a mode to change how the selection is displayed. For information about each mode, hover the pointer over it until a tool tip appears. Show Original displays the original selection for comparison. Show Radius displays the selection border where edge refinement occurs.

Edge Detection

Refine Radius and Erase Refinements tools

These tools let you precisely adjust the border area in which edge refinement occurs. To quickly toggle from one tool to the other, press Shift+E. To change the brush size, press the bracket keys.

Brush over soft areas such as hair or fur to add fine details to the selection.

Smart Radius Automatically adjusts the radius for hard and soft edges found in the border region. Deselect this option if the border is uniformly hard- or soft-edged, or if you want to control the Radius setting and refinement brushes more precisely.

Radius Determines the size of the selection border in which edge refinement occurs. Use a small radius for sharp edges, and a large one for softer edges.

Adjust Edge

Smooth Reduces irregular areas ("hills and valleys") in the selection border to create a smoother outline.

Feather Blurs the transition between the selection and surrounding pixels.

Contrast When increased, soft-edged transitions along the selection border become more abrupt. Typically, the Smart Radius option and refinement tools are more effective.

Shift Edge Moves soft-edged borders inward with negative values or outward with positive ones. Shifting these borders inward can help remove unwanted background colors from selection edges.

Output

Decontaminate Colors Replaces color fringes with the color of fully selected pixels nearby. The strength of color replacement is proportionate to the softness of selection edges.

Note: *Because this option changes pixel color, it requires output to a new layer or document. Retain the original layer so you can revert back to it if needed. (To easily see changes in pixel color, choose Reveal Layer for the View Mode.)*

Amount Changes the level of decontamination and fringe replacement.

Output To Determines whether the refined selection becomes a selection or mask on the current layer, or produces a new layer or document.

Soften the edges of selections

You can smooth the hard edges of a selection by anti-aliasing and by feathering.

Anti-aliasing Smooths the jagged edges of a selection by softening the color transition between edge pixels and background pixels. Because only the edge pixels change, no detail is lost. Anti-aliasing is useful when cutting, copying, and pasting selections to create composite images.

Anti-aliasing is available for the Lasso tool, the Polygonal Lasso tool, the Magnetic Lasso tool, the Elliptical Marquee tool, and the Magic Wand tool. (Select a tool to display its options bar.)

Note: *You must specify this option before using these tools. After a selection is made, you cannot add anti-aliasing.*

Feathering Blurs edges by building a transition boundary between the selection and its surrounding pixels. This blurring can cause some loss of detail at the edge of the selection.

You can define feathering for the Marquee tools, the Lasso tool, the Polygonal Lasso tool, or the Magnetic Lasso tool as you use the tool, or you can add feathering to an existing selection.

Note: *Feathering effects become apparent only after you move, cut, copy, or fill the selection.*

Select pixels using anti-aliasing

1 Select the Lasso tool, the Polygonal Lasso tool, the Magnetic Lasso tool, the Elliptical Marquee tool, or the Magic Wand tool.

2 Select Anti-aliased in the options bar.

Define a feathered edge for a selection tool

1 Select any of the lasso or marquee tools.

2 Enter a Feather value in the options bar. This value defines the width of the feathered edge and can range from 0 to 250 pixels.

Define a feathered edge for an existing selection

1 Choose Select > Modify > Feather.

2 Enter a value for the Feather Radius, and click OK.

Note: *A small selection made with a large feather radius may be so faint that its edges are invisible and thus not selectable. If you see the message "No pixels are more than 50% selected," either decrease the feather radius or increase the size of the selection. Or click OK to accept the mask at its current setting and create a selection in which you cannot see the edges.*



A *Selection with no feather, same selection filled with pattern* ***B*** *Selection with feather, same selection filled with pattern*

Remove fringe pixels from a selection

When you move or paste an anti-aliased selection, some of the pixels surrounding the selection border are included with the selection. This can result in a fringe or halo around the edges of the pasted selection. These Layer > Matting commands let you edit unwanted edge pixels:

- Color Decontaminate replaces background colors in fringe pixels with the color of fully selected pixels nearby.
- Defringe replaces the color of fringe pixels with the color of pixels farther in from the edge of the selection that lack the background color.

- Remove Black Matte and Remove White Matte are useful when a selection is anti-aliased against a white or black background and you want to paste it onto a different background. For example, anti-aliased black text on a white background has gray pixels at the edges, which are visible against a colored background.

You can also remove fringe areas by using the Advanced Blending sliders in the Layer Styles dialog box to remove, or make transparent, areas from the layer. In this case, you would make the black or white areas transparent. Alt-click (Windows) or Option-click (Mac OS) the sliders to separate them; separating the sliders allows you to remove fringe pixels and retain a smooth edge.

Decrease fringe on a selection

1 Choose Layer > Matting > Defringe.

2 Enter a value in the Width box to specify the area in which to search for replacement pixels. In most cases, a distance of 1 or 2 pixels is enough.

3 Click OK.

Remove a matte from a selection

? Choose Layer > Matting > Remove Black Matte or Layer > Matting > Remove White Matte.

More Help topics

Show or hide Extras

Extract an object from its background

When you extract an object, Photoshop erases its background to transparency. Pixels on the edge of the object lose the color components derived from the background, so they can blend with a new background without producing a color halo.

Use the more effective and flexible Refine Edge command

For superior results and nondestructive processing, use the Select > Refine Edge command. See Refine selection edgesfor instructions and links to additional helpful tutorials.

The Refine Edge command is particularly impressive with highly complex edge content such as wispy hair. Unlike the older Extract plug-in, which permanently erases pixel data, the Refine Edge command creates selection masks that you can later readjust and fine-tune.

Use the older, optional Extract plug-in (Windows only)

Note: *The Extract plug-in is not available for Mac OS because it is incompatible with recent versions of that operating system, and the Refine Edge command produces better extractions.*



1 Because the Refine Edge command is superior, the Extract plug-in is not installed with Photoshop. Download the optional Windows plug-in here.

2 In the Layers palette, select the layer containing the object you want to extract. If you select a background layer, it becomes a normal layer after the extraction. If the layer contains a selection, the extraction erases the background only in the selected area.

To avoid losing the original image information, duplicate the layer or make a snapshot of the original image state.

3 Choose Filter > Extract, and then specify tool options:

Brush Size Enter a value, or drag the slider to specify the width of the Edge Highlighter tool . You also use the Brush Size option to specify the width of the Eraser, Cleanup, and Edge Touchup tools.

Highlight Choose a preset color option for the highlight that appears around objects when you use the Edge Highlighter tool, or choose Other to pick a custom color for the highlight.

Fill Choose a preset color option, or choose Other to pick a custom color for the area covered by the Fill tool.

Smart Highlighting Select this option if you are highlighting a well-defined edge. The option helps you keep the highlight on the edge, and applies a highlight that is just wide enough to cover the edge, regardless of the current brush size.

Note: *If you use Smart Highlighting to mark an object edge that's near another edge, decrease the brush size if conflicting edges pull the highlight off the object edge. If the object edge has a uniform color on one side and high-contrast edges on the other side, keep the object edge within the brush area but center the brush on the uniform color.*

Specify Extraction options:

Textured Image Select this option if the foreground or background of your image contains a lot of texture.

Smooth Enter a value or drag the slider to increase or decrease the smoothness of the outline. It's usually best to begin with zero or a small value to avoid unwanted blurring of details. If there are sharp artifacts in the extraction result, you can increase the Smooth value to help remove them in the next extraction.

Channel Choose the alpha channel from the Channel menu to base the highlight on a selection saved in an alpha channel. The alpha channel should be based on a selection from the edge boundary. If you modify a highlight based on a channel, the channel name in the menu changes to Custom. Your image must have an alpha channel for the Channel option to be available.

Force Foreground Select this option if the object is especially intricate or lacks a clear interior.

4 Select the Edge Highlighter tool , and draw to define the edge of the object you want to extract. Drag so that the highlight slightly overlaps both the foreground object and its background. Use a large brush to cover wispy, intricate edges where the foreground blends into the background, as with hair or trees.

Use either the Zoom tool or the Hand tool to adjust the view as needed.

If you need to erase the highlight, select the Eraser tool , and drag it over the highlight. To erase the entire highlight, press Alt+Backspace (Windows) or Option+Delete (Mac OS).

If the object has a well-defined interior, make sure the highlight forms a complete enclosure. You do not need to highlight areas where the object touches the image boundaries. If the object lacks a clear interior, highlight the entire object.

Note: *You can't highlight the entire object if you've selected Textured Image or Force Foreground.*

5 Define the foreground area by doing one of the following:

- If the object has a well-defined interior, select the Fill tool . Click inside the object to fill its interior. Clicking a filled area again with the Fill tool removes the fill.
- If you've selected Force Foreground, select the Eyedropper tool , and click inside the object to sample the foreground color, or click in the Color text box and use a Color Picker to select the foreground color. This technique works best with objects that contain tones of a single color.

6 (Optional) Click Preview to preview the extracted object. Zoom in as needed.

Show Choose a menu option to switch between views of the original and the extracted image.

Display Choose a menu option to preview the extracted object against a colored matte background or a grayscale background. To display a transparent background, choose None.

7 (Optional) Improve the extraction by doing one of the following:

- Choose new Highlight and Fill options and draw again with the Edge Highlighter tool. Define the foreground area once more, and then preview the extracted object.
- Specify new Extraction settings (Smooth, Force Foreground, or Color) and then preview the extracted object.

When you are satisfied with the extraction, you can do the final touchups.

8 Touch up the extraction results by doing one of the following:

- To erase background traces in the extracted area, use the Cleanup tool . The tool subtracts opacity and has a cumulative effect. You can also use the Cleanup tool to fill gaps in the extracted object. Hold down Alt (Windows) or Option (Mac OS) while dragging to add back opacity.
- To edit the edge of the extracted object, use the Edge Touchup tool . The tool sharpens edges and has a cumulative effect. If there is no clear edge, the Edge Touchup tool adds opacity to the object or subtracts opacity from the background.

You can also clean up the image after an extraction by using the Background Eraser and History Brush tools in the toolbox.

9 Click OK to apply the final extraction. On the layer, all pixels outside the extracted object are erased to transparency.

After an extraction, you can add opacity back to the background and create other effects by choosing Edit > Fade Extract.

Select the image areas in focus

Photoshop lets you easily select the areas/pixels of an image that are in focus.

Do the following:

1 With the image open in Photoshop, choose Select > Focus Area. In the Focus Area dialog box, you can make changes to the default selection.

2 Adjust the In-Focus Range parameter to broaden or narrow down the selection. If you move the slider to 0, the entire image gets selected. However, if you move the slider to the extreme right, only the parts of the image in clearest focus remain selected.



? Use the brush controls to manually add ( ) or remove ( ) areas from the selection.



? If the selection area has noise, control it by adjusting the Advanced > Image Noise Level slider control.

You can leave the Auto option selected for In-Focus Range and Image Noise Level. Photoshop automatically selects appropriate values for these parameters.

? At any point, while making changes to the Focus Area selection, you can toggle the Preview option to see the original image.



1 If necessary, select Soften Edge to feather the edges of the selection.

2 If you want to fine-tune the selection edges, click Refine Edge. For information about specifying the settings in the Refine Edge dialog box, see Refine selection edges.

? Once you've adjusted the selection to your satisfaction, determine whether the refined selection should become a selection or mask on the current layer, or produce a new layer or document. You can choose one of the following output options:

- Selection (default)
- Layer Mask
- New Layer
- New Layer With Layer Mask
- New Document
- New Document With Layer Mask

? Click OK.

More Help topics

Focus-based image selections

Save selections and alpha channel masks

About masks and alpha channels

When you select part of an image, the area that is not selected is *masked*, or protected from editing. So, when you create a mask, you isolate and protect areas of an image as you apply color changes, filters, or other effects to the rest of the image. You can also use masks for complex image editing such as gradually applying color or filter effects to an image.



A *Opaque mask used to protect the background and edit the butterfly* ***B*** *Opaque mask used to protect the butterfly and color the background* ***C*** *Semitransparent mask used to color the background and part of the butterfly*

Masks are stored in alpha channels. Masks and channels are grayscale images, so you can edit them like any other image with painting tools, editing tools, and filters. Areas painted black on a mask are protected, and areas painted white are editable.

Use Quick Mask mode to convert a selection to a temporary mask for easier editing. The Quick Mask appears as a colored overlay with adjustable opacity. You can edit the Quick Mask using any painting tool or modify it with a filter. Once you exit Quick Mask mode, the mask is converted back to a selection on the image.

To save a selection more permanently, you can store it as an alpha channel. The alpha channel stores the selection as an editable grayscale mask in the Channels panel. Once you store the selection as an alpha channel, you can reload it at any time or even load it into another image.

Note: *You can mask or hide parts of a layer using a layer mask.*

Create and edit alpha channel masks

You can create a new alpha channel and then use painting tools, editing tools, and filters to create a mask from the alpha channel. You can also save an existing selection in a Photoshop image as an alpha channel that appears in the Channels panel. See Save and load selections.

Create an alpha channel mask using current options

1 Click the New Channel button at the bottom of the Channels panel.

2 Paint on the new channel to mask out image areas.

Select areas of the image before you create the channel for the mask. Then paint on the channel to refine the mask.

Create an alpha channel mask and set options

1 Alt-click (Windows) or Option-click (Mac OS) the New Channel button at the bottom of the Channels panel, or choose New Channel from the Channels panel menu.

2 Specify options in the New Channel dialog box.

3 Paint on the new channel to mask out image areas.

Edit channel options

To change options for an existing channel, double-click the channel thumbnail in the Channels panel or select Channel Options from the Channels panel menu.

Options available in the New Channel and Channel Options dialog boxes:

Masked Areas Sets masked areas to black (opaque) and selected areas to white (transparent). Painting with black increases the masked area; painting with white increases the selected area. When this option is selected, the Quick Mask button in the toolbox becomes a white circle on a gray background .

Selected Areas Sets masked areas to white (transparent) and selected areas to black (opaque). Painting with white increases the masked area; painting with black increases the selected area. When this option is selected, the Quick Mask button in the toolbox becomes a gray circle on a white background .

Spot Color Converts an alpha channel to a spot color channel. Only available for existing channels.

Color Sets the color and opacity of the mask. Click the color field to change the color. The color and opacity settings affect only the appearance of the mask and have no effect on how underlying areas are protected. Changing these settings may make the mask more easily visible against the colors in the image.

Paint on a channel to mask image areas

When the new channel appears at the bottom of the Channels panel, it is the only channel visible in the image window. Click the eye icon for the composite color channel (RGB, CMYK) to display the image with a color overlay showing the mask.

? Select the brush or an editing tool and do one of the following to add or subtract from the mask created from the alpha channel:

- To remove areas in the new channel, paint with white.
- To add areas in the new channel, paint with black.
- To add or remove areas using opacities less than 100%, set the Opacity in the options bar of the painting or editing tool and then paint with white or black. You can also paint with a color to achieve lower opacities.

Save and load selections

You can save any selection as a mask in a new or existing alpha channel and later reload the selection from the mask.

You can use a selection as a layer mask by loading the selection to make it active, then adding a new layer mask.

Save a selection to a new channel

1 Select the area or areas of the image you want to isolate.

2 Click the Save Selection button at the bottom of the Channels panel. A new channel appears, named according to the sequence in which it was created.

Save a selection to a new or existing channel

1 Use a selection tool to select the area or areas of the image you want to isolate.

2 Choose Select > Save Selection.

3 Specify the following in the Save Selection dialog box, and click OK:

Document Chooses a destination image for the selection. By default, the selection is placed in a channel in your active image. You can choose to save the selection to a channel in another open image with the same pixel dimensions or to a new image.

Channel Chooses a destination channel for the selection. By default, the selection is saved in a new channel. You can choose to save the selection to any existing channel in the selected image or to a layer mask if the image contains layers.

4 If you're saving the selection as a new channel, type a name for the channel in the Name text box.

5 If you're saving the selection to an existing channel, select how to combine the selections:

Replace Channel Replaces the current selection in the channel.

Add to Channel Adds the selection to the current channel contents.

Subtract From Channel Deletes the selection from the channel contents.

Intersect With Channel Keeps the areas of the new selection that intersect with the channel contents.

You can select the channel from the Channels panel to see the saved selection displayed in grayscale.

Load a saved selection from the Channels panel

You can reuse a previously saved selection by loading it into an image. You can also load the selection into an image after you finish modifying an alpha channel.

? Do one of the following in the Channels panel:

- Select the alpha channel, click the Load Selection button at the bottom of the panel, and then click the composite color channel near the top of the panel.
- Drag the channel containing the selection you want to load onto the Load Selection button.
- Ctrl-click (Windows) or Command-click (Mac OS) the channel containing the selection you want to load.
- To add the mask to an existing selection, press Ctrl+Shift (Windows) or Command+Shift (Mac OS), and click the channel.
- To subtract the mask from an existing selection, press Ctrl+Alt (Windows) or Command+Option (Mac OS), and click the channel.

- To load the intersection of the saved selection and an existing selection, press Ctrl+Alt+Shift (Windows) or Command+Option+Shift (Mac OS), and select the channel.

You can drag a selection from one open Photoshop image into another.

Load a saved selection

Note: *If you are loading a saved selection from another image, make sure to open it. Also, make sure your destination image is active.*

1 Choose Select > Load Selection.

2 Specify the Source options in the Load Selection dialog box:

Document Chooses the source to load.

Channel Chooses the channel containing the selection you want to load.

Invert Selects the non-selected areas.

3 Select an Operation option to specify how to combine the selections if the image already has a selection:

New Selection Adds the loaded selection.

Add To Selection Adds the loaded selection to any existing selections in the image.

Subtract From Selection Subtracts the loaded selection from existing selections in the image.

Intersect With Selection Saves a selection from an area intersected by the loaded selection and existing selections in the image.

You can drag a selection from one open Photoshop image into another.

More Help topics

About layer and vector masks

Create a temporary quick mask

About channels

Add layer masks

Move, copy, and delete selected pixels

Note: *Looking for help with modifying your selection? See Adjust pixel selections.*

Move a selection

1 Select the Move tool .

2 Move the pointer inside the selection border, and drag the selection to a new position. If you selected multiple areas, all move as you drag.



Copy and paste selections

You can use the Move tool to copy selections as you drag them within or between images, or you can copy and move selections using the Copy, Copy Merged, Cut, and Paste commands. Dragging with the Move tool saves memory because you don't use the clipboard.

When you paste a selection or layer between images with different resolutions, the pasted data retains its pixel dimensions. This can make the pasted portion appear out of proportion to the new image. Use the Image Size command to make the source and destination images the same resolution before copying and pasting, or use the Free Transform command to resize the pasted content.

Note: *Depending on your color management settings and the color profile associated with the file (or imported data), you may be prompted to specify how to handle color information in the file (or imported data).*

Understanding the Copy and Paste commands

Copy Copies the selected area on the active layer.

Copy Merged Makes a merged copy of all the visible layers in the selected area.

Paste Pastes a copied selection into another part of the image or into another image as a new layer. If you have a selection, the Paste command places the copied selection over the current selection. Without an active selection, Paste places the copied selection in the middle of the view area.

Paste In Place If the clipboard contains pixels copied from another Photoshop document, pastes the selection into the same relative location in the target document as it occupied in the source.

Paste Into or Paste Outside Pastes a copied selection into or outside another selection in any image. The source selection is pasted onto a new layer, and the destination selection border is converted into a layer mask.

Copy a selection

1 Select the area you want to copy.

2 Choose Edit > Copy, or Edit > Copy Merged.

Copy a selection while dragging

1 Select the Move tool , or hold down Ctrl (Windows) or Command (Mac OS) to activate the Move tool.

2 Hold down Alt (Windows) or Option (Mac OS), and drag the selection you want to copy and move.

When copying between images, drag the selection from the active image window into the destination image window. If nothing is selected, the entire active layer is copied. As you drag the selection over another image window, a border highlights the window if you can drop the selection into it.



Create multiple copies of a selection within an image

1 Select the Move tool , or hold down Ctrl (Windows) or Command (Mac OS) to activate the Move tool.

2 Copy the selection:

- Hold down Alt (Windows) or Option (Mac OS), and drag the selection.
- To copy the selection and offset the duplicate by 1 pixel, hold down Alt or Option, and press an arrow key.
- To copy the selection and offset the duplicate by 10 pixels, press Alt+Shift (Windows) or Option+Shift (Mac OS), and press an arrow key.

  As long as you hold down Alt or Option, each press of an arrow key creates a copy of the selection and offsets it by the specified distance from the last duplicate. In this case, the copy is made on the same layer.

Paste one selection into or outside another

1 Cut or copy the part of the image you want to paste.

2 In the same image or another, select the area you want to paste into or outside.

Note: *If you're pasting outside, select an area smaller than the copied selection.*

3 Do either of the following:

- Choose Edit > Paste Special > Paste Into. The contents of the source selection appear within the destination selection.
- Choose Edit > Paste Special > Paste Outside. The contents of the source selection appear around the destination selection.

The Paste Into or Paste Outside command adds a layer and layer mask to the image. In the Layers panel, the new layer contains a layer thumbnail for the pasted selection next to a layer mask thumbnail. The layer mask is based on the selection you pasted into: the selection is unmasked (white), the rest of the layer is masked (black). The layer and layer mask are unlinked—that is, you can move each one independently.



A Window panes selected B Copied image C Paste Into command D Layer thumbnails and layer mask in Layers panel E Pasted image repositioned

4 Select the Move tool , or hold down the Ctrl (Windows) or Command (Mac OS) key to activate the Move tool. Then drag the source contents until the part you want appears through the mask.

5 To specify how much of the underlying image shows through, click the layer mask thumbnail in the Layers panel, select a painting tool, and edit the mask:

- To hide more of the image underlying the layer, paint the mask with black.
- To reveal more of the underlying image, paint the mask with white.
- To partially reveal the underlying image, paint the mask with gray.

6 If you are satisfied with your results, you can choose Layer > Merge Down to merge the new layer and layer mask with the underlying layer and make the changes permanent.

Copy and paste between applications

You can use the Cut, Copy, or Paste commands to copy selections from Photoshop and paste them into other applications, or to paste artwork from other applications into Photoshop. The cut or copied selection remains on the clipboard until you cut or copy another selection. You can also copy artwork between Photoshop and Illustrator by dragging and dropping.

In some cases, the contents of the clipboard are converted to a raster image. Photoshop prompts you when vector artwork will be rasterized.

Note: *The image is rasterized at the resolution of the file into which you paste it. Vector Smart Objects are not rasterized.*

Paste PostScript artwork into Photoshop from another application

1 In the supporting application, select your artwork, and choose Edit > Copy.

2 In Photoshop, select the image into which you'll paste the selection.

3 Choose Edit > Paste.

4 In the Paste dialog box, select from the following Paste As options:

Smart Object Places the artwork in a new layer as a Smart Object.

Pixels Rasterizes the artwork as it is pasted. Rasterizing converts mathematically-defined vector artwork to pixels.

Paths Pastes the copy as a path in the Paths panel. When copying type from Illustrator, you must first convert it to outlines.

Shape Layer Creates a new shape layer that uses the path as a vector mask.

Note: *When copying artwork from Adobe Illustrator, the default clipboard preferences in Illustrator may prevent the Paste dialog box from appearing in Photoshop. Select AICB in the File Handling and Clipboard area of the Preferences dialog box in Illustrator if you want the Paste options to appear when you paste the artwork into Photoshop.*

5 If you chose Paste As Pixels in the previous step, you can choose Anti-aliased in the options bar to make a smooth transition between the edges of the selection and the surrounding pixels.

Note: *You can use the Matting commands if you have already merged data and are trying to reextract the rasterized data.*

Save clipboard contents when you quit Photoshop

Set up Photoshop to save your clipboard contents after quitting so that you can still paste the contents elsewhere.

1 Do one of the following:

- (Windows) Choose Edit > Preferences > General.
- (Mac OS) Choose Photoshop > Preferences > General.

2 Select Export Clipboard to save any Photoshop contents to the clipboard when you quit Photoshop.

Copy artwork from Illustrator by dragging and dropping

? Do one of the following:

- Drag one or more Illustrator vector objects into an open image in Photoshop. This creates a vector Smart Object layer in the image. Choose Layer > Smart Objects > Edit Content to reopen the content in Illustrator for editing.
- To copy the vector object as a path in Photoshop, hold down Ctrl (Windows) or Command (Mac OS) as you drag from Illustrator.
- To copy the contents of the currently selected layer in Photoshop to Illustrator, use the Move tool to drag the content from the Photoshop window into an open Illustrator document.

Delete or cut selected pixels

? Choose Edit > Clear, or press Backspace (Windows) or Delete (Mac OS). To cut a selection to the clipboard, choose Edit > Cut.

Deleting a selection on a background layer replaces the original color with the background color. Deleting a selection on a standard layer replaces the original color with layer transparency.

More Help topics

Make selections

Adjust pixel selections

About layer and vector masks

Understand Smart Objects

Remove fringe pixels from a selection

Duplicate, split, and merge channels

Duplicate channels

You can copy a channel and use it in the current image or another image.

For example, you may want to use the Duplicate Channel feature to create a channel mask; or you may want to back up a copy of a channel before you edit it.

Duplicate a channel

If you are duplicating alpha channels between images, the channels must have identical pixel dimensions. You cannot duplicate a channel to a Bitmap-mode image.

1 In the Channels panel, select the channel to duplicate.

2 Choose Duplicate Channel from the Channels panel menu.

3 Type a name for the duplicate channel.

4 For Document, do one of the following:

- Choose a destination. Open images only with pixel dimensions identical to the current image are available. To duplicate the channel in the same file, select the channel's current file.
- Choose New to copy the channel to a new image, creating a multichannel image containing a single channel. Type a name for the new image.

5 To reverse the selected and masked areas in the duplicate channel, select Invert.

Duplicate a channel in an image

1 In the Channels panel, select the channel you want to duplicate.

2 Drag the channel onto the Create New Channel button at the bottom of the panel.

Duplicate a channel in another image

1 In the Channels panel, select the channel you want to duplicate.

2 Make sure that the destination image is open.

Note: *The destination image does not have to have the same pixel dimensions as the duplicated channel.*

3 Do one of the following:

- Drag the channel from the Channels panel into the destination image window. The duplicated channel appears at the bottom of the Channels panel.
- Choose Select > All, and then choose Edit > Copy. Select the channel in the destination image and choose Edit > Paste. The pasted channel overwrites the existing channel.

Split channels into separate images

You can split channels of flattened images only. Splitting channels is useful when you want to retain individual channel information in a file format that doesn't preserve channels.

? To split channels into separate images, choose Split Channels from the Channels panel menu.

The original file is closed, and the individual channels appear in separate grayscale image windows. The title bars in the new windows show the original filename plus the channel. You save and edit the new images separately.

Merge channels

Multiple grayscale images can be combined as the channels of a single image. The images you want to merge must be in grayscale mode, be flattened (have no layers), have the same pixel dimensions, and be open. The number of grayscale images you have open determines the color modes available when merging channels. For example, if you have three images open, you can merge them into an RGB image; if you have four images open, they can become a CMYK image.

If you are working with DCS files that have accidentally lost their links (and so cannot be opened, placed, or printed), open the channel files, and merge them into a CMYK image. Then re-save the file as a DCS EPS file.

1 Open the grayscale images containing the channels you want to merge, and make one of the images active.

You must have more than one image open for the Merge Channels option to be available.

2 Choose Merge Channels from the Channels panel menu.

3 For Mode, choose the color mode you want to create. The number of channels appropriate for the mode appears in the Channels text box.

4 If necessary, enter a number in the Channels text box.

If you enter a number that is incompatible with the selected mode, Multichannel mode is automatically selected. This creates a multichannel image with two or more channels.

5 Click OK.

6 For each channel, make sure the image you want is open. If you change your mind about the image type, click Mode to return to the Merge Channels dialog box.

7 If you are merging channels into a multichannel image, click Next, and select the remaining channels.

Note: *All channels of a multichannel image are alpha channels or spot channels.*

8 When you have finished selecting channels, click OK.

The selected channels are merged into a new image of the specified type, and the original images are closed without any changes. The new image appears in an untitled window.

Note: *You cannot split and recombine (merge) an image with spot color channels. The spot color channel will be added as an alpha channel.*

More Help topics

Channel basics

Create a temporary quick mask

Creating and editing a quick mask

To use Quick Mask mode to create and edit selections quickly, start with a selection and then add to or subtract from it to make the mask. You can also create the mask entirely in Quick Mask mode. Color differentiates the protected and unprotected areas. When you leave Quick Mask mode, the unprotected areas become a selection.

Note: *A temporary Quick Mask channel appears in the Channels panel while you work in Quick Mask mode. However, you do all mask editing in the image window.*

1 Using any selection tool, select the part of the image you want to change.

2 Click the Quick Mask mode button in the toolbox.

A color overlay (similar to a rubylith) covers and protects the area outside the selection. Selected areas are left unprotected by this mask. By default, Quick Mask mode colors the protected area using a red, 50% opaque overlay.



A *Standard mode* ***B*** *Quick Mask mode* ***C*** *Selected pixels appear as white in channel thumbnail* ***D*** *Rubylith overlay protects area outside selection, and unselected pixels appear as black in channel thumbnail*

3 To edit the mask, select a painting tool from the toolbox. The swatches in the toolbox automatically become black and white.

4 Paint with white to select more of an image (the color overlay is removed from areas painted with white). To deselect areas, paint over them with black (the color overlay covers areas painted with black). Painting with gray or another color creates a semitransparent area, useful for feathering or anti-aliased effects. (Semitransparent areas may not appear to be selected when you exit Quick Mask mode, but they are.)



A Original selection and Quick Mask mode with green chosen as mask color ***B*** *Painting with white in Quick Mask mode adds to the selection* ***C*** *Painting with black in Quick Mask mode subtracts from the selection*

5 Click the Standard Mode button in the toolbox to turn off the quick mask and return to your original image. A selection border now surrounds the unprotected area of the quick mask.

If a feathered mask is converted to a selection, the boundary line runs halfway between the black pixels and the white pixels of the mask gradient. The selection boundary indicates the transition between pixels that are less than 50% selected and those that are more than 50% selected.

6 Apply the desired changes to the image. Changes affect only the selected area.

7 Choose Select > Deselect to deselect the selection.

You can convert this temporary mask to a permanent alpha channel by switching to standard mode and choosing Select > Save Selection.

Change Quick Mask options

1 Double-click the Quick Mask Mode button in the toolbox.

2 Choose from the following display options:

Masked Areas Sets masked areas to black (opaque) and selected areas to white (transparent). Painting with black increases the masked area; painting with white increases the selected area. When this option is selected, the Quick Mask button in the toolbox becomes a white circle on a gray background .

Selected Areas Sets masked areas to white (transparent) and selected areas to black (opaque). Painting with white increases the masked area; painting with black increases the selected area. When this option is selected, the Quick Mask button in the toolbox becomes a gray circle on a white background .

To toggle between the Masked Areas and Selected Areas options for quick masks, Alt-click (Windows) or Option-click (Mac OS) the Quick Mask Mode button.

3 To choose a new mask color, click the color box, and choose a new color.

4 To change the opacity, enter a value between 0% and 100%.

Both the color and opacity settings affect only the appearance of the mask and have no effect on how underlying areas are protected. Changing these settings may make the mask more easily visible against the colors in the image.

More Help topics

Save selections and alpha channel masks

About layer and vector masks

Choose a color with the Adobe Color Picker

Convert between paths and selection borders

Convert paths to selection borders

Paths provide smooth outlines that you can convert into precise selection borders. You can also convert selection borders into paths, using the Direct Selection tool for fine-tuning.

You can define any closed path as a selection border. A closed path can be added to, subtracted from, or combined with the current selection.

Convert a path to a selection border using the current settings

1 Select the path in the Paths panel.

2 To convert the path, do one of the following:

- Click the Load Path As A Selection button at the bottom of the Paths panel.
- Ctrl-click (Windows) or Command-click (Mac OS) the path thumbnail in the Paths panel.

Convert a path to a selection border and specify settings

1 Select the path in the Paths panel.

2 Do one of the following:

- Alt-click (Windows) or Option-click (Mac OS) the Load Path As A Selection button at the bottom of the Paths panel.
- Alt-drag (Windows) or Option-drag (Mac OS) the path to the Load Path As A Selection button.
- Choose Make Selection from the Paths panel menu.

3 In the Make Selection dialog box, select a Rendering option:

Feather Radius Defines how far inside and outside the selection border the feather edge extends. Enter a value in pixels.

Anti-aliased Creates a finer transition between the pixels in the selection and the surrounding pixels. Make sure the Feather Radius is set to 0.

For more information on these options, see Soften the edges of selections.

4 Select an Operation option:

New Selection Selects only the area defined by the path.

Add To Selection Adds the area defined by the path to the original selection.

Subtract From Selection Removes the area defined by the path from the current selection.

Intersect With Selection Selects the area common to both the path and the original selection. If the path and selection do not overlap, nothing is selected.

5 Click OK.

Convert a selection to a path

Any selection made with a selection tool can be defined as a path. The Make Work Path command eliminates any feathering applied to the selection. It can also alter the shape of the selection, depending on the complexity of the path and the tolerance value you choose in the Make Work Path dialog box.

1 Make the selection, and do one of the following:

- Click the Make Work Path button at the bottom of the Paths panel to use the current tolerance setting, without opening the Make Work Path dialog box.
- Alt-click (Windows) or Option-click (Mac OS) the Make Work Path button at the bottom of the Paths panel.
- Choose Make Work Path from the Paths panel menu.

2 Enter a Tolerance value or use the default value in the Make Work Path dialog box.

Tolerance values can range from 0.5 to 10 pixels and determine how sensitive the Make Work Path command is to slight changes in the selection shape. The higher the tolerance value, the fewer the anchor points used to draw the path and the smoother the path. If the path is used as a clipping path and you have problems printing the image, use a higher tolerance value. (See Print image clipping paths.)

3 Click OK. The path appears at the bottom of the Paths panel.

Channel calculations

Blend layers and channels

You can use the blending effects associated with layers to combine channels within and between images into new images. You can use either the Apply Image command (on single and composite channels) or the Calculations command (on single channels). These commands offer two additional blending modes not available in the Layers panel—Add and Subtract. Although it's possible to create new combinations of channels by copying channels to layers in the Layers panel, you may find it quicker to use the calculation commands to blend channel information.

The calculation commands perform mathematical operations on the corresponding pixels of two channels (the pixels with identical locations in the image) and then combine the results in a single channel. Two concepts are fundamental to understanding how the calculation commands work:

- Each pixel in a channel has a brightness value. The Calculations and Apply Image commands manipulate these values to produce the resulting composite pixels.

- These commands overlay the pixels in two or more channels. Thus, the images used for calculations must have the same pixel dimensions.

Blend channels with the Apply Image command

The Apply Image command lets you blend one image's layer and channel (the *source*) with a layer and channel of the active image (the *destination*).

1 Open the source and destination images, and select the desired layer and channel in the destination image. The pixel dimensions of the images must match for image names to appear in the Apply Image dialog box.

   Note: *If the color modes of the two images differ (for example, one image is RGB and the other is CMYK), you can apply a single channel (but not the source's composite) to the destination layer's composite channel.*

2 Choose Image > Apply Image.

3 Choose the source image, layer, and channel you want to combine with the destination. To use all layers in the source image, select Merged For Layer.

4 To preview the results in the image window, select Preview.

5 To use the negative of the channel contents in the calculation, select Invert.

6 For Blending, choose a blending option.

   For information on the Add and Subtract options, see Add and Subtract blending modes. For information on other blending options, see Blending mode descriptions.

7 Enter an Opacity value to specify the effect's strength.

8 To apply the results only to opaque areas in the result layer, select Preserve Transparency.

9 If you want to apply the blending through a mask, select Mask. Then choose the image and layer containing the mask. For Channel, you can choose any color or alpha channel to use as the mask. You can also use a mask based on the active selection or the boundaries of the chosen layer (Transparency). Select Invert to reverse the masked and unmasked areas of the channel.

Blend channels with the Calculations command

The Calculations command lets you blend two individual channels from one or more source images. You can then apply the results to a new image or to a new channel or selection in the active image. You cannot apply the Calculations command to composite channels.

1 Open the source image or images.

   Note: *If you are using more than one source image, the images must have the same pixel dimensions.*

2 Choose Image > Calculations.

3 To preview the results in the image window, select Preview.

4 Choose the first source image, layer, and channel. To use all the layers in the source image, choose Merged For Layer.

5 To use the negative of the channel contents in the calculation, select Invert. For Channel, choose Gray if you want to duplicate the effect of converting the image to grayscale.

6 Choose the second source image, layer, and channel, and specify options.

7 For Blending, choose a blending mode.

   For information on the Add and Subtract options, see Add and Subtract blending modes. For information on other blending options, see Blending mode descriptions.

8 Enter an Opacity value to specify the effect's strength.

9 If you want to apply the blending through a mask, select Mask. Then choose the image and layer containing the mask. For Channel, you can choose any color or alpha channel to use as the mask. You can also use a mask based on the active selection or the boundaries of the chosen layer (Transparency). Select Invert to reverse the masked and unmasked areas of the channel.

10 For Result, specify whether to place the blending results in a new document or in a new channel or selection in the active image.

Add and Subtract blending modes

The Add and Subtract blending modes are available only for the Apply Image and Calculations commands.

Add

Adds the pixel values in two channels. This is a good way to combine non-overlapping images in two channels.

Because higher pixel values represent lighter colors, adding channels with overlapping pixels lightens the image. Black areas in both channels remain black (0 + 0 = 0). White in either channel results in white (255 + any value = 255 or greater).

Add mode divides the sum of the pixel values by the Scale amount, and then adds the Offset value to the sum. For example, to find the average of the pixels in two channels, add them, divide by 2, and enter no Offset value.

The Scale factor may be any number between 1.000 and 2.000. Entering a higher Scale value darkens the image.

The Offset value lets you lighten or darken the pixels in the destination channel by any brightness value between +255 and –255. Negative values darken the image; positive values lighten the image.

Subtract

Subtracts the pixel values in the source channel from the corresponding pixels in the target channel. As with Add mode, the result is then divided by the Scale factor and added to the Offset value.

The Scale factor may be any number between 1.000 and 2.000. The Offset value lets you lighten or darken the pixels in the destination channel by any brightness value between +255 and –255.

Channel basics

About channels

Channels are grayscale images that store different types of information:

- Color information channels are created automatically when you open a new image. The image's color mode determines the number of color channels created. For example, an RGB image has a channel for each color (red, green, and blue) plus a composite channel used for editing the image.
- Alpha channels store selections as grayscale images. You can add alpha channels to create and store masks, which let you manipulate or protect parts of an image. (See About masks and alpha channels.)
- Spot color channels specify additional plates for printing with spot color inks. (See About spot colors.)

  An image can have up to 56 channels. All new channels have the same dimensions and number of pixels as the original image.

The file size required for a channel depends on the pixel information in the channel. Certain file formats, including TIFF and Photoshop formats, compress channel information and can save space. The size of an uncompressed file, including alpha channels and layers, appears as the right-most value in the status bar at the bottom of the window when you choose Document Sizes from the pop-up menu.

Note: *As long as you save a file in a format supporting the image's color mode, the color channels are preserved. Alpha channels are preserved only when you save a file in Photoshop, PDF, TIFF, PSB, or raw formats. DCS 2.0 format preserves only spot channels. Saving in other formats may cause channel information to be discarded.*

Channels panel overview

The Channels panel lists all channels in the image—composite channel first (for RGB, CMYK, and Lab images). A thumbnail of the channel's contents appears to the left of the channel name; the thumbnail is automatically updated as you edit the channel.



A *Color channels* ***B*** *Spot channels* ***C*** *Alpha channels*

Display the Channels panel

? Choose Windows > Channels.

Resize or hide channel thumbnails

? Choose Panel Options from the Channels panel menu. Click a thumbnail size or click None to turn off the display of thumbnails.

Viewing thumbnails is a convenient way of tracking channel contents; however, turning off the display of thumbnails can improve performance.

Show or hide a channel

You can use the Channels panel to view any combination of channels in the document window. For example, you can view an alpha channel and the composite channel together to see how changes made in the alpha channel relate to the entire image.

? Click in the eye column next to the channel to show or hide that channel. (Click the composite channel to view all default color channels. The composite channel is displayed whenever all the color channels are visible.)

To show or hide multiple channels, drag through the eye column in the Channels panel.

Show color channels in color

Individual channels are displayed in grayscale. In RGB, CMYK, or Lab images, you can view the individual channels in color. (In Lab images, only the *a* and *b* channels appear in color.) If more than one channel is active, the channels always appear in color.

You can change the default to show the individual color channels in color. When a channel is visible in the image, an eye icon appears to its left in the panel.

1 Do one of the following:
   - In Windows, choose Edit > Preferences > Interface.
   - In Mac OS, choose Photoshop > Preferences > Interface.
2 Select Show Channels In Color, and click OK.

Select and edit channels

You can select one or more channels in the Channels panel. The names of all selected, or *active*, channels are highlighted.



***A** Not visible or editable **B** Visible but not selected for editing **C** Selected for viewing and editing **D** Selected for editing but not viewing*

- To select a channel, click the channel name. Shift-click to select (or deselect) multiple channels.
- To edit a channel, select it and then use a painting or editing tool to paint in the image. You can paint on only one channel at a time. Paint with white to add the selected channel's color at 100% intensity. Paint with a value of gray to add the channel's color at a lower intensity. Paint with black to fully remove the channel's color.

Rearrange and rename alpha and spot channels

You can move alpha or spot channels above the default color channels only if the image is in Multichannel mode (Image > Mode > Multichannel). For information about that mode's limitations, see Multichannel mode.

- To change the order of alpha or spot channels, drag the channel up or down in the Channels panel. When a line appears in the position you want, release the mouse button.

***Note:** Spot colors are overprinted in the order of their appearance from top to bottom in the Channels panel.*

- To rename an alpha or spot channel, double-click the channel's name in the Channels panel, and enter a new name.

For more information, see Create a new spot channel.

Delete a channel

You may want to delete spot or alpha channels you no longer need before saving an image. Complex alpha channels can substantially increase the disk space required for an image.

? In Photoshop, select the channel in the Channels panel and do one of the following:

- Alt-click (Windows) or Option-click (Mac OS) the Delete icon .
- Drag the channel name in the panel to the Delete icon.
- Choose Delete Channel from the Channels panel menu.
- Click the Delete icon at the bottom of the panel, and then click Yes.

Note: *When you delete a color channel from a file with layers, visible layers are flattened and hidden layers are discarded. This is done because removing a color channel converts the image to Multichannel mode, which does not support layers. An image isn't flattened when you delete an alpha channel, a spot channel, or a quick mask.*

More Help topics

Duplicate, split, and merge channels

Refine a selection

Refine a selection or mask edge

Refine a selection

Selecting areas of a photo

Discover the basic building block of image editing.

Selecting areas of a photo

Chapter 8: Image adjustments

Perspective Warp

Photoshop lets you easily adjust perspective in images. This feature is particularly useful for images having straight lines and flat surfaces—for example, architectural images and images of buildings. You can also use this feature to composite objects having different perspectives in a single image.

Background

Sometimes, an object may look different in an image from how it appears in real life. This mismatch is due to perspective distortion. Images of the same object captured from different camera distances and angles of view exhibit different perspective distortion.

Perspective distortion in images of the same object captured from different distances and angles

(Creative Commons image courtesy: SharkD)

Prerequisite: Enable the graphics processor

Photoshop requires at least 512 MB of video RAM (VRAM) to run the perspective warp feature on 16-bit and 32-bit documents. For details, see Photoshop CC GPU FAQ.

As a prerequisite to adjusting perspective, ensure that the graphics processor is enabled in your Photoshop preferences.

1. Select Edit > Preferences > Performance.
2. In the Graphics Processor Settings area, select Use Graphics Processor.
3. Click Advanced Settings. Ensure that Use Graphics Processor To Accelerate Computation is selected.
4. Click OK.

Adjust perspective

Define planes

Before you adjust perspective, you must define the planes of the architecture in the image.

1. Open the image in Photoshop.
2. Select Edit > Perspective Warp. Review the onscreen tip and close it.
3. Draw quads along the planes of the architecture in the image. While drawing the quads, try to keep their edges parallel to the straight lines in the architecture.

Manipulate the planes

? Switch to the Warp mode from the Layout mode.

? Manipulate perspective in one of the several available ways:

- Move around the corners of the quads (pins) as appropriate. For example, you can adjust the perspective of this image, such that the two sides of the building exhibit foreshortening in equal measures. The resulting perspective would approximate a direct view of the building from a corner.

- Shift-click an individual edge of a quad to straighten it and keep it straight during further perspective manipulation. Such a straightened edge is highlighted in yellow in the Warp mode. You can manipulate the corners of the quads (pins) for finer control while adjusting perspective.

Shift-click the edge again if you don't want to preserve its straightening.

- In the Warp mode, you can click the following icons for automatic perspective adjustment:

Automatically level near horizontal lines



Automatically straighten near vertical lines

Automatically straighten both vertically and horizontally

? Once you're done adjusting the perspective, click the Commit Perspective Warp icon ( ).

Keyboard shortcuts

The following keyboard shortcuts make it easier to adjust perspective:

Arrow keys Slightly move a corner of a quad (pin)

H Hides the grid when you're working in the Warp mode

L Switches to the Layout mode

W Switches to the Warp mode

Enter key In the Layout mode, you can press the Enter key to quickly switch to the Warp mode. In the Warp mode, the Enter key commits the current changes to the perspective.

Shift-click (Warp mode) Straightens an individual edge of a quad and keeps it straight during further perspective manipulation. If you don't want to preserve the straightening of the edge, Shift-click it again.

Shift-(drag an edge) (Warp mode) Constrains the shape of a plane while lengthening it

FAQ

- **Can I edit different perspectives in the same image?**

  Yes. When you edit different perspectives in the same image, you can choose to:

  - Keep one part of the image having a certain perspective unchanged while adjusting the perspective for the rest of the image. To do so:

    1. Draw a quad around the part of the image whose perspective you want to preserve. Ensure that this quad is not snapped to any of the other planes whose perspective you're adjusting.
    2. Keep this quad unchanged while working with the other planes whose perspective you want to adjust.

  - Edit parts of the image having different perspectives independent of each other.

    1. Draw unconnected quads around the relevant parts of the image.
    2. Manipulate the quads independent of one another.

- **How much VRAM do I need to run the perspective warp feature?**

  Photoshop requires at least 512 MB of video RAM (VRAM) to run the perspective warp feature on 16-bit and 32-bit documents. If your GPU has 256 MB of VRAM, you can run the perspective warp feature only on 8-bit documents.

  Also, the nVidia GeForce GT 120 video card isn't currently supported for the perspective warp feature.

- **The onscreen tips are no longer displaying. How do I bring them back?**

  Follow these steps:

  1. Select Edit > Preferences > General.
  2. Click Reset All Warning Dialogs and then click OK.

- **Can I define different sets of planes for the same architecture?**

  Yes. As an illustration, here are two different ways of defining planes for the gateway to the Taj Mahal:



Reduce camera shake blurring

Photoshop features an intelligent mechanism to automatically reduce image blurring caused by camera motion. If necessary, you can adjust advanced settings to further sharpen the image. The Shake Reduction filter in the Filter > Sharpen menu can reduce blurring resulting from several types of camera motion; including linear motion, arc-shaped motion, rotational motion, and zigzag motion.



Images suitable for camera shake reduction

The camera shake reduction feature works best with decently lit still camera images having low noise. The following types of still images are particularly suitable for shake reduction:

- Indoor or outdoor images captured using a lens with a long focal length
- Indoor images of a static scene taken with a slow shutter speed and no flash

In addition, shake reduction can help sharpen blurred text in images affected by camera motion.

Use automatic camera shake reduction

1 Open the image.

2 Select Filter > Sharpen > Shake Reduction. Photoshop automatically analyzes the region of the image best suited for shake reduction, determines the nature of the blur, and extrapolates the appropriate corrections to the entire image. The corrected image is displayed for your review in the Shake Reductiondialog.

The Detail loupe in the lower-right pane lets you closely examine the region in focus. If necessary, zoom in or zoom out on an image element. As you drag the Hand tool over the Detail loupe to examine an image region, release the mouse button to see a quick preview of the shake reduction changes for that region.

Note: *If no corrections seem to be applied to the image in the Shake Reduction dialog, ensure that the Preview option in the right pane is enabled.*

Use multiple blur traces for camera shake reduction

A blur trace represents the shape and extent of the blur that affects a selected region of the image. Different regions of the image may have differently shaped blurs. Automatic camera shake reduction takes into account the blur trace for just the default region of the image that Photoshop has determined as most suitable for blur estimation. To further fine-tune the image, you can have Photoshop compute and consider blur traces for multiple regions.

Available blur traces are listed in the Advanced panel of the Shake Reduction dialog. You can click a blur trace to zoom in on it.



Create and modify blur traces

Photoshop provides several ways to create and modify blur traces. For best results, create blur traces in regions of the image that have edge contrast. For example, the region labeled **A** in the illustration below is better suited for blur estimation than the region labeled **B**.



Resize/reposition the boundaries of the current region in focus

You can simply resize the boundaries of the region in focus to update the associated blur trace. To shift focus to a different region, drag the center pin of the region currently in focus.

Have Photoshop suggest a new region for blur estimation

1 Click the Add Suggested Blur Trace icon ( ) in the Advanced panel in the right-pane. Photoshop highlights a new region of the image suitable for blur estimation and creates its blur trace.

2 Add more blur traces if necessary.

Click the trash can icon ( ) to delete one or more selected blur traces.

Manually select a new image region

1 Click the Blur Estimation Tool icon ( ) in the upper-left corner of the Shake Reduction dialog.

2 Draw a selection rectangle anywhere on the image. Photoshop automatically creates a blur trace for the region you selected.

3 Add more blur traces if necessary.

Create a blur trace using the Blur Direction Tool

1 Select the Blur Direction Tool ( ) from the left panel.

2 Draw a straight line representing the blur direction on the image.

? If necessary, adjust the Blur Trace Length and Blur Trace Direction.



Modify a blur trace using the Detail loupe

1 Using the Detail loupe, focus on a new image region suitable for camera shake reduction.

2 Click the Enhance At Loupe Location icon ( ) to move focus in the left-pane to the region highlighted in the Detail loupe. The blur trace for the region displayed earlier in the Detail loupe is automatically updated.

The keyboard shortcut Q lets you dock/undock the Detail loupe.



Preview and apply multiple blur traces

Once you've added the required blur traces, you can select one or more blur traces in the Advanced panel to apply them to the image.

Preview and compare the results of two blur traces

- With the Ctrl key (Windows) or the Command key (Mac) held down, select the blur traces in the Advanced panel. Photoshop displays the multiple preview pane for the selected blur traces.



While previewing the results for two blur traces side-by-side, you can quickly adjust Smoothing and Artifact Suppression and check how your changes affect the image. See Smoothingand Artifact Suppression.

Duplicate a blur trace

- Drag a blur trace onto the Add Suggested Blur Trace icon ( ).

Photoshop creates a copy of the blur trace and locks the duplicate copy.

Creating duplicate copies of blur traces is helpful when you want to quickly adjust Smoothing and Artifact Suppression, and preview how your changes affect the image. See Smoothingand Artifact Suppression.



Reuse blur traces

Once you've created blur traces; you can save them, so that they can be applied to different images.

1 Select one or more blur traces.

2 Select Save Blur Trace from the Advanced panel flyout menu. You can save blur traces in two formats—KNL and PNG.

When you want to reuse the saved blur traces for a different image, you can use the Load option in the Advanced panel flyout menu.



Advanced blur trace settings

Advanced blur trace settings help you further fine-tune camera shake reduction.

Blur Trace Bounds

The Blur Trace Bounds setting represents the bound size of the blur trace. You can adjust this value if necessary.

Source Noise

Photoshop automatically estimates the amount of noise in the image. If necessary, select a different value (Auto/Low/Medium/High).

Smoothing

Smoothing reduces high-frequency sharpening noise. You can move the slider to a value different from the default 30%. A low Smoothing setting is recommended.

Artifact Suppression

Sometimes, in the course of sharpening the image, you may observe some noticeable noise artifacts. Follow these steps to suppress these artifacts:

? Select Artifact Suppression.

Note: *When Artifact Suppression is not turned on, Photoshop generates coarse previews. Coarse previews are sharper, but they also have more noise artifacts.*

? Adjust the Artifact Suppression slider to a higher value. 100% artifact suppression yields the original image, while 0% artifact suppression does not suppress any noise artifacts.

Artifact suppression works best to suppress medium-frequency noise.



Healing brush examples

Diffusion slider control

The Healing Brush, Spot Healing Brush, and Patch tool in Photoshop have a Diffusion slider which controls how quickly the pasted region adapts to the surrounding image.

As a general guideline, low slider values are good for images with grain or fine details whereas high values are good for smooth images.

Examples: Photoshop healing in action

Let's go through some of the examples to illustrate how to use the Photoshop healing feature.

Example 1

In the below example, a rectangular region from the left image has been pasted into the right image



The following three images demonstrate the effect of increasing Diffusion slider.



Low diffusion value



Medium diffusion value



High diffusion value

Example 2

Next, we will remove the two bulbous objects from an image.

View full image

View full image

View full image

Example 3

The new healing algorithm is better in diffusing the color and spreading them over an area. However, you need to be very clear about the area being sampled or filled. For soft selection, Photoshop thresholds the soft selection at 128 to display an 8-bit mask. As a result, the screen feedback in patch tool can misrepresent what user is actually sampling or trying to heal. This can manifest itself in bright or dark color contamination at the boundary of the filled area, which will be spread over the filled area. The new algorithm is enhanced to deal with very soft brushes. To limit the contamination, you may want to try different diffusion slider values and be careful with the sampling region. The patch tool can be prone to this sort of error as illustrated in the next example.

View full image



View full image

View full image

Photographer: Takeshi FujishimaModel: Asaka Kubo

The next six examples will compare the effect of various slider values on the healing result. The focus will be on the content with noise, high texture, and details.

Example 4

View full image

View full image

View full image

View full image

View full image

View full image

View full image

Original image courtsey of Giuseppe Circhetta

Example 5



View full image

View full image

View full image

Original image courtsey of Giuseppe Circhetta

Example 6



View full image

View full image

View full image

View full image

View full image

View full image

View full image

Original image courtsey of Josh Withers

Example 7

View full image

View full image

View full image

View full image

View full image

View full image

View full image

Original image courtsey of Steve Brown

Example 8

View full image

View full image

View full image

View full image

View full image

View full image

Original image courtsey of Marko Saari

Example 9



View full image



View full image



View full image



View full image



View full image



View full image

Original image courtsey of Bram Declercq

skin-original-hr.pngskin-healed-2014_hr.pngskin-healed-diffusion-2_hr.pngskin-healed-diffusion-3_hr.pngskin-healed-diffusion-4_hr.pngskin-healed-diffusion-5_hr.pngskin-healed-diffusion-6_hr.png

Export color lookup tables

You can now export color lookup tables from Photoshop in multiple formats. The exported files can then be applied in Photoshop, After Effects, SpeedGrade, and other image/video editing applications.

You can export color lookup tables only from documents that have a background layer and additional layers to modify colors.

Export lookup tables

1. Open an image having a background layer.
2. Add adjustment layers to give the image the desired look or effect.
3. Select Fill > Export > Color Lookup Tables.
4. In the Export Color Lookup Tables dialog, enter a Description.
5. Optionally, enter a Copyright string. Photoshop automatically prefixes **© Copyright <current year>** to the text you entered.
6. Enter a value in the Grid Points field (0-256). A higher value for this field creates bigger files having higher quality. Alternatively, select a fuzzy quality setting—Poor, Low, Medium, High, or Maximum—from the pop-up menu.
7. Select one or more of the available formats in which you want to export the color lookup table:
   - 3DL
   - CUBE
   - CSP
   - ICC Profile
1. Click OK.
2. Select the location on your computer where you want to save the generated files. Also, enter a base filename to which Photoshop automatically appends the file extensions.

Considerations for exporting to different formats

- If you start with a document in the LAB color mode, you can export the color lookup table as an ICC abstract profile. Abstract profiles are the most flexible of the formats and you can apply them to any color mode. When you export the table in an RGB-only format, Photoshop automatically converts the document to the RGB color mode.
- If you start with a document in the CMYK color profile, you can export the color lookup table as an ICC CMYK device link profile. When you export the table in an RGB-only format, Photoshop automatically converts the document to the RGB color mode.
- If you start with a document in the RGB color mode, you can export the color lookup table only in 3DLUT (3DL, CUBE, and CSP) and RGB device link formats.

Adjust image sharpness and blur

Photoshop offers a variety of tools, filters, and masks that give you fine control over image sharpness (or blur).

Sharpening recommendations

Sharpening enhances the definition of edges in an image. Whether your images come from a digital camera or a scanner, most images can benefit from sharpening. The degree of sharpening needed varies depending on the quality of the digital camera or scanner. Keep in mind that sharpening cannot correct a severely blurred image.

Tips for better sharpening:

- Sharpen your image on a separate layer so that you can resharpen it later to output to a different medium.
- If you sharpen your image on a separate layer, set the layer's blending mode to Luminosity to avoid color shifts along edges.
- Sharpening increases image contrast. If you find that highlights or shadows are clipped after you sharpen, use the layer blending controls (if you sharpen a separate layer) to prevent sharpening in highlights and shadows. See Specify a tonal range for blending layers.
- Reduce image noise before sharpening so that you don't intensify the noise.
- Sharpen your image multiple times in small amounts. Sharpen the first time to correct blur caused by capturing your image (scanning it or taking it with your digital camera). After you've color corrected and sized your image, sharpen it again (or a copy of it) to add the appropriate amount of sharpening for your output medium.
- If possible, judge your sharpening by outputting it to the final medium. The amount of sharpening needed varies among output media.

Use the Unsharp Mask (USM) filter or the Smart Sharpen filter for better control when sharpening your images. Although Photoshop also has the Sharpen, Sharpen Edges, and Sharpen More filter options, these filters are automatic and do not provide controls and options.

You can sharpen your entire image or just a portion using a selection or mask. Because the Unsharp Mask and Smart Sharpen filters can be applied to only one layer at a time, you might need to merge layers or flatten your file to sharpen all image layers in a multilayered file.

Note: *The name Unsharp Mask comes from a darkroom technique used in traditional film-based photography. The filter sharpens images rather than the opposite.*

Sharpen using Smart Sharpen

The Smart Sharpen filter has sharpening controls not available with the Unsharp Mask filter. You can set the sharpening algorithm or control the amount of sharpening that occurs in shadow and highlight areas.



1 Zoom the document window to 100% to get an accurate view of the sharpening.

2 Choose Filter > Sharpen > Smart Sharpen.

3 Set the controls in the Sharpen tabs:

Amount Sets the amount of sharpening. A higher value increases the contrast between edge pixels, giving the appearance of greater sharpness.

Radius Determines the number of pixels surrounding the edge pixels affected by the sharpening. The greater the radius value, the wider the edge effects and the more obvious the sharpening.

Reduce Noise (Photoshop CC only) Reduce unwanted noise while keeping important edges unaffected.

Remove Sets the sharpening algorithm used to sharpen the image.

Gaussian Blur is the method used by the Unsharp Mask filter.

Lens Blur detects the edges and detail in an image, and provides finer sharpening of detail and reduced sharpening halos.

Motion Blur attempts to reduce the effects of blur due to camera or subject movement. Set the Angle control if you choose Motion Blur.

Angle Sets the direction of motion for the Motion Blur option of the Remove control.

More Accurate (CS6 only) Processes the file slowly for a more accurate removal of blurring.

4 Adjust sharpening of dark and light areas using in the Shadow and Highlight tabs. (Click the Advanced button to display the tabs). If the dark or light sharpening halos appear too strong you can reduce them with these controls, which are only available for 8-bits and 16-bits-per-channel images:

Fade Amount Adjusts the amount of sharpening in the highlights or shadows.

Tonal Width Controls the range of tones in the shadows or highlights that are modified. Move the slider to the left or right to decrease or increase the Tonal Width value. Smaller values restrict the adjustments to only the darker regions for shadow correction and only the lighter regions for highlight correction.

Radius Controls the size of the area around each pixel that is used to determine whether a pixel is in the shadows or highlights. Moving the slider to the left specifies a smaller area, and moving it to the right specifies a larger area.

5 Click OK.

Sharpen using Unsharp Mask

The Unsharp Mask sharpens an image by increasing contrast along the edges in an image. The Unsharp Mask does not detect edges in an image. Instead, it locates pixels that differ in value from surrounding pixels by the threshold you specify. It then increases the contrast of neighboring pixels by the amount you specify. So, for neighboring pixels the lighter pixels get lighter and the darker pixels get darker.

In addition, you specify the radius of the region to which each pixel is compared. The greater the radius, the larger the edge effects.

The degree of sharpening applied to an image is often a matter of personal choice. Keep in mind that oversharpening an image produces a halo effect around the edges.

The effects of the Unsharp Mask filter are more pronounced on-screen than in high-resolution output. If your final destination is print, experiment to determine what settings work best for your image.

1 (Optional) If your image is multilayered, select the layer containing the image you want to sharpen. You can apply Unsharp Mask to only one layer at a time, even if layers are linked or grouped. You can merge the layers before applying the Unsharp Mask filter.

2 Choose Filter > Sharpen > Unsharp Mask. Make sure the Preview option is selected.

   Click the image in the preview window and hold down the mouse to see how the image looks without the sharpening. Drag in the preview window to see different parts of the image, and click + or – to zoom in or out.

   Although there is a preview window in the Unsharp Mask dialog box, it's best to move the dialog box so you can preview the effects of the filter in the document window.

3 Drag the Radius slider or enter a value to determine the number of pixels surrounding the edge pixels that affect the sharpening. The greater the radius value, the wider the edge effects. And the wider the edge effects, the more obvious the sharpening.

   The Radius value varies according to the subject matter, the size of the final reproduction, and the output method. For high-resolution images, a Radius value between 1 and 2 is usually recommended. A lower value sharpens only the edge pixels, whereas a higher value sharpens a wider band of pixels. This effect is much less noticeable in print than on-screen, because a 2-pixel radius represents a smaller area in a high-resolution printed image.

4 Drag the Amount slider or enter a value to determine how much to increase the contrast of pixels. For high-resolution printed images, an amount between 150% and 200% is usually recommended.

5 Drag the Threshold slider or enter a value to determine how different the sharpened pixels must be from the surrounding area before they are considered edge pixels and sharpened by the filter. For instance, a threshold of 4 affects all pixels that have tonal values that differ by a value of 4 or more, on a scale of 0 to 255. So, if adjacent pixels have tonal values of 128 and 129, they are not affected. To avoid introducing noise or posterization (in images with flesh tones, for example), use an edge mask or try experimenting with Threshold values between 2 and 20. The default Threshold value (0) sharpens all pixels in the image.

If applying Unsharp Mask makes already bright colors appear overly saturated, choose Edit > Fade Unsharp Mask and choose Luminosity from the Mode menu.

Sharpen selectively

You can sharpen parts of your image by using a mask or a selection to prevent sharpening in certain parts of your image. For example, you can use an edge mask with the Unsharp Mask filter on a portrait to sharpen the eyes, mouth, nose, and outline of the head, but not the texture of the skin.

Sharpen a selection

1 With the image layer selected in the Layers panel, draw a selection.

2 Choose Filter > Sharpen > Unsharp Mask. Adjust the options and click OK.

Only the selection is sharpened, leaving the rest of the image untouched.

Sharpen an image using an edge mask

1 Create a mask to apply sharpening selectively. There are many ways to create an edge mask. Use your favorite method, or try this one:

- Open the Channels panel and select the channel that displays the grayscale image with the greatest contrast in the document window. Often, this is the green or the red channel.



- Duplicate the selected channel.
- With the duplicate channel selected, choose Filter > Stylize > Find Edges.
- Choose Image > Adjustments > Invert to invert the image.



- With the inverted image still selected, choose Filter > Other > Maximum. Set the radius to a low number and click OK to thicken the edges and randomize the pixels.
- Choose Filter > Noise > Median. Set the radius to a low number and click OK. This averages the neighboring pixels.
- Choose Image > Adjustment > Levels and set the black point high to get rid of random pixels. If necessary, you can also paint with black to retouch the final edge mask.

- Choose Filter > Blur > Gaussian Blur to feather the edges.

Note: *The Maximum, the Median, and the Gaussian Blur filters soften the edge mask so that the sharpening effects blend better in the final image. Although all three filters are used in this procedure, you can experiment using only one or two.*

2 In the Channels panel, Ctrl-click (Windows) or Command-click (Mac OS) the duplicate channel to make the edge mask a selection.

3 In the Layers panel, select the image layer. Make sure the selection is still visible on the image.

4 Choose Select > Inverse.

5 With the selection active on the image layer, choose Filter > Sharpen > Unsharp Mask. Set the desired options and click OK.

To view your results, select the RGB channel in the Channels panel and deselect the selection in the image.

You can create an action to conveniently apply all the steps in the procedure.

Add lens blur

Add blur to an image to give the effect of a narrower depth of field so that some objects in the image stay in focus and others areas are blurred. You can use a simple selection to determine which areas are blurred, or you can provide a separate alpha channel depth map to describe exactly how you want the blur added.

The Lens Blur filter uses the depth map to determine the position of pixels in an image. With a depth map selected, you can also use the crosshair cursor to set the starting point of a given blur. You can use alpha channels and layer masks to create depth maps; black areas in an alpha channel are treated as though they're at the front of the photo, and white areas are treated as if they're far in the distance.

For a gradual blurring effect (none at the bottom to maximum at the top), create a new alpha channel and apply a gradient so that the channel is white at the top of the image and black at the bottom. Then select the Lens Blur filter and choose the alpha channel from the Source pop-up menu. To change the direction of the gradient, select the Invert check box.

The way the blur appears depends on the iris shape you choose. The number of blades determines the iris shape. You can change blades of an iris by curving them (making them more circular) or rotating them. You can also reduce or magnify the preview by clicking the minus button or the plus button.

1 Choose Filter > Blur > Lens Blur.

2 For Preview, choose Faster to generate quicker previews. Choose More Accurate to view the final version of the image. More Accurate previews take longer to generate.

3 For Depth Map, choose a source (if you have one) from the Source pop-up menu. Drag the Blur Focal Distance slider to set the depth at which pixels are in focus. For example, if you set focal distance to 100, pixels at 1 and at 255 are completely blurred, and pixels closer to 100 are blurred less. If you click in the preview image, the Blur Focal Distance slider changes to reflect the clicked location and brings the depth of the clicked location into focus.

4 To invert the selection or alpha channel you're using as the depth map source, select Invert.

5 Choose an iris from the Shape pop-up menu. If you wish, drag the Blade Curvature slider to smooth the edges of the iris, or drag the Rotation slider to rotate it. To add more blur, drag the Radius slider.

6 For Specular Highlight, drag the Threshold slider to select a brightness cutoff; all pixels brighter than the cutoff value are treated as specular highlights. To increase the brightness of the highlights, drag the Brightness slider.

7 To add noise to an image, choose Uniform or Gaussian. To add noise without affecting color, choose Monochromatic. Drag the Amount slider to increase or decrease noise.

Blurring removes film grain and noise from the original image. To make the image look realistic and unretouched, you can return some of the removed noise to the image.

8 Click OK to apply the changes to your image.

Blur image areas

The Blur tool softens hard edges or reduces detail in an image. The more you paint over an area with the tool, the blurrier it becomes.

1 Select the Blur tool .

2 Do the following in the options bar:

- Choose a brush tip and set options for the blending mode and strength in the options bar.
- Select Sample All Layers in the options bar to blur using data from all visible layers. Deselect this option and the tool uses data from only the active layer.

3 Drag over the part of the image you want to blur.

Sharpen image areas

The Sharpen tool increases contrast along edges to increase apparent sharpness. The more you paint over an area with the tool, the more sharpening increases.

1 Select the Sharpen tool . (If the tool isn't visible, hold down the Blur tool.)

2 Do the following in the options bar:

- Choose a brush tip and set options for the blending mode and strength.
- Select Sample All Layers to sharpen using data from all visible layers. If this is deselected, the tool uses data from only the active layer.
- Select Protect Detail to enhance details and minimize pixelated artifacts. Deselect this option if you want to produce more exaggerated sharpening effects.

3 Drag over the part of the image you want to sharpen.

More Help topics

Video | Sharpen your photos with Smart Sharpen

Video | How to sharpen photos in Photoshop

Understand color adjustments

Before making color and tonal adjustments

The powerful tools in Photoshop can enhance, repair, and correct the color and tonality (lightness, darkness, and contrast) in an image. Here are some items to consider before making color and tonal adjustments.

- Work with a monitor that's calibrated and profiled. For critical image editing, calibration and profiling are essential. Otherwise, the image you see on your monitor looks different on other monitors or when printed.
- Plan to use adjustment layers to adjust the tonal range and color balance of your image. Adjustment layers let you go back and make successive tonal adjustments without discarding or permanently modifying data from the image layer. Keep in mind that using adjustment layers adds to the file size of the image and demands more RAM from your computer. Accessing the color and tonal commands in the Adjustments panel automatically creates adjustment layers.

- If you don't want to use adjustment layers, you can apply adjustments directly to an image layer. Remember that some image information is discarded, when making a color or tonal adjustment directly to an image layer.
- For critical work and maximum preservation of image data, it's best if the image you work with is 16 bits per channel (16-bit image) rather than 8 bits per channel (8-bit image). Data is discarded when you make tonal and color adjustments. The loss of image information is more critical in an 8-bit image than a 16-bit image. Generally, 16-bit images have a larger file size than 8-bit images.
- Duplicate or make a copy of the image file. Working on a copy of your image preserves the original in the event you want to use the image in its original state.
- Remove any flaws such as dust spots, blemishes, and scratches from the image before making color and tonal adjustments.
- Open the Info or Histogram panel in Expanded view. As you evaluate and correct the image, both panels display invaluable feedback on your adjustments.
- You can make a selection or use a mask to confine your color and tonal adjustments to part of an image. Another way to apply color and tonal adjustments selectively is to set up your document with image components on different layers. Color and tonal adjustments are applied to only one layer at a time. Only the image components on the targeted layer are affected.

Correcting images

Here is the general workflow you follow when you correct the tonality and color of an image:

1. Use the histogram to check the quality and tonal range of the image.
2. Make sure that the Adjustments panel is open to access color and tonal adjustments. Click an icon to access the adjustments described in the following steps. Applying corrections from the Adjustments panel creates an adjustment layer, which gives you more flexibility and doesn't discard image information. See Adjustments panel overviewand About adjustment and fill layers.
3. Adjust the color balance to remove unwanted color casts or to correct oversaturated or undersaturated colors. See Color adjustment commands.
4. Adjust the tonal range, using either the Levels or Curves adjustments.

   Begin tonal corrections by adjusting the values of the extreme highlight and shadow pixels in the image, setting an overall tonal range for the image. This process is known as setting the highlights and shadows or setting the white and black points. Setting the highlights and shadows typically redistributes the midtone pixels appropriately. However, you might need to adjust your midtones manually.

   To adjust the tonality in just shadow and highlight areas, use the Shadow/Highlight command. See Improve shadow and highlight detail.
5. (Optional) Make other color adjustments.

   After you correct the overall color balance of your image, you can make optional adjustments to enhance colors or produce special effects.
6. Sharpen the edges in the image.

   As one of the final steps, use the Unsharp Mask or the Smart Sharpen filter to sharpen the clarity of edges in the image. The amount of sharpening required for an image varies according to the image quality produced by the digital camera or scanner you use. See Sharpening recommendations.
7. (Optional) Target the image for printer or press characteristics.

You can use options in the Levels or Curves adjustments to import highlight and shadow information into the gamut of an output device, like a desktop printer. This procedure can also be done if you are sending your image to a printing press, and know the characteristics of the press.

Because sharpening increases the contrast of neighboring pixels, it's possible that some pixels in critical areas might become unprintable on the printer or press that you're using. For this reason, it's best to fine-tune the output settings after sharpening. For more information on adjusting the output settings, see Setting highlight and shadow target values.

Adjustments panel overview

The tools for making color and tonal adjustments can be found in the Adjustments panel. Clicking a tool icon both selects an adjustment and automatically creates an adjustment layer. The adjustments you make using the controls and options in the Adjustments panel create nondestructive adjustment layers. See About adjustment layers and fill layers.

The Properties panel has a Presets menu with the adjustment presets. Presets are available for Levels, Curves, Exposure, Hue/Saturation, Black & White, Channel Mixer, and Selective Color. Clicking a preset applies it to the image using an adjustment layer. You can always save adjustment settings as a preset, which is added to the presets list.

Clicking an adjustment icon or a preset displays the settings options for the specific adjustment.

For a video, see Control which layers are affected by an adjustment layer .

Apply a correction using the Adjustments panel

1 In the Adjustments panel, click an adjustment icon or choose an adjustment from the panel menu.

2 Use the controls and options in the Properties panel to apply the settings you want.

3 (Optional) Do any of the following:

- To toggle the visibility of the adjustment, click the Toggle Layer Visibility button .
- To return the adjustment to its original settings, click the Reset button .
- To discard an adjustment, click the Delete This Adjustment Layer button .
- To expand the width of the Adjustment panel, drag a bottom corner of the panel.

Apply a correction to only the layer below

1 In the Adjustments panel, click an adjustment icon or choose an adjustment from the panel menu.

2 The Adjustments, click the Clip to Layer button . Click the icon again to make the adjustment apply to all layers below it in the Layers panel.

Save and apply adjustment presets

The Properties panel has a Preset menu with the adjustment presets for the tool that you clicked in the Adjustments panel. Additionally, you can save and apply presets for Levels, Curves, Exposure, Hue/Saturation, Black & White, Channel Mixer, and Selective Color. When you save a preset, it's added to the presets list.

- To save adjustment settings as a preset, choose the Save Preset option from the Properties panel menu.
- To apply an adjustment preset, choose a preset from the Preset menu in the Properties panel.

Automatically select text fields or the targeted adjustment tool

If you often change adjustment parameters using text fields or the targeted adjustment tool, maximize your efficiency by automatically selecting these items.

? From the Properties panel menu, select Auto-Select Parameter or Auto-Select Targeted Adjustment Tool.

If you prefer to select text fields as needed, press Shift-Enter (Windows) or Shift-Return (Mac OS).

Color adjustment commands

You can choose from the following color adjustment commands:

Adjust Levels Auto Quickly corrects the color balance in an image. Although its name implies an automatic adjustment, you can fine-tune how the Auto Color command behaves. See Remove a color cast using Auto Color.

Levels command Adjusts color balance by setting the pixel distribution for individual color channels. See Adjust color using Levels.

Curves command Provides up to 14 control points for highlight, midtone, and shadow adjustments for individual channels. See Curves overview.

Exposure command Adjusts tonality by performing calculations in a linear color space. Exposure is primarily for use in HDR images. See Adjust HDR exposure and toning.

Vibrance command Adjusts color saturation so clipping is minimized. See Adjust color saturation using Vibrance.

Photo Filter command Makes color adjustments by simulating the effects of using a Kodak Wratten or Fuji filter in front of a camera lens.

Color Balance command Changes the overall mixture of colors in an image. See Apply the Color Balance adjustment.

Hue/Saturation command Adjusts the hue, saturation, and lightness values of the entire image or of individual color components. See Adjust hue and saturation.

Match Color command Matches the color: from one photo to another photo, from one layer to another layer, and from a selection in an image to another selection in the same image or a different image. This command also adjusts the luminance and color range and neutralizes color casts in an image. See .

Replace Color command Replaces specified colors in an image with new color values. See .

Selective Color command Adjusts the amount of process colors in individual color components. See .

Channel Mixer command Modifies a color channel and makes color adjustments not easily done with other color adjustment tools. See .

Make a color adjustment

All Photoshop color adjustment tools work essentially the same way; they map an existing range of pixel values to a new range of values. The difference between the tools is the amount of control they provide. Color adjustment tools and their option settings are accessed in the Adjustments panel. For an overview of the color adjustment tools, see Color adjustment commands.

You can adjust the color in an image in different ways. The most flexible method is to use an adjustment layer. When you select a color adjustment tool in the Adjustments panel, Photoshop automatically creates an adjustment layer. Adjustment layers let you experiment with color and tonal adjustments without permanently modifying the pixels in the image. The color and tonal changes reside within the adjustment layer, which acts as a veil through which the underlying image layers appear.

1 If you want to make adjustments to a portion of your image, select that portion. If you make no selection, the adjustment is applied to the entire image.

2 Do one of the following:

- Click an adjustment icon in the Adjustments panel.
- Create an adjustment layer. See Create and confine adjustment and fill layers.
- Double-click the thumbnail of an existing adjustment layer in the Layers panel.

Note: *You can also choose Image > Adjustments, and choose a command from the submenu to apply adjustments directly to the image layer. Keep in mind that this method discards image information.*

A new adjustment layer includes a layer mask, which by default is empty (or white), meaning that your adjustment is applied to the entire image. (If you have an active selection on the image when you add an adjustment layer, the initial layer mask masks out the unselected area in black.) Using the Brush tool, you can paint black areas on the mask where you don't want the adjustment to affect the image. See Edit a layer mask .

3 To toggle the view of your image with and without adjustments, click the Toggle Layer Visibility icon in the Properties.

To cancel changes, click the Reset button .

Save adjustment settings

You can save your color adjustment settings and apply them to other images. Once a setting is saved, it can be accessed in the Preset menu in the Properties panel. You can also choose the Load Preset option from an adjustment dialog box menu. If you are saving color adjustment settings using the Match Color command, see .

- To save a setting in the Preset menu, choose the Save Preset option from the panel menu. This option is only available for Levels, Curves, Exposure, Hue/Saturation, Black & White, Channel Mixer, and Selective Color.
- To save a setting in the Shadows/Highlights or Replace Color image adjustment dialog box, click Save. In the Levels, Curves, Exposure, Hue/Saturation, Black & White, Channel Mixer, or Selective Color image adjustment dialog box, choose Save Preset from the panel menu. Enter a name for the setting, then click Save.

Reapply adjustment settings

Once an adjustment setting is saved, it's stored as a preset and can be reapplied.

- Choose an adjustment preset from the Preset menu in the Properties panel.
- In an adjustment dialog box, click Load. Locate and load the saved adjustment file. In the Curves, Black & White, Exposure, Hue/Saturation, Selective Color, Levels, or Channel Mixer dialog boxes, saved presets appear in the Presets menu. Choose Load Preset from the Preset option to load a preset not shown on the Preset pop-up menu from a different location.

To remove default presets, navigate to the following folders, move the presets out of the folders, and restart Photoshop.

- Windows: [startup drive]/Program Files/Adobe/Adobe Photoshop [version_number]/Presets/[adjustment type]/[preset name]

- Mac OS: [startup drive]/Applications/Adobe Photoshop [version_number]/Presets/[adjustment type]/[preset name]

Correcting colors in CMYK and RGB

Although you can perform all color and tonal corrections in RGB mode and most adjustments in CMYK mode, choose a mode carefully. Avoid multiple conversions between modes, because color values are rounded and lost with each conversion. Don't convert RGB images to CMYK mode if they are meant for on-screen display. For CMYK images that are separated and printed, do not make color corrections in RGB mode.

If you must convert your image from one mode to another, perform most of your tonal and color corrections in RGB mode. You can then use CMYK mode for fine-tuning. The advantages of working in RGB mode are:

- RGB has fewer channels. As a result, your computer uses less memory.
- RGB has a wider range of colors than CMYK, and more colors are likely to be preserved after adjustments.

  You can soft proof colors to see an on-screen preview of how your document's colors will look when reproduced on a particular output device. See About soft-proofing colors.

You can edit an image in RGB mode in one window and view the same image in CMYK colors in another window. Choose Window > Arrange > New Window For (Filename) to open a second window. Select the Working CMYK option for Proof Setup, then choose the Proof Color command to turn on the CMYK preview in one of the windows.

Identify out-of-gamut colors

A *gamut* is the range of colors that a color system can display or print. A color that can be displayed in RGB could be *out of gamut*, and therefore unprintable, for your CMYK setting.

In RGB mode, you can tell whether a color is out of gamut in the following ways:

- In the Info panel, an exclamation point appears next to the CMYK values whenever you move the pointer over an out-of-gamut color.
- In both the Color Picker and the Color panel, an alert triangle appears. When you select an out-of-gamut color, the closest CMYK equivalent is displayed. To select the CMYK equivalent, click the triangle or the color patch.

  Photoshop automatically brings all colors into gamut when you convert an RGB image to CMYK. Note that some detail in the image may be lost, depending on your conversion options. You can identify the out-of-gamut colors in an image or correct them manually before converting to CMYK. You can use the Gamut Warning command to highlight out-of-gamut colors.

Find out-of-gamut colors

1. Choose View > Proof Setup, then choose the proof profile on which you want to base the gamut warning.
2. Choose View > Gamut Warning.

All pixels outside the gamut of the current proof profile space are highlighted in gray.

Change the gamut warning color

1. Do one of the following:
   - (Windows) Choose Edit > Preferences > Transparency & Gamut.
   - (Mac OS) Choose Photoshop > Preferences > Transparency & Gamut.
2. Under Gamut Warning, click the color box to display the Color Picker. Then choose a new warning color, and click OK.

For best results, use a color that is not already present in the image.

3 Enter a value in the Opacity box, then click OK.

Use this option to reveal more or less of the underlying image through the warning color. Values can range from 1 % to 100%.

More Help topics

Convert a color image to black and white

The Black & White adjustment lets you convert a color image to grayscale while maintaining full control over how individual colors are converted. You can also tint the grayscale by applying a color tone to the image, for example to create a sepia effect.

1 Do one of the following:

- Click the Black & White icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Black & White. In the New Layer dialog box, type a name for the adjustment layer and then click OK.

Photoshop applies a default grayscale conversion.

Note: *You can also choose Image > Adjustments > Black & White. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 (Optional) choose a Black & White preset from the Preset menu in the Properties panel.

3 In the Properties panel, manually adjust the conversion using the color sliders, apply an Auto conversion, or select a previously saved custom mix.

Preset menu Select a predefined grayscale mix or a previously saved mix. To save a mix, choose Save Black & White Preset from the panel menu.

Auto Sets a grayscale mix based on the color values of the images, maximizing the distribution of gray values. The Auto mix often produces excellent results, or can be used as the starting point for tweaking gray values using the color sliders.

Color sliders Adjust the gray tones of specific colors in an image. Drag a slider left to darken or right to lighten the gray tones of an image's original color.

- To adjust a particular color component, select the On-image adjustment tool and then click in the image. Drag left or right to modify the color slider for the predominant color at that location, making it darker or brighter in the image.
- Click the Reset button to reset all color sliders to the default grayscale conversion.

Preview Deselect to view the image in its original color mode.

4 To apply a color tone, select Tint. To fine-tune the tint color, click the color swatch to open the Color Picker.

More Help topics

Adjusting image color and tone

View histograms and pixel values

About histograms

A *histogram* illustrates how pixels in an image are distributed by graphing the number of pixels at each color intensity level. The histogram shows detail in the shadows (shown in the left part of the histogram), midtones (shown in the middle), and highlights (shown in the right part) A histogram can help you determine whether an image has enough detail to make a good correction.

The histogram also gives a quick picture of the tonal range of the image, or the image *key type*. A low-key image has detail concentrated in the shadows. A high-key image has detail concentrated in the highlights. And, an average-key image has detail concentrated in the midtones. An image with full tonal range has some pixels in all areas. Identifying the tonal range helps determine appropriate tonal corrections.



A *Overexposed photo* ***B*** *Properly exposed photo with full tonality* ***C*** *Underexposed photo*

The Histogram panel offers many options for viewing tonal and color information about an image. By default, the histogram displays the tonal range of the entire image. To display histogram data for a portion of the image, first select that portion.

You can view an image histogram as an overlay in the Curves dialog box by selecting the histogram option under Curve Display Options, and in the Curves Properties panel, or by choosing Curve Display Options from the panel menu, then Histogram.

Histogram panel overview

? Choose Window > Histogram or click the Histogram tab to open the Histogram panel. By default, the Histogram panel opens in Compact View with no controls or statistics, but you can adjust the view.



***A** Channel menu **B** panel menu **C** Uncached Refresh button **D** Cached Data Warning icon **E** Statistics*

Adjust the view of the Histogram panel

? Choose a view from the Histogram panel menu.

Expanded View Displays the histogram with statistics. It also displays: controls for choosing the channel represented by the histogram, viewing options in the Histogram panel, refreshing the histogram to display uncached data, and choosing a specific layer in a multilayered document.

Compact View Displays a histogram with no controls or statistics. The histogram represents the entire image.

All Channels View Displays individual histograms of the channels in addition to all the options of the Expanded View. The individual histograms do not include alpha channels, spot channels, or masks.



View a specific channel in the histogram

If you chose the Expanded View or All Channels View of the Histogram panel, you can choose a setting from the Channel menu. Photoshop remembers the channel setting if you switch from either Expanded View or All Channels View back to Compact View.

- Choose an individual channel to display a histogram of the channel, including color channels, alpha channels, and spot channels.
- Depending on the color mode of the image, choose RGB, CMYK, or Composite to view a composite histogram of all the channels.
- If the image is RGB or CMYK, choose Luminosity to display a histogram representing the luminance or intensity values of the composite channel.
- If the image is RGB or CMYK, choose Colors to display a composite histogram of the individual color channels in color. This option is the default view for RGB and CMYK images when you first choose Expanded View or All Channels View.

  In the All Channels View, choosing from the Channels menu affects only the topmost histogram in the panel.

View channel histograms in color

? From the Histogram panel, do one of the following:

- In the All Channels View, choose Show Channels In Color from the panel menu.
- In Expanded View or All Channels View, choose an individual channel from the Channel menu and choose Show Channels In Color from the panel menu. If you switch to Compact View, the channel continues to be shown in color.

- In Expanded View or All Channels View, choose Colors from the Channel menu to show a composite histogram of the channels in color. If you switch to Compact View, the composite histogram continues to be shown in color.

View histogram statistics

By default, the Histogram panel displays statistics in the Expanded View and All Channels View.

1 Choose Show Statistics from the Histogram panel menu.

2 Do one of the following:

- To view information about a specific pixel value, place the pointer in the histogram.
- To view information about a range of values, drag in the histogram to highlight the range.

The panel displays the following statistical information below the histogram:

Mean Represents the average intensity value.

Std Dev (Standard deviation) Represents how widely intensity values vary.

Median Shows the middle value in the range of intensity values.

Pixels Represents the total number of pixels used to calculate the histogram.

Level Displays the intensity level of the area underneath the pointer.

Count Shows the total number of pixels corresponding to the intensity level underneath the pointer.

Percentile Displays the cumulative number of pixels at or below the level underneath the pointer. This value is expressed as a percentage of all the pixels in the image, from 0% at the far left to 100% at the far right.

Cache Level Shows the current image cache used to create the histogram. When the cache level is higher than 1, the histogram is displayed faster. In this case, the histogram is derived from a representative sampling of pixels in the image (based on the magnification). The original image is cache level 1. At each level above level 1, four adjacent pixels are averaged to arrive at a single pixel value. So, each level is half the dimensions (has 1/4 the number of pixels) of the lower level. When Photoshop makes a quick approximation, it can use one of the upper levels. Click the Uncached Refresh button to redraw the histogram using the actual image layer.

View the histogram for a multilayered document

1 Choose Expanded View from the Histogram panel menu.

2 Choose a setting from the Source menu. (The Source menu is not available for single-layered documents.)

Entire Image Displays a histogram of the entire image, including all layers.

Selected Layer Displays a histogram of the layer that's selected in the Layers panel.

Adjustment Composite Displays a histogram of an adjustment layer selected in the Layers panel, including all the layers below the adjustment layer.

Preview histogram adjustments

You can preview the effect on the histogram of any color and tonal adjustments.

? Select the Preview option in the dialog boxes of any color or tonal adjustment command.

When Preview is selected, the Histogram panel shows how the adjustment affects the histogram.

Note: *When making adjustments using the Adjustments panel, changes are automatically reflected in the Histogram panel.*



A Original histogram *B Adjusted histogram* *C Shadows* *D Midtones* *E Highlights*

Refresh the histogram display

When a histogram is read from a cache instead of the current state of the document, the Cached Data Warning icon appears in the Histogram panel. Histograms based on the image cache are displayed faster and are based on a representative sampling of pixels in the image. You can set the maximum cache level (from 2 to 8) in the Performance preference.

Note: *A higher cache level setting will increase the redraw speed for large, multi-layer files, but requires additional usage of system RAM. If RAM is limited or you work mainly with smaller images, use lower cache level settings*

? To refresh the histogram so that it displays all of the pixels of the original image in its current state, do one of the following:

- Double-click anywhere in the histogram.
- Click the Cached Data Warning icon .
- Click the Uncached Refresh button .
- Choose Uncached Refresh from the Histogram panel menu.

For information about cache level, see Histogram panel overview.

View color values in an image

You can use the Info panel to see the color value of pixels as you make color corrections. When you work with the Properties panel, the Info panel displays two sets of color values for the pixels under the pointer. The value in the left column is the original color value. The value in the right column is the color value after the adjustment is made.



You can view the color of a single location using the Eyedropper tool . You can also use up to four Color Samplers to display color information for one or more locations in the image. These samplers are saved in the image, so you can refer to them repeatedly as you work, even if you close and reopen the image.



1 Choose Window > Info to open the Info panel.

2 Select (then Shift-click) the Eyedropper tool or Color Sampler tool , and if necessary, choose a sample size in the options bar. Point Sample reads the value of a single pixel, other options read the average of a pixel area.

3 If you selected the Color Sampler tool , place up to four color samplers on the image. Click where you want to place a sampler.

View color information while adjusting color

You can view color information for specific pixels in the image while adjusting color in the Properties panel.

1 Add an adjustment using the Adjustments panel.

2 Make adjustments in the Properties panel. As you make adjustments, view the before and after color values in the Info panel. Move the pointer over the image to view color values at the pointer location.

__Note:__ If you are using a command from the Image > Adjustments menu, the Eyedropper tool is activated (and other tools temporarily disabled) when you move the pointer over the image. You still have access to the scroll controls and to the Hand and Zoom tools using keyboard shortcuts.

3 If you've placed color samplers on the image, the color values under the color samplers appear in the lower half of the Info panel. To add new color samplers, select the Color Sampler tool and click in the image, or select the Eyedropper tool and Shift-click in the image.

Adjusting color samplers

Once you've added a color sampler, you can move or delete it, hide it, or change the color sampler information displayed in the Info panel.

Move or delete a color sampler

1 Select the Color Sampler tool .

2 Do one of the following:

- To move a color sampler, drag the sampler to the new location.
- To delete a color sampler, drag the sampler out of the document window. Alternatively, hold down Alt (Windows) or Option (Mac OS) until the pointer becomes a scissors and click the sampler.
- To delete all color samplers, click Clear in the options bar.
- To delete a color sampler while an adjustment dialog box is open, hold down Alt+Shift (Windows) or Option+Shift (Mac OS), and click the sampler.

Hide or show color samplers in an image

? Choose View > Extras. A check mark indicates that color samplers are visible.

Change the display of color sampler information in the Info panel

- To display or hide color sampler information in the Info panel, choose Color Samplers from the panel menu. A check mark indicates that the color sampler information is visible.
- To change the color space in which a color sampler displays values, move the pointer onto the color sampler icon in the Info panel. Then, hold down the mouse button, and choose another color space from the menu.

Target images for press

Setting highlight and shadow target values

Assigning (targeting) highlight and shadow values of an image is necessary because most output devices (usually printing presses) cannot print detail in the blackest shadow values (near level 0) or the whitest highlight values (near level 255). Specifying the minimum shadow level and maximum highlight level helps to bring the important shadow and highlight details within the gamut of the output device.

If you are printing an image on a desktop printer and your system is color-managed, don't set target values. The Photoshop color management system automatically makes adjustments to the image you see on the screen so that it prints properly on your profiled desktop printer.

Using Levels to preserve highlight and shadow details for printing

The Output Levels sliders let you set the shadow and highlight levels to compress the image into a range less than 0 to 255. Use this adjustment to preserve the shadow and highlight details when an image is being printed on a press whose characteristics you know. For example, suppose there are important image details in the highlights with a value of 245, and the printing press that you're using won't hold a dot smaller than 5%. You can pull the highlight slider to level 242 (which is a 5% dot on the press) to shift the highlight detail from 245 to 242. Now, the highlight detail can safely print on that press.

Generally, it is not a good idea to use the Output Levels sliders to target images with specular highlights. Your specular highlight will look gray rather than blow out to pure white. Use the highlight eyedropper for images with specular highlights.



Set target values using the eyedroppers

1 Select the Eyedropper tool in the toolbox. You can choose 3 by 3 Average from the Sample Size menu in the Eyedropper tool options. This ensures a representative sample of an area rather than the value of a single screen pixel.

2 Click the Levels or Curves icon in the Adjustments panel.

When you select Levels or Curves, the Eyedropper tool is active outside the Properties panel. You still have access to the scroll controls, the Hand tool, and the Zoom tool through keyboard shortcuts.

3 Do one of the following to identify areas of highlights and shadows that you want to preserve in the image:

- Move the pointer around the image, and look at the Info panel to find the lightest and darkest areas that you want preserved (not clipped to pure black or white). (See View color values in an image.)
- Drag the pointer in the image, and look at Curves in the Properties panel to find the lightest and darkest points you want to preserve. This method does not work if the Curves adjustment is set to the CMYK composite channel.

When identifying the lightest highlight details that you want targeted to a printable (lower) value, don't include specular highlights. Specular highlights such as the highlight glint in jewelry or a spot of glare are meant to be the brightest points in an image. It's desirable to clip specular highlight pixels (pure white, no detail) so that no ink is printed on the paper.

You can also use the Threshold command to identify representative highlights and shadows before accessing Levels or Curves. (See Create a two-valued black and white image.)

4 To assign highlight values to the lightest area of the image, double-click the Set White Point Eyedropper tool in the Levels or Curves adjustment to display the Color Picker. Enter the values you want to assign to the lightest area in the image, and click OK. Then click the highlight you identified in step 3.

If you accidentally click the wrong highlight, click the Reset button in the Adjustments panel.

Depending on the output device, you can achieve a good highlight in an average-key image using CMYK values of 5, 3, 3, and 0, respectively, when you are printing on white paper. An approximate RGB equivalent is 244, 244, 244, and an approximate grayscale equivalent is a 4% dot. You can approximate these target values quickly by entering 96 in the Brightness (B) box under the HSB area of the Color Picker.

With a low-key image, you may want to set the highlight to a lower value to avoid too much contrast. Experiment with Brightness values from 96 through 80.

The pixel values are adjusted throughout the image proportionately to the new highlight values. Any pixels lighter than the area you clicked are clipped (adjusted to level 255, pure white). The Info panel shows the values both before and after the color adjustment.



5 To assign shadow values to the darkest area of the image that you want preserved, double-click the Set Black Point Eyedropper tool in the Properties panel to display the Color Picker. Enter the values you want to assign to the darkest area in the image, and click OK. Then click the shadow you identified in step 3.

When you're printing on white paper, you can usually achieve a good shadow in an average-key image using CMYK values of 65, 53, 51, and 95. An approximate RGB equivalent is 10, 10, 10, and an approximate grayscale equivalent is a 96% dot. You can approximate these values quickly by entering 4 in the Brightness (B) box under the HSB area of the Color Picker.

With a high-key image, you may want to set the shadow to a higher value to maintain detail in the highlights. Experiment with Brightness values from 4 through 20.

More Help topics

Printing with color management in Photoshop

Make quick tonal adjustments

Apply the Auto Contrast adjustment

The Auto Contrast command adjusts image contrast automatically. Because Auto Contrast does not adjust channels individually, it does not introduce or remove color casts. It clips the shadow and highlight values in an image and then maps the remaining lightest and darkest pixels in the image to pure white (level 255) and pure black (level 0). This makes the highlights appear lighter and shadows appear darker.

By default, when identifying the lightest and darkest pixels in an image, Auto Contrast clips the white and black pixels by 0.5%—that is, it ignores the first 0.5% of either extreme. You can change this default using the Auto Color Correction Options found in the Levels and the Curves dialog boxes.

Auto Contrast can improve the appearance of many photographic or continuous-tone images. It does not improve flat-color images.

1 Do one of the following:
   - Click the Levels or Curves icon in the Adjustments panel.
   - Choose Layer > New Adjustment Layer and choose either Levels or Curves. Click OK in the New Layer dialog box.

   Note: *You can also choose Image > Auto Contrast to apply the adjustment directly to the image layer. Keep in mind that this method discards image information and its application is automatic. You cannot adjust any of the options in the following steps.*

2 In the Properties panel, Alt-click (Windows) or Option-click (Mac OS) the Auto button.

3 Under Algorithms in the Auto Color Correction Options dialog box, select the Enhance Monochromatic Contrast option.

4 Specify the shadows and highlights that are clipped, and adjust the target color for the midtones.

5 Click OK to apply Auto Contrast.

Remove a color cast using Auto Color

Auto Color adjusts the contrast and color of an image by searching the image to identify shadows, midtones, and highlights. By default, Auto Color neutralizes the midtones using a target color of RGB 128 gray and clips the shadows and highlight pixels by 0.5%. You can change these defaults in the Auto Color Correction Options dialog box.

1 Do one of the following:
   - Click the Levels or Curves icon in the Adjustments panel.
   - Choose Layer > New Adjustment Layer and choose either Levels or Curves. Click OK in the New Layer dialog box.

   Note: *You can also choose Image > Auto Color to apply the adjustment directly to the image layer. Keep in mind that this method discards image information and is automatic. You cannot adjust any of the options in the following steps.*

2 In the Properties panel, Alt-click (Windows) or Option-click (Mac OS) the Auto button.

3 Under Algorithms in the Auto Color Correction Options dialog box, select the Find Dark & Light colors option.

4 Select the Snap Neutral Midtones option.

5 Specify the shadows and highlights that are clipped, and adjust the target color for the midtones.

6 Click OK to apply Auto Color.

Set Auto adjustment options

The Auto Color Correction options control the automatic tone and color corrections available in both Levels and Curves. It also controls the settings for the Auto Tone, Auto Contrast, and Auto Color commands. The Auto Color Correction options let you specify shadow and highlight clipping percentages, and assign color values to shadows, midtones, and highlights.

You can apply the settings during a single use of the Levels or Curves adjustment, or you can save the settings as default values when applying Auto Tone, Auto Contrast, Auto Color, and the Auto option for Levels and Curves.



***A** Auto Contrast option **B** Auto Levels option **C** Auto Color option **D** Set target colors, black point, and white point*

1 Click the Levels or Curves icon in the Adjustments panel.

2 Alt-click (Windows) or Option-click (Mac OS) the Auto button in the Properties panel.

3 Specify the algorithm you want Photoshop to use to adjust the overall tonal range of an image:

Enhance Monochromatic Contrast Clips all channels identically. This preserves the overall color relationship while making highlights appear lighter and shadows appear darker. The Auto Contrast command uses this algorithm.

Enhance Per Channel Contrast Maximizes the tonal range in each channel to produce a more dramatic correction. Because each channel is adjusted individually, Enhance Per Channel Contrast may remove or introduce color casts. The Auto Tone command uses this algorithm.

Find Dark & Light Colors Finds the average lightest and darkest pixels in an image and uses them to maximize contrast while minimizing clipping. The Auto Color command uses this algorithm.

4 Select Snap Neutral Midtones if you want Photoshop to find an average nearly-neutral color in an image and then adjust the gamma (midtone) values to make the color neutral. The Auto Color command uses this algorithm.

5 To specify how much to clip black and white pixels, enter percentages in the Clip text boxes. A value between 0.0% and 1% is recommended.

By default, Photoshop clips the black and white pixels by 0.1%—that is, it ignores the first 0.1% of either extreme when identifying the lightest and darkest pixels in the image. Because of the better output quality of modern scanners and digital cameras, these default clipping percentages might be too high.

6 To assign (target) color values to the darkest, neutral, and lightest areas of an image, click a color swatch.

7 Do one of the following:

- To use the settings in the current Levels or Curves adjustment, click OK. If you then click the Auto button, Photoshop reapplies the same settings to the image.
- To save the settings as the default, select Save as Defaults, and then click OK. The next time you access Levels or Curves in the Adjustments panel, you can apply the same setting by clicking the Auto button. The Auto Tone, Auto Contrast, and Auto Color commands also use the default clipping percentages.

Note: *When you save the Auto Color Correction options as defaults for Auto Color, Auto Tone, and Auto Contrast, it does not matter what algorithm you select in step 3. The three auto-correction commands use only those values that you set for the target colors and clipping. The only exception is that the Auto Color command also uses the Snap Neutral Midtones option.*

Using the Equalize command

The Equalize command redistributes the brightness values of the pixels in an image so that they more evenly represent the entire range of brightness levels. Equalize remaps pixel values in the composite image so that the brightest value represents white, the darkest value represents black, and intermediate values are evenly distributed throughout the grayscale.

You can use the Equalize command when a scanned image appears darker than the original and you want to balance the values to produce a lighter image. Using Equalize together with the Histogram panel lets you see before-and-after brightness comparisons.

Keep in mind that the Equalize command applies adjustments directly to the image layer and deletes image information. For nondestructive adjustments, use adjustment layers or edit in Adobe Camera Raw.

1 (Optional) Select an area of the image to equalize.

2 Choose Image > Adjustments > Equalize.

3 If you selected an area of the image, select what to equalize in the dialog box, and click OK:

Equalize Selected Area Only Evenly distributes only the pixels in the selection.

Equalize Entire Image Based On Selected Area Evenly distributes all image layers based on those in the selection.

Adjust black and white points with the Auto option

The Auto option for Levels and Curves and the Auto Tone command automatically adjust the black point and white point in an image. This clips a portion of the shadows and highlights in each channel and maps the lightest and darkest pixels in each color channel to pure white (level 255) and pure black (level 0). The intermediate pixel values are redistributed proportionately. As a result, using the Auto option or Auto Tone increases the contrast in an image because the pixel values are expanded. Because the Auto option and Auto Tone adjust each color channel individually, it may remove color or introduce color casts.

The Auto option and Auto Tone give good results in certain images with an average distribution of pixel values that need a simple increase in contrast.

By default, the Auto option and the Auto Tone command clip the white and black pixels by 0.1%—that is, it ignores the first 0.1% of either extreme when identifying the lightest and darkest pixels in the image. The default settings for the Auto option can be changed in the Auto Color Correction Options dialog box.

1 Do one of the following:

- Click the Levels or Curves icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer and choose either Levels or Curves. Click OK in the New Layer dialog box.

Note: *You can choose Image > Auto Tone to apply the adjustment directly to the image layer. Keep in mind that this method discards image information and is automatic. You cannot adjust any of the options in the following steps.*

2 In the Properties panel, Alt-click (Windows) or Option-click (Mac OS) the Auto button.

3 Under Algorithms in the Auto Color Correction Options dialog box, select Enhance Per Channel Contrast.

4 Adjust the amount of shadow and highlight values that are clipped, and adjust the target color for the midtones.

5 Click OK to apply the Auto option settings.

More Help topics

Adjusting image color and tone

Adjust color using Levels

Applying the Color Balance adjustment

Apply a Brightness/Contrast adjustment

Adjusting image color and tone

Apply a Brightness/Contrast adjustment

Apply the Brightness/Contrast adjustment

The Brightness/Contrast adjustment lets you make simple adjustments to the tonal range of an image. Moving the brightness slider to the right increases tonal values and expands image highlights, to the left decreases values and expands shadows. The contrast slider expands or shrinks the overall range of tonal values in the image.

In normal mode, Brightness/Contrast applies proportionate (nonlinear) adjustments to the image layer, as with Levels and Curves adjustments. When Use Legacy is selected, Brightness/Contrast simply shifts all pixel values higher or lower when adjusting brightness. Since this can cause clipping or loss of image detail in highlight or shadow areas, using Brightness/Contrast in Legacy mode is not recommended for photographic images (but can be useful for editing masks or scientific imagery).

Note: *Use Legacy is automatically selected when editing Brightness/Contrast adjustment layers created with previous versions of Photoshop.*

1 Do one of the following:

- Click the Brightness/Contrast icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Brightness/Contrast. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Brightness/Contrast. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, drag the sliders to adjust the brightness and contrast.

Dragging to the left decreases the level, and dragging to the right increases it. The number at the right of each slider reflects the brightness or contrast value. Values can range from -150 to +150 for Brightness, -50 to +100 for Contrast.

More Help topics

Make quick tonal adjustments

Adjusting image color and tone

Adjust color and tone with Levels and Curves eyedroppers

Set black and white points using the Eyedropper tools

Keep in mind that using the eyedroppers undoes any previous adjustment you made in Levels or Curves. If you plan to use the eyedroppers, it's best to use them first and then fine-tune your adjustments with the Levels sliders or Curves points.

1 Apply a Curves or Levels adjustment.

2 In the Properties panel, do any of the following:

- Double-click the Set Black Point eyedropper tool to set the black point.
- Double-click the Set White Point eyedropper tool to set the white point.

3 In the Adobe Color Picker, determine the values you want for the darkest and lightest tones in the image:

- To set the black point value to pure black, type 0 for R, G, and B.
- To set the white point value to pure white, type 255 for R, G, and B.
- To specify a shade of gray for either the black or white point, type identical values (between 0 and 255) for R, G, and B. The lower the values, the darker the gray. The higher the values, the lighter the gray.

4 Do one of the following to adjust the tonal areas to the black or white points you specified in Step 2:

- With the Set Black Point eyedropper, click an image area that represents the black point (area with the lowest tonal values).
- With the Set White Point eyedropper, click an image area that represents the white point (area with the lightest tonal values).

Color correct using the eyedroppers

You can use the eyedroppers in the Levels or Curves adjustment to correct a color cast such as an unwanted tint from an excess of color (red, green, blue, or cyan, magenta, yellow). It's easier to color-balance an image by first identifying an area that you want to be neutral and then removing the color cast from that area. Depending on the image, you can use one or all three of the eyedroppers. The Set Gray Point eyedropper works best on images that don't require large adjustments and have easily identified neutrals.

Keep in mind that using the eyedroppers undoes any previous adjustment you made in Levels or Curves. If you plan to use the eyedroppers, it's best to use them first and then fine-tune your adjustments with the Levels sliders or Curves points.

Note: *The eyedropper tool that sets the gray point is used primarily for color correction and is unavailable when you work with grayscale images.*

1 Before applying an adjustment, identify an area in the image that you want to be neutral gray. For example, a paved road.

Use a color sampler to mark a neutral area so that you can click it with an eyedropper later.

2 Click the Levels or Curves icon in the Adjustments panel.

3 In the Properties panel, double-click the Set Gray Point tool .

4 In the Adobe Color Picker, verify that the currently selected color has identical R, G, and B values for a neutral gray (for example, 128,128,128). If necessary, type the identical values for R, G, and B. Photoshop asks whether you want to save the new target color as a default.

5 With the Set Gray Point eyedropper tool, click the neutral area that you identified in Step 1. This should reset midtones and remove the color cast from the image.

6 (Optional) Make final Levels or Curves adjustments in the Properties panel.

More Help topics

Levels adjustment

Curves adjustment

Adjusting image color and tone in CS6

Adjusting hue and saturation

Convert a color image to black and white

Adjust shadow and highlight detail

Add contrast to a photo with Levels

Adjust HDR exposure and toning

Note: *In Photoshop CS6, 3D functionality is part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

The Exposure and HDR Toning adjustments are primarily designed for 32-bit HDR images, but you can also apply them to 16- and 8-bit images to create HDR-like effects.

Adjust HDR exposure

Exposure works by performing calculations in a linear color space (gamma 1.0) rather than the current color space.

1 Do one of the following:

- Click the Exposure icon or an Exposure preset in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Exposure.

Note: *You can also choose Image > Adjustments > Exposure. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Adjustments panel, set any of the following options:

Exposure Adjusts the highlight end of the tonal scale with minimal effect in the extreme shadows.

With 32-bit images, you can also access the Exposure slider at the bottom of the image window.

Offset Darkens the shadows and midtones with minimal effect on the highlights.

Gamma Adjusts the image gamma, using a simple power function. Negative values are mirrored around zero (that is, they remain negative but still get adjusted as if they are positive).

The eyedroppers adjust the luminance values of images (unlike the Levels eyedroppers that affect all color channels).

- The Set Black Point eyedropper sets the Offset, shifting the pixel you click to zero.
- The Set White Point eyedropper sets the Exposure, shifting the point you click to white (1.0 for HDR images).
- The Midtone eyedropper sets the Exposure, making the value you click middle gray.

Adjust HDR toning

The HDR Toning command lets you apply the full range of HDR contrast and exposure settings to individual images.

Note: *HDR toning requires flattened layers.*

1. Open a 32-, 16-, or 8-bit image in RGB or Grayscale color mode.
2. Choose Image > Adjustments > HDR Toning.

   For detailed information about each setting, see Options for 16- or 8-bit images. (In the HDR Toning dialog box, these options appy to images of all bit depths.)

More Help topics

High dynamic range images

Levels adjustment

Levels overview

You use the Levels adjustment to correct the tonal range and color balance of an image by adjusting intensity levels of image shadows, midtones, and highlights. The Levels histogram is a visual guide for adjusting the image key tones. For more information on how to read a histogram, see View histograms and pixel values.

You can save Levels settings as a preset, then apply them to other images. See Save adjustment settingsand Reapply adjustment settings.



A Shadows *B Midtones* *C Highlights* *D Output Level sliders*

For another tutorial, see How to correct color and tone .

Adjust tonal range using Levels

The outer two Input Levels sliders map the black point and white point to the settings of the Output sliders. By default, the Output sliders are at level 0, where the pixels are black, and level 255, where the pixels are white. With the Output sliders in the default positions, moving the black input slider maps the pixel value to level 0 and moving the white point slider maps the pixel value to level 255. The remaining levels are redistributed between levels 0 and 255. This redistribution increases the tonal range of the image, in effect increasing the overall contrast of the image.

Note: *When shadows are clipped, the pixels are black, with no detail. When highlights are clipped, the pixels are white, with no detail.*

The middle Input slider adjusts the gamma in the image. It moves the midtone (level 128) and changes the intensity values of the middle range of gray tones without dramatically altering the highlights and shadows.

1 Do one of the following:

- Click the Levels icon in the Adjustments panel, or choose Levels from the panel menu.
- Choose Layer > New Adjustment Layer > Levels. Click OK in the New Layer dialog box.

Note: *Choosing Image > Adjustments > Levels makes direct adjustments to the image layer and discards image information.*

2 (Optional) To adjust tones for a specific color channel, choose an option from the Channel menu.

3 (Optional) To edit a combination of color channels at the same time, Shift-select the channels in the Channels panel before choosing the Image > Adjustments > Levels command. (This method does not work in a Levels adjustment layer.) The Channel menu then displays the abbreviations for the target channels—for example, CM for cyan and magenta. The menu also contains the individual channels for the selected combination. Edit spot channels and alpha channels individually.

4 To adjust the shadows and highlights manually, drag the black and white Input Levels sliders to the edge of the first group of pixels at either end of the histogram.

For example, if you move the black point slider to the right at level 5, Photoshop maps all the pixels at level 5 and lower to level 0. Similarly, if you move the white point slider to the left at level 243, Photoshop maps all pixels at level 243 and higher to level 255. The mapping affects the darkest and lightest pixels in each channel. The corresponding pixels in the other channels are adjusted proportionately to avoid altering the color balance.

Note: *You can also enter values directly into the first and third Input Levels text boxes.*



5 (Optional) To identify areas in the image that are being clipped (completely black or completely white), do one of the following:

- Hold down Alt (Windows) or Option (Mac OS) as you drag the black point and white point sliders.
- Choose Show Clipping For Black/White Points from the panel menu.

6 To adjust midtones, use the middle Input slider to make a gamma adjustment.

Moving the middle Input slider to the left makes the overall image lighter. This slider adjustment maps a lower (darker) level up to the midpoint level between the Output sliders. If the Output sliders are in their default position (0 and 255), the midpoint is level 128. In this example, the shadows expand to fill the tonal range from 0 to 128, and the highlights are compressed. Moving the middle Input slider to the right has the opposite effect, making the image darker.

Note: *You can also enter a gamma adjustment value directly in the middle Input Levels box.*

You can view the adjusted histogram in the Histogram panel.

Adjust color using Levels

1 In the Adjustments panel, click the Levels icon or choose Levels from the panel menu.

2 In the Properties panel, do one of the following to neutralize a color cast:

- Click the eyedropper tool to set the gray point . Then click in a part of the image that is neutral gray.
- Click Auto to apply the default automatic levels adjustment. To experiment with other automatic adjustment options, choose Auto Options from the Properties panel menu, then change Algorithms in the Auto Color Corrections Options dialog box.

In general, assign equal color component values to achieve a neutral gray. For example, assign equal red, green, and blue values to produce a neutral gray in an RGB image.

Add contrast to a photo with Levels

If the image needs overall contrast because it doesn't use the full tonal range, click the Levels icon in the Adjustments panel. Then drag the Shadow and Highlight input sliders inward until they touch the ends of the histogram.



***A** Shadow Input slider **B** Highlight Input slider*

More Help topics

Adjust image color and tone with Levels and Curves eyedroppers

Curves adjustment

Adjusting image tone and color

Adjusting hue and saturation

Convert a color image to black and white

Adjust shadow and highlight detail

Adjust image color and tone

Overview of adjusting image color and tone

Two ways to adjust image tone and color are to use adjustment layers or to edit in Adobe Camera Raw. Both offer a wide range of control and flexibility, without permanently altering or damaging the original image information. The integrity of your original images is preserved. This nondestructive editing gives you the flexibility to make further changes, start over with a different editing approach, or undo the adjustments even after you've saved the edits.

With adjustment layers, you apply edits on a separate layer in the image file, leaving the original image (background layer) intact. The easiest way to access the adjustment layer tools is clicking an icon in the Adjustments panel. You can add more than one adjustment layer for more complex image editing. You can also use a mask to apply the adjustment to a specific part of the image. For more information, see Mask layers.

Adobe Camera Raw is a Photoshop plug-in for making color and tonal adjustments. In its editing window, there is a large preview image and the adjustment tools are laid out in the order that you would normally use them. Despite its name, Adobe Camera Raw can edit JPEGs and TIFFs in addition to camera raw files. If you want to apply the same adjustment to multiple images, you can save the settings as a preset and apply as needed.

***Note:** Unless a specific adjustment isn't available as an adjustment layer or in Camera Raw, don't use the commands in the Image > Adjustments menu. The adjustments under the Image menu permanently alter or delete pixel information in your image.*

Adjusting image color and tone with adjustment layers

1 In the Adjustments panel, click the tool icon for the adjustment you want to make:
   - For tonality and color, click Levels adjustmentor Curves adjustment.
   - For adjusting color, click Color Balance or Hue/Saturation.
   - For converting a color image to black and white, click Black & White.
2 In the Properties panel, adjust the adjustment layer tool settings.

Adjusting image color and tone in Camera Raw

1 Choose File > Open.
2 In the Open window, select one or more camera raw files, TIFFs, or JPEGs, and then choose Camera Raw from the Format menu.
3 Click Open.
4 Use the controls in Adobe Camera Raw to adjust the settings. You can use the Adjustment brush to apply edits to specific areas of the image. For more information, see Make color and tonal adjustments in Camera Raw.

Note: *You can set preferences to always open JPEGs and TIFFs in Camera Raw.Tip: For tips on setting your JPGs to open in Adobe Camera Raw, see this tutorial video by Terry White.*

Enable editing of JPEGs and TIFFs in Camera Raw

1 Choose (Windows) Edit > Preferences > Camera Raw or (Mac OS) Photoshop > Preferences > Camera Raw.
2 In the JPEG and TIFF Handling section of the Camera Raw Preferences dialog box, do any of the following:
   - In the JPEG menu, choose Automatically Open All Supported JPEGs.
   - In the TIFF menu, choose Automatically Open All Supported TIFFs from the TIFF menu.

In addition to the two workflows described above, you can also use Smart Objects for editing layers nondestructively. See Linked Smart Objects for more information.

More Help topics

Adobe Camera Raw topics

Adjustment and fill layers

Adjustment and fill layers

About adjustment and fill layers

An adjustment layer applies color and tonal adjustments to your image without permanently changing pixel values. For example, rather than making a Levels or Curves adjustment directly to your image, you can create a Levels or Curves adjustment layer. The color and tonal adjustments are stored in the adjustment layer and apply to all the layers below it; you can correct multiple layers by making a single adjustment, rather than adjusting each layer separately. You can discard your changes and restore the original image at any time.

Fill layers let you fill a layer with a solid color, a gradient, or a pattern. Unlike adjustment layers, fill layers do not affect the layers underneath them.

Adjustment layers provide the following advantages:

- Nondestructive edits. You can try different settings and re-edit the adjustment layer at any time. You can also reduce the effect of the adjustment by lowering the opacity of the layer.
- Selective editing. Paint on the adjustment layer's image mask to apply an adjustment to part of an image. Later you can control which parts of the image are adjusted by re-editing the layer mask. You can vary the adjustment by painting on the mask with different tones of gray.
- Ability to apply adjustments to multiple images. Copy and paste adjustment layers between images to apply the same color and tonal adjustments.

Adjustment layers have many of the same characteristics as other layers. You can adjust their opacity and blending mode, and you can group them to apply the adjustment to specific layers. Likewise, you can turn their visibility on and off to apply or preview the effect.

Because adjustment layers contain adjustment data rather than pixels, they increase file size far less than standard pixel layers. If you are working with an unusually large file, however, you may want to reduce file size by merging adjustment layers into pixel layers.

Create and confine adjustment and fill layers

Adjustment and fill layers have the same opacity and blending mode options as image layers. You can rearrange, delete, hide, and duplicate them just as you do image layers.



***A** Adjustment layer confined to "Log home" layer only **B** Layer thumbnail **C** Fill layer **D** Layer mask*

Create an adjustment layer

? Do one of the following:

- Click the New Adjustment Layer button at the bottom of the Layers panel, and choose an adjustment layer type.
- Choose Layer > New Adjustment Layer, and choose an option. Name the layer, set layer options, and click OK.

To confine the effects of an adjustment layer to specific image layers, select the image layers, choose Layer > New > Group From Layers, and change the Mode from Pass Through to any other blending mode. Then place the adjustment layer at the top of the layer group.

Create a fill layer

? Do one of the following:

- Choose Layer > New Fill Layer, and choose an option. Name the layer, set layer options, and click OK.
- Click the New Adjustment Layer button at the bottom of the Layers panel, and choose a fill layer type.

Solid Color

Fills the adjustment layer with the current foreground color. Use the Color Picker to select a different a fill color.

Gradient

Click the gradient to display the Gradient Editor, or click the inverted arrow and choose a gradient from the pop-up panel. Set additional options if desired.

- Style specifies the shape of the gradient.
- Angle specifies the angle at which the gradient is applied.
- Scale changes the size of the gradient.
- Reverse flips the orientation of the gradient.
- Dither reduces banding by applying dithering to the gradient.
- Align With Layer uses the bounding box of the layer to calculate the gradient fill. You can drag in the image window to move the center of the gradient.

Pattern

Click the pattern, and choose a pattern from the pop-up panel. Click Scale, and enter a value or drag the slider. Click Snap To Origin to make the origin of the pattern the same as the origin of the document. Select Link With Layer if you want the pattern to move along with the layer as the layer moves. When Link With Layer is selected, you can drag in the image to position the pattern while the Pattern Fill dialog box is open.

Confine adjustment and fill layers to specific areas

To confine adjustment and fill layers to specific areas, use layer masks. By default, adjustment and fill layers automatically have layer masks, indicated by the mask icon to the right of the layer thumbnail. (To create adjustment layers without masks, deselect Add Mask by Default in the Adjustments panel menu.)

To change the shape of a mask on an existing layer, see Edit layer masks. To create a new adjustment or fill layer with a mask of specific shape, complete one of the following procedures.

Create an adjustment or fill layer mask using a selection or path

1. In the Layers panel, select the layer to which you want to apply the adjustment or fill layer.
2. In the image, create a pixel selection, or create and select a closed path.

   A selection confines the new adjustment or fill layer with a layer mask. A path confines the new adjustment or fill layer with a vector mask.

3 Create an adjustment or fill layer.

Create an adjustment layer mask using a color range

The Color Range feature, which is useful for creating a selection area based on sampled colors in an image, can also be used to create an adjustment layer mask. For more information, see Select a color range in an image.

1 In the Layers panel, select the layer to which you want to apply the adjustment layer.

2 Choose Layer > New Adjustment Layer, and choose an adjustment type.

3 In the Masks section of the Properties panel, click Color Range.

4 In the Color Range dialog box, choose Sampled Colors from the Select menu.

5 Select Localized Color Clusters to build a mask based on different color ranges in the image.

6 Set the display option to Selection, and Selection Preview to None.

7 Click a color area in the image.

To sample multiple areas, hold down Shift to activate the plus eyedropper. Hold down Alt (Windows) or Option (Mac OS) to activate the minus eyedropper.

As you click on image areas, you can preview the mask in the Color Range dialog box. White areas are unmasked pixels, black areas masked, and gray areas partially masked.

8 Use the Fuzziness slider to increase or decrease the range of colors around your sample colors that are included in the masked area. Use the Range slider to control how far or near a color must be from the sample points to be included in the mask. After adjusting the mask, click OK to close the Color Range dialog box.

9 Modify the adjustment as needed in the Properties panel.

The adjustment is only applied to the unmasked (or partially masked) areas of the image. If necessary click Color Range again to make further adjustments to the adjustment layer mask.

Edit or merge adjustment and fill layers

Editing adjustment and fill layers

You can edit an adjustment or fill-layer setting. You can also edit the mask of an adjustment or fill layer to control the effect that the layer has on the image. By default, all areas of an adjustment or fill layer are "unmasked" and are therefore visible. (See About layer and vector masks.)

Change adjustment and fill layer options

1 Do one of the following:

- Double-click the adjustment or fill-layer thumbnail in the Layers panel.
- Choose Layer > Layer Content Options.

2 Make the desired changes in the Properties panel.

Note: *Inverted adjustment layers do not have editable settings.*

Merging adjustment or fill layers

You can merge an adjustment or fill layer several ways: with the layer below it, with the layers in its own grouped layer, with other selected layers, and with all other visible layers. You cannot, however, use an adjustment or fill layer as the target layer for a merge. When you merge an adjustment or fill layer with the layer below it, the adjustments are rasterized and become permanently applied within the merged layer. You can also rasterize a fill layer without merging it. (See Rasterize layers.)

Adjustment and fill layers whose masks contain only white values do not add significantly to the file size, so it is not necessary to merge these adjustment layers to conserve file space.

More Help topics

Make local adjustments in Camera Raw

Adjusting image color and tone

Apply special color effects to images

Desaturate colors

The Desaturate command converts a color image to grayscale values, but leaves the image in the same color mode. For example, it assigns equal red, green, and blue values to each pixel in an RGB image. The lightness value of each pixel does not change.

Keep in mind that the Desaturate command permanently alters the original image information in the background layer. This command has the same effect as setting Saturation to minus (-)100 in the Hue/Saturation adjustment. For nondestructive editing, use a Hue/Saturation adjustment layer.

Note: *If you are working with a multilayer image, Desaturate converts the selected layer only.*

? Choose Image > Adjustments > Desaturate.

Invert colors

The Invert adjustment inverts the colors in an image. You can use Invert as part of the process of making an edge mask to apply sharpening and other adjustments to selected areas of an image.

Note: *Because color print film contains an orange mask in its base, the Invert adjustment cannot make accurate positive images from scanned color negatives. Be sure to use the proper settings for color negatives when scanning film.*

When you invert an image, the brightness value of each pixel in the channels is converted to the inverse value on the 256-step color-values scale. For example, a pixel in a positive image with a value of 255 is changed to 0, and a pixel with a value of 5 is changed to 250.

Do one of the following:

- Click the Invert icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Invert. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Invert. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

Create a two-valued black and white image

The Threshold adjustment converts grayscale or color images to high-contrast, black-and-white images. You can specify a certain level as a threshold. All pixels lighter than the threshold are converted to white; all pixels darker are converted to black.

1 Do one of the following:
   - Click the Threshold icon in the Adjustments panel.
   - Choose Layer > New Adjustment Layer > Threshold. Click OK in the New Layer dialog box.

   The Properties panel displays a histogram of the luminance levels of the pixels in the current selection.

   Note: *You can also choose Image > Adjustments > Threshold. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, drag the slider below the histogram until the threshold level you want appears. As you drag, the image changes to reflect the new threshold setting.

Posterize an image

The Posterize adjustment lets you specify the number of tonal levels (or brightness values) for each channel in an image and then maps pixels to the closest matching level. For example, choosing two tonal levels in an RGB image gives six colors: two for red, two for green, and two for blue.

This adjustment is useful for creating special effects, such as large, flat areas in a photograph. Its effects are most evident when you reduce the number of gray levels in a grayscale image, but it also produces interesting effects in color images.

If you want a specific number of colors in your image, convert the image to grayscale and specify the number of levels you want. Then convert the image back to the previous color mode, and replace the various gray tones with the colors you want.

1 Do one of the following:
   - Click the Posterize icon in the Adjustments panel.
   - Choose Layer > New Adjustment Layer > Posterize.

   Note: *You can also choose Image > Adjustments > Posterize. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, move the Levels slider or enter the number of tonal levels you want.

Apply a gradient map to an image

The Gradient Map adjustment maps the equivalent grayscale range of an image to the colors of a specified gradient fill. If you specify a two-color gradient fill, for example, shadows in the image are mapped to one of the endpoint colors of the gradient fill, highlights are mapped to the other endpoint color, and midtones are mapped to the gradations in between.

1 Do one of the following:
   - Click the Gradient Map icon in the Adjustments panel.
   - Choose Layer > New Adjustment Layer > Gradient Map. Click OK in the New Layer dialog box.

   Note: *You can also choose Image > Adjustments > Gradient Map. But keep in mind that this method applies the adjustment directly to the image layer and discards image information.*

2 In the Properties panel, specify the gradient fill you want to use:

- To choose from a list of gradient fills, click the triangle to the right of the gradient fill. Click to select the desired gradient fill, and then click in a blank area of the Properties panel to dismiss the list. For information on customizing the gradient fill list, see Work with the Preset Manager.
- To edit the currently-displayed gradient fill, click the gradient fill, and then modify the existing gradient fill or create a gradient fill in the Gradient Editor. (See Create a smooth gradient.)

By default, the shadows, midtones, and highlights of the image are mapped respectively to the starting (left) color, midpoint, and ending (right) color of the gradient fill.

3 Select either, none, or both of the Gradient options:

Dither Adds random noise to smooth the appearance of the gradient fill and reduces banding effects.

Reverse Switches the direction of the gradient fill, reversing the gradient map.

More Help topics

Adjust hue and saturation

Apply the Color Balance adjustment

Apply the Color Balance adjustment

The Color Balance command changes the overall mixture of colors in an image for generalized color correction.

1 Make sure that the composite channel is selected in the Channels panel. This command is available only when you're viewing the composite channel.

2 Do one of the following:

- Click the Color Balance icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Color Balance. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Color Balance. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

3 In the Properties panel, select Shadows, Midtones, or Highlights to select the tonal range in which you want to focus the changes.

4 (Optional) Select Preserve Luminosity to prevent changing the luminosity values in the image while changing the color. This option maintains the tonal balance in the image.

5 Drag a slider toward a color that you want to increase in the image; drag a slider away from a color that you want to decrease in the image.

The values above the color bars show the color changes for the red, green, and blue channels. (For Lab images, the values are for the A and B channels.) Values can range from -100 to +100.

Change the color balance using the Photo Filter command

The Photo Filter adjustment mimics the technique of placing a colored filter in front of the camera lens to adjust the color balance and color temperature of the light transmitted through the lens and exposing the film. Photo Filter also lets you choose a color preset to apply a hue adjustment to an image. If you want to apply a custom color adjustment, the Photo Filter adjustment lets you specify a color using the Adobe Color Picker.

1 Do one of the following:

- Click the Photo Filter icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Photo Filter. Click OK in the New Layer dialog box.

Note: *You can also choose Image > Adjustments > Photo Filter. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, choose the filter color, either a custom filter or a preset. For a custom filter, select the Color option, click the color square, and use the Adobe Color Picker to specify a color for a custom color filter. For a preset filter, select the Filter option and choose one of the following presets from the Filter menu:

Warming Filter (85 and LBA) and Cooling Filter (80 and LBB) Color conversion filters that tune the white balance in an image. If an image was photographed with a lower color temperature of light (yellowish), the Cooling Filter (80) makes the image colors bluer to compensate for the lower color temperature of the ambient light. Conversely, if the photo was taken with a higher color temperature of light (bluish), the Warming Filter (85) makes the image colors warmer to compensate for the higher color temperature of the ambient light.

Warming Filter (81) and Cooling Filter (82) Use light-balancing filters for minor adjustments in the color quality of an image. The Warming Filter (81) makes the image warmer (more yellow), and the Cooling Filter (82) makes the image cooler (bluer).

Individual Colors Apply a hue adjustment to the image depending on the color preset you choose. Your choice of color depends on how you're using the Photo Filter adjustment. If your photo has a color cast, you can choose a complementary color to neutralize the color cast. You can also apply colors for special color effects or enhancements. For example, the Underwater color simulates the greenish blue color cast in underwater photos.

Make sure that Preview is selected to view the results of using a color filter. If you don't want the image darkened by adding the color filter, be sure that the Preserve Luminosity option is selected.

3 To adjust the amount of color applied to the image, use the Density slider or enter a percentage in the Density box. A higher density results in a stronger color adjustment.

More Help topics

Make quick tonal adjustments

Adjusting image color and tone

Curves adjustment

Curves overview

In the Curves adjustment, you adjust points throughout an image's tonal range. Initially, the image's tonality is represented as a straight diagonal line on a graph. When adjusting an RGB image, the upper-right area of the graph represents the highlights and the lower-left area represents the shadows. The horizontal axis of the graph represents the input levels (original image values) and the vertical axis represents the output levels (new adjusted values). As you add control points to the line and move them, the shape of the curve changes, reflecting your image adjustments. The steeper sections of the curve represent areas of higher contrast while flatter sections represent areas of lower contrast.

You can save Curves adjustment settings as presets. See Save adjustment settingsand Reapply adjustment settings.

Note: *The Curves adjustment can also be applied to CMYK, LAB, or Grayscale images. For CMYK images, the graph displays percentages of ink/pigment. For LAB and Grayscale images, the graph displays light values.*



A *On-image adjustment tool* ***B*** *Sample in image to set black point.* ***C*** *Sample in image to set gray point.* ***D*** *Sample in image to set white point.* ***E*** *Edit points to modify the curve.* ***F*** *Draw to modify the curve.* ***G*** *Curves presets menu* ***H*** *Set black point.* ***I*** *Set gray point.* ***J*** *Set white point.* ***K*** *Show clipping.*

Adjust image color and tone with Curves

Moving a point in the top portion of the curve adjusts the highlights. Moving a point in the center of the curve adjusts the midtones, and moving a point in the bottom section of the curve adjusts the shadows. To darken highlights, move a point near the top of the curve downward. Moving a point either down or to the right maps the Input value to a lower Output value, and the image darkens. To lighten the shadows, move a point near the bottom of the curve upward. Moving a point either up or to the left maps a lower Input value to a higher Output value, and the image lightens.

1 To apply a Curves adjustment, do one of the following:

- Click the Curves icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Curves. Click OK in the New Layer dialog box.

Note: *Choosing Image > Adjustments > Curves applies the adjustment directly to the image layer and discards image information.*

2 (Optional) To adjust the color balance, in the Properties panel, choose the channel you want to adjust from the menu to the left of the Auto button.

3 In the Properties panel, do any of the following:

- Click directly on the curve line and then drag the control point to adjust a tonal area.
- Select the On-image adjustment tool and then drag in the area of the image you want to adjust.

- Select the On-image adjustment tool and click the tonal areas in the image that you want to adjust. This places control points along the curve line.
- Choose a preset from the Preset menu.

Dragging a control point up or down lightens or darkens the tonal area you're adjusting. Dragging a control point left or right increases or decreases the contrast. You can add up to 14 control points to the curve. To remove a control point, drag it off the graph. As you adjust the tonality, the graph continues displaying the original diagonal baseline and image histogram as references. These options can be turned off, see Set Curves Display Options.

4 (Optional) Do any of the following to modify the adjustment:

- Add more points directly to the curve to adjust different tonal areas.
- Click the On-image adjustment tool in other areas of the image, and drag up or down.
- Move the Set Black and White Point sliders or use the Eyedropper tools to specify the darkest and lightest values in the image.
- Click a point on the curve, and enter values in the Input and Output text boxes.
- Select the pencil icon and draw a new curve over the existing one. When you have finished, click the Smooth the Curve Values icon or to smooth the curve you drew. Clicking more than once continues to smooth the curve further.

Points on the curve remain anchored until you move them. You can make an adjustment in one tonal area without affecting other areas.



Removing control points from a curve

To remove a control point, do any of the following:

- Drag the control point off the graph.
- Select the control point and press Delete.
- Ctrl-click (Windows) or Command-click (Mac OS) the control point.

Set Curve display options

You can control the curve grid display using the Curve display options.

1 Apply a Curves adjustment.

2 In the Properties panel, choose Curves Display Options from the panel menu.

Note: If you chose Image > Adjustments > Curves, expand the Curve Display Options in the Curves dialog box.

3 In the Curves Display Options dialog box, select any of the following:

Light (0-255) Displays the intensity values for RGB images in a range from 0 to 255, with black (0) at the lower-left corner.**Pigment/Ink %** Displays the percentages for CMYK images are displayed in a range from 0 to 100, with highlights (0%) at the lower-left corner.**Simple Grid** Displays gridlines in 25% increments.**Detailed Grid** Displays gridlines in 10% increments.**Show Channel Overlays** Displays color channel curves superimposed on the composite curve.**Histogram** Displays a histogram of the original image tonal values behind the graph.**Baseline** Displays the original image color and tonality as a 45-degree angle line for reference,**Intersection Line** Displays horizontal and vertical lines to help you align control points as your drag them relative to the histogram or grid.

To change the gridline increment, Alt-click (Windows) or Option-click (Mac OS) the grid.

Apply an Auto correction in Curves

? Click Auto in the Properties panel.

Auto applies an automatic color correction using the current default setting. To change the default setting, choose Auto Options from the Properties panel menu and set the options in the Auto Color Correction Options dialog box. You can apply an Auto Color, Auto Contrast, or Auto Tone correction to an image. For more information on these options, see Make quick tonal adjustments.

Set black and white points using the black point and white point sliders

When applying a Curves adjustment, use the black and white sliders to quickly set the black and white points (pure black and pure white values) in the image.

1 Drag the black and white point sliders to any point along the horizontal axis. Note that the Input value changes as your drag.

2 To preview clipping as you adjust black and white points, do one of the following:

- Hold down Alt (Windows) or Option (Mac OS).
- Choose Show Clipping For Black/White Points from the panel menu.

Add contrast to the midtones of a photo with Curves

If the image uses the full tonal range, but needs midtone contrast, Click the Curves icon in the Adjustments panel. Drag the curve into an S shape.



Keyboard shortcuts: Curves

You can use these keyboard shortcuts for Curves:

- To set a point on the curve for the selected color in each color component channel (but not in the composite channel), Shift+Ctrl-click (Windows) or Shift+Command-click (Mac OS) in the image.
- To select multiple points, Shift-click points on the curve. Selected points are filled with black.
- To deselect all points on the curve, click in the grid, or press Ctrl-D (Windows) or Command-D (Mac OS).
- To select the next higher point on the curve, press the plus key; to select the next lowest, press the minus key.
- To move selected points on the curve, press the arrow keys.
- (Curves dialog box) To set a point on the curve for the current channel, Ctrl-click (Windows) or Command-click (Mac OS) in the image.

If you're instead using the Curves adjustment, simply click in the image with the On-image adjustment tool .

More Help topics

Adjust color and tone with Levels and Curves eyedroppers

Adjusting image color and tone

Adjusting hue and saturation

Convert a color image to black and white

Adjust shadow and highlight detail

Levels adjustment

Adjust hue and saturation

Hue/Saturation lets you adjust the hue, saturation, and lightness of a specific range of colors in an image or simultaneously adjust all the colors in an image. This adjustment is especially good for fine-tuning colors in a CMYK image so that they are in the gamut of an output device.

You can save Hue/Saturation settings in the Properties panel, and then load them for reuse in other images. For more information, see Save adjustment settingsand Reapply adjustment settings.

For more information on image adjustments, see Adjusting image color and tone in.

Apply a Hue/Saturation adjustment

1 Do one of the following:

- Click the Hue/Saturation icon in the Adjustments panel.
- Choose Layer > New Adjustment Layer > Hue/Saturation. Click OK in the New Layer dialog box.

The two color bars in the dialog box represent the colors in their order on the color wheel. The upper color bar shows the color before the adjustment; the lower bar shows how the adjustment affects all of the hues at full saturation.

Note: *You can also choose Image > Adjustments > Hue/Saturation. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, choose from the menu to the right of the On-image adjustment tool :

- Choose Master to adjust all colors at once.
- Choose one of the other preset color ranges listed for the color you want to adjust. To modify the color range, see Specify the range of colors adjusted using Hue/Saturation.
- Choose a Hue/Saturation preset from the Preset menu.

3 For Hue, enter a value or drag the slider until you are satisfied with the colors.

The values displayed in the box reflect the number of degrees of rotation around the wheel from the original color of the pixel. A positive value indicates clockwise rotation; a negative value, counterclockwise rotation. Values can range from -180 to +180.



A *Saturation* ***B*** *Hue*

You can also select the On-image adjustment tool in the Properties panel, and then Ctrl-click (Windows) or Command-click (Mac OS) a color in the image. Drag left or right in the image to modify the hue value.

4 For Saturation, enter a value or drag the slider to the right to increase the saturation or to the left to decrease it.

The color shifts away from or toward the center of the color wheel. Values can range from -100 (percentage of desaturation, duller colors) to +100 (percentage of saturation increase).

You can also, select the On-image adjustment tool in the Properties panel, and click a color in the image. Drag left or right in the image to decrease or increase saturation of the color range that includes the pixel you clicked.

5 For Lightness, enter a value or drag the slider to the right to increase the lightness (add white to a color) or to the left to decrease it (add black to a color). Values can range from -100 (percentage of black) to +100 (percentage of white).

Note: *Click the Reset button to undo a Hue/Saturation setting in the Properties panel.*

Specify the range of colors adjusted using Hue/Saturation

1 Apply a Hue/Saturation adjustment.

2 In the Properties panel, choose a color from the menu to the right of the On-image adjustment button .

Four color wheel values (in degrees) appear in the Properties panel. They correspond to the adjustment sliders that appear between the color bars. The two inner vertical sliders define the color range. The two outer triangle sliders show where the adjustments on a color range "fall off" (fall-off is a feathering or tapering of the adjustments instead of a sharply defined on/off application of the adjustments).

3 Use either the eyedropper tools or the adjustment sliders to modify the range of colors.

- Click or drag in the image with the Eyedropper tool to select a color range. To expand the range, click or drag in the image with the Add To Sample Eyedropper tool . To reduce the range of color, click or drag in the image with the Subtract From Sample Eyedropper tool . While an eyedropper tool is selected, you can also press Shift to add to the range, or Alt (Windows) or Option (Mac OS) to subtract from it.
- Drag one of the white triangle sliders to adjust the amount of color fall-off (feathering of adjustment) without affecting the range.
- Drag the area between the triangle and the vertical bar to adjust the range without affecting the amount of fall-off.
- Drag the center area to move the entire adjustment slider (which includes the triangles and vertical bars) to select a different color area.
- Drag one of the vertical white bars to adjust the range of the color component. Moving a vertical bar from the center of the adjustment slider and closer to a triangle increases the color range and decreases the fall-off. Moving a vertical bar closer to the center of the adjustment slider and away from a triangle decreases the color range and increases the fall-off.
- Ctrl-drag (Windows) or Command-drag (Mac OS) the color bar so that a different color is in the center of the bar.



A Hue slider values B Adjusts fall-off without affecting range C Adjusts range without affecting fall-off D Adjusts range of color and fall-off E Moves entire slider

If you modify the adjustment slider so that it falls into a different color range, the name in the Edit menu changes to reflect this change. For example, if you choose Yellow and alter its range so that it falls in the red part of the color bar, the name changes to Red 2. You can convert up to six of the individual color ranges to varieties of the same color range (for example, Red through Red 6).

By default, the range of color selected when you choose a color component is 30° wide, with 30° of fall-off on either side. Setting the fall-off too low can produce banding in the image.

Colorize a grayscale image or create a monotone effect

1 (Optional) If you are colorizing a grayscale image, choose Image > Mode > RGB Color to convert the image to RGB.

2 Apply a Hue/Saturation adjustment.

3 In the Properties panel, select the Colorize option. If the foreground color is black or white, the image is converted to a red hue (0°). If the foreground color is not black or white, the image is converted to the hue of the current foreground color. The lightness value of each pixel does not change.

4 (Optional) Use the Hue slider to select a new color. Use the Saturation and Lightness sliders to adjust the saturation and lightness of the pixels.

Adjust color saturation using Vibrance

Vibrance adjusts the saturation so that clipping is minimized as colors approach full saturation. This adjustment increases the saturation of less-saturated colors more than the colors that are already saturated. Vibrance also prevents skintones from becoming over saturated.

1 Do one of the following:
   - In the Adjustments panel, click the Vibrance icon .
   - Choose Layer > New Adjustment Layer > Vibrance. In the New Layer dialog box, type a name for the Vibrance adjustment layer and click OK.

   Note: *You can also choose Image > Adjustments > Vibrance. But keep in mind that this method makes direct adjustments to the image layer and discards image information.*

2 In the Properties panel, drag the Vibrance slider to increase or decrease color saturation without clipping when colors become more saturated. Then, do one of the following:
   - To apply more adjustment to less saturated colors and prevent colors clipping as they reach total saturation, move the Vibrance slider to the right.
   - To apply the same amount of saturation adjustment to all colors regardless of their current saturation, move the Saturation slider. In some situations, this may produce less banding than the Saturation slider in the Hue/Saturation Adjustments panel or Hue/Saturation dialog box.
   - To decrease saturation, move either the Vibrance or the Saturation slider to the left.

Adjust color saturation in image areas

The Sponge tool subtly changes the color saturation of an area. When an image is in Grayscale mode, the tool increases or decreases contrast by moving gray levels away from or toward the middle gray.

1 Select the Sponge tool .
2 Choose a brush tip and set brush options in the options bar.
3 In the options bar, choose the way you want to change the color from the Mode menu:

   Saturate Intensifies the color's saturation

   Desaturate Dilutes the color's saturation

4 Specify the flow for the Sponge tool.
5 Select the Vibrance option to minimize clipping for fully saturated or desaturated colors.
6 Drag over the part of the image you want to modify.

More Help topics

Applying the Color Balance adjustment

Adjusting image color and tone

Adjust shadow and highlight detail

Improve shadow and highlight detail

The Shadow/Highlight command is one method for correcting photos with silhouetted images due to strong backlighting or correcting subjects that have been slightly washed out because they were too close to the camera flash. The adjustment can also be used for brightening areas of shadow in an otherwise well-lit image. The Shadow/Highlight command does not simply lighten or darken an image; it lightens or darkens based on the surrounding pixels (local neighborhood) in the shadows or highlights. For this reason, there are separate controls of the shadows and the highlights. The defaults are set to fix images with backlighting problems.

The Shadow/Highlight command also has a Midtone Contrast slider, Black Clip option, and White Clip option for adjusting the overall contrast of the image, and a Color Correction slider for adjusting saturation.

Note: *Keep in mind that the Shadow/Highlight command applies adjustments directly to the image and will discard image information. For nondestructive image editing, it is recommended that you use adjustment layers or Camera Raw. See Adjustment and fill layers and Introduction to Camera Raw .*

Adjust image shadows and highlights

1 Choose Image > Adjustments > Shadow/Highlight.

   Make sure that the Preview option is selected in the dialog box if you want the image to be updated as you make adjustments.

2 Adjust the amount of lighting correction by moving the Amount slider or entering a value in the Shadows or Highlights percentage box. Larger values provide either greater lightening of shadows or greater darkening of highlights. You can adjust both Shadows and Highlights in an image.

3 For finer control, select Show More Options to make the additional adjustments.

   Note: *To increase shadow detail in an otherwise well-exposed image, try values in the 0-25% range for Shadows Amount and Shadows Tonal Width.*

4 (Optional) Click the Save As Defaults button to save your current settings and make them the default settings for the Shadow/Highlights command. To restore the original default settings, hold down the Shift key while clicking the Save As Defaults button.

   Note: *You can reuse Shadow/Highlight settings by clicking the Save button to save the current settings to a file and later using the Load button to reload them. For more information on saving and loading settings, see Save adjustment settings.*

5 Click OK.

Shadow/Highlight command options

Amount Controls (separately for the highlight and shadow values in the image) how much of a correction to make.

Note: *Extreme Amount values may lead to a crossover, where what started as a highlight becomes darker than something that started as a shadow; this can make the adjusted images look 'unnatural'.*

Tonal Width Controls the range of tones in the shadows or highlights that are modified. Smaller values restrict the adjustments to the darker regions for shadow correction and the lighter regions for highlight correction. Larger values increase the range of tones that are adjusted further into the midtones. For example, at 100% the shadow tonal width slider affects the shadows the most, the midtones are partially affected, but the brightest highlights are not affected. Tonal width varies from image to image. Too large a value may introduce halos around dark or light edges. The default settings attempt to reduce these artifacts. Halos may also occur when the Shadow or Highlight Amount values are too large.

Tonal Width is set to 50% by default. If you find that you are trying to lighten a dark subject but the midtones or lighter regions are changing too much, try reducing Shadow Tone Width toward zero so that only the darkest regions are lightened. If, however, you want to brighten the midtones as well as the shadows, increase Shadows Tonal Width toward 100%

Radius Controls the size of the local neighborhood around each pixel. Neighboring pixels are used to determine whether a pixel is in the shadows or highlights. Moving the slider to the left specifies a smaller area, and moving it to the right specifies a larger area. The optimum local neighborhood size depends on the image. It's best to experiment with the adjustment. If the radius is too large, the adjustment tends to brighten (or darken) the whole image rather than brightening the subject only. It's best to set the radius to roughly the size of the subjects of interest in the image. Experiment with different Radius settings to obtain the best balance between subject contrast and differential brightening (or darkening) of the subject compared to the background.

Brightness Adjusts the brightness in a grayscale image. This adjustment is available only for grayscale images. Moving the Brightness slider to the left darkens a grayscale image, and moving the slider to the right lightens a grayscale image.

Midtone Contrast Adjusts the contrast in the midtones. Move the slider to the left to reduce the contrast and to the right to increase the contrast. You can also enter a value in the Midtone Contrast box. A negative value reduces contrast, and a positive value increases contrast. Increasing midtone contrast produces greater contrast in the midtones while tending to darken the shadows and lighten the highlights.

Black Clip And White Clip Specifies how greatly the shadows and highlights are clipped to the new extreme shadow (level 0) and highlight (level 255) colors in the image. Larger values produce an image with greater contrast. Be careful not to make the clipping values too large, because doing so reduces detail in the shadows or highlights (the intensity values are clipped and rendered as pure black or pure white).

More Help topics

Adjusting image color and tone

Auto color corrections

One-click corrections to common image issues.

Auto color corrections

Using adjustment layers

Change color and tone with total flexibility.

Using adjustment layers

Dodge or burn image areas

The Dodge tool and the Burn tool lighten or darken areas of the image. These tools are based on a traditional darkroom technique for regulating exposure on specific areas of a print. Photographers hold back light to lighten an area on the print (dodging) or increase the exposure to darken areas on a print (burning). The more you paint over an area with the Dodge or Burn tool, the lighter or darker it becomes.

Note: *Applying the Dodge tool or Burn tool to the background layer permanently alters the image information. To edit your images nondestructively, work on a duplicate layer. For information on duplicating layers, see Layer basics.*

1 Select the Dodge tool or the Burn tool .

2 Choose a brush tip and set brush options in the options bar.

3 In the options bar, select one of the following from the Range menu:

Midtones Changes the middle range of grays

Shadows Changes the dark areas

Highlights Changes the light areas

4 Specify the exposure for the Dodge tool or the Burn tool.

5 Click the airbrush button to use the brush as an airbrush. Alternatively, select the Airbrush option in the Brush panel.

6 Select the Protect Tones option to minimize clipping in the shadows and highlights. This option also tries to keep colors from shifting hue.

7 Drag over the part of the image you want to lighten or darken.

More Help topics

Retouching tools gallery

Chapter 9: Camera Raw

New features summary



Adobe Camera Raw 9.2

Dehaze as a local adjustment

New in this release of Adobe Camera Raw

Dehaze is now available as a local adjustment. While working with the Radial Filter, Graduated Filter, or the Adjustment Brush, adjust the Dehaze slider control.

For more information, see Make local adjustments in Camera Raw .



Navigate quickly across an image

New in this release of Adobe Camera Raw

When the GPU is enabled, you can navigate quickly across an image. Follow these steps:

1 Press and hold the H key.

2 Click and drag to set the position of the zoom rectangle.

3 Release the mouse button. The image zooms in to the area you defined. The selected tool remains unchanged.

Adobe Camera Raw 9.1

Dehaze

New in this release of Adobe Camera Raw

With Adobe Camera Raw, you can now easily decrease or increase the amount of haze or fog in a photograph.

Start with making basic adjustments to the photo, such as adjusting the White Balance. Now, use the Dehaze slider on the Effects panel.

For more information, see .



Local adjustments: Whites and Blacks sliders

New in this release of Adobe Camera Raw

Local adjustment controls in Adobe Camera Raw now include Whites and Blacks sliders. These new controls let you selectively adjust the white and black points in photos. For example, you may want to enhance the color of the tires on a vehicle using the Blacks slider.

These new sliders are available when you use the Adjustment Brush, Graduated Filter, or Radial Filter in Adobe Camera Raw.

For more information, see **Make local adjustments in Camera Raw** .

Adobe Camera Raw 9.0

GPU acceleration

New in this release of Adobe Camera Raw

Adobe Camera Raw now provides a new preference, enabled by default, that lets you use your computer's graphics processing unit (GPU) for many operations.

In Photoshop, select Preferences > Camera Raw. Now, under Performance, ensure that Use Graphics Processor is enabled.

Note: *GPU support for Adobe Camera Raw is 64-bit-only and available on the following platforms:*

- Mac OS X 10.9 and higher
- Windows 7 and higher

For more information, see **Camera Raw GPU FAQ** .

HDR photo merge

New in this release of Adobe Camera Raw

Adobe Camera Raw now lets you merge multiple exposure-bracketed images into a single HDR image. You can preview the merged DNG file and make changes to it, including adjusting the amount of deghosting.

Do the following:

1 Open the source images in Camera Raw and then select them from the Filmstrip.

2 Right-click the selection in the Filmstrip and select Merge To HDR.



1 Make the necessary adjustments in the HDR Merge Preview dialog. For more information about the available settings, see HDR photo merge .

2 Once you've made the adjustments, click Merge.

3 Navigate to the location where you want to save the merged HDR image (.dng). Click Save.

4 Click Done to close the Camera Raw dialog.

Panorama merge

New in this release of Adobe Camera Raw

With Adobe Camera Raw, you can now easily merge photos of a landscape into a breathtaking panorama. You can see a quick preview of the panorama and make adjustments to it before the merged image is generated.



While previewing the panorama, you can choose to Auto Crop the merged image to remove undesired areas of transparency. You can also choose the appropriate layout projection for the panorama—Spherical, Perspective, or Cylindrical.

Follow these steps:

1 Open the source images in Camera Raw and then select them from the Filmstrip.

2 Right-click the selection in the Filmstrip and choose Merge To Panorama.

3 In the Panorama Merge Preview dialog, make the necessary adjustments. See Create panoramas for more information about the available settings.

4 Once you've made the adjustments, click Merge.

5 Navigate to the location where you want to save the panorama. Click Save.

6 Click Done to close the Camera Raw dialog.

What's changed

- UX improvement: For faster access and to make the Filmstrip pane design more space-efficient, the Select All and Synchronize options are now part of the flyout menu/context menu.



A Camera Raw 9.0 B Camera Raw 8.x

Introduction to Camera Raw

About camera raw files

A *camera raw* file contains unprocessed, uncompressed grayscale picture data from a digital camera's image sensor, along with information about how the image was captured (metadata). Photoshop® Camera Raw software interprets the camera raw file, using information about the camera and the image's metadata to construct and process a color image.

Think of a camera raw file as your photo negative. You can reprocess the file at any time, achieving the results that you want by making adjustments for white balance, tonal range, contrast, color saturation, and sharpening. When you adjust a camera raw image, the original camera raw data is preserved. Adjustments are stored as metadata in an accompanying sidecar file, in a database, or in the file itself (in the case of DNG format).

When you shoot JPEG files with your camera, the camera automatically processes the JPEG file to enhance and compress the image. You generally have little control over how this processing occurs. Shooting camera raw images with your camera gives you greater control than shooting JPEG images, because camera raw does not lock you into processing done by your camera. You can still edit JPEG and TIFF images in Camera Raw, but you will be editing pixels that were already processed by the camera. Camera raw files always contain the original, unprocessed pixels from the camera.

To shoot camera raw images, you must set your camera to save files in its own camera raw file format.

Note: *The Photoshop Raw format (.raw) is a file format for transferring images between applications and computer platforms. Don't confuse Photoshop raw with camera raw file formats. File extensions for camera raw files vary depending on the camera manufacturer.*

Digital cameras capture and store camera raw data with a linear tone response curve (gamma 1.0). Both film and the human eye have a nonlinear, logarithmic response to light (gamma greater than 2). An unprocessed camera raw image viewed as a grayscale image would seem very dark, because what appears twice as bright to the photosensor and computer seems less than twice as bright to the human eye.

For a list of supported cameras and for more information about Camera Raw, see Digital camera raw file support.

To see a list of cameras and which version of Camera Raw each camera requires, see Camera Raw plug-in | Supported cameras.

About Adobe Camera Raw

Camera Raw software is included as a plug-in with Adobe After Effects® and Adobe Photoshop, and also adds functionality to Adobe Bridge. Camera Raw gives each of these applications the ability to import and work with camera raw files. You can also use Camera Raw to work with JPEG and TIFF files.

Note: *Camera Raw supports images up to 65,000 pixels long or wide and up to 512 megapixels. Camera Raw converts CMYK images to RGB upon opening. For a list of supported cameras, see Digital camera raw file support.*

You must have Photoshop or After Effects installed to open files in the Camera Raw dialog box from Adobe Bridge. However, if Photoshop or After Effects is not installed, you can still preview the images and see their metadata in Adobe Bridge. If another application is associated with the image file type, it's possible to open the file in that application from Adobe Bridge.

Using Adobe Bridge, you can apply, copy, and clear image settings, and you can see previews and metadata for camera raw files without opening them in the Camera Raw dialog box. The preview in Adobe Bridge is a JPEG image generated using the current image settings; the preview is not the raw camera data itself, which would appear as a very dark grayscale image.

Note: A caution icon appears in the thumbnails and preview image in the Camera Raw dialog box while the preview is generated from the camera raw image.

You can modify the default settings that Camera Raw uses for a particular model of camera. For each camera model, you can also modify the defaults for a particular ISO setting or a particular camera (by serial number). You can modify and save image settings as presets for use with other images.

When you use Camera Raw to make adjustments (including straightening and cropping) to a camera raw image, the image's original camera raw data is preserved. The adjustments are stored in either the Camera Raw database, as metadata embedded in the image file, or in a sidecar XMP file (a metadata file that accompanies a camera raw file). For more information, see .

After you process and edit a camera raw file using the Camera Raw plug-in, an icon appears in the image thumbnail in Adobe Bridge.

If you open a camera raw file in Photoshop, you can save the image in other image formats, such as PSD, JPEG, Large Document Format (PSB), TIFF, Cineon, Photoshop Raw, PNG, or PBM. From the Camera Raw dialog box in Photoshop, you can save the processed files in Digital Negative (DNG), JPEG, TIFF, or Photoshop (PSD) formats. Although Photoshop Camera Raw software can open and edit a camera raw image file, it cannot save an image in a camera raw format.

As new versions of Camera Raw become available, you can update this software by installing a new version of the plug-in. You can check for updates to Adobe software by choosing Help > Updates.

Different camera models save camera raw images in many different formats, and the data must be interpreted differently for these formats. Camera Raw includes support for many camera models, and it can interpret many camera raw formats.

If you have trouble opening Camera Raw files, see Why doesn't my version of Photoshop or Lightroom support my camera?

About the Digital Negative (DNG) format

The Digital Negative (DNG) format is a non-proprietary, publicly documented, and widely supported format for storing raw camera data. Hardware and software developers use DNG because it results in a flexible workflow for processing and archiving camera raw data. You may also use DNG as an intermediate format for storing images that were originally captured using a proprietary camera raw format.

Because DNG metadata is publicly documented, software readers such as Camera Raw do not need camera-specific knowledge to decode and process files created by a camera that supports DNG. If support for a proprietary format is discontinued, users may not be able to access images stored in that format, and the images may be lost forever. Because DNG is publicly documented, it is far more likely that raw images stored as DNG files will be readable by software in the distant future, making DNG a safer choice for archival storage.

Metadata for adjustments made to images stored as DNG files can be embedded in the DNG file itself instead of in a sidecar XMP file or in the Camera Raw database.

You can convert camera raw files to the DNG format by using the Adobe DNG Converter or the Camera Raw dialog box. For more information on the DNG format and DNG Converter, see the Digital Negative (DNG) product page. To download the latest DNG Converter, go to the Adobe downloads page.

Process images with Camera Raw

Copy camera raw files to your hard disk, organize them, and (optionally) convert them to DNG.

Before you do any work on the images that your camera raw files represent, transfer them from the camera's memory card, organize them, give them useful names, and otherwise prepare them for use. Use the Get Photos From Camera command in Adobe Bridge to accomplish these tasks automatically.

Open the image files in Camera Raw.

You can open camera raw files in Camera Raw from Adobe Bridge, After Effects, or Photoshop. You can also open JPEG and TIFF files in Camera Raw from Adobe Bridge.

Adjust color.

Color adjustments include white balance, tone, and saturation. You can make most adjustments on the Basic tab, and then use controls on the other tabs to fine-tune the results. If you want Camera Raw to analyze your image and apply approximate tonal adjustments, click Auto on the Basic tab.

To apply the settings used for the previous image, or to apply the default settings for the camera model, camera, or ISO settings, choose the appropriate command from the Camera Raw Settings menu . (See .)

For a video tutorial on making nondestructive color (and other) adjustments to photos in Camera Raw, watch How to make non-destructive edits in Camera Raw .

Make other adjustments and image corrections.

Use other tools and controls in the Camera Raw dialog box to perform such tasks as sharpening the image, reducing noise, correcting for lens defects, and retouching.

(Optional) Save image settings as a preset or as default image settings.

To apply the same adjustments to other images later, save the settings as a preset. To save the adjustments as the defaults to be applied to all images from a specific camera model, a specific camera, or a specific ISO setting, save the image settings as the new Camera Raw defaults. (See .)

Set workflow options for Photoshop.

Set options to specify how images are saved from Camera Raw and how Photoshop should open them. You can access the Workflow Options settings by clicking the link beneath the image preview in the Camera Raw dialog box.

Save the image, or open it in Photoshop or After Effects.

When you finish adjusting the image in Camera Raw, you can apply the adjustments to the camera raw file, open the adjusted image in Photoshop or After Effects, save the adjusted image to another format, or cancel and discard adjustments. If you open the Camera Raw dialog box from After Effects, the Save Image and Done buttons are unavailable.

- **Save Image** Applies the Camera Raw settings to the images and saves copies of them in JPEG, PSD, TIFF, or DNG format. Press Alt (Windows) or Option (Mac OS) to suppress the Camera Raw Save Options dialog box and save the files using the last set of save options. (See .)
- **Open Image or OK** Opens copies of the camera raw image files (with the Camera Raw settings applied) in Photoshop or After Effects. The original camera raw image file remains unaltered. Press Shift while clicking Open Image to open the raw file in Photoshop as a Smart Object. At any time, you can double-click the Smart Object layer that contains the raw file to adjust the Camera Raw settings.
- **Done** Closes the Camera Raw dialog box and stores file settings either in the camera raw database file, in the sidecar XMP file, or in the DNG file.
- **Cancel** Cancels the adjustments specified in the Camera Raw dialog box.

Camera Raw dialog box overview



A Camera name or file format ***B*** *Toggle full-screen mode* ***C*** *Image adjustment tabs* ***D*** *Histogram* ***E*** *Camera Raw Settings menu* ***F*** *Adjustment sliders* ***G*** *Preview options* ***H*** *Workflow options* ***I*** *Zoom levels*

Note: *Some controls, such as the Workflow Options link, that are available when you open the Camera Raw dialog box from Adobe Bridge or Photoshop are not available when you open the Camera Raw dialog box from After Effects.*

You can invoke the Auto Temperature and Auto Tint functionality by Shift-double-clicking within the image preview.

- To open the Camera Raw Settings menu, click the button in the upper-right corner of any of the image adjustment tabs. Several of the commands in this menu are also available from the Edit > Develop Settings menu in Adobe Bridge.

The Camera Raw zoom controls are:

- **Zoom tool**

  Sets the preview zoom to the next higher preset value when you click the preview image. Alt-click (Windows) or Option-click (Mac OS) to use the next lower zoom value. Drag the Zoom tool in the preview image to zoom in on a selected area. To return to 100%, double-click the Zoom tool.

- **Hand tool**

  Moves the image in the preview window if the preview image is set at a zoom level higher than 100%. Hold down the spacebar to temporarily activate the Hand tool while using another tool. Double-click the Hand tool to fit the preview image to the window.

- **Select Zoom Level**

  Choose a magnification setting from the menu or click the Select Zoom Level buttons.

Preview

Displays a preview of the image adjustments made in the current tab, combined with the settings in the other tabs. Deselect to show the image with the original settings of the current tab combined with the settings in the other tabs.

Beginning with version 8.4 for Photoshop CC, Camera Raw provides advanced Preview controls that let you quickly compare the Before/After states of an image:

- Save the current settings as the Before state of the image Swap the current settings and the saved Before state settings. The current settings are saved as the Before state, and the settings previously saved as the Before state are applied to the image Select a mode for displaying the preview
- See only the After settings applied to the image
- Before/After settings applied to the left and right halves of the image
- Before/After settings applied to the whole image and displayed side-by-side
- Before/After settings applied to the top and bottom halves of the image
- Before/After settings applied to the whole image and displayed vertically for quick comparison

RGB

Shows the red, green, and blue values of the pixel under the pointer in the preview image.

Shadows and Highlights

Displays shadow and highlight clipping using the buttons at the top of the Histogram. Clipped shadows appear in blue, and clipped highlights appear in red. Highlight clipping is shown if any one of the three RGB channels is clipped (fully saturated with no detail). Shadow clipping is shown if all three RGB channels are clipped (black with no detail).

The Camera Raw image adjustment tabs are:

Basic

Adjust white balance, color saturation, and tonality.

Tone Curve

Fine-tune tonality using a Parametric curve and a Point curve.

Detail

Sharpen images or reduce noise.

HSL / Grayscale

Fine-tune colors using Hue, Saturation, and Luminance adjustments.

Split Toning

Color monochrome images or create special effects with color images.

Lens Corrections

Compensate for chromatic aberration, geometric distortions, and vignetting caused by the camera lens.

Effects

Simulate film grain or apply a postcrop vignette.

Camera Calibration

Apply camera profiles to raw images to correct color casts and adjust non-neutral colors to compensate for the behavior of a camera's image sensor.

Presets

Save and apply sets of image adjustments as presets.

Snapshots

Create versions of a photo that record its state at any point during the editing process.

Preview images

Work with the Camera Raw cache in Adobe Bridge

When you view camera raw files in Adobe Bridge, the thumbnails and previews use either the default settings or your adjusted settings. The Adobe Bridge cache stores data for the file thumbnails, metadata, and file information. Caching this data shortens the loading time when you return to a previously viewed folder in Adobe Bridge. The Camera Raw cache speeds the opening of images in Camera Raw and rebuilds of previews in Adobe Bridge when image settings change in Camera Raw.

Because caches can become very large, you may want to purge the Camera Raw cache or limit its size. You can also purge and regenerate the cache if you suspect that it is corrupted or old.

Note: *The Camera Raw cache holds data for about 200 images for each gigabyte of disk storage allocated to it. By default, the Camera Raw cache is set to a maximum size of 1 GB. You can increase its limit in the Camera Raw preferences.*

1. In Adobe Bridge, choose Edit > Camera Raw Preferences (Windows) or Bridge > Camera Raw Preferences (Mac OS). Or, with the Camera Raw dialog box open, click the Open Preferences Dialog button .
2. Do any of the following:
   - To change the cache size, enter a Maximum Size value.
   - To purge the camera raw cache, click the Purge Cache button.
   - To change the location of the camera raw cache, click Select Location.

Work with Camera Raw and Lightroom

Camera Raw and Lightroom share the same image-processing technology to ensure consistent and compatible results across applications. For Camera Raw to view image adjustments made in the Develop module of Lightroom, metadata changes must be saved to XMP in Lightroom.

Adjustments made in Camera Raw are also displayed in the Adobe Bridge Content and Preview panels.

To view Lightroom changes in Camera Raw, and to ensure that Camera Raw adjustments can be viewed in Lightroom and Adobe Bridge, do the following:

1. In Adobe Bridge, choose Edit > Camera Raw Preferences (Windows) or Bridge > Camera Raw Preferences (Mac OS). Or, with the Camera Raw dialog box open, click the Open Preferences Dialog button .
2. Choose Save Image Settings In > Sidecar ".XMP" Files, and deselect Ignore Sidecar ".XMP" Files.
3. After applying adjustments to a photo in Camera Raw, save them by clicking Done or Open Image.

Note: *Camera Raw reads only the current settings for the primary image in the Lightroom catalog. Adjustments made to virtual copies are not displayed or available in Camera Raw.*

Vignette, grain, and dehaze effects in Camera Raw

Simulate film grain

The Grain section of the Effects tab has controls for simulating film grain for a stylistic effect reminiscent of particular film stocks. You can also use the Grain effect to mask enlargement artifacts when making large prints.

Together, the Size and Roughness controls determine the character of the grain. Check grain at varying zoom levels to ensure that the character appears as desired.



Amount Controls the amount of grain applied to the image. Drag to the right to increase the amount. Set to zero to disable grain.

Size Controls grain particle size. Specifying a value of 25% or higher may cause some image blurring.

Roughness Controls the regularity of the grain. Drag to the left to make the grain more uniform; drag to the right to make the grain more uneven.

Apply a postcrop vignette

To apply a vignette to a cropped image for artistic effect, use the Post Crop Vignetting feature.

1 Crop your image. See .

2 In the Post Crop Vignetting area of the Effects tab, choose a Style.

   Highlight Priority Applies the postcrop vignette while protecting highlight contrast but may lead to color shifts in darkened areas of an image. Appropriate for images with important highlight areas.

Color Priority Applies the postcrop vignette while preserving color hues but may lead to loss of detail in bright highlights.

Paint Overlay Applies the postcrop vignette by blending original image colors with black or white. Appropriate when a soft effect is desired but may reduce highlight contrast.

3 Refine the effect by adjusting any of the following sliders:

Amount Positive values lighten the corners, negative values darken them.

Midpoint Higher values restrict the adjustment to the area closer to the corners, lower values apply the adjustment to a larger area away from the corners.

Roundness Positive values make the effect more circular, negative values make the effect more oval.

Feather Higher values increase the softening between the effect and its surrounding pixels, lower values reduce the softening between the effect and its surrounding pixels.

Highlights (Available for a Highlight Priority or Color Priority effect when Amount is a negative value) Controls the degree of highlight "punch" in bright areas of an image, such as in the glow of a streetlight or other bright light source.

Dehaze

Adobe Camere Raw now lets you easily decrease or increase the amount of haze or fog in a photograph. Once you have made basic adjustments to the photograph, switch to the Effects panel and adjust the Dehaze slider control.



Amount Controls the amount of haze in a photograph. Drag to the right to remove haze; drag to the left to add haze.

Radial Filter Radial filters in Adobe Camera Raw direct attention to specific portions of the image. See, .

Note: Dehaze is now available as a local adjustment. While working with the Radial Filter, Graduated Filter, or the Adjustment Brush, adjust the Dehaze slider control. For more information, see Make local adjustments in Camera Raw
.



Automatic perspective correction in Camera Raw

Using an incorrect lens, or camera shake can cause the perspective of photographs to be tilted or skewed. The perspective may be distorted, and is more evident in photographs containing continuous vertical lines or geometric shapes.

Adobe Camera Raw has Upright modes—four settings that you can use to automatically fix perspective (although manually applying perspective corrections is still an option.) After applying an Upright mode, you can adjust the image further by manually modifying the available slider-based settings.

Note: *Make sure that you apply any lens correction profiles available for your camera and lens combination before you apply one of the four new presets. Applying the lens correction profile prepares the image to be analyzed better for distortion correction.*

Manually correcting lens distortion using Upright presets

1 Do one of the following:

- Open a camera raw file.
- With an image open in Photoshop, click Filter > Camera Raw Filter.

2 In the Camera Raw dialog box, navigate to the Lens Corrections panel.

3 (Optional) In the Profile tab, select the Enable Lens Profile Corrections checkbox.

Enabling Lens profile correction based on your camera and lens combination is highly recommended before processing the photo with the Upright presets.

4 In the Manual tab, four Upright modes are available. Click a mode to apply the correction to the photo.

AutoApplies a balanced set of perspective corrections.

LevelApplies perspective correction to ensure that the image is level.

VerticalApplies level and vertical perspective corrections.

FullApplies level, vertical, and horizontal perspective corrections.

Note: *While trying out the four Upright modes, if you select or clear the Enable Lens Profile Correction checkbox (Lens Correction > Profile), click the Reanalyze link below the Upright preset buttons.*



5 Cycle through the Upright modes until you find the settings you like.

The four Upright modes correct and manage distortion and perspective errors. There is no recommended or preferable setting. The best setting varies from one photo to another. Experiment with the four Upright modes before deciding on the best possible Upright mode for your photo.

6 Use the Transform sliders to make any further modifications, as necessary. A new slider (Aspect) has been introduced in Camera Raw.

- Move the Aspect slider left to adjust the horizontal perspective of the photo.
- Move the Aspect slider right to adjust the vertical perspective of the photo.

Sample images



How to make non-destructive edits using Camera Raw

Learn the basics of Camera Raw, including how to use Camera Raw as a filter in Photoshop video-tutorial.

How to make non-destructive edits using Camera Raw

Radial Filter in Camera Raw

To fully control where a viewer's attention is drawn to on a photo, highlight the subject of the image. Some filters that create a vignetting effect help you achieve that purpose. However, such filters require the main subject to be in the center of the photo.

Radial filters in Adobe Camera Raw 8.0 direct attention to specific portions of the image. For example, you can use the Radial Filter tool to draw an elliptical shape around the subject, and increase the exposure and clarity of the area within the shape to bring more attention to the subject. The subject can be off-center, or anywhere in the photograph.

This is the main workflow to modify a photo with Radial filters:

1 Open a photo in Adobe Camera Raw.

2 Identify one or more areas where you'd like to attract the viewer's attention.

3 Set up:

- (Optional) A Radial filter to weaken focus on the background
- A Radial filter to highlight the subject
- Additional Radial filters, if you have more than one subject to highlight

Apply a Radial Filter to enhance a photo

1 Do one of the following:

- Open a camera raw file.
- With an image open in Photoshop, choose Filter > Camera Raw Filter.

2 Select the Radial Filter tool from the toolbar.

Press J to toggle the Radial Filter tool.

3 Use the New and Edit radio button options to choose whether you want to create a filter or edit an existing filter.

4 Do one of the following:

- To create a Radial filter, click and drag across the region, and draw a circular or elliptical shape. This shape determines the area affected or excluded from the alterations you are about to perform.
- To edit a Radial filter, click any of the gray handles on the photo. When selected, the handle turns red.

5 To determine what area of the photo is modified, choose an Effect option (located below the sliders).

- **Outside** All modifications are applied outside the selected area.
- **Inside** All modifications are applied to the selected area.

6 Adjust the size (width and height) and orientation of the Radial filter added. Select a filter and:

- Click and drag the center of the filter to move and reposition it.
- Hover the pointer over any of the four filter handles, and when the pointer icon changes, click and drag to change the size of the filter.
- Hover the pointer close to the edge of the filter, and when the pointer icon changes, click and drag the edge of the filter to change the orientation.

7 Use the sliders to modify the selected Radial filter area. The Feather slider adjusts the falloff of the applied effect.



8 Repeat steps 3 through 6 to continue adding or editing Radial filters.

9 Clear the Overlay checkbox, to show how the finished photo appears. If you want to delete all the Radial filters and start from scratch, click Clear All (this action cannot be undone).

10 Use the Mask option to enable mask visualization. Alternatively, press Y to toggle the Mask setting.

For more information, see The Radial Filter in Camera Raw in Photoshop CC.

Modify a Radial Filter instance using brush controls

You can modify Radial Filter masks using brush controls. Once you've added a mask, to access brush controls, select the Brush option next to New/Edit. Alternatively, press Shift+K.

As appropriate, use the + and – brushes.

Note: *For a video description of the brush controls, see Filter Brush in Adobe Camera Raw 8.5.*



Keyboard shortcuts and modifiers for the Radial Filter tool

New adjustments

- Press and hold Shift while dragging to create an adjustment that is constrained to a circle.
- While dragging, press and hold the spacebar to move the ellipse; release the spacebar to resume defining the shape of the new adjustment.

Editing adjustments

- While dragging inside an adjustment to move it, press and hold Shift to constrain the movement in the horizontal or vertical direction.
- While dragging one of the four handles to resize an adjustment, press and hold Shift to preserve the aspect ratio of the adjustment shape.
- While dragging the boundary of an adjustment to rotate it, press and hold Shift to snap the rotation to 15-degree increments.
- While an adjustment is selected, press X to flip the effect direction (for example, from outside to inside).

Deleting adjustments

- While an adjustment is selected, press Delete to delete the adjustment.
- Press Option/Alt + click an existing adjustment to delete it.

Adjustments with maximum coverage

- Press Command/Control and double-click an empty area to create an adjustment that is centered and covers the cropped image area.
- Press Command/Control and double-click within an existing adjustment to expand that adjustment to cover the cropped image area.

Manage Camera Raw settings

Save image states as snapshots

You can record the state of an image at any time by creating a snapshot. Snapshots are stored renditions of an image that contain the complete set of edits made up until the time the snapshot is created. By creating snapshots of an image at various times during the editing process, you can easily compare the effects of the adjustments you make. You can also return to an earlier state if you want to use it at another time. Another benefit of snapshots is that you can work from multiple versions of an image without having to duplicate the original.

Create and manage snapshots using the Snapshots tab of the Camera Raw dialog box.

1 Click the New Snapshot button at the bottom of the Snapshots tab to create a snapshot.

2 Type a name in the New Snapshot dialog box and click OK.

The snapshot appears in the Snapshots tab list.

When working with snapshots, you can do any of the following:

- To rename a snapshot, right-click (Windows) or Control-click (Mac OS) it and choose Rename.
- Click a snapshot to change the current image settings to those of the selected snapshot. The image preview updates accordingly.
- To update, or overwrite, an existing snapshot with the current image settings, right-click (Windows) or Control-click (Mac OS) the snapshot and choose Update With Current Settings.
- To undo changes made to a snapshot, click Cancel.

  ***Note**: Use caution when clicking Cancel to undo snapshot changes. All image adjustments made during the current editing session are also lost.*

- To delete a snapshot, select it and click the Trash button at the bottom of the tab. Or, right-click (Windows) or Control-click (Mac OS) the snapshot and choose Delete.

If you apply snapshots in Photoshop Lightroom, you can edit them in the Camera Raw dialog box (and vice versa).

Save, reset, and load Camera Raw settings

You can reuse the adjustments you've made to an image. You can save all the current Camera Raw image settings, or any subset of them, as a preset or as a new set of defaults. The default settings apply to a specific camera model, a specific camera serial number, or a specific ISO setting, depending on the settings in the Default Image Settings section of the Camera Raw preferences.

Presets appear by name in the Presets tab, in the Edit > Develop Settings menu in Adobe Bridge, in the context menu for camera raw images in Adobe Bridge, and in the Apply Presets submenu of the Camera Raw Settings menu in the Camera Raw dialog box. Presets are not listed in these locations if you don't save them to the Camera Raw settings folder. However, you can use the Load Settings command to browse for and apply settings saved elsewhere.

You can save and delete presets using the buttons at the bottom of the Presets tab.

? Click the Camera Raw Settings menu button and choose a command from the menu:

Save Settings Saves the current settings as a preset. Choose which settings to save in the preset, and then name and save the preset.

Save New Camera Raw Defaults Saves the current settings as the new default settings for other images taken with the same camera, with the same camera model, or with the same ISO setting. Select the appropriate options in the Default Image Settings section of the Camera Raw preferences to specify whether to associate the defaults with a specific camera's serial number or with an ISO setting.

Reset Camera Raw Defaults Restores the original default settings for the current camera, camera model, or ISO setting.

Load Settings Opens the Load Raw Conversion Settings dialog box, in which you browse to the settings file, select it, and then click Load.

Specify where Camera Raw settings are stored

Choose a preference to specify where the settings are stored. The XMP files are useful if you plan to move or store the image files and want to retain the camera raw settings. You can use the Export Settings command to copy the settings in the Camera Raw database to sidecar XMP files or embed the settings in Digital Negative (DNG) files.

When a camera raw image file is processed with Camera Raw, the image settings are stored in one of two places: the Camera Raw database file or a sidecar XMP file. When a DNG file is processed in Camera Raw, the settings are stored in the DNG file itself, but they can be stored in a sidecar XMP file instead. Settings for TIFF and JPEG files are always stored in the file itself.

Note: *When you import a sequence of camera raw files in After Effects, the settings for the first file are applied to all files in the sequence that do not have their own XMP sidecar files. After Effects does not check the Camera Raw database.*

You can set a preference to determine where settings are stored. When you reopen a camera raw image, all settings default to the values used when the file was last opened. Image attributes (target color space profile, bit depth, pixel size, and resolution) are not stored with the settings.

1 In Adobe Bridge, choose Edit > Camera Raw Preferences (Windows) or Bridge > Camera Raw Preferences (Mac OS). Or, in the Camera Raw dialog box, click the Open Preferences Dialog button . Or, in Photoshop, choose Edit > Preferences > Camera Raw (Windows) or Photoshop > Preferences > Camera Raw (Mac OS).

2 In the Camera Raw Preferences dialog box, choose one of the following from the Save Image Settings In menu:

Camera Raw Database Stores the settings in a Camera Raw database file in the folder Document and Settings/*[user name]*/Application Data/Adobe/CameraRaw (Windows) or Users/*[user name]*/Library/Preferences (Mac OS). This database is indexed by file content, so the image retains camera raw settings even if the camera raw image file is moved or renamed.

Sidecar ".XMP" Files Stores the settings in a separate file, in the same folder as the camera raw file, with the same base name and an .xmp extension. This option is useful for long-term archiving of raw files with their associated settings, and for the exchange of camera raw files with associated settings in multiuser workflows. These same sidecar XMP files can store IPTC (International Press Telecommunications Council) data or other metadata associated with a camera raw image file. If you open files from a read-only volume such as a CD or DVD, be sure to copy the files to your hard disk before opening them. The Camera Raw plug-in cannot write an XMP file to a read-only volume and writes the settings to the Camera Raw database file instead. You can view XMP files in Adobe Bridge by choosing View > Show Hidden Files.

Note: *If you are using a revision control system to manage your files and are storing settings in sidecar XMP files, keep in mind that you must check your sidecar files in and out to change camera raw images; similarly, you must manage (e.g., rename, move, delete) XMP sidecar files together with their camera raw files. Adobe Bridge, Photoshop, After Effects, and Camera Raw take care of this file synchronization when you work with files locally.*

If you store the camera raw settings in the Camera Raw database and plan to move the files to a different location (CD, DVD, another computer, and so forth), you can use the Export Settings To XMP command to export the settings to sidecar XMP files.

3 If you want to store all adjustments to DNG files in the DNG files themselves, select Ignore Sidecar ".XMP" Files in the DNG File Handling section of the Camera Raw Preferences dialog box.

Copy and paste Camera Raw settings

In Adobe Bridge, you can copy and paste the Camera Raw settings from one image file to another.

1 In Adobe Bridge, select a file and choose Edit > Develop Settings > Copy Camera Raw Settings.

2 Select one or more files and choose Edit > Develop Settings > Paste Camera Raw Settings.

You can also right-click (Windows) or Control-click (Mac OS) image files to copy and paste using the context menu.

3 In the Paste Camera Raw Settings dialog box, choose which settings to apply.

Apply saved Camera Raw settings

1 In Adobe Bridge or in the Camera Raw dialog box, select one or more files.

2 In Adobe Bridge, choose Edit > Develop Settings, or right-click a selected file. Or, in the Camera Raw dialog box, click the Camera Raw Settings menu .

3 Choose one of the following:

Image Settings Uses the settings from the selected camera raw image. This option is available only from the Camera Raw Settings menu in the Camera Raw dialog box.

Camera Raw Defaults Uses the saved default settings for a specific camera, camera model, or ISO setting.

Previous Conversion Uses the settings from the previous image of the same camera, camera model, or ISO setting.

Preset name Uses the settings (which can be a subset of all image settings) saved as a preset.



Note: *You can also apply presets from the Presets tab.*

Export Camera Raw settings and DNG previews

If you store file settings in the Camera Raw database, you can use the Export Settings To XMP command to copy the settings to sidecar XMP files or embed them in DNG files. This is useful for preserving the image settings with your camera raw files when you move them.

You can also update the JPEG previews embedded in DNG files.

1 Open the files in the Camera Raw dialog box.

2 If you are exporting settings or previews for multiple files, select their thumbnails in the Filmstrip view.

3 In the Camera Raw Settings menu , choose Export Settings To XMP or Update DNG Previews.

The sidecar XMP files are created in the same folder as the camera raw image files. If you saved the camera raw image files in DNG format, the settings are embedded in the DNG files themselves.

Specify Camera Raw workflow options

Workflow options specify settings for all files output from Camera Raw, including the color bit depth, color space, output sharpening, and pixel dimensions. Workflow options determine how Photoshop opens these files but not how After Effects imports a camera raw file. Workflow options settings do not affect the camera raw data itself.

You can specify workflow options settings by clicking the underlined text at the bottom of the Camera Raw dialog box.

Space Specifies the target color profile. Generally, set Space to the color profile you use for your Photoshop RGB working space. The source profile for camera raw image files is usually the camera-native color space. The profiles listed in the Space menu are built in to Camera Raw. To use a color space that's not listed in the Space menu, choose ProPhoto RGB, and then convert to the working space of your choice when the file opens in Photoshop.

Depth Specifies whether the file opens as an 8-bpc or 16-bpc image in Photoshop.

Size Specifies the pixel dimensions of the image when imported into Photoshop. The default pixel dimensions are those used to photograph the image. To resample the image, use the Crop Size menu.

For square-pixel cameras, choosing a smaller-than-native size can speed processing when you are planning a smaller final image. Picking a larger size is like upsampling in Photoshop.

For non-square pixel cameras, the native size is the size that most closely preserves the total pixel count. Selecting a different size minimizes the resampling that Camera Raw performs, resulting in slightly higher image quality. The best quality size is marked with an asterisk (*) in the Size menu.

Note: You can always change the pixel size of the image after it opens in Photoshop.

Resolution Specifies the resolution at which the image is printed. This setting does not affect the pixel dimensions. For example, a 2048 x 1536 pixel image, when printed at 72 dpi, is approximately 28-1/2 x 21-1/4 inches. When printed at 300 dpi, the same image is approximately 6-3/4 x 5-1/8 inches. You can also use the Image Size command to adjust resolution in Photoshop.

Sharpen For Allows you to apply output sharpening for Screen, Matte Paper, or Glossy Paper. If you apply output sharpening, you can change the Amount pop-up menu to Low or High to decrease or increase the amount of sharpening applied. In most cases, you can leave the Amount set to the default option, Standard.

Open In Photoshop As Smart Objects Causes Camera Raw images to open in Photoshop as a Smart Object layer instead of a background layer when you click the Open button. To override this preference for selected images, press Shift when clicking Open.

Open, process, and save images in Camera Raw

Process, compare, and rate multiple images

The most convenient way to work with multiple camera raw images is to use the Filmstrip view in Camera Raw. Filmstrip view opens by default when you open multiple images in Camera Raw from Adobe Bridge.

Note: *The Filmstrip view is not available when importing multiple images into After Effects.*

Images can have three states in the Filmstrip pane: deselected, selected (but not active), and active (also selected). In general, adjustments are applied to all selected images.

You can also synchronize settings to apply settings from the active image to all selected images. You can quickly apply a set of adjustments to an entire set of images—such as all shots taken under the same conditions—and then fine-tune the individual shots later, after you've determined which you'll use for your final output. You can synchronize both global and local adjustment settings.

- To select an image, click its thumbnail. To select a range of images, Shift-click two thumbnails. To add an image to a selection, Ctrl-click (Windows) or Command-click (Mac OS) its thumbnail.
- To change which image is active without changing which images are selected, click a navigation arrow at the bottom of the preview pane.
- To apply settings from the active image to all selected images, click the Synchronize button at the top of the Filmstrip pane and choose which settings to synchronize.
- To apply a star rating, click a rating under the image thumbnail.
- To mark selected images for deletion, click Mark For Deletion .

  A red X appears in the thumbnail of an image marked for deletion. The file is sent to the Recycle Bin (Windows) or Trash (Mac OS) when you close the Camera Raw dialog box. (If you decide to keep an image you marked for deletion, select it in the Filmstrip pane and click Mark For Deletion again, before you close the Camera Raw dialog box.)

For a tutorial on synchronizing edits across multiple Camera Raw photos, see Synchronizing edits in Adobe Camera Raw by Dan Moughamian.

Automate image processing

You can create an action to automate the processing of image files with Camera Raw. You can automate the editing process, and the process of saving the files in formats such as PSD, DNG, JPEG, Large Document Format (PSB), TIFF, and PDF. In Photoshop, you can also use the Batch command, the Image Processor, or the Create Droplet command to process one or more image files. The Image Processor is especially useful for saving image files in different file formats during the same processing session.

Here are some tips for automating the processing of camera raw image files:

- When you record an action, first select Image Settings from the Camera Raw Settings menu in the Camera Raw dialog box. In this way, the settings particular to each image (from the Camera Raw database or sidecar XMP files) are used to play back the action.
- If you plan to use the action with the Batch command, you may want to use the Save As command and choose the file format when saving the camera raw image.

- When you use an action to open a camera raw file, the Camera Raw dialog box reflects the settings that were in effect when the action was recorded. You may want to create different actions for opening camera raw image files with different settings.
- When using the Batch command, select Override Action "Open" Commands. Any Open commands in the action will then operate on the batched files rather than the files specified by name in the action. Deselect Override Action "Open" Commands only if you want the action to operate on open files or if the action uses the Open command to retrieve needed information.
- When using the Batch command, select Suppress File Open Options Dialogs to prevent the display of the Camera Raw dialog box as each camera raw image is processed.
- When using the Batch command, select Override Action "Save As" Commands if you want to use the Save As instructions from the Batch command instead of the Save As instructions in the action. If you select this option, the action must contain a Save As command, because the Batch command does not automatically save the source files. Deselect Override Action "Save As" Commands to save the files processed by the Batch command in the location specified in the Batch dialog box.
- When creating a droplet, select Suppress File Open Options Dialogs in the Play area of the Create Droplet dialog box. This prevents the display of the Camera Raw dialog box as each camera raw image is processed.

Open images

- To process raw images in Camera Raw, select one or more camera raw files in Adobe Bridge, and then choose File > Open In Camera Raw or press Ctrl+R (Windows) or Command+R (Mac OS). When you finish making adjustments in the Camera Raw dialog box, click Done to accept changes and close the dialog box. You can also click Open Image to open a copy of the adjusted image in Photoshop.
- To process JPEG or TIFF images in Camera Raw, select one or more JPEG or TIFF files in Adobe Bridge, and then choose File > Open In Camera Raw or press Ctrl+R (Windows) or Command+R (Mac OS). When you finish making adjustments in the Camera Raw dialog box, click Done to accept changes and close the dialog box. You can specify whether JPEG or TIFF images with Camera Raw settings are automatically opened in Camera Raw in the JPEG and TIFF Handling section of the Camera Raw preferences.
- To import camera raw images in Photoshop, select one or more camera raw files in Adobe Bridge, and then choose File > Open With > Adobe Photoshop CS5. (You can also choose the File > Open command in Photoshop, and browse to select camera raw files.) When you finish making adjustments in the Camera Raw dialog box, click Open Image to accept changes and open the adjusted image in Photoshop. Press Alt (Windows) or Option (Mac OS) to open a copy of the adjusted image and not save the adjustments to the original image's metadata. Press Shift while clicking Open Image to open the image as a Smart Object in Photoshop. At any time, you can double-click the Smart Object layer that contains the raw file to adjust the Camera Raw settings.

  Tip: Shift-double-click a thumbnail in Adobe Bridge to open a camera raw image in Photoshop without opening the Camera Raw dialog box. Hold down Shift while choosing File > Open to open multiple selected images.
- To import camera raw images in After Effects using Adobe Bridge, select one or more camera raw files in Adobe Bridge, and then choose File > Open With > Adobe After Effects CS5. (You can also choose a File > Import command in After Effects and browse to select camera raw files.) When you finish making adjustments in the Camera Raw dialog box, click OK to accept changes.
- To import TIFF and JPEG files into After Effects using Camera Raw, choose the File > Import command in After Effects, and then choose All Files from the Enable menu (Mac OS) or Files Of Type menu (Windows) in the After Effects Import File dialog box. Select the file to import, choose Camera Raw from the Format menu, and click Open.

- To import Camera Raw images into After Effects as a sequence, choose File > Import in After Effects. Select the images, select the Camera Raw Sequence option, and click Open. Camera Raw settings applied to the first camera raw file upon import are applied to the remaining files in the sequence unless an XMP sidecar file is present for any subsequent file in the sequence. In that case, the settings in the XMP file or in the DNG file are applied to that specific frame in the sequence. All other frames use the settings that the first file in the sequence specifies.

If you have trouble opening Camera Raw files, see Why doesn't my version of Photoshop or Lightroom support my camera?

Save a camera raw image in another format

You can save camera raw files from the Camera Raw dialog box in PSD, TIFF, JPEG, or DNG format.

When you use the Save Image command in the Camera Raw dialog box, files are placed in a queue to be processed and saved. This is useful if you are processing several files in the Camera Raw dialog box and saving them in the same format.

1 In the Camera Raw dialog box, click the Save Image button in the lower-left corner of the dialog box.

Alt-click (Windows) or Option-click (Mac OS) Save to suppress the Camera Raw Save Options dialog box when saving a file.

2 In the Save Options dialog box, specify the following options:

Destination Specifies where to save the file. If necessary, click the Select Folder button and navigate to the location.

File Naming Specifies the filename using a naming convention that includes elements such as date and camera serial number. Using informative filenames based on a naming convention helps you keep image files organized.

3 Choose a file format from the Format menu.

Digital Negative Saves a copy of the camera raw file in the DNG file format.

Compatibility

Specifies the versions of Camera Raw and Lightroom that can read the file.

If you choose Custom, specify whether you want compatibility with DNG 1.1 or DNG 1.3. By default, the conversion uses lossless compression, which means no information is lost while reducing file size. Choosing Linear (Demosaiced) stores the image data in an interpolated format. That means other software can read the file even if that software does not have a profile for the digital camera that captured the image.

JPEG Preview

Embeds a JPEG preview in the DNG file. If you decide to embed a JPEG preview, you can choose the preview size. If you embed JPEG previews, other applications can view the contents of the DNG file without parsing the camera raw data.

Embed Original Raw File

Stores all the original camera raw image data in the DNG file.

JPEG Saves copies of the camera raw files in JPEG (Joint Photographic Experts Group) format. To specify the amount of compression, enter a value from 0 to 12 or choose from the menu. Entering a higher value, or choosing High or Maximum, applies less compression and increases file size and image quality. JPEG format is commonly

used to display photographs and other continuous-tone images in web photo galleries, slide shows, presentations, and other online services.

TIFF Saves copies of the camera raw files as TIFF (Tagged-ImageFile Format) files. Specify whether to apply no compression, or LZW or ZIP file compression. TIFF is a flexible bitmap image format supported by virtually all paint, image-editing, and page-layout applications. TIFF provides greater compression and compatibility with other applications than does PSD format.

Photoshop Saves copies of the camera raw files in the PSD file format. You can specify whether to preserve cropped pixel data in the PSD file.

4 Click Save.

Repair images with the Enhanced Spot Removal tool in Camera Raw

The Spot Removal tool in Camera Raw lets you repair a selected area of an image by sampling from a different area of the same image. Its default behavior enables you to mark areas to touch up by dragging the brush across the photo. For example, in the following photo you could remove a portion of the wire (connecting the helmet and the overhead wire) that is distracting the view of the blue sky.

Using the Spot Removal tool on a raw image means that you are processing the raw image data directly. Working with raw image data directly can provide cleaner matches for retouching (healing or cloning) actions. Also, since any edits and modifications to camera raw images are stored in sidecar files, this process is non-destructive.

Use the Spot Removal tool

1 Do one of the following:

- Open a camera raw file.
- With an image open in Photoshop, choose Filter > Camera Raw Filter.

2 Select the Spot Removal tool from the toolbar.

3 Select one of the following from the Type menu:

HealMatches the texture, lighting, and shading of the sampled area to the selected area.**Clone**Applies the sampled area of the image to the selected area.

4 (Optional) In the Spot Removal tool options area under the Histogram, drag the Size slider to specify the size of the area the Spot Removal tool affects.

Use the bracket keys on your keyboard to change brush size

•Left bracket ([) reduces the tool radius size.

- Right bracket (]) increases the tool radius size.

5 In the photo, click and drag the part of the photo to retouch.

- A red-and-white marquee area (red handle) designates your selection.
- A green-and-white marquee area (green handle) designates the sampled area.



6 (Optional) To change the sampled area selected by default, do one of the following:

- **Automatically** Click the handle of a selected area, and press the forward slash key (/). A new area is sampled. Press the forward slash key until you find a sample area that fits best.
- **Manually** Use the green handle to reposition the sampled area.

When you select larger portions of an image using longer strokes, the right sample area match is not found immediately. To experiment with various options, click the forward slash (/), and the tool auto-samples more areas for you.

7 To remove all the adjustments made using the Spot Removal tool, click Clear All.

Keyboard shortcuts and modifiers

Circular spot:

- Control/Command + click to create a circular spot; drag to set the source of the spot.
- Command/Control + Option/Alt + click to create a circular spot; drag to set the size of the spot.

Rectangular selection:

- Click Option/Alt + drag to define a rectangular selection. All spots within that selection (highlighted in red) are deleted once the mouse is released.

Extend a selected area or spot:

- Shift + click to extend an existing selected spot in "connect the dots" fashion.

Delete a selected area or spot:

- Select a red or green handle, and press Delete to delete a selected adjustment.

- Press Option/Alt and click a handle to delete it.

Clean up a photo with the Visualize Spots feature

While working on a computer screen, you may be able to identify and remove most visible spots or imperfections. However, when you print a photo at its full resolution, the printed output may contain many imperfections that were not visible on a computer screen. These imperfections could be of many types: dust on a camera sensor, blemishes on a model's skin in a portrait, tiny wisps of clouds on blue skies. At full resolution, these imperfections are visually distracting.

The Visualize Spots feature lets you search for imperfections that may not be immediately visible. When you select the Visualize Spots checkbox (found in the options for the Spot Removal tool), the image is inverted. You can then use the Spot Removal tool in the Visualize Spots mode to clean up the image further.



1 Do one of the following:
   - Open a camera raw file.
   - With an image open in Photoshop CC, choose Filter > Camera Raw Filter.
2 Select the Spot Removal tool from the toolbar, and then select the Visualize Spots checkbox.

   The image is inverted, and the outlines of the image's elements are visible.

3 Use the Visualize Spots slider to vary the contrast threshold of the inverted image. Move the slider to different contrast levels to view imperfections like sensor dust, dots, or other unwanted elements.

When the Spot Visualization checkbox is selected, to change the visualization threshold:

•Increase: Press period (.)

- Increase (in larger steps): Press Shift+period (.)
- Reduce: Press comma (,)
- Reduce (in larger steps): Press Shift=comma (,)

4 Use the Spot Removal tool to clone or heal out unwanted elements in the photo. Uncheck the Visualize Spots checkbox to view the resulting image.

5 Repeat steps 2, 3, and 4 as needed.

Make local adjustments in Camera Raw

About local adjustments

The controls in the image adjustment tabs of Camera Raw affect the color and tone of an entire photo. To adjust a specific area of a photo (or make local adjustments, such as dodging or burning) use the Adjustment Brush tool and the Graduated Filter tool in Camera Raw.

With the Adjustment Brush tool, you can selectively apply Exposure, Brightness, Clarity, and other adjustments by "painting" them onto the photo.

With the Graduated Filter tool, you can apply the same types of adjustments gradually across a region of a photo. You can make the region as wide or as narrow as you like.

You can apply both types of local adjustments to any photo. You can synchronize local adjustment settings across multiple selected images. You can also create local adjustment presets so that you can quickly reapply an effect you use frequently.

Getting local adjustments "right" in Camera Raw takes some experimentation. The recommended workflow is to select a tool and specify its options, and then apply the adjustment to the photo. Then you can go back and edit that adjustment, or apply a new one.

As with all other adjustments applied in Camera Raw, local adjustments are nondestructive. They are never permanently applied to the photo. Local adjustments are saved with an image in an XMP sidecar file or in the Camera Raw database, depending on what's specified in Camera Raw preferences.

Apply local adjustments with the Adjustment Brush tool in Camera Raw

1 Select the Adjustment Brush tool from the toolbar (or press K).

   Camera Raw opens the Adjustment Brush tool options under the Histogram and sets the mask mode to New.

2 Choose the type of adjustment you want to make in the Adjustment Brush tool options by dragging an effects slider.

   Note: *The effects that are available depend on whether you are working in Process Version 2012, 2010, or 2003, as noted. To update a photo to PV2012, click the exclamation-point icon in the lower-right corner of the image preview.*

   Temp Adjusts the color temperature of an area of the image, making it warmer or cooler. A graduated filter temperature effect can improve images captured in mixed-lighting conditions.

   Tint Compensates for a green or magenta color cast.

   Exposure Sets the overall image brightness. Applying an Exposure local correction can achieve results similar to traditional dodging and burning.

   Highlights Recovers detail in overexposed highlight areas of an image.

   Shadows Recovers detail in underexposed shadow areas of an image.

   Whites Adjusts the white points in a photo

   Blacks Adjusts the black points in a photo

   Brightness Adjusts the image brightness, with a greater effect in the midtones.

   Contrast Adjusts the image contrast, with a greater effect in the midtones.

   Saturation Changes the vividness or purity of the color.

   Clarity Adds depth to an image by increasing local contrast.

Dehaze Reduces or increases existing haze in a photo

Sharpness Enhances edge definition to bring out details in a photo. A negative value blurs details.

Noise Reduction Reduces luminance noise, which can become apparent when shadow areas are opened.

Moiré Reduction Removes moiré artifacts, or color aliasing.

Defringe Removes fringe colors along edges. See .

Color Applies a tint to the selected area. Select the hue by clicking the color sample box to the right of the effect name.

Click the Plus icons (+) or the Minus icons (–) to increase or decrease the effect by a preset amount. Click multiple times to select a stronger adjustment. Double-click the slider to reset the effect to zero.

3 Specify brush options:

Size Specifies the diameter of the brush tip, in pixels.

Feather Controls the hardness of the brush stroke.

Flow Controls the rate of application of the adjustment.

Density Controls the amount of transparency in the stroke.

Auto Mask Confines brush strokes to areas of similar color.

Show Mask Toggles visibility of the mask overlay in the image preview.

4 Move the Adjustment Brush tool over the image.

The cross hair indicates the application point. The solid circle indicates the brush size. The black-and-white dashed circle indicates the feather amount.

Note: *If the Feather is set to 0, the black-and-white circle indicates the brush size. With very small feather amounts, the solid circle may not be visible.*

5 Paint with the Adjustment Brush tool in the area of the image you want to adjust.

When you release the mouse, a pin icon appears at the application point. In the Adjustment Brush tool options, the mask mode changes to Add.

6 (Optional) Refine the adjustment by doing any of the following:

- Drag any of the effect sliders in the Adjustment Brush tool options to customize the effect in the image.
- Press V to hide or show the pin icon.
- To toggle visibility of the mask overlay, use the Show Mask option, press Y, or position the pointer over the pin icon.

To customize the color of the mask overlay, click the color swatch next to the Show Mask option. Then, choose a new color from the Color Picker.

- To undo part of the adjustment, click Erase in the Adjustment Brush tool options and paint over the adjustment.

To create an eraser brush that has different characteristics from the current Adjustment Brush tool, click the Local Adjustment Settings menu button and choose Separate Eraser Size. Then, specify the Size, Feather, Flow, and Density you want for the eraser.

- Remove the adjustment completely by selecting the pin and pressing Delete.
- Press Ctrl+Z (Windows) or Command+Z (Mac OS) to undo your last adjustment.
- Click Clear All at the bottom of the tool options to remove all Adjustment Brush tool adjustments and set the mask mode to New.

7 (Optional) Click New to apply an additional Adjustment Brush tool adjustment, and refine it as desired using the techniques in step 6.

Note: *When working with multiple Adjustment Brush adjustments, make sure you're in Add mode to switch between them. Click a pin icon to select that adjustment and refine it.*

Apply local adjustments with the Graduated Filter tool in Camera Raw

1 Select the Graduated Filter tool from the toolbar (or press G).

Camera Raw opens the Graduated Filter tool options under the Histogram and sets the mask mode to New.

2 Choose the type of adjustment you want to make in the Graduated Filter tool options by dragging the slider for any of the following effects:

Note: *The effects that are available depend on whether you are working in Process Version 2012, 2010, or 2003, as noted. To update a photo to PV2012, click the exclamation-point icon in the lower-right corner of the image preview.*

Temp Adjusts the color temperature of an area of the image, making it warmer or cooler. A graduated filter temperature effect can improve images captured in mixed-lighting conditions.

Tint Compensates for a green or magenta color cast.

Exposure Sets the overall image brightness. Applying an Exposure graduated filter can achieve results similar to traditional dodging and burning.

Highlights Recovers detail in overexposed highlight areas of an image.

Shadows Recovers detail in underexposed shadow areas of an image.

Whites Adjusts the white points in a photo

Blacks Adjusts the black points in a photo

Brightness Adjusts the image brightness, with a greater effect in the midtones.

Contrast Adjusts the image contrast, with a greater effect in the midtones.

Saturation Changes the vividness or purity of the color.

Clarity Adds depth to an image by increasing local contrast.

Dehaze Reduces or increases existing haze in a photo

Sharpness Enhances edge definition to bring out details in the photo. A negative value blurs details.

Noise Reduction Reduces luminance noise, which can become apparent when shadow areas are opened.

Moiré Reduction Removes moiré artifacts, or color aliasing.

Defringe Removes fringe color along edges. See .

Color Applies a tint to the selected area. Select the hue by clicking the color sample box to the right of the effect name.

Click the Plus icon (+) or the Minus icon (–) to increase or decrease the effect by a preset amount. Double-click the slider to reset the effect to zero.

3 Drag in the photo to apply a graduated filter across a region of the photo.

The filter starts at the red dot and red dotted line, and it continues past the green dot and green dotted line.

The mask mode switches to Edit in the Graduated Filter tool options.

4 (Optional) Refine the filter by doing any of the following:

- Drag any of the effect sliders in the Graduated Filter tool options to customize the filter.
- Toggle visibility of the guide overlays by selecting the Overlay option (or press V).
- Drag the green or red dot to freely expand, contract, and rotate the effect.
- Drag the black-and-white dotted line to shift the effect.
- Position the pointer over the green-and-white or red-and-white dotted line, near the green or red dot, until a double-pointing arrow appears. Then, drag to expand or contract the effect at that end of the range.
- Position the pointer over the green-and-white or red-and-white dotted line, away from the green or red dot, until a curved double-pointing arrow appears. Then, drag to rotate the effect.
- Remove the filter by pressing Delete.
- Press Ctrl+Z (Windows) or Command+Z (Mac OS) to undo your last adjustment.
- Use the Mask option to enable mask visualization. Alternatively, press Y to toggle the Mask setting.
- Click Clear All at the bottom of the tool options to remove all Graduated Filter tool effects and set the mask mode to New.

5 (Optional) Click New to apply an additional Graduated Filter tool effect, and refine it as desired using the techniques in step 4.

Note: *When working with multiple Graduated Filter effects, click an overlay to select that effect and refine it.*

Modify a Graduated Filter instance using brush controls

You can modify Graduated Filter masks using brush controls. Once you've added a mask, to access brush controls select the Brush option next to New/Edit. Alternatively, with a Graduated Filter instance selected, press Shift+K.

As appropriate, use the + and – brushes.

For a video description of the brush controls, see **Filter Brush in Adobe Camera Raw**.

Note: *The add/remove functionality is available only to Photoshop CC customers using Camera Raw 8.5 or later.*

Save and apply local adjustment presets

You can save local adjustments as presets so that you can quickly apply the effects to other images. You create, select, and manage local adjustment presets using the Camera Raw Settings menu in the Adjustment Brush or Graduated Filter tool options. You apply local adjustment presets using the Adjustment Brush tool or the Graduated Filter tool .

Note: *Local adjustments cannot be saved with Camera Raw image presets.*

? In the Adjustment Brush or Graduated Filter tool options in the Camera Raw dialog box, click the Camera Raw Settings menu button . Then, choose one of the following commands:

New Local Correction Setting Saves the current local adjustment effect settings as a preset. Type a name and click OK. Saved presets appear in the Local Adjustment Settings menu and can be applied to any image that is opened in Camera Raw.

Delete "preset name" Deletes the selected local adjustment preset.

Rename "preset name" Renames the selected local adjustment preset. Type a name and click OK.

Preset name Select a preset to apply its settings with the Adjustment Brush tool or the Graduated Filter tool.

When using local adjustment presets, keep in mind the following:

- Only one local adjustment preset can be selected at a time.
- When applying a local adjustment preset with the Adjustment Brush tool, you can still customize the brush options, including Size, Feather, Flow, and Density. The preset applies the effect settings at the specified brush size.
- After a local adjustment preset is applied, you can refine it as desired.
- The same effect settings are available for the Adjustment Brush tool and the Graduated Filter tool. As a result, local adjustment presets can be applied using either tool, regardless of which tool was used to create the preset.

More Help topics

Process versions in Camera Raw

Rotate, crop, and adjust images

Rotate images

- Click the Rotate Image 90° Counter Clockwise button (or press L).
- Click the Rotate Image 90° Clockwise button (or press R).

Note: *Using commands in the Edit menu, you can also rotate images in Adobe Bridge without opening the Camera Raw dialog box.*

Straighten images

1 In the Camera Raw dialog box, select the Straighten tool . Alternatively, press the A key.

2 Drag the Straighten tool in the preview image to baseline horizontal and vertical.

Note: *The Crop tool becomes active immediately after you use the Straighten tool.*

Automatically straighten an image

You can automatically straighten an image in one of the following three ways:

- Double-click the Straighten tool ( ) in the toolbar.
- With the Straighten tool selected, double-click anywhere in the preview image.

- With the Crop tool selected, press the Command key (Mac OS) or Ctrl key (Windows) to temporarily switch to the Straighten tool. Now, double-click anywhere within the preview image.

Crop images

1 In the Camera Raw dialog box, select the Crop tool (or press C).

   To constrain the initial crop area to a specific aspect ratio, hold the mouse button down as you select the Crop tool and choose an option from the menu. To apply a constraint to a previously applied crop, Ctrl-click (Mac OS) or right-click (Windows) on the crop.

2 Drag in the preview image to draw the crop area box.

3 To move, scale, or rotate the crop area, drag the crop area or its handles.

   Note: *To cancel the crop operation, press Esc with the Crop tool active, or click and hold the Crop tool button and choose Clear Crop from the menu. To cancel the crop and close the Camera Raw dialog box without processing the camera raw image file, click the Cancel button or deselect the Crop tool and press Esc.*

4 When you are satisfied with the crop, press Enter (Windows) or Return (Mac OS).

The cropped image resizes to fill the preview area, and the workflow options link under the preview area displays the updated image size and dimensions.

Correct red eyes

1 Zoom the image in to at least 100%.

2 From the toolbar, select the Red Eye Removal tool ( ).

3 In the right pane, select Red Eye or Pet Eye from the Type pop-up menu.

4 Drag a selection in the photo around the affected eye.

   Camera Raw sizes the selection to match the pupil. You can adjust the size of the selection by dragging its edges.

5 In the tool options under the Histogram, drag the Pupil Size slider to the right to increase the size of the area corrected.

6 (Only for correcting red eyes in pictures of pets) If necessary, select Add Catchlight. A catchlight provides a specular highlight in the image of an eye.

7 (Only for correcting red eyes in pictures of humans) Drag the Darken slider to the right to darken the pupil area within the selection and the iris area outside the selection.

8 Deselect Show Overlay to turn off the selection and check your correction.

   Note: *Move between multiple affected eye areas by clicking the selection.*

Remove spots

The Spot Removal tool lets you repair a selected area of an image with a sample from another area.

1 Select the Spot Removal tool from the toolbar.

2 Select one of the following from the Type menu:

   Heal Matches the texture, lighting, and shading of the sampled area to the selected area.

   Clone Applies the sampled area of the image to the selected area.

3 (Optional) In the tool options under the Histogram, drag the Radius slider to specify the size of the area that the Spot Removal tool affects.

4 Move the Spot Removal tool into the photo and click the part of the photo to retouch. A red-and-white dashed circle appears over the selected area. The green-and-white dashed circle designates the sampled area of the photo used to clone or heal.

5 Do any of the following:

- To specify the sampled area, drag inside the green-and-white circle to move it to another area of the image.
- To specify the selected area being cloned or healed, drag inside the red-and-white circle.
- To adjust the size of the circles, move the pointer over the edge of either circle until it changes to a double-pointing arrow, and then drag to make both circles larger or smaller.
- To cancel the operation, press Backspace (Windows) or Delete (Mac OS).

Repeat this procedure for each area of the image that needs retouching. To remove all sample areas and start over, click the Clear All button in the tool options.

Sharpening and noise reduction in Camera Raw

Sharpen photos

The sharpening controls on the Detail tab adjust edge definition in the image. The Adjustment Brush tool and Graduated Filter tool use the Radius, Detail, and Masking values when local sharpening is applied.

Use the Apply Sharpening To option in the Camera Raw preferences to specify whether sharpening is applied to all images or just to previews.

To open preferences from within Camera Raw, click the Open Preferences Dialog button in the toolbar.

1 Zoom the preview image to at least 100%.

2 In the Detail tab, adjust any of these controls:

Amount Adjusts edge definition. Increase the Amount value to increase sharpening. A value of zero (0) turns off sharpening. In general, set Amount to a lower value for cleaner images. The adjustment is a variation of Unsharp Mask, which locates pixels that differ from surrounding pixels based on the threshold you specify and increases the pixels' contrast by the amount you specify. When opening a camera raw image file, the Camera Raw plug-in calculates the threshold to use based on camera model, ISO, and exposure compensation.

Radius Adjusts the size of the details that sharpening is applied to. Photos with fine details generally need a lower setting. Photos with larger details can use a larger radius. Using too large a radius generally results in unnatural-looking results.

Detail Adjusts how much high-frequency information is sharpened in the image and how much the sharpening process emphasizes edges. Lower settings primarily sharpen edges to remove blurring. Higher values are useful for making the textures in the image more pronounced.

Masking Controls an edge mask. With a setting of zero (0), everything in the image receives the same amount of sharpening. With a setting of 100, sharpening is mostly restricted to those areas near the strongest edges. Press Alt

(Windows) or Option (Mac OS) while dragging this slider to see the areas to be sharpened (white) versus the areas masked out (black).

3 (Optional) To apply the newest sharpening algorithms to images, click the Update To Current Process (2012) button in the lower-right corner of the image preview.

Reduce noise

The Noise Reduction section of the Detail tab has controls for reducing *image noise*, the extraneous visible artifacts that degrade image quality. Image noise includes luminance (grayscale) noise, which makes an image look grainy, and chroma (color) noise, which is visible as colored artifacts in the image. Photos taken with high ISO speeds or less-sophisticated digital cameras can have noticeable noise.

Note: *When making noise reduction adjustments, first zoom in on the preview image to at least 100% to see the noise reduction previewed.*

Note: *If the Luminance Detail, Luminance Contrast, and Color Detail sliders are dimmed, click the Update To Current Process (2012) button in the lower-right corner of the image.*

Luminance Reduces luminance noise.

Luminance Detail Controls the luminance noise threshold. Useful for noisy photos. Higher values preserve more detail but can produce noisier results. Lower values produce cleaner results but also remove some detail.

Luminance Contrast Controls the luminance contrast. Useful for noisy photos. Higher values preserve contrast but can produce noisy blotches or mottling. Lower values produce smoother results but can also have less contrast.

Color Reduces color noise.

Color Detail Controls the color noise threshold. Higher values protect thin, detailed color edges but can result in color specking. Lower values remove color speckles but can result in color bleeding.

For video tutorials about reducing noise in Camera Raw, see:

- Better noise reduction in Photoshop by Matt Kloskowski
- Lens correction and noise reduction with Adobe Camera Raw by Russell Brown

Correct lens distortions in Camera Raw

About lens corrections

Camera lenses can exhibit different types of defects at certain focal lengths, f-stops, and focus distances. You can correct for these apparent distortions and aberrations using the Lens Corrections tab of the Camera Raw dialog box.

Vignetting causes the edges, especially the corners, of an image to be darker than the center. Use controls in the Lens Vignetting section of the Lens Corrections tab to compensate for vignetting.

Barrel distortion causes straight lines to appear to bow outward.

Pincushion distortion causes straight lines to appear to bend inward.

Chromatic aberration is caused by the failure of the lens to focus different colors to the same spot. In one type of chromatic aberration, the image from each color of light is in focus, but each image is a slightly different size. Another type of chromatic artifact affects the edges of specular highlights, such as those found when light reflects off water or polished metal. This situation usually results in a purple fringe around each specular highlight.

Correct image perspective and lens flaws automatically

The options in the nested Profile tab of the Lens Corrections tab of the Camera Raw dialog box correct distortions in common camera lenses. The profiles are based on Exif metadata that identifies the camera and lens that captured the photo, and the profiles compensate accordingly.

1 In the nested Profile tab of the Lens Corrections tab, select Enable Lens Profile Corrections.

2 If Camera Raw does not find a suitable profile automatically, selecte a Make, Model, and Profile.

__Note:__ Some cameras have only one lens, and some lenses have only one profile. The lenses that are available depend on whether you're adjusting a raw or a non-raw file. For tips for working with lens profiles and a list of supported lenses, see the support article Lens profile support. To create custom profiles, use the Adobe Lens Profile Creator.

3 If desired, customize the correction applied by the profile by using the Amount sliders:

Distortion The default value 100 applies 100% of the distortion correction in the profile. Values over 100 apply greater correction to the distortion; values under 100 apply less correction to the distortion.

Chromatic Aberration The default value 100 applies 100% of the chromatic aberration correction in the profile. Values over 100 apply greater correction to color fringing; values under 100 apply less correction to color fringing.

Vignetting The default value 100 applies 100% of the vignetting correction in the profile. Values over 100 apply greater correction to vignetting; values under 100 apply less correction to vignetting.

4 (Optional) To apply your changes to the default profile, choose Setup > Save New Lens Profile Defaults.

Correct image perspective and lens flaws manually

Transform and vignette corrections can be applied to original and cropped photos. Lens vignettes adjust exposure values to brighten dark corners.

1 Click the nested Manual tab of the Lens Corrections tab of the Camera Raw dialog box.

2 Under Transform, adjust any of the following:

Distortion Drag to the right to correct barrel distortion and straighten lines that bend away from the center. Drag to the left to correct pincushion distortion and straighten lines that bend toward the center.

Vertical Corrects perspective caused by tilting the camera up or down. Makes vertical lines appear parallel.

Horizontal Corrects perspective caused by angling the camera left or right. Makes horizontal lines parallel.

Rotate Corrects for camera tilt.

Scale Adjusts the image scale up or down. Helps to remove empty areas caused by perspective corrections and distortions. Displays areas of the image that extend beyond the crop boundary.

3 Under Chromatic Aberration, adjust any of the following:

Fix Red/Cyan Fringe Adjusts the size of the red channel relative to the green channel.

Fix Blue/Yellow Fringe Adjusts the size of the blue channel relative to the green channel.

Zoom in on an area that contains very dark or black detail against a very light or white background. Look for color fringing. To more clearly see the color fringing, press Alt (Windows) or Option (Mac OS) as you move a slider to hide any color fringe corrected by the other color slider.

Defringe Choose All Edges to correct color fringing for all edges, including any sharp change in color values. If choosing All Edges results in thin gray lines or other undesired effects, choose Highlight Edges to correct color fringing only in the edges of highlighting where fringing is most likely to occur. Choose Off to turn off defringing.

4 Under Lens Vignetting adjust the following:

Amount Move the Amount slider to the right (positive values) to lighten the corners of the photo. Move the slider to the left (negative values) to darken the corners of the photo.

Midpoint Drag the Midpoint slider to the left (lower value) to apply the Amount adjustment to a larger area away from the corners. Drag the slider to the right (higher value) to restrict the adjustment to an area closer to the corners.

Correct Chromatic Aberration in Camera Raw 7.1

Camera Raw 7.1 provides a checkbox to automatically correct blue-yellow and red-green fringes (lateral chromatic aberration). Slider controls correct purple/magenta and green aberration (axial chromatic aberration). Axial chromatic aberration often occurs in images made with large apertures.

Remove red-green and blue-yellow color shifts

- In the Color tab of the Lens Correction panel, select the Remove Chromatic Aberration checkbox.

Remove global purple/magenta and green fringes

In the Color tab of the Lens Correction panel, adjust the purple and green Amount sliders. The higher the amount, the more color defringing. Take care not apply an adjustment that affects purple or green objects in your image.

You can adjust the affected purple or green hue range using the Purple Hue and the Green Hue sliders. Drag either end-point control to expand or decrease the range of affected colors. Drag between the end point controls to move the hue range. The minimum space between end points is ten units. The default spacing for the green sliders is narrow to protect green/yellow image colors, like foliage.

Note: *You can protect edges of purple and green objects using the local adjustment brush.*

Press the Alt/Option key as you drag any of the sliders to help visualize the adjustment. The fringe color becomes neutral as you drag to remove the color.

Remove local color fringes

Local brush and gradient adjustments remove fringes of all colors. Local defringe is available for Process Version 2012 only.

- Select the brush or gradient tools and drag in the image.
- Adjust the Defringe slider. A positive value removes the color fringe. Negative values protect image areas from defringing that you apply globally. A value of -100 protects the area from any defringing. For example, applying a strong global purple defringe can desaturate or alter edges of purple objects in your image. Painting with Defringe -100 over those areas protects them and keeps them at their original color.

For best results, perform any Transform lens corrections before applying local color defringe adjustments.

Make color and tonal adjustments in Camera Raw

Histogram and RGB levels

A *histogram* is a representation of the number of pixels at each luminance value in an image. A histogram that has nonzero values for each luminance value indicates an image that takes advantage of the full tonal scale. A histogram that doesn't use the full tonal range corresponds to a dull image that lacks contrast. A histogram with a spike at the left side indicates shadow clipping; a histogram with a spike on the right side indicates highlight clipping.

Select Shadows or Highlights to see in the preview image which pixels are being clipped. For more information, see .

One common task for adjusting an image is to spread out the pixel values more evenly from left to right on the histogram, instead of having them bunched up at one end or the other.

A histogram is made up of three layers of color that represent the red, green, and blue color channels. White appears when all three channels overlap. Yellow, magenta, and cyan appear when two of the RGB channels overlap (yellow equals the red + green channels, magenta equals the red + blue channels, and cyan equals the green + blue channels).

The histogram changes automatically as you adjust the settings in the Camera Raw dialog box.

The RGB values of the pixel under the pointer (in the preview image) appear below the histogram.

Note: *You can also use the Color Sampler tool to place up to nine color samplers in the preview image. The RGB values appear above the preview image. To remove a color sampler, Alt-click (Windows) or Option-click (Mac OS) it. To clear the color samplers, click Clear Samplers.*



Preview highlight and shadow clipping

Clipping occurs when the color values of a pixel are higher than the highest value or lower than the lowest value that can be represented in the image. Overly bright values are clipped to output white, and overly dark values are clipped to output black. The result is a loss of image detail.

- To see which pixels are being clipped with the rest of the preview image, select Shadows or Highlights options at the top of the histogram. Or press U to see shadow clipping, O to see highlight clipping.
- To see only the pixels that are being clipped, press Alt (Windows) or Option (Mac OS) while dragging the Exposure, Recovery, or Blacks sliders.

For the Exposure and Recovery sliders, the image turns black, and clipped areas appear white. For the Blacks slider, the image turns white and clipped areas appear black. Colored areas indicate clipping in one color channel (red, green, blue) or two color channels (cyan, magenta, yellow).

Note: *In some cases, clipping occurs because the color space you are working in has a gamut that is too small. If your colors are being clipped, consider working in a color space with a large gamut, such as ProPhoto RGB.*

White balance controls

To adjust the white balance, identify which objects in the image you want to be neutral-colored (white or gray), and then adjust the colors to make those objects neutral. A white or gray object in a scene takes on the color cast by the ambient light or flash used to shoot the picture. When you use the White Balance tool to specify an object that you want white or gray, Camera Raw can determine the color of the light in which the scene was shot and then adjust for scene lighting automatically.

Color temperature (in Kelvins) is used as a measure of scene lighting. Natural and incandescent light sources give off light in a predictable distribution according to their temperature.

A digital camera records the white balance at the time of exposure as a metadata entry. The Camera Raw plug-in reads this value and makes it the initial setting when you open the file in the Camera Raw dialog box. This setting usually yields the correct color temperature, or nearly so. You can adjust the white balance if it is not right.

Note: *Not all color casts are a result of incorrect white balance. Use the DNG Profile Editor to correct a color cast that remains after the white balance is adjusted. See Adjust color rendering for your camera in Camera Raw.*

The Basic tab in the Camera Raw dialog box has three controls for correcting a color cast in an image:

White Balance Camera Raw applies the white balance setting and changes the Temperature and Tint properties in the Basic tab accordingly. Use these controls to fine-tune the color balance.

As Shot Uses the camera's white balance settings, if they are available.

Auto Calculates the white balance based on the image data.

Camera raw and DNG files also have the following white balance settings: Daylight, Cloudy, Shade, Tungsten, Fluorescent, and Flash.

Note: *If Camera Raw doesn't recognize the white balance setting of a camera, choosing As Shot is the same as choosing Auto.*

Temperature Sets the white balance to a custom color temperature. Decrease Temperature to correct a photo taken with a lower color temperature of light; the Camera Raw plug-in makes the image colors bluer to compensate for the lower color temperature (yellowish) of the ambient light. Conversely, increase Temperature to correct a photo taken with a higher color temperature of light; the image colors become warmer (yellowish) to compensate for the higher color temperature (bluish) of the ambient light.

Note: *The range and units for the Temperature and Tint controls are different when you are adjusting a TIFF or JPEG image. For example, Camera Raw provides a true-temperature adjustment slider for raw files from 2,000 Kelvin to 50,000 Kelvin. For JPEG or TIFF files, Camera Raw attempts to approximate a different color temperature or white balance. Because the original value was already used to alter the pixel data in the file, Camera Raw does not provide the true Kelvin temperature scale. In these instances, an approximate scale of -100 to 100 is used in place of the temperature scale.*



A *Moving the Temperature slider to the right corrects a photo taken with a higher color temperature of light* ***B*** *Moving the Temperature slider to the left corrects a photo taken with a lower color temperature of light* ***C*** *Photo after color temperature adjustment*

Tint Sets the white balance to compensate for a green or magenta tint. Decrease Tint to add green to the image; increase Tint to add magenta.

To adjust the white balance quickly, select the White Balance tool and then click an area in the image that you want to be a neutral gray. The Temperature and Tint properties adjust to make the selected color exactly neutral (if possible). If you're clicking whites, choose a highlight area that contains significant white detail rather than a specular highlight. You can double-click the White Balance tool to reset White Balance to As Shot.

Adjust tone

You adjust the image tonal scale using the tone controls in the Basic tab.

When you click Auto at the top of the tone controls section of the Basic tab, Camera Raw analyzes the image and makes automatic adjustments to the tone controls.

You can also apply automatic settings separately for individual tone controls. To apply an automatic adjustment to an individual tone control, such as Exposure or Contrast, press Shift and double-click the slider. To return an individual tone control to its original value, double-click its slider.

When you adjust tone automatically, Camera Raw ignores any adjustments previously made in other tabs (such as fine-tuning of tone in the Tone Curves tab). For this reason, apply automatic tone adjustments first—if at all—to get an initial approximation of the best settings for your image. If you are careful during shooting and have deliberately shot with different exposures, you probably don't want to undo that work by applying automatic tone adjustments. On the other hand, you can always try clicking Auto and then undo the adjustments if you don't like them.

Previews in Adobe Bridge use the default image settings. If you want the default image settings to include automatic tone adjustments, select Apply Auto Tone Adjustments in the Default Image settings section of the Camera Raw preferences.

Note: *If you are comparing images based on their previews in Adobe Bridge, leave the Apply Auto Tone Adjustments preference deselected, which is the default. Otherwise, you'll be comparing images that have already been adjusted.*

As you make adjustments, keep an eye on the end points of the histogram, or use the shadow and highlight clipping previews.

While moving the tone controls sliders, hold down Alt (Windows) or Option (Mac OS) to preview where highlights or shadows are clipped. Move the slider until clipping begins, and then reverse the adjustment slightly. (For more information, see .)

- To manually adjust a tone control, drag the slider, type a number in the box, or select the value in the box and press the Up or Down arrow key.
- To reset a value to its default, double-click the slider control.

Note: *The tone controls that appear in the Basic panel depend on whether you are working in Process Version PV2012, PV2010, or PV2003, as noted.*

Exposure (All) Adjusts the overall image brightness. Adjust the slider until the photo looks good and the image is the desired brightness. Exposure values are in increments equivalent to aperture values (f-stops) on a camera. An adjustment of +1.00 is similar to opening the aperture 1 stop. Similarly, an adjustment of -1.00 is like closing the aperture 1 stop.

Contrast (All) Increases or decreases image contrast, mainly affecting midtones. When you increase contrast, the middle-to-dark image areas become darker, and the middle-to-light image areas become lighter. The image tones are inversely affected as you decrease contrast.

Highlights (PV2012) Adjusts bright image areas. Drag to the left to darken highlights and recover "blown out" highlight details. Drag to the right to brighten highlights while minimizing clipping.

Shadows (PV2012) Adjusts dark image areas. Drag to the left to darken shadows while minimizing clipping. Drag to the right to brighten shadows and recover shadow details.

Whites (PV2012) Adjusts white clipping. Drag to the left to reduce clipping in highlights. Drag to the right to increase highlight clipping. (Increased clipping may be desirable for specular highlights, such as metallic surfaces.)

Blacks (PV2012) Adjusts black clipping. Drag to the left to increase black clipping (map more shadows to pure black). Drag to the right to reduce shadow clipping.

Blacks (PV2010 and PV2003) Specifies which image values map to black. Moving the slider to the right increases the areas that become black, sometimes creating the impression of increased image contrast. The greatest effect is in the shadows, with much less change in the midtones and highlights.

Recovery (PV2010 and PV2003) Attempts to recover details from highlights. Camera Raw can reconstruct some details from areas in which one or two color channels are clipped to white.

Fill Light (PV2010 and PV2003) Attempts to recover details from shadows, without brightening blacks. Camera Raw can reconstruct some details from areas in which one or two color channels are clipped to black. Using Fill Light is like using the shadows portion of the Photoshop Shadow/Highlight filter or the After Effects Shadow/Highlight effect.

Brightness (PV2010 and PV2003) Adjusts the brightness or darkness of the image, much as the Exposure property does. However, instead of clipping the image in the highlights or shadows, Brightness compresses the highlights and expands the shadows when you move the slider to the right. Often, the best way to use this control is to set the overall tonal scale by first setting Exposure, Recovery, and Blacks; then set Brightness. Large Brightness adjustments can affect shadow or highlight clipping, so you may want to readjust the Exposure, Recovery, or Blacks property after adjusting Brightness.

Learn More: Watch the video tutorials What's New in Camera Raw by Matt Kloskowski and Why You Should Set Photoshop to Open Your JPGs in Adobe Camera RAW by Terry White.

Fine-tune tone curves

Use the controls in the Tone Curve tab to fine-tune images after you've made tone adjustments in the Basic tab. The tone curves represent changes made to the tonal scale of an image. The horizontal axis represents the original tone values of the image (input values), with black on the left and progressively lighter values toward the right. The vertical axis represents the changed tone values (output values), with black on the bottom and progressing to white at the top.

If a point on the curve moves up, the output is a lighter tone; if it moves down, the output is a darker tone. A straight, 45-degree line indicates no changes to the tone response curve: The original input values exactly match the output values.

Use the tone curve in the nested Parametric tab to adjust the values in specific tonal ranges in the image. The areas of the curve affected by the region properties (Highlights, Lights, Darks, or Shadows) depend on where you set the split controls at the bottom of the graph. The middle region properties (Darks and Lights) mostly affect the middle region of the curve. The Highlight and Shadows properties mostly affect the ends of the tonal range.

? To adjust tone curves, do any of the following:

- Drag the Highlights, Lights, Darks, or Shadows slider in the nested Parametric tab. You can expand or contract the curve regions that the sliders affect by dragging the region divider controls along the horizontal axis of the graph.
- Drag a point on the curve in the nested Point tab. As you drag the point, the Input and Output tonal values are displayed beneath the tone curve.
- Choose an option from the Curve menu in the nested Point tab. The setting you choose is reflected in the Point tab, but not in the settings in the Parametric tab. Medium Contrast is the default setting.
- Select the Parametric Curve Targeted Adjustment tool in the toolbar and drag in the image. The Parametric Curve Targeted Adjustment tool adjusts the Highlights, Lights, Darks, or Shadows curve region based on the values in the image where you click.

Note: *The Targeted Adjustment tool does not affect point curves.*

Clarity, Vibrance, and Saturation controls

You can change the color saturation of all colors by adjusting the Clarity, Vibrance, and Saturation controls on the Basic tab. (To adjust saturation for a specific range of colors, use the controls on the HSL / Grayscale tab.)

Clarity Adds depth to an image by increasing local contrast, with greatest effect on the midtones. This setting is like a large-radius unsharp mask. When using this setting, it is best to zoom in to 100% or greater. To maximize the effect, increase the setting until you see halos near the edge details of the image and then reduce the setting slightly.

Vibrance Adjusts the saturation so that clipping is minimized as colors approach full saturation. This setting changes the saturation of all lower-saturated colors with less effect on the higher-saturated colors. Vibrance also prevents skin tones from becoming oversaturated.

Saturation Adjusts the saturation of all image colors equally from -100 (monochrome) to +100 (double the saturation).

HSL / Grayscale controls

You can use the controls in the HSL / Grayscale tab to adjust individual color ranges. For example, if a red object looks too vivid and distracting, you can decrease the Reds values in the nested Saturation tab.

The following nested tabs contain controls for adjusting a color component for a specific color range:

Hue Changes the color. For example, you can change a blue sky (and all other blue objects) from cyan to purple.

Saturation Changes how vivid or pure the color is. For example, you can change a sky from gray to highly saturated blue.

Luminance Changes the brightness of the color range.

If you select Convert To Grayscale, you see only one nested tab:

Grayscale Mix Use controls in this tab to specify the contribution of each color range to the grayscale version of the image.

Adjust color or tone using the Targeted Adjustment tool

The Targeted Adjustment tool allows you to make tonal and color corrections by dragging directly on a photo. Using the Targeted Adjustment tool, you can drag down on a blue sky to desaturate it, for example, or drag up on a red jacket to intensify its hue.

1. To make color adjustments with the Targeted Adjustment tool , click it in the toolbar and choose the type of correction you want to make: Hue, Saturation, Luminance, or Grayscale Mix. Then, drag in the image.

   Dragging up or right increases values; dragging down or left decreases values. Sliders for more than one color may be affected when you drag with the Targeted Adjustment tool. Selecting the Grayscale Mix Targeted Adjustment tool converts the image to grayscale.

2. To make tone curve adjustments using the Targeted Adjustment tool , click it in the toolbar and choose Parametric Curve. Then, drag in the image.

   The Parametric Curve Targeted Adjustment tool adjusts the Highlights, Lights, Darks, or Shadows curve region based on the values in the image where you click.

The keyboard shortcut T toggles the last Targeted Adjustment tool you used.

Tone a grayscale image

Use the controls in the Split Toning tab to color a grayscale image. You can add one color throughout the tonal range, such as a sepia appearance, or create a split tone result, in which a different color is applied to the shadows and the highlights. The extreme shadows and highlights remain black and white.

You can also apply special treatments, such as a cross-processed look, to a color image.

1 Select a grayscale image. (It can be an image that you converted to grayscale by selecting Convert To Grayscale in the HSL / Grayscale tab.)

2 In the Split Toning tab, adjust the Hue and Saturation properties for the highlights and shadows. Hue sets the color of the tone; Saturation sets the magnitude of the result.

3 Adjust the Balance control to balance the influence between the Highlight and Shadow controls. Positive values increase the influence of the Highlight controls; negative values increase the influence of the Shadow controls.

Edit HDR images in Camera Raw

In Camera Raw 7.1 or later, you can work with 16-, 24-, and 32-bit floating point images—often referred to as HDR (high dynamic range images). Camera Raw opens TIFF and DNG format HDR images. Make sure that the images are in process version 2012. (See Process versions in Camera Raw .)

You can use the Basic tab controls to edit HDR images. The Basic tab Exposure control has an expanded range when working with HDR images (+10 to -10).

When you are done editing, click Done or Open Image to open the image in Photoshop. The image opens as a 16-bit or 8-bit image, depending on how you have the Workflow Options set.

To open an HDR image in Camera Raw:

? In Bridge, select the image and choose File > Open In Camera Raw. In mini-Bridge, right-click the image (Ctlr-click on Mac) and choose Open With > Camera Raw.

For more information about HDR images, see High dynamic range images in Photoshop Help.

Process versions in Camera Raw

The process version is the technology that Camera Raw uses to adjust and render photos. Depending on which process version you use, different options and settings are available to you in the Basic tab and when you make local adjustments.

Process Version 2012 Images edited for the first time in Camera Raw 7 use process version 2012. PV2012 offers new tone controls and new tone-mapping algorithms for high-contrast images. With PV2012, you can adjust Highlights, Shadows, Whites, Blacks, Exposure, and Contrast in the Basic panel. You can also apply local corrections for white balance (Temp and Tint), Highlights, Shadows, Noise, and Moiré.

Process Version 2010 Images edited in Camera Raw 6 used PV2010 by default. PV2010 offers improved sharpening and noise-reduction from the previous process version, PV2003.

Process Version 2003 The original processing engine used by Camera Raw versions 5.x and earlier.

To take advantage of the newer processing, you can update previously edited photos to the current process version.

To update a photo to the Camera Raw 7 process (PV2012), do either of the following:

- Click the Update To Current Process button (the exclamation-point icon) in the lower-right corner of the image preview.
- In the Camera Calibration tab, choose Process > 2012 (Current).

To apply an older process version to a photo, go to the Camera Calibration tab and choose Process > 2010 or Process > 2003.

More Help topics

Make local adjustments in Camera Raw

Adjust color rendering for your camera in Camera Raw

For each camera model it supports, Camera Raw uses color profiles to process raw images. These profiles are produced by photographing color targets under standardized lighting conditions and are *not* ICC color profiles.

ACR version These profiles are compatible with older versions of Camera Raw and Lightroom. The version corresponds to the version of Camera Raw in which the profile first appeared. ACR profiles offer consistent behavior with legacy photos.

Adobe Standard Standard profiles significantly improve color rendering, especially in warm tones such as reds, yellows, and oranges, from earlier Adobe camera profiles.

Camera Matching Camera Matching profiles attempt to match the camera manufacturer's color appearance under specific settings. Use Camera Matching profiles if you prefer the color rendering offered by your camera manufacturer's software.

Both Adobe Standard and Camera Matching camera profiles are intended to serve as a starting point for further image adjustments. Therefore, use the profiles in conjunction with the color and tone controls in the Basic, Tone Curve, HSL / Grayscale, and other image adjustment tabs.

To manually install camera profiles, place them in the following locations:

Windows XP C:\Documents and Settings\All Users\Application Data\Adobe\CameraRaw\CameraProfiles

Windows Vista C:\ProgramData\Adobe\CameraRaw\CameraProfiles

Windows 7 C:\ProgramData\Adobe\CameraRaw\CameraProfiles

Mac OS /Library/Application Support/Adobe/CameraRaw/CameraProfiles

1 Step text

2 Step text

3 Step text

4 Step text

5 Step text

Apply a camera profile to images

1 To apply a camera profile, select it from the Camera Profile pop-up menu in the Camera Calibration tab of the Camera Raw dialog box.

   The Adobe Standard profile for a camera is named Adobe Standard. Camera Matching profiles include the prefix Camera in the profile name. The Camera Profile pop-up menu displays only profiles for your camera.

   If the only profile in the Camera Profile menu is Embedded, it means that you have selected a TIFF or JPEG image. Adobe Standard and Camera Matching profiles work only with raw images.

   Note: *If you have selected a raw file and Adobe Standardand Camera Matching profiles do not appear in the Camera Profilepop-up menu, download the latest Camera Raw update from the Digital camera raw file support page.*

2 Choose a profile from the Camera Profile pop-up menu in the Camera Calibration tab of the Camera Raw dialog box.

3 Click the Camera Raw Settings menu button and choose Save New Camera Raw Defaults from the menu.

Apply a profile to a group of images

1 Select the images in the Filmstrip view.

2 Choose a profile from the Camera Profile pop-up menu in the Camera Calibration tab of the Camera Raw dialog box.

3 Click the Synchronize button.

4 In the Synchronize dialog box, choose Synchronize > Camera Calibration, and then click OK.

Create a camera profile preset

If you find yourself often applying the same profile, you can work more efficiently by creating and applying a preset.

1 Choose a profile from the Camera Profile pop-up menu in the Camera Calibration tab of the Camera Raw dialog box.

2 Click the Camera Raw Settings menu button and choose Save Settings from the menu.

3 In the Save Settings dialog box, choose Subset > Camera Calibration, and then click OK.

4 Name your preset and click Save.

5 To apply the preset to a group of images, select the images and then choose Apply Preset > Preset Name from the Camera Raw Settings menu.

Customize profiles using the DNG Profile Editor

To improve color rendering or customize a camera profile, use the standalone DNG Profile Editor utility. For example, use the DNG Profile Editor to correct an unwanted color cast in a profile or to optimize colors for a specific application, such as studio portraits or fall foliage.

The DNG Profile Editor and documentation for it are available on Adobe Labs.

Note: *Leave the Camera Calibration tab sliders set to 0 when adjusting camera profiles with the DNG Profile Editor.*

More Help topics

Save, reset, and load Camera Raw settings

Apply saved Camera Raw settings

New features summary

Adobe Camera Raw 9.x is now available!
View the New Features Summary.

New feature

Enhanced feature

Adobe Camera Raw 8.7

Adobe Camera Raw 8.7 adds support for HiDPI monitors on Windows. Do the following to enable this feature:

1 Select Photoshop > Preferences > Experimental Features.

2 Select Scale UI 200% For High-Density Displays.

For more information, see Scale the UI 200% for high-density displays .

Adobe Camera Raw 8.5

You can now modify Graduated and Radial Filter masks using brush controls. Once you've added a mask, to access brush controls, select the Brush option next to New/Edit. Alternatively, use the Shift+K keyboard shortcut.

As appropriate, use the + and–brushes to add or remove from the existing Radial or Graduated Filter mask.

Note: *For a video description of the new brush controls for Graduated and Radial Filter masks, see Filter Brush in Adobe Camera Raw 8.5.*



Mask visualization is now available for Graduated and Radial Filters. Use the Mask option at the bottom of the local corrections pane. Alternatively, press Y to toggle the Mask setting.



New preview features

New per-panel default toggle button ( ):

- Click the per-panel toggle button ( ) to reset the panel to the default settings. The toggle button is next to the Before/After controls.

Support for several new cameras and lens profiles

Key issues addressed

- Image noise issues while applying spot healing to floating-point (HDR) images
- Issue while reading lossless compressed Nikon raw files (NEF files) from several Nikon camera models
- Issue that caused Fujifilm X-T1 raw images to appear too bright at high ISO settings when using Dynamic Range 200% and 400%. This fix may affect the appearance of existing images captured with this combination of settings. As a resolution, do the following:
  - Purge the Camera Raw cache through the Camera Raw Preferences dialog
  - Review images shot at ISO settings higher than 1600 for unexpected brightness changes

Adobe Camera Raw 8.4

Adobe Camera Raw 8.4 provides advanced Preview controls that let you quickly compare the Before/After states of an image:

Save the current settings as the Before state of the image Swap the current settings and the saved Before state settings. The current settings are saved as the Before state and the settings previously saved as the Before state are applied to the image. Select a mode for displaying the preview:

• See only After settings applied to the image • Before/After settings applied to the left and right halves of the image • Before/After settings applied to the whole image and displayed side-by-side • Before/After settings applied to the top and bottom halves of the image • Before/After settings applied to the whole image and displayed vertically for quick comparison

For more information, see

Adobe Camera Raw 8.4 lets you correct red eyes in both human and pet eyes. In Adobe Camera Raw, click the Red Eye Removal icon ( ) and then select Pet Eye from the Type pop up menu. For more information, see

Adobe Camera Raw 8.4 provides camera color profiles for Fujifilm X-Trans sensor cameras. These color matching profiles include Fujifilm Provia, Fujifilm Velvia, Fujifilm Astia, and Fujifilm Monochrome.

Follow these steps:

1. Ensure that you're working with an image taken using the X-Trans sensor.
2. In Adobe Camera Raw, click the Camera Calibration icon ( ).
3. Select the desired profile from the Camera Profile pop-up menu.

Adobe Camera Raw 8.3

Adobe Camera Raw 8.3 offers the following enhancements:

Automatic straightening of an image through one of the following three interactions:

- Double-click the Straighten tool ( ) in the toolbar.
- With the Straighten tool selected, double-click anywhere in the preview image.

- With the Crop tool selected, press the Command key (on Mac) or Ctrl key (on Windows) to temporarily switch to the Straighten tool. Now, double-click anywhere within the preview image.

Whites and Blacks now support Auto Levels–like functionality when you double-click the sliders while keeping the Shift key pressed (Shift-double-click).

Auto Temperature and Auto Tint functionality. Shift-double-click within the image preview to invoke this functionality.

Option to choose a background color for the work area and toggle the visibility of the hairline frame around the image. Right-click outside the image in the work area and select an option from the pop-up menu.

Option-click shortcut support for the Synchronize, New Preset, Save Settings, and Copy/Paste (Bridge) dialog boxes. When you option-click a checkbox, it is selected exclusively. You can Option-click again to toggle to the previous checkbox state.

Adobe Camera Raw 8.1 and 8.2

Note: *For detailed information about the enhancements in this section, see Adobe Camera Raw Enhancements | ACR 8.1 and 8.2.*

Soft proofing from within the ACR dialog. You can now choose an ICC color profile and simulate additional factors like rendering intent and the paper and ink. These options can now be applied to the photograph through the ACR dialog, even before you open it in Photoshop.

ICC-based color spaces support from within the ACR dialog. The ACR dialog now allows you to preview your photographs with arbitrary ICC-based output color spaces. Available color spaces include grayscale, RGB, Lab, and CMYK color spaces.

Image sizing is now more flexible, with the ACR dialog providing multiple options to resize a photograph. These options are placed within the Image Sizing section, immediately beneath the Color Space section.

Presets. Store commonly used settings as a preset. Save frequently applied settings from the Workflow Options or Save Options dialog as a preset, and then apply the preset on multiple photos with ease.

Cropping follows a modified workflow with the introduction of the new Image Sizing workflow. Use the Image Sizing option in the Workflow Options and Save Options dialogs to specify a desired absolute image size.

Camera Raw 7 plug-in

Tap into the latest noise, color, and dynamic range controls.

Camera Raw 7 plug-in

Enhancing Raw images

Draw upon the full range of image data.

Enhancing Raw images

Chapter 10: Repair and restoration

Content-Aware Patch and Move

Legacy: For information about using the Patch tool in versions earlier than Photoshop CS6, see Patch an area.

Content-Aware Patch

The Patch tool is used to remove unwanted image elements. The Content-Aware option in the Patch tool synthesizes nearby content for seamless blending with the surrounding content.

The results are similar to Use Content-aware, pattern, or history fills, but using this tool gives you the flexibility to choose the source area.

1 In the toolbar, hold down the **Spot Healing Brush** and select the Patch tool .

2 In the options bar, do the following:

Patch Choose Content-Aware to select the content-aware option.

Structure Enter a value between 1 and 7 to specify how closely the patch should reflect existing image patterns. If you enter 7, the patch adheres very strongly to existing image patterns. If you enter 1, the patch adheres very loosely to the existing image patterns.

Color Enter a value between 0 and 10 to specify the extent to which you want Photoshop to apply algorithmic color-blending to the patch. If you enter 0, color blending is disabled. A Color value of 10 applies maximum color blending.

Sample All Layers Enable this option to create the result of the move in another layer using information from all layers. Select the target layer in the Layers panel.

3 Select an area to replace on the image. You can use the Patch tool to draw a selection, or use any of the other Selection tools as well.

4 Drag the selection over the area you want to generate a fill from.

Content-Aware Move

Use the Content-Aware Move tool to select and move a part of a picture. The image is recomposed, and the hole left behind is filled using matching elements from the picture. You do not need to carry out intensive edits involving layers and complex selections.

You can use the Content-Aware Move tool in two modes:

- Use the Move mode to place objects in different locations (most effectively when the background remains similar).

- Use the Extend mode to expand or contract objects such as hair, trees, or buildings. To best extend architectural objects, use photos shot on a parallel plane, rather than at an angle.

1 In the toolbar, hold down the **Spot Healing Brush** and select the **Content-Aware Move** tool .

2 In the options bar, do the following:

Mode Use the Move mode to place selected objects at at a different location. Use the Extend mode to expand or contract objects.

Structure Enter a value between 1 and 7 to specify how closely the patch should reflect existing image patterns. If you enter 7, the patch adheres very strongly to existing image patterns. If you enter 1, the patch adheres very loosely to the existing image patterns.

Color Enter a value between 0 and 10 to specify the extent to which you want Photoshop to apply algorithmic color-blending to the patch. If you enter 0, color blending is disabled. A Color value of 10 applies maximum color blending.



A Without color blending *B With color blending*

Sample All Layers Enable this option to use information from all layers to create the result of the move in the selected layer. Select the target layer in the Layers panel.

Transform On Drop When this option is enabled, you can scale the part of the image that you've just moved to its new location. Simply adjust the resizing handles for the moved part of the image.

3 Select an area to move or extend. You can use the Move tool to draw a selection, or use any of the other selection tools as well.

4 Drag the selection to the area you want to place the object.

More Help topics

Video | Remove objects from photos

Tutorial | Retouch photos

Retouch and repair photos

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Using a variety of Photoshop tools, you can easily touch up blemishes, whiten teeth, correct red eye, and fix many other imperfections in your images.

About the Clone Source panel

The Clone Source panel (Window > Clone Source) has options for the Clone Stamp tools or Healing Brush tools. You can set up to five different sample sources and quickly select the one you need without resampling each time you change to a different source. You can view an overlay of your sample source to make it easier to clone the source in a specific location. You can also scale or rotate the sample source to better match the size and orientation of the cloning destination.

For timeline-based animations, the Clone Source panel also has options for specifying the frame relationship between the sample source video/animation frame and the target video/animation frame. See also Cloning content in video and animation frames.

Retouch with the Clone Stamp tool

The Clone Stamp tool paints one part of an image over another part of the same image or over another part of any open document that has the same color mode. You can also paint part of one layer over another layer. The Clone Stamp tool is useful for duplicating objects or removing a defect in an image.

You can also use the Clone Stamp tool to paint content on video or animation frames. See also Cloning content in video and animation frames.

To use the Clone Stamp tool, you set a sampling point on the area you want to copy (clone) the pixels from and paint over another area. To paint with the most current sampling point whenever you stop and resume painting, select the Aligned option. Deselect the Aligned option to paint starting from the initial sampling point no matter how many times you stop and resume painting.

You can use any brush tip with the Clone Stamp tool, which gives you precise control over the size of the clone area. You can also use opacity and flow settings to control the paint application to the cloned area.

1 Select the Clone Stamp tool .

2 Choose a brush tip and set brush options for the blending mode, opacity, and flow in the options bar.

3 To specify how you want to align the sampled pixels and how to sample data from the layers in your document, set any of the following in the options bar:

Aligned Samples pixels continuously, without losing the current sampling point, even if you release the mouse button. Deselect Aligned to continue to use the sampled pixels from the initial sampling point each time you stop and resume painting.

Sample Samples data from the layers you specify. To sample from the active layer and visible layers below it, choose Current And Below. To sample only from the active layer, choose Current Layer. To sample from all visible layers, choose All Layers. To sample from all visible layers except adjustment layers, choose All Layers and click the Ignore Adjustment Layers icon to the right of the Sample pop-up menu.

4 Set the sampling point by positioning the pointer in any open image and Alt-clicking (Windows) or Option-clicking (Mac OS).

Note: *Make sure you are not working on an adjustment layer. The Clone Stamp tool does not work on adjustment layers.*

5 (Optional) In the Clone Source panel, click a clone source button and set an additional sampling point.

You can set up to five different sampling sources. The Clone Source panel saves the sampled sources until you close the document.

6 (Optional) Do any of the following in the Clone Source panel:

- To scale or rotate the source that you're cloning, enter a value for W (width), H (height), or the rotation in degrees .
- To reverse the direction of the source (good for mirroring features like eyes), click the Flip Horizontal or Flip Vertical buttons.
- To show an overlay of the source that you're cloning, select Show Overlay and specify the overlay options.

Note: *Select Clipped to clip the overlay to the brush size.*

7 Drag over the area of the image you want to correct.

Set sample sources for cloning and healing

Using the Clone Stamp or Healing Brush tool, you can sample sources in the current document or any open document in Photoshop.

When cloning video or animation, you can set sampling points in the current frame you're painting or sample sources in a different frame, even if the frame is in a different video layer or in a different open document.

You can set up to five different sampling sources at a time in the Clone Source panel. The Clone Source panel saves the sampling sources until you close the document.

1 To clone video or animation frames, open the Animation panel (if you're not cloning video or animation frames, skip to step 2). Select the timeline animation option and move the current-time indicator to the frame with the source you want to sample.

2 To set the sampling point, select the Clone Stamp tool and Alt-click (Windows) or Option-click (Mac OS) in any open document window.

3 (Optional) To set another sampling point, click a different Clone Source button in the Clone Source panel.

You can change the sampling source for a Clone Source button by setting a different sampling point.

Scale or rotate the sample source

1 Select the Clone Stamp or Healing Brush tool and set one or more source samples.

2 In the Clone Source panel, select a clone source and then do any of the following:

- To scale the sample source, enter a percentage value for W (width) or H (height) or scrub W or H. The default is to constrain proportions. To adjust the dimensions independently or restore the constrain option, click the Maintain Aspect Ratio button .
- To rotate the sample source, enter a degree value or scrub the Rotate The Clone Source icon .
- To reset the sample source to its original size and orientation, click the Reset Transform button .

Adjust the sample source overlay options

Adjust the sample source overlay options to see the overlay and underlying images better when painting with the Clone Stamp and Healing Brush tools.

To temporarily display the overlay while painting with the Clone Stamp tool, press Alt+Shift (Windows) or Option+Shift (Mac OS). The brush changes temporarily to the Move Source Overlay tool. Drag to move the overlay to another location.

? In the Clone Source panel, select Show Overlay and do any of the following:

- To hide the overlay while you apply the paint strokes, select Auto Hide.
- To clip the overlay to the brush size, enable the Clipped option.
- To set the opacity of the overlay, enter a percentage value in the Opacity text box.
- To set the appearance of the overlay, choose either the Normal, Darken, Lighten, or Difference blending mode from the pop-up menu at the bottom of the Clone Source panel.
- To invert the colors in the overlay, select Invert.

To help align identical areas in the source overlay and underlying image, set Opacity to 50%, select Invert, and deselect Clipped. Matching image areas will appear solid gray when aligned.

Specify the clone source offset

When using the Clone Stamp tool or Healing Brush tool, you can paint with the sampled source anywhere in the target image. The overlay options help you visualize where you want to paint. However, if you paint in a specific location relative to the sampling point, you can specify the x and y pixel offset.

? In the Clone Source panel, select the source you want to use and enter the x and y pixel values for the Offset option.

Retouch with the Healing Brush tool

The Healing Brush tool lets you correct imperfections, causing them to disappear into the surrounding image. Like the cloning tools, you use the Healing Brush tool to paint with sampled pixels from an image or pattern. However, the Healing Brush tool also matches the texture, lighting, transparency, and shading of the sampled pixels to the pixels being healed. As a result, the repaired pixels blend seamlessly into the rest of the image.

The Healing Brush tool can be applied to video or animation frames.

1 Select the Healing Brush tool .

2 Click the brush sample in the options bar and set brush options in the pop-up panel:

Note: If you're using a pressure-sensitive digitizing tablet, choose an option from the Size menu to vary the size of the healing brush over the course of a stroke. Choose Pen Pressure to base the variation on the pen pressure. Choose Stylus Wheel to base the variation on the position of the pen thumbwheel. Choose Off if you don't want to vary the size.

Mode Specifies the blending mode. Choose Replace to preserve noise, film grain, and texture at the edges of the brush stroke when using a soft-edge brush.

Source Specifies the source to use for repairing pixels. Sampled to use pixels from the current image, or Pattern to use pixels from a pattern. If you chose Pattern, select a pattern from the Pattern pop-up panel.

Aligned Samples pixels continuously, without losing the current sampling point, even if you release the mouse button. Deselect Aligned to continue to use the sampled pixels from the initial sampling point each time you stop and resume painting.

Sample Samples data from the layers you specify. To sample from the active layer and visible layers below it, choose Current And Below. To sample only from the active layer, choose Current Layer. To sample from all visible layers, choose All Layers. To sample from all visible layers except adjustment layers, choose All Layers and click the Ignore Adjustment Layers icon to the right of the Sample pop-up menu.

Diffusion Controls how quickly the pasted region adapts to the surrounding image. Select a lower value for images with grain or fine details, or a higher value for smooth images.

3 Set the sampling point by positioning the pointer over an area of the image and Alt-clicking (Windows) or Option-clicking (Mac OS).

Note: If you are sampling from one image and applying to another, both images must be in the same color mode unless one of the images is in Grayscale mode.

4 (Optional) In the Clone Source panel, click a clone source button and set an additional sampling point.

You can set up to five different sampling sources. The Clone Source panel remembers the sampled sources until you close the document you're editing.

5 (Optional) In the Clone Source panel, click a clone source button to select the sampled source you want.

6 (Optional) Do any of the following in the Clone Source panel:

- To scale or rotate the source that you're cloning, enter a value for W (width), H (height), or the rotation in degrees .
- To show an overlay of the source that you're cloning, select Show Overlay and specify the overlay options.

7 Drag in the image.

The sampled pixels are melded with the existing pixels each time you release the mouse button.

If there is a strong contrast at the edges of the area you want to heal, make a selection before you use the Healing Brush tool. The selection should be bigger than the area you want to heal and precisely follow the boundary of contrasting pixels. When you paint with the Healing Brush tool, the selection prevents colors from bleeding in from the outside.

Retouch with the Spot Healing Brush tool

The Spot Healing Brush tool quickly removes blemishes and other imperfections in your photos. The Spot Healing Brush works similarly to the Healing Brush: it paints with sampled pixels from an image or pattern and matches the texture, lighting, transparency, and shading of the sampled pixels to the pixels being healed. Unlike the Healing Brush, the Spot Healing Brush doesn't require you to specify a sample spot. The Spot Healing Brush automatically samples from around the retouched area.



For retouching a large area or for more control over the source sampling, you can use the Healing Brush instead of the Spot Healing Brush.

1 Select the Spot Healing Brush tool from the toolbox. If necessary, click either the Healing Brush tool, Patch tool, or Red Eye tool to show the hidden tools and make your selection.

2 Choose a brush size in the options bar. A brush that is slightly larger than the area you want to fix works best so that you can cover the entire area with one click.

3 (Optional) Choose a blending mode from the Mode menu in the options bar. Choose Replace to preserve noise, film grain, and texture at the edges of the brush stroke when using a soft-edge brush.

4 Choose a Type option in the options bar:

Proximity Match Uses pixels around the edge of the selection to find an area to use as a patch.

Create Texture Uses pixels in the selection to create a texture. If the texture doesn't work, try dragging through the area a second time.

Content-Aware Compares nearby image content to seamlessly fill the selection, realistically maintaining key details such as shadows and object edges.

The create a larger or more precise selection for the Content-Aware option, use the Edit > Fill command. (See Use Content-aware, pattern, or history fills.)

5 Select Sample All Layers in the options bar to sample data from all visible layers. Deselect Sample All Layers to sample only from the active layer.

6 Click the area you want to fix, or click and drag to smooth over imperfections in a larger area.

Patch an area

The Patch tool lets you repair a selected area with pixels from another area or a pattern. Like the Healing Brush tool, the Patch tool matches the texture, lighting, and shading of the sampled pixels to the source pixels. You can also use the Patch tool to clone isolated areas of an image. The Patch tool works with 8-bits or 16-bits-per-channel images.

When repairing with pixels from the image, select a small area to produce the best result.

For information about using the Content-Aware Patch tool options, see Content-Aware Patch and Move.





Repair an area using sampled pixels

1 Select the Patch tool .

2 Do one of the following:

- Drag in the image to select the area you want to repair, and select Source in the options bar.
- Drag in the image to select the area from which you want to sample, and select Destination in the options bar.

Note: *You can also make a selection prior to selecting the Patch tool.*

3 To adjust the selection, do one of the following:

- Shift-drag in the image to add to the existing selection.
- Alt-drag (Windows) or Option-drag (Mac OS) in the image to subtract from the existing selection.
- Alt+Shift-drag (Windows) or Option+Shift-drag (Mac OS) in the image to select an area intersected by the existing selection.

4 To extract texture with a transparent background from the sampled area, select Transparent. Deselect this option if you want to fully replace the target area with the sampled area.

The Transparent option works best for solid or gradient backgrounds with clearly distinct textures (such as a bird in a blue sky).

5 To control how quickly the pasted region adapts to the surrounding image, adjust the Diffusion slider. Select a lower value for images with grain or fine details, or a higher value for smooth images.

6 Position the pointer inside the selection, and do one of the following:

- If Source is selected in the options bar, drag the selection border to the area from which you want to sample. When you release the mouse button, the originally selected area is patched with the sampled pixels.
- If Destination is selected in the options bar, drag the selection border to the area you want to patch. When you release the mouse button, the newly selected area is patched with the sampled pixels.

Repair an area using a pattern

1 Select the Patch tool .

2 Drag in the image to select the area you want to repair.

Note: *You can also make a selection prior to selecting the Patch tool.*

3 If desired, complete steps 3-4 above to adjust the selection and apply pattern texture with a transparent background.

4 Select a pattern from the Pattern panel in the options bar, and click Use Pattern.

Remove red eye

The Red Eye tool removes red eye in flash photos of people or animals.

1 In RGB Color mode, select the Red Eye tool . (The Red Eye tool is in the same group as the Spot Healing Brush tool . Hold down a tool to display additional tools in the group.)

2 Click in the red eye. If you are not satisfied with the result, undo the correction, set one or more of the following options in the options bar, and click the red eye again:

Pupil Size Increases or decreases the area affected by the Red Eye tool.

Darken Amount Sets the darkness of the correction.

A reflection of the camera flash in the subject's retina causes red eye. You'll see it more often when taking pictures in a darkened room because the subject's iris is wide open. To avoid red eye, use the camera's red eye reduction feature. Or, better yet, use a separate flash unit that you can mount on the camera farther away from the camera's lens.

More Help topics

Blending modes

Retouching tools gallery

Creating patterns

Blur filters

Sharpen filters

Select a preset brush

Healing brush examples

Correct image distortion and noise

About lens distortion

Barrel distortion is a lens defect that causes straight lines to bow out toward the edges of the image. *Pincushion distortion* is the opposite effect, where straight lines bend inward.

Vignetting is a defect that darkens the corners of an image due to light falloff around the perimeter of the lens. *Chromatic aberration* appears as a color fringe along the edges of objects, caused by the lens focusing on different colors of light in different planes.

Some lenses exhibit different defects at certain focal lengths, f-stops, and focus distances. With the Lens Correction filter, you can specify the combination of settings used to make the image.

Correct lens distortion and adjust perspective

The Lens Correction filter fixes common lens flaws such as barrel and pincushion distortion, vignetting, and chromatic aberration. The filter works only with 8- and 16-bit-per-channel images in RGB or Grayscale mode.

You can also use the filter to rotate an image or fix image perspective caused by vertical or horizontal camera tilt. The filter's image grid makes these adjustments easier and more accurate than using the Transform command.

Automatically correct image perspective and lens flaws

Using lens profiles, the default Auto Correction option quickly and accurately fixes distortion. For proper automatic correction, Photoshop requires Exif metadata that identifies the camera and lens that created the image, and a matching lens profile on your system.

1 Choose Filter > Lens Correction.

2 Set the following options:

Correction Select the problems you want to fix. If corrections undesirably extend or contract the image beyond original dimensions, select Auto Scale Image.

The Edge menu specifies how to handle blank areas that result from pincushion, rotation, or perspective corrections. You can fill blank areas with transparency or a color, or you can extend the edge pixels of the image.

Search Criteria Filters the Lens Profiles list. By default, profiles based on image sensor size appear first. To list RAW profiles first, click the pop-up menu , and select Prefer RAW Profiles.

Lens Profiles Select a matching profile. By default, Photoshop displays only profiles that match the camera and lens used to create the image. (The camera model does not have to match perfectly.) Photoshop also automatically selects a matching sub-profile for the selected lens based on focal length, f-stop and focus distance. To change the automatic selection, right-click the current lens profile, and select a different sub-profile.

If you find no matching lens profile, click Search Online to acquire additional profiles created by the Photoshop community. To store online profiles for future use, click the pop-up menu , and choose Save Online Profile Locally.

For tips for working with lens profiles and a list of supported lenses, see the support article Lens profile support. To create custom profiles, use the Adobe Lens Profile Creator.

Manually correct image perspective and lens flaws

You can apply manual correction alone or use it to refine automatic lens correction.

1 Choose Filter > Lens Correction.

2 In the upper-right corner of the dialog box, click the Custom tab.

3 (Optional) Choose a preset list of settings from the Settings menu. Lens Default uses settings that you previously saved for the camera, lens, focal length, f-stop, and focus distance used to create the image. Previous Conversion uses the settings used in your last lens correction. Any group of custom settings you saved are listed at the bottom of the menu. (See Save settings and set camera and lens defaults.)

4 Set any of the following options to correct your image.

Remove Distortion Corrects lens barrel or pincushion distortion. Move the slider to straighten horizontal and vertical lines that bend either away from or toward the center of the image. You can also use the Remove Distortion tool to make this correction. Drag toward the center of the image to correct for barrel distortion and toward the edge of the image to correct for pincushion distortion. To compensate for any blank image edges that result, adjust the Edge option on the Auto Correction tab.

Fix Fringe settings Compensate for fringing by adjusting the size of one color channel relative to another.

Zoom in on the image preview to get a closer view of the fringing as you make the correction.

Vignette Amount Sets the amount of lightening or darkening along the edges of an image. Corrects images that have darkened corners caused by lens faults or improper lens shading.

You can also apply vignetting for a creative effect.

Vignette Midpoint Specifies the width of area affected by the Amount slider. Specify a lower number to affect more of the image. Specify a higher number to restrict the effect to the edges of the image.

Vertical Perspective Corrects image perspective caused by tilting the camera up or down. Makes vertical lines in an image parallel.

Horizontal Perspective Corrects image perspective, making horizontal lines parallel.

Angle Rotates the image to correct for camera tilt or to make adjustments after correcting perspective. You can also use the Straighten tool to make this correction. Drag along a line in the image that you want to make vertical or horizontal.

Note: *To avoid unintended scaling when adjusting perspective or angle settings, deselect Auto Scale Image on the Auto Correction tab.*

Scale Adjusts the image scale up or down. The image pixel dimensions aren't changed. The main use is to remove blank areas of the image caused by pincushion, rotation, or perspective corrections. Scaling up effectively results in cropping the image and interpolating up to the original pixel dimensions.

Adjust the Lens Correction preview and grid

Adjust the preview magnification and grid lines to better judge the necessary amount of correction.

- To change the image preview magnification, use the Zoom tool or the zoom controls in the lower left side of the preview image.
- To move the image in the preview window, select the Hand tool and drag in the image preview.
- To use the grid, select Show Grid at the bottom of the dialog box. Use the Size control to adjust the grid spacing and the Color control to change the color of the grid. You can move the grid to line it up with your image using the Move Grid tool .

Save settings and set camera and lens defaults

You can save the settings in the Lens Correction dialog box to reuse with other images made with the same camera, lens, and focal length. Photoshop saves both Auto Correction settings and Custom settings for distortion, chromatic aberration, and vignetting. Perspective correction settings are not saved because they typically vary from one image to another.

You can save and reuse settings in two ways:

- Manually save and load settings. Set options in the dialog box, and then choose Save Settings from the Settings menu . To use the saved settings, choose them from the Settings menu. (If you save settings outside the default folder, they don't appear in the menu; use the Load Settings command to access them.)
- Set a lens default. If your image has EXIF metadata for the camera, lens, focal length, and f-stop, you can save the current settings as a lens default. To save the settings, click the Set Lens Default button. When you correct an image that matches the camera, lens, focal length, and f-stop, the Lens Default option becomes available in the Settings menu. This option is not available if your image doesn't have EXIF metadata.

Reduce image noise and JPEG artifacts

Image noise appears as random extraneous pixels that aren't part of the image detail. Noise can be caused by photographing with a high ISO setting on a digital camera, underexposure, or shooting in a dark area with a long shutter speed. Low-end consumer cameras usually exhibit more image noise than high-end cameras. Scanned images may have image noise caused by the scanning sensor. Often, the film's grain pattern appears in the scanned image.

Image noise can appear in two forms: luminance (grayscale) noise, which makes an image look grainy or patchy, and color noise, which is usually visible as colored artifacts in the image.

Luminance noise may be more pronounced in one channel of the image, usually the blue channel. You can adjust the noise for each channel separately in Advanced mode. Before opening the filter, examine each channel in your image separately to see if noise is prevalent in one channel. You preserve more image detail by correcting one channel rather than making an overall correction to all channels.

1. Choose Filter > Noise > Reduce Noise.
2. Zoom in on the preview image to get a better view of image noise.

3 Set options:

Strength Controls the amount of luminance noise reduction applied to all image channels.

Preserve Details Preserves edges and image details such as hair or texture objects. A value of 100 preserves the most image detail, but reduces luminance noise the least. Balance the Strength and Preserve Details controls to fine-tune noise reduction.

Reduce Color Noise Removes random color pixels. A higher value reduces more color noise.

Sharpen Details Sharpens the image. Removing noise reduces image sharpness. Use the sharpening control in the dialog box or use one of the other Photoshop sharpening filters later to restore sharpness.

Remove JPEG Artifacts Removes blocky image artifacts and halos caused by saving a image using a low JPEG quality setting.

4 If luminance noise is more prevalent in one or two color channels, click the Advanced button and then choose the color channel from the Channel menu. Use the Strength and Preserve Details controls to reduce noise in that channel.

More Help topics

Correct lens distortion and noise in Camera Raw

Using Content-Aware Patch

Seamlessly repair imperfections.

Using Content-Aware Patch

Using Content-Aware Move and Extend

Recompose images with these simple steps.

Using Content-Aware Move and Extend

Basic troubleshooting steps to fix most issues

This document contains basic troubleshooting steps that should solve most problems you can encounter while using Photoshop. Try all the steps below before reporting a problem, posting on the forums, or contacting support for Photoshop-specific issues.

If you happen to encounter a crash, be sure to submit all crash reports. If you submit a crash report for a known issue to Adobe with your email address, we can email you a solution for correcting the problem.

Get the latest Camera Raw support

The most commonly asked support question is "Photoshop doesn't recognize my new camera's raw files. How to I get Photoshop to open my raw files?"

For solutions, see Why doesn’t my version of Photoshop or Lightroom support my camera?

Install application updates

You can fix many problems by simply making sure that your Adobe software is up-to-date. See Keep Photoshop up to date.

Install operating system updates

You can fix many problems by simply making sure your operating system is up-to-date. For Mac OS, see Get software updates for your Mac. For Windows, see Windows Service Pack and Update Center.

Creative Cloud doesn’t show available updates, or applications are in trial mode

Not seeing the available updates? Are your applications showing as trials? See Available updates not listed.

I can't activate Photoshop, or applications are in trial mode

If you can't activate Photoshop, or applications are appearing as trials, then a firewall or host file might be blocking the software from talking with the activation server. See Troubleshoot connectivity issues.

Install video adapter driver updates

If you're experiencing image rendering issues, slow performance, or crashes, the cause could be a defective, unsupported, or incompatible graphics driver. See GPU and graphics driver troubleshooting steps.

*IMPORTANT: Windows Update won't always give you the latest updated drivers. G**o directly to your card manufacturer’s website** to check for driver updates.*

Troubleshoot graphics processor

In some cases, having the latest driver may not cure all problems related to video adapters and drivers.

The quickest and easiest way to determine if the problem is with your video adapter or driver is to disable the Use Graphics Processor preference. See Disable the GPU to quickly narrow to down the issue.

For specific errors, see the following:

- “Graphics hardware not officially supported for 3D”
- "Photoshop has encountered a problem with the display driver, and has temporarily disabled enhancements which use the graphics hardware"

Reset tool

If a tool in Photoshop isn't working properly (for example, the crop tool crops a tiny little gray square, or painting with a brush paints the wrong color or nothing at all), try resetting the tool settings:

- Right-click (Windows) or Control-click (Mac OS) the Tool Preset Picker in the Tool options bar and choose Reset Tool to reset the active tool, or choose Reset All Tools to reset all tools to their factory default settings.



Restore preferences

Returning Photoshop's preferences to their factory fresh state can solve many issues. See Restore preference files to default.

Troubleshoot plug-ins

Many issues arise from using incompatible plug-ins created for previous versions of Photoshop in a newer version or simply by installing plug-ins incorrectly. See Photoshop plug-ins troubleshooting.

Troubleshoot fonts

Many problems can occur when you use third-party fonts, including crashing or hangs when selecting the Type tool or when making the Character panel active/visible. A bad font or fonts can also cause general performance issues when launching or using Photoshop. Validate and remove duplicate or troublesome fonts to improve stability and text tool performance. See Troubleshoot fonts.

Troubleshoot user permissions

If none of the troubleshooting steps above solve your problem, your problem may be user permissions–related. Using the Repair Permissions command repairs permissions for the operating system, but not for applications, such as Photoshop.

Create an admin user account to identify permissions problems. For instructions on creating an admin user account, see the following:

Mac OS:

- Set up users on your Mac (OS X Yosemite)
- Set up users on your Mac (OS X Mavericks)

Be sure to change the New Account pop-up window from [Standard] to [Administrator] when creating the user.

Windows:

- Create a local administrator account

After you create the admin user account, log in to the new user and run Photoshop to see if the problem goes away.

Windows:

- Create local administrator account

Windows:

- Create local administrator account

Start in safe mode

Sometimes, third-party extensions and other utilities can interfere with Photoshop's operation.

If you start your computer in safe mode, third-party extensions and utilities are turned off, which can help solve your problem.

Mac OS:

- Starting up in safe mode: On Mac OS, safe mode disables all third-party extension and startup items and runs only required kernel extensions and Apple-installed startup items.

Windows:

- Start your computer in safe mode: On Windows, safe mode starts Windows with a limited set of files and drivers.

Additional troubleshooting

If you have a how-to question or question about changes in behavior between Photoshop versions, see the following:

- Common questions
- New features summary
- Top issues

If you need additional general troubleshooting help, see the following:

- Resolve issues that occur when you download, install, update, or launch Creative Cloud apps
- Troubleshoot system errors, freezes | Mac OS 10.x | Adobe software
- Troubleshoot system errors, freezes | Windows | Adobe software

If you need help with app installation/downloads or your Creative Cloud membership, see the following:

- Download and installation
- Adobe ID, sign-in, and account
- Manage your Creative Cloud membership

Chapter 11: Reshaping and transforming

Transform objects

Apply transformations

Transforming scales, rotates, skews, stretches, or warps an image. You can apply transformations to a selection, an entire layer, multiple layers, or a layer mask. You can also apply transformations to a path, a vector shape, a vector mask, a selection border, or an alpha channel. Transforming affects image quality when you manipulate the pixels. To apply non-destructive transformations to raster images, use Smart Objects. (See Work with Smart Objects.) Transforming a vector shape or path is always non-destructive because you're only changing the mathematical calculations producing the object.

To make a transformation, first select an item to transform and then choose a transformation command. If necessary, adjust the reference point before manipulating the transformation. You can perform several manipulations in succession before applying the cumulative transformation. For example, you can choose Scale and drag a handle to scale, and then choose Distort and drag a handle to distort. Then press Enter or Return to apply both transformations.

Photoshop uses the interpolation method selected in the General area of the Preferences dialog box to calculate the color values of pixels that are added or deleted during transformations. This interpolation setting directly affects the speed and quality of the transformation. Bicubic interpolation, the default, is slowest but yields the best results.

Note: *You can also warp and distort raster images using the Liquify filter.*



A *Original image* ***B*** *Layer flipped* ***C*** *Selection border rotated* ***D*** *Part of object scaled*

Transform submenu commands

Scale Enlarges or reduces an item relative to its reference point, the fixed point around which transformations are performed. You can scale horizontally, vertically, or both horizontally and vertically.

Rotate Turns an item around a reference point. By default, this point is at the center of the object; however, you can move it to another location.

Skew Slants an item vertically and horizontally.

Distort Stretches an item in all directions.

Perspective Applies one-point perspective to an item.

Warp Manipulates the shape of an item.

Rotate 180, Rotate 90 CW, Rotate 90 CCW Rotates the item by the specified number of degrees, either clockwise or counterclockwise.

Flip Flips the item vertically or horizontally.

Select an item to transform

? Do one of the following:

- To transform an entire layer, make the layer active, and make sure nothing is selected.

Note: *You cannot transform the background layer. To transform it, first convert it to a regular layer.*

- To transform part of a layer, select the layer in the Layers panel, and then select part of the image on that layer.
- To transform multiple layers, do either of the following in the Layers panel: Link the layers together, or select multiple layers by Ctrl-clicking (Windows) or Command-clicking (Mac OS) more than one layer. In the Layers panel, you can also Shift-click to select continguous layers. (See Select, group, and link layers.)
- To transform a layer mask or a vector mask, unlink the mask and select the mask thumbnail in the Layers panel.
- To transform a path or vector shape, use the Path Selection tool to select the entire path or the Direct Selection tool to select part of the path. If you select one or more points on a path, only those path segments connected to the points are transformed. (See Select a path.)
- To transform a selection border, make or load a selection. Then choose Select > Transform Selection.
- To transform an alpha channel, select the channel in the Channels panel.

Set or move the reference point for a transformation

All transformations are performed around a fixed point called the *reference point*. By default, this point is at the center of the item you are transforming. However, you can change the reference point or move the center point to a different location using the reference point locator in the options bar.

1 Choose a transformation command. A bounding box appears in the image.

2 Do one of the following:

- In the options bar, click a square on the reference point locator . Each square represents a point on the bounding box. For example, to move the reference point to the upper-left corner of the bounding box, click the top left square on the reference point locator.
- In the transform bounding box that appears in the image, drag the reference point . The reference point can be outside the item you want to transform.

Scale, rotate, skew, distort, apply perspective, or warp

1 Select what you want to transform.

2 Choose Edit > Transform > Scale, Rotate, Skew, Distort, Perspective, or Warp.

Note: If you are transforming a shape or entire path, the Transform menu becomes the Transform Path menu. If you are transforming multiple path segments (but not the entire path), the Transform menu becomes the Transform Points menu.

3 (Optional) In the options bar, click a square on the reference point locator .

4 Do one or more of the following:

- If you chose Scale, drag a handle on the bounding box. Press Shift as you drag a corner handle to scale proportionately. When positioned over a handle, the pointer becomes a double arrow.
- If you chose Rotate, move the pointer outside the bounding border (it becomes a curved, two-sided arrow), and then drag. Press Shift to constrain the rotation to 15° increments.
- If you chose Skew, drag a side handle to slant the bounding box.
- If you chose Distort, drag a corner handle to stretch the bounding box.
- If you chose Perspective, drag a corner handle to apply perspective to the bounding box.
- If you chose Warp, choose a warp from the Warp Style pop-up menu in the options bar, or to perform a custom warp, drag the control points, a line, or an area within the mesh to change the shape of the bounding box and mesh.
- For all types of transformations, enter a value in the options bar. For example, to rotate an item, specify degrees in the rotation text box.

5 (Optional) If desired, switch to a different type of transformation by selecting a command from the Edit > Transform submenu.

Note: When you transform a bitmap image (versus a shape or path), the image becomes slightly less sharp each time you commit a transformation; therefore, performing multiple commands before applying the cumulative transformation is preferable to applying each transformation separately.

6 (Optional) If you want to warp the image, click the Switch Between Free Transform And Warp Mode button in the options bar.

7 When you finish, do one of the following:

- Press Enter (Windows) or Return (Mac OS), click the Commit button in the options bar, or double-click inside the transformation marquee.
- To cancel the transformation, press Esc or click the Cancel button in the options bar.

Flip or rotate precisely

1 Select what you want to transform.

2 Choose Edit > Transform and choose one of the following commands from the submenu:

- Rotate to specify degrees in the options bar
- Rotate 180° to rotate by a half-turn
- Rotate 90° CW to rotate clockwise by a quarter-turn
- Rotate 90° CCW to rotate counterclockwise by a quarter-turn
- Flip Horizontal to flip horizontally, along the vertical axis

- Flip Vertical to flip vertically, along the horizontal axis

Note: *If you are transforming a shape or entire path, the Transform command becomes the Transform Path command. If you are transforming multiple path segments (but not the entire path), the Transform command becomes the Transform Points command.*

Repeat a transformation

? Choose Edit > Transform > Again, Edit > Transform Path > Again, or Edit > Transform Points > Again.

Duplicate an item when transforming it

? Hold down Alt (Windows) or Option (Mac OS) when selecting the Transform command.

More Help topics

Perspective Warp

Free transformations of images, shapes, and paths

Warp images, shapes, and paths

Adjust crop, rotation, and canvas size

This document outlines the different methods you can use to adjust your image's cropping, rotation, and canvas size.

Crop an image using the Crop tool

1 Select the Crop tool .

2 (Optional) Set resample options in the options bar.

- To crop the image without resampling (default), make sure that the Resolution text box in the options bar is empty. You can click the Clear button to quickly clear all text boxes.
- To resample the image during cropping, enter values for height, width, and resolution in the options bar. To switch the height and width dimensions, click the Swaps Height And Width icon .
- To resample an image based on the dimensions and resolution of another image, open the other image, select the Crop tool, and click Front Image in the options bar. Then make the image you want to crop active.

Resampling while cropping uses the default interpolation method set in the General preferences.

To select or create a resampling preset, click the triangle next to the Crop tool icon in the options bar. (See Create and use tool presets .)

3 Drag over the part of the image you want to keep to create a marquee.

4 If necessary, adjust the cropping marquee:

- To move the marquee to another position, place the pointer inside the bounding box and drag.
- To scale the marquee, drag a handle. To constrain the proportions, hold down Shift as you drag a corner handle.
- To rotate the marquee, position the pointer outside the bounding box (the pointer turns into a curved arrow), and drag. To move the center point around which the marquee rotates, drag the circle at the center of the bounding box. (The marquee can't be rotated in Bitmap mode.)

5 In the options bar, set the following:

Cropped Area Select Hide to preserve the cropped area in the image file. You can make the hidden area visible by moving the image with the Move tool . Select Delete to discard the cropped area.

Note: *The Hide option is not available for images that contain only a background layer; you must convert the background to a regular layer.*

Crop Guide Overlay Select Rule Of Thirds to add guides that help you place compostional elements at 1/3 increments. Select Grid to display fixed guidelines with spacing that depends upon crop size.

Shield The cropping shield shades the image area that will be deleted or hidden. When Shield is selected, you can specify color and opacity for the shield. When Shield is deselected, the area outside the cropping marquee is revealed.

6 Do one of the following:

- To complete the crop, press Enter (Windows) or Return (Mac OS), click the Commit button in the options bar, or double-click inside the cropping marquee.
- To cancel the cropping operation, press Esc or click the Cancel button in the options bar.

Crop an image using the Crop command

1 Use a selection tool to select the part of the image you want to keep.

2 Choose Image > Crop.

Crop an image using the Trim command

The Trim command crops an image by removing unwanted image data in different ways than the Crop command. You can crop an image by trimming surrounding transparent pixels, or background pixels of the color you specify.

1 Choose Image > Trim.

2 In the Trim dialog box, select an option:

- Transparent Pixels to trim away transparency at the edges of the image, leaving the smallest image containing nontransparent pixels.
- Top Left Pixel Color to remove an area the color of the upper-left pixel from the image.
- Bottom Right Pixel Color to remove an area the color of the lower right pixel from the image.

3 Select one or more areas of the image to trim away: Top, Bottom, Left, or Right.

Crop and straighten scanned photos

You can place several photos on your scanner and scan them in one pass, which creates a single image file. The Crop and Straighten Photos command is an automated feature that can create separate image files from the multiple-image scan.

For best results, keep 1/8 inch between the images in your scan, and the background (typically the scanner bed) should be a uniform color with little noise. The Crop and Straighten Photos command works best on images with clearly delineated outlines. If the Crop and Straighten Photos command cannot properly process the image file, use the Crop tool.

1 Open the scanned file that contains the images you want to separate.

2 Select the layer that contains the images.

3 (Optional) Draw a selection around the images you want to process.

4 Choose File > Automate > Crop And Straighten Photos. The scanned images are processed, and then each image opens in its own window.

If the Crop And Straighten Photos command incorrectly splits one of your images, make a selection border around the image and some background, and then hold down Alt (Windows) or Option (Mac OS) as you choose the command. The modifier key indicates that only one image should be separated from the background.

Straighten an image

The Ruler tool provides a Straighten option that quickly aligns images with horizon lines, building walls, and other key elements.

1 Select the Ruler tool . (If necessary, click and hold the Eyedropper tool to reveal the Ruler.)

2 In the image, drag across a key horizontal or vertical element.

3 In the options bar, click Straighten.

Photoshop straightens the image and automatically crops it. To reveal image areas that extend beyond the new document boundaries, choose Edit > Undo.

To entirely avoid automatic cropping, hold down Alt (Windows) or Option (Mac OS) when you click Straighten.

Rotate or flip an entire image

Note: *Image Rotation is destructive editing and actually modifies the file information. If you want to non-destructively rotate the image for viewing, use the Rotation tool.*

The Image Rotation commands let you rotate or flip an entire image. The commands do not work on individual layers or parts of layers, paths, or selection borders. If you want to rotate a selection or layer, use the Transform or Free Transform commands.



A *Flip Horizontal* ***B*** *Original image* ***C*** *Flip Vertical* ***D*** *Rotate 90° CCW* ***E*** *Rotate 180°* ***F*** *Rotate 90° CW*

? Choose Image > Image Rotation, and choose one of the following commands from the submenu:

180° Rotates the image by a half-turn.

90° CW Rotates the image clockwise by a quarter-turn.

90° CCW Rotates the image counterclockwise by a quarter-turn.

Arbitrary Rotates the image by the angle you specify. If you choose this option, enter an angle between -359.99 and 359.99 in the angle text box. (In Photoshop, you can select °CW or °CCW to rotate clockwise or counterclockwise.) Then click OK.

Flip Canvas Horizontal or Vertical Flips the image along the corresponding axis.

Change the canvas size

The canvas size is the full editable area of an image. The Canvas Size command lets you increase or decrease an image's canvas size. Increasing the canvas size adds space around an existing image. Decreasing an image's canvas size crops into the image. If you increase the canvas size of an image with a transparent background, the added canvas is transparent. If the image doesn't have a transparent background, there are several options for determining the color of the added canvas.

1 Choose Image > Canvas Size.

2 Do one of the following:

- Enter the dimensions for the canvas in the Width and Height boxes. Choose the units of measurement you want from the pop-up menus next to the Width and Height boxes.
- Select Relative, and enter the amount you want to add or subtract from the image's current canvas size. Enter a positive number to add to the canvas, and enter a negative number to subtract from the canvas.

3 For Anchor, click a square to indicate where to position the existing image on the new canvas.

4 Choose an option from the Canvas Extension Color menu:

- Foreground to fill the new canvas with the current foreground color
- Background to fill the new canvas with the current background color
- White, Black, or Gray to fill the new canvas with that color
- Other to select a new canvas color using the Color Picker

Note: *You can also click the white square to the right of the Canvas Extension Color menu to open the Color Picker.*

The Canvas Extension Color menu isn't available if an image doesn't contain a background layer.

5 Click OK.



Make a frame by increasing the canvas size

You can make a photo frame by increasing the canvas size and filling it with a color.

You can also use one of the prerecorded actions to make a styled photo frame. It's best to work on a copy of your photo.

1 Open the Actions panel. Choose Window > Actions.

2 Choose Frames from the Actions panel menu.

3 Choose one of the frame actions from the list.

4 Click the Play Selection button.

The action plays, creating the frame around your photo.

More Help topics

Crop a photo

Flip or rotate precisely

Crop and straighten photos

Cropping is the process of removing portions of an image to create focus or strengthen the composition. Use the Crop tool to crop and straighten images in Photoshop. The Crop tool is non-destructive, and you can choose to retain the cropped pixels to optimize the crop boundaries later. The Crop tool also provides intuitive methods to straighten the image while cropping.

For all operations, visual guides provide an interactive preview. When you crop or straighten photos, real-time feedback helps you visualize the final result.

Crop or remove part of an image

1 From the toolbar, select the Crop Tool . Crop borders display on the edges of the image.

2 Draw a new cropping area or drag the corner and edge handles to specify the crop boundaries in your image.

3 (Optional) Specify the Crop options using the Control bar.

A Aspect Ratio menu B Swap Width and Height values C Overlay Options

Size and proportions Choose a ratio or size for the crop box. You can also choose a preset, enter your own, or even define your own preset values for later use.

Overlay Options Choose a view to display overlay guides while cropping. Guides such as Rule of Thirds, Grid, and Golden Ratio are available. To cycle through all the options, press O.

Crop Options Click the Settings (gear) menu to specify additional crop options.

Use Classic mode Enable this option if you want to use the Crop tool like it was in previous versions of Photoshop. See Adjust crop, rotation, and canvas sizefor information on using the Crop tool in classic mode.

Auto Center Preview Enable this option to place the preview in the center of the canvas.

Show Cropped Area Enable this option to display the area that is cropped. If this option is disabled, only the final area is previewed.

Enable Crop Shield Use the crop shield to overlay the cropped areas with a tint. You can specify a color and opacity. If you Enable Auto Adjust Opacity, the opacity is reduced when you edit the crop boundaries.

Delete cropped pixels Disable this option to apply a non-destructive crop and retain pixels outside the crop boundaries. Non-destructive cropping does not remove any pixels. You can later click the image to see areas outside current crop borders.

Enable this option to delete any pixels that are outside the crop area. These pixels are lost and are not available for future adjustments.

Right-click the Crop box to access common crop options from the context menu.

4 Press Enter (Windows) or Return (Mac OS) to crop the photo.

For information on cropping, see Crop a photo .

The following updates were introduced in the Creative Cloud release for Photoshop CS6:

- **Front Image** and new presets in the Aspect Ratio menu.
- Clicking the double-arrow icon changes the crop orientation by swapping the **Width** and **Height** values. This icon replaces the Rotate Crop Box button.
- Choosing **W x H x Resolution** from the **Aspect Ratio** menu displays a **Resolution** field in the options bar and auto-fills the **Width** and **Height** values.
- Clicking the **Clear** button clears the values in the **Width** and **Height** fields in the options bar. If displayed, the value in the **Resolution** field is also cleared.
- The keyboard shortcut for **Front Image** has changed from **F** to **I** for both the **Crop** tool and the **Perspective Crop** tool.

Straighten an image while cropping

You can straighten an image while cropping. The image is rotated and aligned to straighten it. The image canvas is automatically resized to accommodate the rotated pixels.



? To straighten an image do one of the following:

- Place the pointer a little outside the corner handles and drag to rotate the image. A grid displays inside the crop box and the image rotates behind it.
- Click Straighten in the control bar and then using the Straighten tool, draw a reference line to straighten the photo. For example, draw a line along the horizon or an edge to straighten the image along it.

See Straightening a Crooked Image to watch a video explaining straightening an image using the Crop tool.

Transform perspective while cropping

The Perspective Crop tool lets you transform the perspective in an image while cropping. Use the Perspective Crop tool when working with images that contain keystone distortion. Keystone distortion occurs when an object is photographed from an angle rather than from a straight-on view. For example, if you take a picture of a tall building from ground level, the edges of the building appear closer to each other at the top than they do at the bottom.

A Original image ***B*** *Adjust cropping marquee to match the object's edges* ***C*** *Final image*

1 To correct image perspective, hold down the Crop tool and select the Perspective Crop tool .

2 Draw a marquee around the distorted object. Match the edges of the marquee to the rectangular edges of the object.

3 Press Enter (Windows) or Return (Mac OS) to complete the perspective crop.

See the video Adjust perspective in a photo for more information.

Resize the canvas using the Crop tool

You can use the Crop tool to resize the image canvas.

1 From the toolbar, select the Crop Tool . Crop borders display on the edges of the image.

2 Drag the crop handles outwards to enlarge the canvas. Use the Alt/Option modifier key to enlarge from all sides.

3 Press Enter (Windows) or Return (Mac OS) to confirm the action.

To resize the canvas, you can also choose Image > Canvas Size. See Change the Canvas size or the tutorial video Understanding canvas size for more information.

Create panoramic images with Photomerge

About Photomerge

The Photomerge™ command combines several photographs into one continuous image. For example, you can take five overlapping photographs of a city skyline, and then merge them into a panorama. The Photomerge command can assemble photos that are tiled horizontally as well as vertically.

Take pictures for Photomerge

Your source photographs play a large role in panoramic compositions. To avoid problems, follow these guidelines when taking pictures for use with Photomerge:

Overlap images sufficiently Images should overlap by approximately 40%. If the overlap is less, Photomerge may not be able to automatically assemble the panorama. However, keep in mind that the images shouldn't overlap too much. If images overlap by 70% or more, Photomerge may not be able to blend the images. Try to keep the individual photos at least somewhat distinct from each other.

Use one focal length If you use a zoom lens, don't change the focal length (zoom in or out) while taking your pictures.

Keep the camera level Although Photomerge can process slight rotations between pictures, a tilt of more than a few degrees can result in errors when the panorama is assembled. Using a tripod with a rotating head helps maintain camera alignment and viewpoint.

Stay in the same position Try not to change your position as you take a series of photographs, so that the pictures are from the same viewpoint. Using the optical viewfinder with the camera held close to the eye helps keep the viewpoint consistent. Or try using a tripod to keep the camera in the same place.

Avoid using distortion lenses Distortion lenses can interfere with Photomerge. However, the Auto option adjusts for images taken with fish-eye lenses.

Maintain the same exposure Avoid using the flash in some pictures and not in others. The blending features in Photomerge helps smooth out different exposures, but extreme differences make alignment difficult. Some digital cameras change exposure settings automatically as you take pictures, so you may need to check your camera settings to be sure that all the images have the same exposure.

Create a Photomerge composition

1 Choose File > Automate > Photomerge.

2 Under Source Files in the Photomerge dialog box, choose one of the following from the Use menu:

Files Generates the Photomerge composition using individual files.

Folders Uses all the images stored in a folder to create the Photomerge composition.

3 Specify which images to use by doing one of the following:

- To select image files or a folder of images, click the Browse button and navigate to the files or folder.
- To use the images currently open in Photoshop, click Add Open Files.
- To remove images from the Source File list, select the file and click the Remove button.

4 Select a Layout option:

Auto Photoshop analyzes the source images and applies either a Perspective, Cylindrical, and Spherical layout, depending on which produces a better photomerge.

Perspective Creates a consistent composition by designating one of the source images (by default, the middle image) as the reference image. The other images are then transformed (repositioned, stretched or skewed as necessary) so that overlapping content across layers is matched.

Cylindrical Reduces the "bow-tie" distortion that can occur with the Perspective layout by displaying individual images as on an unfolded cylinder. Overlapping content across files is still matched. The reference image is placed at the center. Best suited for creating wide panoramas.



A

B

Spherical Aligns and transforms the images as if they were for mapping the inside of a sphere, which simulates the experience of viewing a 360-degree panorama. If you have taken a set of images that cover 360 degrees, use this for 360 degree panoramas. You might also use Spherical to produce nice panoramic results with other file sets.

Collage Aligns the layers and matches overlapping content and transforms (rotate or scale) any of the source layers.

Reposition Aligns the layers and matches overlapping content, but does not transform (stretch or skew) any of the source layers.

5 Select any of the following options:

Blend Images Together Finds the optimal borders between the images and creates seams based on those borders, and color matches the images. With Blend Images Together turned off, a simple rectangular blend is performed. This may be preferable if you intend to retouch the blending masks by hand.

Vignette Removal Removes and performs exposure compensation in images that have darkened edges caused by lens flaws or improper lens shading.

Geometric Distortion Correction Compensates for barrel, pincushion, or fisheye distortion.

Content Aware Fill Transparent Areas Seamlessly fill the transparent areas with similar image content nearby.

6 Click OK.

Photoshop creates one multi-layer image from the source images, adding layer masks as needed to create optimal blending where the images overlap. You can edit the layer masks or add adjustment layers to further fine-tune the different areas of the panorama.

To replace empty areas around image borders, use a content-aware fill. (See Use Content-aware, pattern, or history fills.)

Create 360-degree panoramas

Combine Photomerge with 3D features to create a 360-degree panorama. First, you stitch together the images to create a panorama; then you use the Spherical Panorama command to wrap the panorama so it's continuous.

Be sure to photograph a full circle of images with sufficient overlap. Photographing with a pano head on a tripod helps produce better results.

1 Choose File > Automate > Photomerge.

2 In the Photomerge dialog box, add the images you want to use.

Do not include images that cover the top (zenith) or bottom (nadir) of the scene. You'll add these images later.

3 Select Spherical for the Layout.

If you photographed with a fisheye lens, select the Auto layout and Geometric Distortion Correction. If Photoshop cannot automatically identify your lens, download the free Adobe Lens Profile Creator from the Adobe website.

4 (Optional) Select Vignette Removal or Geometric Distortion for the Lens Correction.

5 (Optional) Select Content Aware Fill Transparent Areas to avoid transparent pixels on the edges of the panoramic image.

6 Click OK.

7 Choose 3D > New Shape From Layer > Spherical Panorama.

8 (Optional) Manually add the top and bottom images into the sphere. You could also paint out any remaining transparent pixels in the 3D spherical panorama layer.

More Help topics

Crop images

Create 3D objects and animations

Warp images, shapes, and paths

Warp an item

The Warp command lets you drag control points to manipulate the shape of images, shapes, or paths, and so on. You can also warp using a shape in the Warp Style pop-up menu in the options bar. Shapes in the Warp Style pop-up menu are also malleable; drag their control points.

When using the control points to distort an item, choosing View > Extras shows or hides the warp mesh and control points.



A Selecting the shape to be warped ***B*** *Choosing a warp from the Warp Style pop-up menu in the options bar* ***C*** *Result using several warp options*

1. Select what you want to warp.
2. Do one of the following:
   - Choose Edit > Transform > Warp.
   - If you chose a different transform command or the Free Transform command, click the Switch Between Free Transform And Warp Modes button in the options bar.
3. Do one or more of the following:
   - To warp using a specific shape, choose a warp style from the Warp pop-up menu in the options bar.



- To the manipulate the shape, drag the control points, a segment of the bounding box or mesh, or an area within the mesh. When adjusting a curve, use the control point handles. This is similar to adjusting the handles in the curved segment of a vector graphic.

To undo the last handle adjustment, choose Edit > Undo.



A B

- To change the orientation of a warp style that you chose from the Warp menu, click the Change The Warp Orientation button in the options bar.
- To change the reference point, click a square on the Reference point locator in the options bar.
- To specify the amount of warp using numeric values, enter the values in the Bend (set bend), X (set horizontal distortion), and Y (set vertical distortion) text boxes in the options bar. You can't enter numeric values if you have chosen None or Custom from the Warp Style pop-up menu.

4 Do one of the following:

- Press Enter (Windows) or Return (Mac OS), or click the Commit button in the options bar.
- To cancel the transformation, press Esc or click the Cancel button in the options bar.

Note: *When you warp a bitmap image (versus a shape or path), the image becomes slightly less sharp each time you commit a transformation; therefore, performing multiple commands before applying the cumulative transformation is preferable to applying each transformation separately.*

Puppet Warp

Puppet Warp provides a visual mesh that lets you drastically distort specific image areas, while leaving other areas intact. Applications range from subtle image retouching (such as shaping hair) to total transformations (such as repositioning arms or legs).

In addition to image layers, you can apply Puppet Warp to layer and vector masks. To nondestructively distort images, use Smart Objects. (See Work with Smart Objects.)

1 In the Layers panel, select the layer or mask you want to transform.

2 Choose Edit > Puppet Warp.

3 In the options bar, adjust the following mesh settings:

Mode Determines the overall elasticity of the mesh.

Choose Distort for a highly elastic mesh good for warping wide-angle images or texture maps.

Density Determines the spacing of mesh points. More Points increases precision but requires more processing time; Fewer Points does the opposite.

Expansion Expands or contracts the outer edge of the mesh.

Show Mesh Deselect to show only adjustment pins, providing a clearer preview of your transformations.

To temporarily hide adjustment pins, press the H key.

4 In the image window, click to add pins to areas you want to transform and areas you want to anchor in place.



5 To reposition or remove pins, do any of the following:

- Drag pins to warp the mesh.
- To reveal a mesh area you've overlapped with another, click the Pin Depth buttons in the options bar.
- To remove selected pins, press Delete. To remove other individual pins, place the cursor directly over them, and press Alt (Windows) or Option (Mac OS); when the scissors icon appears, click.
- Click the Remove All Pins button in the options bar.

To select multiple pins, Shift-click them or choose Select All from the context menu.

6 To rotate the mesh around a pin, select it, and then do either of the following:

- To rotate the mesh a fixed number of degrees, press Alt (Windows) or Option (Mac OS), and position the cursor near to, but not over the pins. When a circle appears, drag to visually rotate the mesh.

The degree of rotation appears in the options bar.

- To rotate the mesh automatically based on the selected Mode option, choose Auto from the Rotate menu in the options bar.

7 When your transformation is complete, press Enter or Return.



More Help topics

Transform objects

Vanishing Point

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Vanishing Point simplifies perspective-correct editing in images that contain perspective planes—for example, the sides of a building, walls, floors, or any rectangular object. In Vanishing Point, you specify the planes in an image, and then apply edits such as painting, cloning, copying or pasting, and transforming. All your edits honor the perspective of the plane you're working in. When you retouch, add, or remove content in an image, the results are more realistic because the edits are properly oriented and scaled to the perspective planes. After you finish working in Vanishing Point, you can continue editing the image in Photoshop. To preserve the perspective plane information in an image, save your document in PSD, TIFF, or JPEG format.

You can also measure objects in an image, and export 3D information and measurements to DXF and 3DS formats for use in 3D applications.

Vanishing Point dialog box overview

The Vanishing Point dialog box (Filter > Vanishing Point) contains tools for defining the perspective planes, tools for editing the image, a measure tool, and an image preview. The Vanishing Point tools (Marquee, Stamp, Brush, and others) behave similarly to their counterparts in the main Photoshop toolbox. You can use the same keyboard shortcuts to set the tool options. Opening the Vanishing Point menu displays additional tool settings and commands.



A Vanishing Point menu *B Options* *C Toolbox* *D Preview of vanishing point session* *E Zoom options*

For the keyboard shortcuts in Vanishing Point, see .

Vanishing Point tools

Vanishing Point tools behave like their counterparts in the main Photoshop toolbox. You can use the same keyboard shortcuts for setting tool options. Selecting a tool changes the available options in the Vanishing Point dialog box.

Edit Plane tool

Selects, edits, moves, and resizes planes.

Create Plane tool

Defines the four corner nodes of a plane, adjusts the size and shape of the plane, and tears off a new plane.

Marquee tool Makes square or rectangular selections, and also moves or clones selections.

Double-clicking the Marquee tool in a plane selects the entire plane.

Stamp tool

Paints with a sample of the image. Unlike the Clone Stamp tool, the Stamp tool in Vanishing Point can't clone elements from another image. See also Paint with sampled pixels in Vanishing Pointand Retouch with the Clone Stamp tool.

Brush tool

Paints a selected color in a plane.

Transform tool

Scales, rotates, and moves a *floating selection* by moving the bounding box handles. Its behavior is similar to using the Free Transform command on a rectangle selection. See also Transform freely.

Eyedropper tool

Selects a color for painting when you click in the preview image.

Measure tool

Measures distances and angles of an item in a plane. See also Measure in Vanishing Point

Zoom tool

Magnifies or reduces the view of the image in the preview window.

Hand tool Moves the image in the preview window.

Magnify or reduce the preview image

? Do any of the following:

- Select the Zoom tool in the Vanishing Point dialog box, and click or drag in the preview image to zoom in; hold down Alt (Windows) or Option (Mac OS), and click or drag to zoom out.
- Specify a magnification level in the Zoom text box at the bottom of the dialog box.
- Click the Plus sign (+) or Minus sign (-) button to zoom in or out, respectively.
- To temporarily zoom into the preview image, hold down the "X" key. This is especially helpful for placing the corner nodes when defining a plane, and for working on details.

Move the image in the preview window

? Do any of the following:

- Select the Hand tool in the Vanishing Point dialog box, and drag in the preview image.
- Hold down the spacebar with any tool selected, and drag in the preview image.

Work in Vanishing Point

1 (Optional) Prepare your image for work in Vanishing Point.

Before choosing the Vanishing Point command, do any of the following:

- To place the results of your Vanishing Point work in a separate layer, first create a new layer before choosing the Vanishing Point command. Placing the Vanishing Point results in a separate layer preserves your original image and you can use the layer opacity control, styles, and blending modes.
- If you plan to clone the content in your image beyond the boundaries of the current image size, increase the canvas size to accommodate the additional content. See also Change the canvas size
- If you plan to paste an item from the Photoshop clipboard into Vanishing Point, copy the item before choosing the Vanishing Point command. The copied item can be from a different Photoshop document. If you're copying type, you must rasterize the text layer before copying to the clipboard.
- To confine the Vanishing Point results to specific areas of your image, either make a selection or add a mask to your image before choosing the Vanishing Point command. See also Select with the marquee toolsand About masks and alpha channels.
- To copy something in perspective from one Photoshop document to another, first copy the item while in Vanishing Point in one document. When you paste the item in another document while in Vanishing Point, the item's perspective is preserved.

2 Choose Filter > Vanishing Point.

3 Define the four corner nodes of the plane surface.

By default, the Create Plane tool is selected. Click in the preview image to define the corner nodes. Try to use a rectangle object in the image as a guide when creating the plane.

To tear off additional planes, use the Create Plane tool and Ctrl-drag (Windows) or Command-drag (Mac OS) an edge node. For more information, see Define and adjust perspective planes in Vanishing Point.



4 Edit the image.

Do any of the following:

- Make a selection. Once drawn, a selection can be cloned, moved, rotated, scaled, filled, or transformed. For detailed information, see About selections in Vanishing Point.
- Paste an item from the clipboard. The pasted item becomes a floating selection, which conforms to the perspective of any plane that it's moved into. For detailed information, see also Paste an item into Vanishing Point.
- Paint with color or sampled pixels. For detailed information, see Paint with a color in Vanishing Pointor Paint with sampled pixels in Vanishing Point.
- Scale, rotate, flip, flop, or move a floating selection. For detailed information, see About selections in Vanishing Point.
- Measure an item in a plane. Measurements can be rendered in Photoshop by choosing Render Measurements To Photoshop from the Vanishing Point menu. For detailed information, see Measure in Vanishing Point.

5 Export 3D information and measurements to DXF or 3DS format.

Textures are also exported to 3DS format. For detailed information, see Export measurements, textures, and 3D information.

6 Click OK.

Grids can be rendered to Photoshop by choosing Render Grids To Photoshop from the Vanishing Point menu before you click OK. For detailed information, see Render grids to Photoshop.

Export measurements, textures, and 3D information

3D information (planes), textures, and measurements created in Vanishing Point can be exported to a format for use in CAD, modeling, animation, and special effects applications. Exporting to DXF creates a file with 3D information and any measurements. Exported 3DS files contain rendered textures in addition to the geometric information.

1 Open the Vanishing Point menu and choose either Export to DXF or Export To 3DS.

2 In the Export DXF or Export 3DS dialog box, select a location for the saved file and click Save.

About perspective planes and the grid

Before you can make edits in Vanishing Point, you define rectangular planes that line up with the perspective in an image. The accuracy of the plane determines whether any edits or adjustments are properly scaled and oriented in your image.

After you establish the four corner nodes, the perspective plane is active and displays a bounding box and a grid. You can scale, move, or reshape to fine-tune the perspective plane. You can also change the grid size so it lines up with elements in the image. Sometimes, lining up the bounding box and grid with a texture or pattern in your image helps you accurately match the image's perspective. Adjusting the grid size can also make it easier for you to count items in the image.

Besides helping to line up the perspective planes with image elements, the grid is helpful for visualizing measurements when used with the Measure tool. An option is available to link the grid size to measurements you make with the Measure tool.

Define and adjust perspective planes in Vanishing Point

1 In the Vanishing Point dialog box, select the Create Plane tool and click in the preview image to add the four corner nodes.

   Try to use a rectangular object or a plane area in the image as a guide when creating the perspective plane. To help with node placement, hold down the "X" key to zoom into the preview image. As you add corner nodes, you can delete the last node if it's not correct by pressing the Backspace key (Windows) or Delete key (Mac OS). You can also reposition a node by dragging it.

2 Select the Edit Plane tool and do one or more of the following:

   - To reshape the perspective plane, drag a corner node.
   - To adjust the grid, enter a value in the Grid Size text box or click the down arrow and move the slider. You can also adjust the grid size when the Create Plane tool is selected.
   - To move the plane, click inside the plane and drag.
   - To scale the plane, drag an edge node in a segment of the bounding box.



The bounding box and grid of a perspective plane is normally blue. If there's a problem with the placement of the corner nodes, the plane is invalid, and the bounding box and grid turn either red or yellow. When your plane is invalid, move the corner nodes until the bounding box and grid are blue.

If you have overlapping planes, Ctrl-click (Windows) or Command-click (Mac OS) to cycle through the overlapping planes.



Create related perspective planes

After creating a plane in Vanishing Point, you can create (tear off) additional planes that share the same perspective. Once a second plane is torn off from the initial perspective plane, you can tear off additional planes from the second plane and so forth. You can tear off as many planes as you want. Although new planes tear off at 90° angles, you can adjust them to any angle. This is useful for making seamless edits between surfaces, matching the geometry of a complex scene. For example, corner cabinets in a kitchen can be part of a continuous surface. In addition to adjusting the angles of a related perspective plane, you can always resize the plane using the Edit Plane tool.

1 Select the Create Plane tool or Edit Plane tool and Ctrl-drag (Windows) or Command-drag (Mac OS) an edge node of an existing plane's bounding box (not a corner node).

   The new plane is torn off at a 90° angle to the original plane.

   Note: *If a newly created plane does not properly line up with the image, select the Edit Plane tool and adjust a corner node. When you adjust one plane, a connected plane is affected. (Corner nodes are unavailable if more than two planes are connected.)*



2 (Optional) Do one of the following to change the angle of the newly torn off plane:

   - With either the Edit Plane tool or Create Plane tool selected, Alt-drag (Windows) or Option-drag (Mac OS) the center edge node on the side that's opposite from the axis of rotation.
   - Enter a value in the Angle text box.
   - Move the Angle slider.



Note: Once you create a new (child) plane from an existing (parent) plane, you can no longer adjust the angle of the parent plane.

Bounding box and grid alerts in Vanishing Point

The bounding box and grid change colors to indicate the plane's current condition. If your plane is invalid, move a corner node until the bounding box and grid are blue.

Blue Indicates a valid plane. Keep in mind that a valid plane doesn't guarantee results with the proper perspective. You must make sure that the bounding box and grid accurately line up with geometric elements or a plane area in the image.

Red Indicates an invalid plane. Vanishing Point cannot calculate the plane's aspect ratio.

Yellow Indicates an invalid plane. Some vanishing points of the plane cannot be resolved.

Note: *Although it's possible to edit an invalid red or yellow plane, including tearing off perpendicular planes, the results will not be oriented properly.*

Show or hide the grid, active selections, and perspective plane boundaries

? Choose Show Edges from the Vanishing Point menu.

Note: Selections temporarily show when they are resized or repositioned even if Show Edges is turned off.

Adjust the spacing of the perspective plane grid

? Do any of the following:

- Select the Edit Plane or the Create Plane tool, and then enter a Grid Size value in the tool options area.
- Select the Measure tool and then select Link Measurements To Grid in the tool options area. Drag the Measure tool in a plane and enter a Length value in the tool options area.

Render grids to Photoshop

By default, the Vanishing Point grids are invisible when viewing an image in the Photoshop document window, even though the grids are preserved in the image and appear whenever you launch Vanishing Point. Grids can be rendered so when you finish working in Vanishing Point, they're visible in the Photoshop document window. The rendered grids are raster not vector.

? Open the Vanishing Point menu and choose Render Grids To Photoshop.

The Render Grids To Photoshop command must be chosen for each Vanishing Point session.

Create a new layer for your Vanishing Point results if you plan to render the grids to Photoshop. This keeps the grids on a separate layer from the main image.

About selections in Vanishing Point

Selections can be helpful when you're painting or retouching to correct flaws, add elements, or enhance an image. In Vanishing Point, making selections let you paint or fill specific areas in an image while honoring the perspective defined by the planes in the image. Selections can also be used to clone and move specific image content in perspective.

Using the Marquee tool in Vanishing Point, you draw a selection within a perspective plane. If you draw a selection that spans more than one plane, it wraps to conform to the perspective of each plane.

Once a selection is drawn, you can move it anywhere in the image and maintain the perspective established by the plane. If your image has multiple planes, the selection conforms to the perspective of the plane it's moved through.

Vanishing Point also lets you clone the image pixels in a selection as it is moved in an image. In Vanishing Point, a selection containing image pixels that you can move anywhere in the image is called a floating selection. Although not on a separate layer, the pixels in a floating selection seem to be a separate layer hovering above the main image. While active, a floating selection can be moved, rotated, or scaled.

Note: *When you paste an item into Vanishing Point, the pasted pixels are in a floating selection.*

Clicking outside a floating selection deselects it. Once deselected, a floating selection's content is pasted into the image, replacing the pixels that were below it. Cloning a copy of a floating selection also deselects the original.



Vanishing Point has another move option for selections. You can fill the selection with pixels from the area where the pointer is moved.



Make selections in Vanishing Point

1 Select the Marquee tool.

2 (Optional) In the tool options area, enter values for any of the following settings before making the selection:

Feather Specifies how much to blur the edges of the selection.

Opacity Specify this value if you plan to use the selection to move image content. This option determines how much the moved pixels obscure or reveal the image underneath.

Heal menu Choose a blending mode if you plan to use a selection to move image content. This option determines how the moved pixels blend with the surrounding image:

- Choose Off so the selection doesn't blend with the colors, shadows, and textures of the surrounding pixels.
- Choose Luminance to blend the selection with the lighting of the surrounding pixels.
- Choose On to blend the selection with the color, lighting, and shading of surrounding pixels.

3 Drag the tool in a plane. You can make a selection that spans more than one plane. Hold the Shift key to constrain the selection to a square that's in perspective.

Note: *To select an entire plane, double-click the Marquee tool in the plane.*

Move selections in Vanishing Point

1 Make a selection in a perspective plane.

2 Choose one of the following from the Move Mode menu to determine the behavior when you move a selection:
   - To select the area you move the selection marquee to, choose Destination.
   - To fill the selection with the image pixels in the area where you drag the Selection tool pointer to (same as Ctrl-dragging or Command-dragging a selection), choose Source.
3 Drag the selection. Hold down the Shift key to constrain the move so it is aligned with the grid of the perspective plane.

Move, rotate and scale floating selections

? Do any of the following:
   - To move a floating selection, select the Marquee or Transform tool, click inside the selection and drag.
   - To rotate a floating selection, select the Transform tool and move the pointer near a node. When the pointer changes to a curved double arrow, drag to rotate the selection. You can also select the Flip option to flip the selection horizontally along the vertical axis of the plane or select the Flop option to flip the selection vertically along the horizontal axis of the plane.

***A** Move **B** Rotate **C** Scale*

   - To scale a floating selection, make sure that it is in a perspective plane. Select the Transform tool and move the pointer on top of a node. When the pointer changes to a straight double arrow, drag to scale the selection. Press the Shift key to constrain the aspect ratio as you scale. Press Alt (Windows) or Option (Mac OS) to scale from the center.

Fill selections with another area of an image

1 Make a selection in a perspective plane.
2 (Optional) Move the selection where you want it. Make sure the Move Mode is set to Destination, when you move the selection.
3 Do one of the following:
   - Ctrl-drag (Windows) or Command-drag (Mac OS) the pointer from inside the selection to the image area that you want to fill the selection.
   - Choose Source from the Move Mode menu and drag the pointer from inside the selection to the image area that you want to fill the selection.

   The filled selection becomes a floating selection that you can scale, rotate, move, or clone using the Transform tool, or move or clone using the Marquee tool.



***A** Original selection **B** Moving the selection to the source image **C** The source image fills the original selection*

Copy selections in Vanishing Point

1 Make a selection in a perspective plane.

2 Alt-drag (Windows) or Option-drag (Mac OS) the selection with the Marquee tool to create a copy of the selection and its image pixels.

The copy becomes a *floating selection*, which seems to hover above the main image. You can move a floating selection, or you can select the Transform tool to scale or rotate the floating selection.

3 Do one of the following:

- Click outside the floating selection to deselect it. The selection's content is pasted into the image, replacing the pixels that were below it.
- Click in the floating selection with either the Marquee or Transform tool and Alt-drag (Windows) or Option-drag (Mac OS) to make another copy. Once copied, the original floating selection is deselected and replaces the pixels that were below it.

Pressing Control+Shift+T (Windows) or Command+Shift+T (Mac OS) duplicates your last duplicating move. This is an easy way to clone content multiple times.

Paste an item into Vanishing Point

You can paste an item from the clipboard in Vanishing Point. The copied item can be from the same document or a different one. Once pasted into Vanishing Point, the item becomes a floating selection that you can scale, rotate, move or clone. When the floating selection moves into a selected plane, it conforms to the plane's perspective.



A *Copied pattern from a separate document* ***B*** *Image with selection (to confine results) created in Photoshop before opening Vanishing Point*
C *Pasted pattern in Vanishing Point is moved into the plane and honors the selection*

For convenience, it's recommended that you create perspective planes in a previous Vanishing Point session.

1 Copy an item to the clipboard. The copied item can be from the same or different document. Keep in mind that you can paste only a raster (not vector) item.

   Note: *If you're copying type, you must first rasterize it. Right-click the text layer, and choose Rasterize. Then choose Select > All and copy to the clipboard.*

2 (Optional) Create a new layer.

3 Choose Filter > Vanishing Point.

4 If necessary, create one or more planes in the image.

5 Press Ctrl+V (Windows) or Command+V (Mac OS) to paste the item.

   The pasted item is now a floating selection in the upper-left corner of the preview image. By default, the Marquee tool is selected.

6 Use the Marquee tool to drag the pasted image to a plane.

   The image conforms to the perspective of the plane.

   Note: *After pasting the image in Vanishing Point, do not click anywhere in the image with the Marquee tool except to drag the pasted image to a perspective plane. Clicking anywhere else deselects the floating selection and permanently pastes the pixels into the image.*

Paint with a color in Vanishing Point

1 Select the Brush tool.

2 Specify a brush color by doing one of the following:

   - Select the Eyedropper tool and click a color in the preview image.
   - Click the Brush Color box to open the Color Picker to select a color.

3 In the tool options area, set the Diameter (brush size), Hardness (edge smoothness), and Opacity (the degree to which painting obscures the image below).

4 Choose a Healing mode:

   - To paint without blending with the color, lighting, and shading of the surrounding pixels, choose Off.
   - To paint and blend the strokes with the lighting of the surrounding pixels while retaining the selected color, choose Luminance.
   - To paint and blend with the colors, lighting, and shading of the surrounding pixels, choose On.

5 (Optional) Specify the paint application options:

- To paint continuously, automatically conforming to the perspective from one plane to another, open the Vanishing Point menu and choose Allow Multi-Surface Operations. Turning this option off lets you paint in the perspective of one plane at a time. You need to stop and then start painting in a different plane to switch perspective.
- To confine painting to the active plane only, open the Vanishing Point menu and choose Clip Operations To Surface Edges. Turning this option off lets you paint in perspective beyond the boundaries of the active plane.

6 Drag in the image to paint. When painting in a plane, the brush size and shape scales and orients properly to the plane's perspective. Shift-drag constrains the stroke to a straight line that conforms to the plane's perspective. You can also click a point with the Brush tool and then Shift-click another point to paint a straight line in perspective.

The Brush tool honors marquee selections and can be used to paint a hard line along the edge of the selection. For example, if you select an entire plane, you can paint a line along the perimeter of the plane.

Paint with sampled pixels in Vanishing Point

In Vanishing Point, the Stamp tool paints with sampled pixels. The cloned image is oriented to the perspective of the plane you're painting in. The Stamp tool is useful for such tasks as blending and retouching image areas, cloning portions of a surface to "paint out" an object, or cloning an image area to duplicate an object or extend a texture or pattern.

1 In Vanishing Point, select the Stamp tool .

2 In the tool options area, set the Diameter (brush size), Hardness (the amount of feathering on the brush), and Opacity (the degree that the painting obscures or reveals the image beneath it).

3 Choose a blending mode from the Heal menu:

- To prevent the strokes from blending with the colors, shadows, and textures of the surrounding pixels, choose Off.
- To blend the strokes with the lighting of the surrounding pixels, choose Luminance.
- To blend the strokes with the color, lighting, and shading of surrounding pixels, choose On.

4 To determine the sampling behavior of the Stamp tool:

- Select Aligned to sample pixels continuously, without losing the current sampling point even when you release the mouse button.
- Deselect Aligned to continue using the sampled pixels from the initial sampling point each time you stop and resume painting.

5 (Optional) Specify the paint application options:

- To paint continuously from one plane to another, open the Vanishing Point menu and choose Allow Multi-Surface Operations.
- To confine painting to the active plane only, open the Vanishing Point menu and choose Clip Operations To Surface Edges.

6 Move the pointer into a plane and Alt-click (Windows) or Option-click (Mac OS) to set the sampling point.

7 Drag over the area of the image you want to paint. Hold the Shift key down to drag a straight line that conforms to the plane's perspective. You can also click a point with the Stamp tool and then Shift-click another point to paint a straight line in perspective.

Measure in Vanishing Point

Users ranging from architects and interior decorators to forensic scientists and woodworkers often need to know the size of objects in an image. In Vanishing Point, the Measure tool lets you draw a measurement line over an object in a perspective plane that you know the size of. The Measure tool has an option for entering a length for the measurement. The measurement line displays two text boxes: one for the length and one showing the angle that the line was drawn relative to the perspective plane. Once the measurement and its length have been set, all subsequent measurements correctly scale to your initial measurement.

There's an option for linking the line's measurement length with the grid spacing of the perspective plane. For example, a measurement length of 5 causes the grid to display 5 spaces, when the link option is selected. This might be useful for visualizing sizes in the image or for counting objects in an image. When unlinked, the grid spacing can be adjusted independent of the measurement. This option is useful in such instances where you find that the grid spacing is too small and visually confusing when linked to the measurement.

The measurements you create can be rendered so they appear in the image after you close the Vanishing Point dialog box. You can also export your measurements and geometric information to formats that can be read by CAD applications.

Measure objects in an image

1 In Vanishing Point, select the Measure tool and then click and drag over an object in a plane.

   It's best to make your initial measurement of an object that you know the size of.

   Note: *Once you start creating a measurement from within a plane, it's possible to continue drawing the measurement beyond the plane boundaries.*

2 With a measurement selected, enter a Length value to set its measured length.

3 (Optional) Draw additional measurements.

   The size of these measurements are scaled to the size of your initial measurement.

4 (Optional) Do one of the following:

   - If you want the size of the grid to be independent of the Length value you assigned to the initial measurement, make sure Link Measurements To Grid is deselected. This is the default setting.
   - If you want the size of the grid to adjust according to the Length value you assigned to the initial measurement, select Link Measurements To Grid.

   Vanishing Point measurements in an image are preserved after closing the dialog box. They appear when you launch Vanishing Point again.

Automatically drawing a measurement in Vanishing Point

The Measure tool can automatically draw the length and width measurements of a surface that's defined by a perspective plane.

? Double-click the Measure tool in a perspective plane.

Move a measurement in Vanishing Point

In Vanishing Point, you can move a measurement line without changing its orientation (angle) or length.

1 Select the Measure tool.

2 Click anywhere along the length of an existing measurement and drag.

Change the length or orientation of a measurement

You can change the length or orientation (angle) of an existing measurement.

1 Select the Measure tool and move it over the end point of an existing measurement line.

2 Do any of the following:

- To change the orientation and length of a measurement, drag an end point.
- To change the length of a measurement and constrain its angle changes to 15 degree increments, Ctrl-drag (Windows) or Command-drag (Mac OS) an end point.
- To change the length of a measurement without changing its orientation, Alt-drag (Windows) or Option-drag (Mac OS) an end point.
- To change the orientation of a measurement without changing its length, Shift-drag an end point.

Delete a measurement in Vanishing Point

? Select a measurement and press Backspace (Windows only) or Delete.

Show or hide measurements in Vanishing Point

? Open the Vanishing Point menu and choose Show Measurements.

Render measurements in Photoshop

The Vanishing Point measurements are invisible when viewing an image in the Photoshop document window, even though the measurements are preserved in the image and appear whenever you launch Vanishing Point. Measurements can be rendered so when you finish working in Vanishing Point, they're visible in the Photoshop document window. The rendered measurements are raster not vector.

? Open the Vanishing Point menu and choose Render Measurements To Photoshop.

The Render Measurements To Photoshop command must be chosen for each Vanishing Point session.

Create a new layer for your Vanishing Point results if you plan to render the measurements to Photoshop. This keeps the measurements on a separate layer from the main image.

More Help topics

Content-aware scaling

Resize images and protect content

Content-Aware Scale resizes an image without changing important visual content such as people, buildings, animals, and so forth. While normal scaling affects all pixels uniformly when resizing an image, content-aware scaling mostly affects pixels in areas that don't have important visual content. Content-Aware Scale lets you upscale or downscale images to improve a composition, fit a layout, or change the orientation. If you want to use some normal scaling when resizing your image, there is an option for specifying a ratio of content-aware scaling to normal scaling.

If you want to preserve specific areas when scaling an image, Content-Aware Scale lets you use an alpha channel to protect content during resizing.

Content-aware scaling works on layers and selections. Images can be in RGB, CMYK, Lab, and Grayscale color modes as well as all bit depths. Content-aware scaling doesn't work on adjustment layers, layer masks, individual channels, Smart Objects, 3D layers, Video layers, multiple layers simultaneously, or layer groups.

***A** Original image **B** Scaled narrower **C** Scaled narrower, using content-aware scaling*

For a video tutorial, see Photoshop and Content-Aware Scale.

Preserve visual content when scaling images

1 (Optional) Choose Select > All if you're scaling a Background layer.

2 Choose Edit > Content-Aware Scale.

3 Specify any of the following in the options bar:

Reference Point Location Click a square on the reference point locator to specify the fixed point around which the image is scaled. By default this point is at the center of the image.

Use Relative Positioning For Reference Point Click the button to specify the new position of the reference point in relation to its current position.

Reference Point Position Positions the reference point at the specific location. Enter X-axis and Y-axis pixel dimensions.

Scaling Percentage Specifies the image scaling as a percentage of the original size. Enter a percentage for the width (W) and height (H). If desired, click Maintain Aspect Ratio .

Amount Specifies the ratio of content-aware scaling to normal scaling. Specify a percentage for content-aware scaling by typing in the text box or clicking the arrow and moving the slider.

Protect Chooses an alpha channel that specifies an area to protect.

Protect Skin Tones Attempts to preserve regions that contain skin-tones.

4 Drag a handle on the bounding box to scale the image. Press Shift as you drag a corner handle to scale proportionately. When positioned over a handle, the pointer becomes a double arrow.

5 Click either Cancel Transform or Commit Transform .

Specify content to protect when scaling

1 Make a selection around the content you want to protect and then, in the Channels panel, click Save Selection As Channel .
2 (Optional) Choose Select > All if you're scaling a Background layer.
3 Choose Edit > Content-Aware Scale.
4 In the options bar, choose the alpha channel you created.
5 Drag a handle on the bounding border to scale the image.

More Help topics

Content-aware patch and move

Tutorial: Fix photos with Content-Aware

Tutorial: Remove that object

Tutorial: Fix photos with Content-Aware

Use the Liquify filter

Liquify filter overview

The Liquify filter lets you push, pull, rotate, reflect, pucker, and bloat any area of an image. The distortions you create can be subtle or drastic, which makes the Liquify command a powerful tool for retouching images as well as creating artistic effects. The Liquify filter can be applied to 8-bits per-channel or 16-bits per-channel images.

Tools, options, and an image preview for the Liquify filter are available in the Liquify dialog box. To display the dialog box, choose Filter > Liquify. Select Advanced Mode to access more options.

Magnify or reduce the preview image

? Select the Zoom tool in the Liquify dialog box, and click or drag in the preview image to zoom in; hold down Alt (Windows) or Option (Mac OS), and click or drag in the preview image to zoom out. Alternatively, you can specify a magnification level in the Zoom text box at the bottom of the dialog box.

Navigate in the preview image

? Select the Hand tool in the Liquify dialog box, and drag in the preview image. Alternatively, hold down the spacebar with any tool selected, and drag in the preview image.

Liquify filter enhancements (Creative Cloud only)

In the Creative Cloud version of Photoshop, the Liquify filter is significantly faster than previous versions.The Liquify filter now supports Smart Objects, including Smart Object video layers, and is applied as a smart filter.

Another enhancement to the Liquify filter is an added behavior for the Reconstruct tool. If you hold down the alt (Windows) or Option (Mac OS) key while dragging the tool across a warp, the Reconstruct tool smooths a warp rather than scaling back or removing it.

Applying Liquify as a smart filter (Creative Cloud only)

The Liquify filter supports Smart Objects, including Smart Object video layers, and is applied as a smart filter. When applying the Liquify filter to a Smart Object, meshes are now automatically saved into your document. Meshes applied to Smart Objects are compressed and re-editable when reapplying the Liquify filter. Keep in mind that the embedded meshes, even compressed ones, increase the file size.

To apply the Liquify filter as a smart filter:

1. In the Layers panel, select a Smart Object layer.
2. Choose Filter > Liquify.

Distortion tools

Several tools in the Liquify dialog box distort the brush area when you hold down the mouse button or drag. The distortion is concentrated at the center of the brush area, and the effect intensifies as you hold down the mouse button or repeatedly drag over an area.

Forward Warp tool

Pushes pixels forward as you drag.

Shift-click with the Warp tool, the Push Left tool, or the Mirror tool to create the effect of dragging in a straight line from the previous point you clicked.

Reconstruct tool

Reverses the distortion you've already added, as you hold down the mouse button and drag.

Twirl Clockwise tool

Rotates pixels clockwise as you hold down the mouse button or drag. To twirl pixels counterclockwise, hold down Alt (Windows) or Option (Mac OS) as you hold down the mouse button or drag.

Pucker tool

Moves pixels toward the center of the brush area as you hold down the mouse button or drag.

Bloat tool

Moves pixels away from the center of the brush area as you hold down the mouse button or drag.

Push Left tool

Moves pixels to the left when you drag the tool straight up (pixels move to the right if you drag down). You can also drag clockwise around an object to increase its size, or drag counterclockwise to decrease its size. To push pixels right when you drag straight up (or to move pixels left when you drag down), hold down Alt (Windows) or Option (Mac OS) as you drag.

Distortion tool options

In the tool options area of the dialog box, set the following options:

Brush Size Sets the width of the brush you'll use to distort the image.

Brush Density Controls how a brush feathers at the edge. An effect is strongest in the center of the brush and lighter at the edge.

Brush Pressure Sets the speed at which distortions are made when you drag a tool in the preview image. Using a low brush pressure makes changes occur more slowly, so it's easier to stop them at exactly the right moment.

Brush Rate Sets the speed at which distortions are applied when you keep a tool (such as the Twirl tool) stationary in the preview image. The higher the setting, the greater the speed at which distortions are applied.

Stylus Pressure Uses pressure readings from a stylus tablet. (This option is available only when you are working with a stylus tablet.) When selected, the brush pressure for the tools is the stylus pressure multiplied by the Brush Pressure value.

Distort an image

Note: *If a type layer or a shape layer is selected, you must rasterize the layer before proceeding, making the type or shape editable by the Liquify filter. To distort type without rasterizing the type layer, use the Warp options for the Type tool.*

1. Select the layer you want to distort. To change only part of the current layer, select that area.
2. Choose Filter > Liquify.
3. Freeze areas of the image that you don't want to alter.
4. Choose any of the liquify tools to distort the preview image. Drag in the preview image to distort the image.
5. After distorting the preview image, you can:
   - Use the Reconstruct tool or Reconstruct Options to fully or partially reverse the changes.
   - Use other tools to change the image in new ways.
6. Do one of the following:
   - Click OK to close the Liquify dialog box and apply the changes to the active layer.
   - Click Cancel to close the Liquify dialog box without applying changes to the layer.
   - Hold down Alt (Windows) or Option (Mac OS) and click Reset to revert all distortions to the preview image and reset all options to their defaults.

You can use the Edit > Fade command to create additional effects.

Freeze and thaw areas

You can freeze areas that you don't want to modify or thaw frozen areas to make them editable again. You can also invert both frozen and thawed areas.

Freeze areas

By freezing areas of the preview image, you protect those areas from changes. Frozen areas are covered by a mask that you paint using the Freeze Mask tool . You can also use an existing mask, selection, or transparency to freeze areas. You can view the mask in the preview image to help you apply distortions.

Using the Freeze Mask tool Select the Freeze Mask tool and drag over the area you want to protect. Shift-click to freeze in a straight line between the current point and the previously clicked point.

Using an existing selection, mask, or transparency channel If you're applying the Liquify filter to a layer with a selection, layer mask, transparency, or alpha channel, choose Selection, Layer Mask, Transparency, or Quick Mask from any of the five icons' pop-up menu in the Mask Options area of the dialog box. This determines how areas of the preview image are frozen or masked.

Freezing all thawed areas Click Mask All in the Mask Options area of the dialog box.

Inverting thawed and frozen areas Click Invert All in the Mask Options area of the dialog box.

Showing or hiding frozen areas Select or deselect Show Mask in the View Options area of the dialog box.

Changing the color of frozen areas Choose a color from the Mask Color pop-up menu in the View Options area of the dialog box.

Mask options with the Liquify filter

When you have an existing selection, transparency, or mask in an image, that information is retained when the Liquify dialog box opens. You can choose one of the following mask options:

Replace Selection

Shows the selection, mask, or transparency in the original image.

Add To Selection

Shows the mask in the original image, so that you can add to the selection using the Freeze Mask tool. Adds selected pixels in channel to the current frozen area.

Subtract From Selection

Subtracts pixels in channel from the current frozen area.

Intersect With Selection

Uses only pixels that are selected and currently frozen.

Invert Selection

Uses selected pixels to invert the current frozen area.

Note: *If a selection exists, the filter limits the preview and processing to the rectangular area containing that selection. (For rectangular marquee selections, the selected area and preview are identical, so choosing Selection from the mask option menus above has no effect.)*

Thaw areas

? To thaw frozen areas so they're editable, do any of the following:

- Select the Thaw Mask tool , and drag over the area. Shift-click to thaw in a straight line between the current point and the previously clicked point.
- To thaw all frozen areas, click the None button in the Mask Options area of the dialog box.
- To invert frozen and thawed areas, click Invert All in the Mask Options area of the dialog box.

Work with meshes

Using a mesh helps you see and keep track of distortions. You can choose the size and color of a mesh, and save the mesh from one image and apply it to other images.

- To show a mesh, select Show Mesh in the View Options area of the dialog box, and choose a mesh size and mesh color.
- To only show a mesh, select Show Mesh and then deselect Show Image.
- To save a distortion mesh, after distorting the preview image, click Save Mesh. Specify a name and location for the mesh file, and click Save.
- To apply a saved distortion mesh, click Load Mesh, select the mesh file you want to apply, and click Open. If the image and distortion mesh aren't the same size, the mesh is scaled to fit the image.
- To apply the last saved distortion mesh, click Load Last Mesh.
- (Creative Cloud) Meshes are automatically saved in your document. Meshes applied to Smart Objects are compressed and re-editable.

Note: *(Creative Cloud) Embedded meshes, even compressed ones, increase file size.*

Work with backdrops

You can choose to show only the active layer in the preview image, or you can show additional layers in the preview image as a backdrop. Using the Mode options, you can position the backdrop in front of or behind the active layer to keep track of your changes, or to line up a distortion with another distortion made in a different layer.

Note: *Only the active layer is distorted, even if other layers are displayed.*

Showing the backdrop Select Show Backdrop, and then choose Background from the Use menu and an option from the Mode menu.

Showing changes to the target layer without showing the backdrop Select All Layers from the Use menu. Setting the Opacity to 0 shows only the target layer with the full effects of the Liquify filter. Setting the Opacity to a higher value shows less of the Liquify filter's effect on the target layer.

Changing the blending between the target layer and the backdrop Specify a Opacity value.

Determining how the target layer and the backdrop are combined in the image preview Choose an option from the Mode menu.

Hiding the backdrop Deselect Show Backdrop in the View Options area of the dialog box.

Reconstruct distortions

After you distort the preview image, you can use a variety of controls and reconstruction modes to reverse changes or redo the changes in new ways. Reconstructions can be applied two ways. You can apply a reconstruction to the entire image, smoothing out the distortion in unfrozen areas, or you can use the reconstruction tool to reconstruct specific areas. If you want to prevent reconstruction of distorted areas, you can use the Freeze Mask tool.



A Original image ***B*** *Distorted with frozen areas* ***C*** *Reconstructed in Rigid mode (using button)* ***D*** *Thawed, edges reconstructed in Smooth mode (using tool)*

Reconstruct an entire image

Click Reconstruct in the Reconstruct Options area of the dialog box. Then, in the Revert Reconstruction dialog box, specify an amount and click OK.

Remove all distortions

? Click Restore All in the Reconstruct Option area of the dialog box. This removes distortions even in frozen areas.

Reconstruct part of a distorted image

1 Freeze areas you want to keep distorted.

2 Select the Reconstruct tool and specify brush options in the Tool Options area of the dialog box.

3 Drag over the area you want to reconstruct. Pixels move more quickly at the brush center. Shift-click to reconstruct in a straight line between the current point and the previously clicked point.

More Help topics

Blend and fade filter effects

Free transformations of images, shapes, and paths

You can use the Free Transform command to make your Facebook cover photo look amazing. See this tutorial to learn how: Make a creative Facebook cover photo .

Transform freely

The Free Transform command lets you apply transformations (rotate, scale, skew, distort, and perspective) in one continuous operation. You can also apply a warp transformation. Instead of choosing different commands, you simply hold down a key on your keyboard to switch between transformation types.

Note: *If you are transforming a shape or entire path, the Transform command becomes the Transform Path command. If you are transforming multiple path segments (but not the entire path), the Transform command becomes the Transform Points command.*

1 Select what you want to transform.

2 Do one of the following:

- Choose Edit > Free Transform.
- If you are transforming a selection, pixel-based layer, or selection border, choose the Move tool . Then select Show Transform Controls in the options bar.
- If you are transforming a vector shape or path, select the Path Selection tool . Then select Show Transform Controls in the options bar.

3 Do one or more of the following:

- To scale by dragging, drag a handle. Press Shift as you drag a corner handle to scale proportionately.
- To scale numerically, enter percentages in the Width and Height text boxes in the options bar. Click the Link icon to maintain the aspect ratio.
- To rotate by dragging, move the pointer outside the bounding border (it becomes a curved, two-sided arrow), and then drag. Press Shift to constrain the rotation to 15° increments.
- To rotate numerically, enter degrees in the rotation text box in the options bar.
- To distort relative to the center point of the bounding border, press Alt (Windows) or Option (Mac OS), and drag a handle.
- To distort freely, press Ctrl (Windows) or Command (Mac OS), and drag a handle.
- To skew, press Ctrl+Shift (Windows) or Command+Shift (Mac OS), and drag a side handle. When positioned over a side handle, the pointer becomes a white arrowhead with a small double arrow.
- To skew numerically, enter degrees in the H (horizontal skew) and V (vertical skew) text boxes in the options bar.
- To apply perspective, press Ctrl+Alt+Shift (Windows) or Command+Option+Shift (Mac OS), and drag a corner handle. When positioned over a corner handle, the pointer becomes a gray arrowhead.
- To warp, click the Switch Between Free Transform And Warp Modes button in the options bar. Drag control points to manipulate the shape of the item or choose a warp style from the Warp pop-up menu in the options bar. After choosing from the Warp pop-up menu, a square handle is available for adjusting the shape of the warp.
- To change the reference point, click a square on the reference point locator in the options bar.
- To move an item, enter values for the new location of the reference in the X (horizontal position) and Y (vertical position) text boxes in the options bar. Click the Relative Positioning button to specify the new position in relation to the current position.

To undo the last handle adjustment, choose Edit > Undo.

4 Do one of the following:

- Press Enter (Windows) or Return (Mac OS), click the Commit button in the options bar, or double-click inside the transformation marquee.
- To cancel the transformation, press Esc or click the Cancel button in the options bar.

Note: *When you transform a bitmap image (versus a shape or path), the image becomes slightly less sharp each time you commit a transformation; therefore, performing multiple commands before applying the cumulative transformation is preferable to applying each transformation separately.*

More Help topics

Transform objects

New Crop tool

Interactive previews help you precisely trim images down to size.

New Crop tool

Wide-angle lens correction

Quickly compensate for lens quirks, drawing from a detailed database.

Wide-angle lens correction

Correcting perspective

Fix photo angles fast.

Correcting perspective

Straightening a crooked image

Define the horizon line.

Straightening a crooked image

Chapter 12: Drawing and painting

Modify shapes

Modify rectangles and rounded rectangles

You can adjust dimensions and placement of a rectangle. In Photoshop CC, you can also modify the corner radii of rounded rectangle shapes after they have been drawn. Each corner can be adjusted independently and adjustments can be simultaneously made to rectangles on multiple layers.

Note: *If you select multiple rectangles, the values for the top-most rectangle are displayed in the Properties panel. The values you type are applied to all selected rectangles.*

1 Use the Path Selection Tool to select one or more rectangles or rounded rectangles.

2 To change the dimensions of the rectangle, type values in the W or H text boxes in the Properties panel or options bar.

   If you do not want to constrain the ratio of the width and height, click the link icon in the options bar to unlink the width and height.

3 To change the placement of the rectangle, do any of the following:

   - Move the contents of the layer using the Move tool.
   - Drag the rectangle using the Path Selection tool.
   - In the Properties panel, type the pixel coordinates into the X and Y text boxes.

4 In the Properties panel, do any of the following to modify the corner radius:

   - Type values in the text boxes to adjust the corner radii individually.
   - Type a value in the Radius text box to adjust all corners to the same radius.

   In the Properties panel, you can also place the pointer over a corner icon and scrub left or right to enter a radius value.

Set shape stroke options

1 Use the Path Selection tool to select the shape whose path you want to modify.

2 In the Properties panel or the tool options bar, click the Set Shape Stroke Type menu icon to open the Stroke Options panel.

3 In the Stroke Options panel, do any of the following:

   - Choose the type of stroke you want.
   - Click the Align icon and choose an option to specify the position of the stroke relative to its path.
   - Click the Caps icon and choose a cap style to specify the appearance of both ends of a path:

Butt cap Creates squared ends that abut (stop at) the endpoints.

Round cap Creates semicircular ends that extend half the stroke width beyond the endpoints.

Projecting cap Creates squared ends that extend half the stroke width beyond the endpoints. This option makes the stroke weight extend evenly in all directions around the path.

Note: Keep in mind that the caps are not visible unless the path is opened. Also, cap styles are easier to see at thicker stroke weights.

- Click the Corner icon to the appearance of the stroke at corner points:

Miter join Creates pointed corners that extend beyond the endpoint when the miter's length is within the miter limit.

Round join Creates rounded corners that extend half the stroke width beyond the endpoints.

Bevel join Creates squared corners that abut the endpoints.

Note: Like caps, miters are easier to see at thicker stroke weights.

Save stroke settings

After specifying the shape stroke options in the Stroke Options panel, you can save your newly created stroke type for reuse.

? Click the gear icon in the upper-right corner of the Stroke Options panel and choose Save Stroke.

Copy and paste shape stroke settings

After specifying shape stroke options, you can apply the settings to another shape by copying and pasting.

1. Click the gear icon in the upper-right corner of the Stroke Options panel and choose Copy Stroke Details.
2. Select the shape you want to modify.
3. In the Properties panel or tool options bar, click the Set Shape Stroke Type menu icon to open the Stroke Options panel.
4. Click the gear icon in the upper-right corner of the Stroke Options panel and choose Paste Stroke Details.

More Help topics

Draw shapes

Warp images, shapes, and paths

Tutorial: Edit rounded rectangles

About drawing

Understand shapes and paths

Drawing in Adobe Photoshop involves creating vector shapes and paths. In Photoshop, you can draw with any of the shape tools, the Pen tool, or the Freeform Pen tool. Options for each tool are available in the options bar.

Before you begin drawing in Photoshop, you must choose a drawing mode from the options bar. The mode you choose to draw in determines whether you create a vector shape on its own layer, a work path on an existing layer, or a rasterized shape on an existing layer.

Vector shapes are lines and curves you draw using the shape or pen tools. (See Draw shapesand Draw with the Pen tools.) Vector shapes are resolution-independent—they maintain crisp edges when resized, printed to a PostScript printer, saved in a PDF file, or imported into a vector-based graphics application. You can create libraries of custom shapes and edit a shape's outline (called a path) and attributes (such as stroke, fill color, and style).

Paths are outlines that you can turn into selections, or fill and stroke with color. You can easily change the shape of a path by editing its anchor points.

A work path is a temporary path that appears in the Paths panel and defines the outline of a shape.

You can use paths in several ways:

- Use a path as a vector mask to hide areas of a layer. (See About layer and vector masks.)
- Convert a path to a selection. (See Convert between paths and selection borders.)
- Fill or stroke a path with color. (See Fill paths with color.)

  Designate a saved path as a clipping path to make part of an image transparent when exporting the image to a page-layout or vector-editing application. (See Create transparency using image clipping paths.)

Drawing modes

When you work with the shape or pen tools, you can draw in three different modes. You choose a mode by selecting an icon in the options bar when you have a shape or pen tool selected.

Shape Layers Creates a shape on a separate layer. You can use either the shape tools or the pen tools to create shape layers. Because they are easily moved, resized, aligned, and distributed, shape layers are ideal for making graphics for web pages. You can choose to draw multiple shapes on a layer. A shape layer consists of a fill layer that defines the shape color and a linked vector mask that defines the shape outline. The outline of a shape is a path, which appears in the Paths panel.

Paths Draws a work path on the current layer that you can then use to make a selection, create a vector mask, or fill and stroke with color to create raster graphics (much as you would using a painting tool). A work path is temporary unless you save it. Paths appear in the Paths panel.

Fill Pixels Paints directly on a layer—much as a painting tool does. When you work in this mode, you're creating raster images—not vector graphics. You work with the shapes you paint just as you do with any raster image. Only the shape tools work in this mode.



A Shape Layers *B Paths* *C Fill Pixels*

More Help topics

Use the options bar

Draw shapes

The shape tools provide an easy way to create buttons, navigation bars, and other items used on web pages. For an overview of all drawing features in Photoshop, see About drawing .

Create a shape on a shape layer

1 Select a shape tool or a Pen tool. Make sure Shape is chosen from the menu in the options bar.

2 To choose the color of the shape, click the color swatch in the options bar, and then choose a color from the Color Picker.

3 (Optional) Set tool options in the options bar. Click the inverted arrow next to the shape buttons to view additional options for each tool. (See Shape tool options.)

4 (Optional) To apply a style to the shape, select a preset style from the Style pop-up menu in the options bar. (See Apply preset styles.)

5 Drag in your image to draw a shape:

- To constrain a rectangle or rounded rectangle to a square, to constrain an ellipse to a circle, or to constrain the line angle to a multiple of 45 degrees, hold down Shift.
- To draw from the center out, position the pointer where you want the center of the shape to be, press Alt (Windows) or Option (Mac OS), and then drag diagonally to any corner or edge until the shape is the desired size.



Note: *Drawing from the center out is the default behavior of the Star tool in Illustrator and the Polygon tool in Illustrator and Photoshop.*

Videos | Create, edit, and work

Photoshop team member **Jeanne Rubbo** shows you how to create, edit, and work with shape layers in a series of informative videos. Learn how to:

- Create a shape layer
- Edit the stroke and fill of a shape layer
- Edit multiple shape layers

- Drag shape paths between layers
- Combine shapes
- Work with subpaths
- Order subpaths
- Align subpaths

For more information, see .

Draw multiple shapes in a layer

You can draw separate shapes on a layer, or use the Add, Subtract, Intersect, or Exclude options to modify the current shape on a layer.

1 Select the layer to which you want to add shapes.

2 Select a drawing tool and set tool-specific options (see Shape tool options).

3 Choose one of the following in the options bar:

Add To Shape Area Adds the new area to the existing shapes or path.

Subtract From Shape Area Removes the overlapping area from the existing shapes or path.

Intersect Shape Areas Restricts the area to the intersection of the new area and the existing shapes or path.

Exclude Overlapping Shape Areas Excludes the overlap area in the consolidated new and existing areas.

4 Draw in the image. You can easily switch between drawing tools by clicking a tool button in the options bar.

Draw a wheel shape

You cut out a shape within an existing shape so that the layers underneath show through. This procedure shows you how to create a doughnut shape, but you can use this technique with any combination of the shape tools, including custom shapes.

1 Select the Ellipse tool in the toolbox. It may be hidden by one of the other shape tools or the Line tool .

2 Make sure Shape is chosen from the menu in the options bar.

3 Drag in the document window to draw the shape. Hold down the Shift key while dragging to constrain the ellipse to a circle.

4 In the options bar, select the Subtract From Shape Area button .

5 Drag within the new shape to create the cutout. When you release the mouse, the image underneath the new shape shows through.

6 To reposition either shape, click the Path Selection tool in the toolbox (it may be hidden by the Direct Selection tool), and select the path. Drag it to its new location or use the arrow keys on the keyboard to nudge it a pixel at a time.

Shift-click to select more than one path.

Draw a custom shape

You can draw custom shapes by using shapes from the Custom Shape pop-up panel, or save a shape or path to use as a custom shape.

1 Select the Custom Shape tool . (If the tool isn't visible, hold down the Rectangle tool near the bottom of the toolbox.)

2 Select a shape from the Custom Shape pop-up panel in the options bar.

   If you don't find a shape you want in the panel, click the arrow in the upper-right corner of the panel, and choose a different category of shapes. When asked to replace current shapes, click either Replace to view only the shapes in the new category or Append to add to the shapes already displayed.

3 Drag in your image to draw the shape.

Save a shape or path as a custom shape

1 In the Paths panel, select a path—either a vector mask for a shape layer, a work path, or a saved path.

2 Choose Edit > Define Custom Shape, and enter a name for the new custom shape in the Shape Name dialog box. The new shape appears in the Shape pop-up panel in the options bar.

3 To save the new custom shape as part of a new library, select Save Shapes from the pop-up panel menu.

For more information, see Work with the Preset Manager.

Create a rasterized shape

When you create a rasterized shape, you're drawing and rasterizing a shape and filling it with the foreground color. You cannot edit a rasterized shape as a vector object. Raster shapes are created using the current foreground color.

1 Select a layer. You cannot create a rasterized shape on a vector-based layer (for example, a type layer).

2 Select a shape tool, and click the Fill Pixels button in the options bar.

3 Set the following options in the options bar:

   Mode Controls how the shape will affect the existing pixels in the image. (See Blending modes.)

   Opacity Determines to what degree the shape will obscure or reveal the pixels beneath it. A shape with 1% opacity appears nearly transparent, while one with 100% opacity appears completely opaque.

   Anti-Aliased Smooths and blends the edge pixels with the surrounding pixels.

4 Set additional tool-specific options. See Shape tool options.

5 Draw the shape.

Shape tool options

Each shape tool provides a unique subset of the options below. To access these options, click the arrow to the right of the row of shape buttons in the options bar.



Arrowheads Start And End Adds arrowheads to a line. Select the Line tool and then select Start to add an arrow to the beginning of the line; select End to add an arrow to the end of the line. Select both options to add arrows to both ends. The shape options appear in the pop-up dialog box. Enter values for Width and Length to specify the proportions of the arrowhead as a percentage of the line width (10% to 1000% for Width, and 10% to 5000% for Length). Enter a value for the concavity of the arrowhead (from –50% to +50%). The concavity value defines the amount of curvature on the widest part of the arrowhead, where the arrowhead meets the line.

Note: *You can also edit an arrowhead directly using the vector selection and drawing tools.*

Circle Constrains an ellipse to a circle.

Defined Proportions Renders a custom shape based on the proportions with which it was created.

Defined Size Renders a custom shape based on the size at which it was created.

Fixed Size Renders a rectangle, rounded rectangle, ellipse, or custom shape as a fixed shape based on the values you enter in the Width and Height text boxes.

From Center Renders a rectangle, rounded rectangle, ellipse, or custom shape from the center.

Indent Sides By Renders a polygon as a star. Enter a percentage in the text box to specify the portion of the star's radius taken up by the points. A 50% setting creates points that are half the total radius of the star; a larger value creates sharper, thinner points; a smaller value creates fuller points.

Proportional Renders a rectangle, rounded rectangle, or ellipse as a proportional shape based on the values you enter in the Width and Height text boxes.

Radius For rounded rectangles, specifies the corner radius. For polygons, specifies the distance from the center of a polygon to the outer points.

Sides Specifies the number of sides in a polygon.

Smooth Corners or Smooth Indents Renders a polygon with smooth corners or indents.

Snap To Pixels Snaps edges of a rectangle or rounded rectangle to the pixel boundaries.

Square Constrains a rectangle or rounded rectangle to a square.

Unconstrained Lets you set the width and height of a rectangle, rounded rectangle, ellipse, or custom shape by dragging.

Weight Determines width, in pixels, for the Line tool.

To change stroke width for other shape tools, choose Layer > Layer Style > Stroke. (See Apply or edit a custom layer style.)

Edit shapes

A shape is a fill layer linked to a vector mask. You can easily change the fill to a different color, a gradient, or a pattern by editing the shape's fill layer. You can also edit the shape's vector mask to modify the shape outline, and apply a style to the layer.

- To change the color of a shape, double-click the shape layer's thumbnail in the Layers panel, and choose a different color using the Color Picker.
- To fill a shape with a pattern or gradient, select the shape layer in the Layers panel and choose Layer > Layer Style > Gradient Overlay.
- To change stroke width, select the shape layer in the Layers panel, and choose Layer > Layer Style > Stroke.
- To modify the outline of a shape, click the shape layer's vector mask thumbnail in the Layers panel or Paths panel. Then change the shape using the Direct Selection and pen tools.
- To move a shape without changing its size or proportions, use the Move tool.

For more information, see Adjust path componentsand Transform freely .

More Help topics

About drawing

Draw with the Pen tool

Painting tools

About painting tools, presets, and options

Adobe Photoshop provides several tools for painting and editing image color. The Brush tool and the Pencil tool work like traditional drawing tools applying color with brush strokes. Tools like the Eraser tool, Blur tool, and Smudge tool modify the existing colors in the image. In the options bar for each of these painting tools, you can set how color is applied to an image and choose from preset brush tips. See .

Brush and tool presets

You can save a set of brush options as a preset so you can quickly access brush characteristics you use frequently. Photoshop includes several sample brush presets. You can start with these presets and modify them to produce new effects. Many original brush presets are available for download on the web.

You can quickly choose presets from the Brush Preset picker in the options bar, which lets you temporarily modify the size and hardness of a brush preset.

Save tool presets when you want to store customized brush tip characteristics along with settings from the options bar such as opacity, flow, and color. To learn more about tool presets, see Tool presets.

Brush tip options

Along with settings in the options bar, brush tip options control how color is applied. You can apply color gradually, with soft edges, with large brush strokes, with various brush dynamics, with different blending properties, and with brushes of different shapes. You can apply a texture with your brush strokes to simulate painting on canvas or art papers. You can also simulate spraying paint with an airbrush. You use the Brush panel to set brush tip options. See Brush panel overview.

If you work with a drawing tablet, you can control how color is applied using pen pressure, angle, rotation, or a stylus wheel. You set options for drawing tablets in the Brush panel and options bar.

Paint with the Brush tool or Pencil tool

The Brush tool and the Pencil tool paint the current foreground color on an image. The Brush tool creates soft strokes of color. The Pencil tool creates hard-edged lines.

Note: *The Rotation tool rotates the canvas, which can facilitate easier painting. See Use the Rotate View tool.*

1 Choose a foreground color. (See Choose colors in the toolbox.)

2 Select the Brush tool or Pencil tool .

3 Choose a brush from the Brush Presets panel. See Select a preset brush.

4 Set tool options for mode, opacity, and so on, in the options bar.

5 Do one or more of the following:

- Click and drag in the image to paint.
- To draw a straight line, click a starting point in the image. Then hold down Shift, and click an ending point.
- When using the Brush tool as an airbrush, hold down the mouse button without dragging to build up color.

Paint tool options

Set the following in the options bar. Options available vary with each tool.

Mode Sets the method for blending the color you paint with the underlying existing pixels. Available modes change with the currently selected tool. Paint modes are similar to layer blending modes. See Blending modes.

Opacity Sets the transparency of color you apply. As you paint over an area, the opacity does not exceed the set level no matter how many times you move the pointer over the area, until you release the mouse button. If you stroke over the area again, you apply additional color, equivalent to the set opacity. Opacity of 100 percent is opaque.

Flow Sets the rate at which color is applied as you move the pointer over an area. As you paint over an area, while holding down the mouse button, the amount of color builds up based on the flow rate, up to the opacity setting. For example, if you set the opacity to 33% and the flow to 33%, each time you move over an area, its color moves 33% toward the brush color. The total will not exceed 33% opacity unless you release the mouse button and stroke over the area again.

Press a single number key to set a tool's opacity in multiples of 10% (pressing 1 sets it to 10%; pressing 0 sets it to 100%). Press two number keys to set a specific opacity. To set Flow, press Shift and number keys.

Airbrush

Simulates painting with an airbrush. As you move the pointer over an area, paint builds up as you hold down the mouse button. Brush hardness, opacity, and flow options control how fast and how much the paint is applied. Click the button to turn on or off this option.

Auto erase (Pencil tool only) Paints the background color over areas containing the foreground color. Select the foreground color you want to erase and the background color you want to change to. (See Auto Erase with the Pencil tool.)

Tablet pressure buttons

Use stylus pressure to override opacity and size settings in the Brush panel.

Selecting a cursor preference

The painting tools have three possible cursors: the standard cursor (the icon from the toolbox), a cross hair +, and a cursor that matches the size and shape of the currently selected brush tip.

1 Choose Edit > Preferences > Cursors (Windows) or Photoshop > Preferences > Cursors (Mac OS).

2 Select the desired cursors in both the Painting Cursors area and the Other Cursors area. The sample cursors change to reflect your choices. For a Brush Tip cursor, choose a size and whether to include a cross hair in the cursor.

- Normal Brush Tip restricts the cursor size to areas of the brush stroke that have 50% or more opacity.
- Full Size Brush Tip sizes the cursor to the entire area affected by the brush stroke. For soft brushes, this produces a larger cursor size than the Normal setting, to include the areas of the brush stroke with lighter opacity.

To combine different types of cursors, select Show Crosshair In Brush Tip or Show Only Crosshair While Painting. Or, for the Pen and Brush tools, press the Caps Lock to toggle between the standard cursor and the cross hair.

More Help topics

Select and display tools

Creating and modifying brushes

Erodible tip options

Creating and managing patterns

Erasing parts of an image

Painting stylized strokes with the Art History Brush

Painting with a pattern

Painting with the Mixer Brush

Create and modify brushes

You can create brushes that apply paint to images in a variety of ways. You select an existing preset brush, a brush tip shape, or create a unique brush tip from part of an image. You choose options from the Brush panel to specify how the paint is applied.

Brush panel overview

In the Brush panel, you can select preset brushes from the Brush Presets panel, but you can also modify existing brushes and design new custom brushes. The Brush panel contains the brush tip options that determine how paint is applied to an image.

The brush stroke preview at the bottom of the panel shows how paint strokes look with the current brush options.



A Locked B Unlocked C Selected brush tip D Brush settings E Brush stroke preview F Pop-up menu G Brush tip shapes (available when Brush Tip Shape option is selected) H Brush options

Display the Brush panel and brush options

1 Choose Window > Brush. Or, select a painting, erasing, toning, or focus tool, and click the panel button on the left side of the options bar.

2 Select an option set on the left side of the panel. The available options for the set appear on the right side of the panel.

Click the checkbox to the left of the option set to enable or disable the options without viewing them.

Create a brush tip from an image

1 Using any selection tool, select the image area you want to use as a custom brush. The brush shape can be up to 2500 pixels by 2500 pixels in size.

When painting, you can't adjust the hardness of sampled brushes. To create a brush with sharp edges, set Feather to zero pixels. To create a brush with soft edges, increase the Feather setting.

Note: *If you select a color image, the brush tip image is converted to grayscale. Any layer mask applied to the image doesn't affect the definition of the brush tip.*

2 Choose Edit > Define Brush Preset.

3 Name the brush, and click OK.

Create a brush and set painting options

1 Select a painting, erasing, toning, or focus tool. Then choose Window > Brush.

2 In the Brush panel, select a brush tip shape, or click Brush Presets to choose an existing preset.

3 Select Brush Tip Shape on the left side of the Brush panel, and set options.

4 To set other options for the brush, see the following topics:

- Add dynamic elements to brushes
- Brush scattering
- Create textured brushes
- Color dynamics brush options
- Draw or paint with a graphics tablet

5 To lock brush tip shape attributes (retaining them if you select another brush preset), click the unlock icon . To unlock the tip, click the lock icon .

6 To save the brush for use later, choose New Brush Preset from the Brush panel menu.

Note: *To save your new brush permanently or distribute it to other users, you must save the brush as part of a set of brushes. Choose Save Brushes from the Brush Presets panel menu, and then save to a new set or overwrite an existing set. If you reset or replace the brushes in the Brush Presets panel without saving it in a set, you could lose your new brush.*

Standard brush tip shape options

For standard brush tips, you can set the following options in the Brush panel:

Size Controls the size of the brush. Enter a value in pixels or drag the slider.



Use Sample Size Resets the brush to its original diameter. This option is available only if the brush tip shape was created by sampling pixels in an image.

Flip X Changes the direction of a brush tip on its *x* axis.



A *Brush tip in its default position* ***B*** *Flip X selected* ***C*** *Flip X and Flip Y selected*

Flip Y Changes the direction of a brush tip on its *y* axis.

A B C

A Brush tip in its default position ***B*** *Flip Y selected* ***C*** *Flip Y and Flip X selected*

Angle Specifies the angle by which an elliptical or sampled brush's long axis is rotated from horizontal. Type a value in degrees, or drag the horizontal axis in the preview box.



Roundness Specifies the ratio between the brush's short and long axes. Enter a percentage value, or drag the points in the preview box. A value of 100% indicates a circular brush, a value of 0% indicates a linear brush, and intermediate values indicate elliptical brushes.



Hardness Controls the size of the brush's hard center. Type a number, or use the slider to enter a value that is a percentage of the brush diameter. You can't change the hardness of sampled brushes.



Spacing Controls the distance between the brush marks in a stroke. To change the spacing, type a number, or use the slider to enter a value that is a percentage of the brush diameter. When this option is deselected, the speed of the cursor determines the spacing.



While using a preset brush, press the [key to decrease the brush width; press the] key to increase the width. For hard round, soft round, and calligraphic brushes, press Shift+[to decrease the brush hardness; press Shift+] to increase the brush hardness.

Bristle tip shape options

Bristle tips let you specify precise bristle characteristics, creating highly realistic, natural-looking strokes. Set the following brush tip shape options in the Brush panel:

Shape Determines the overall arrangement of bristles.

Bristles Controls overall bristle density.

Length Changes bristle length.

Thickness Controls the width of individual bristles.

Stiffness Controls bristle flexibility. At low settings, brush shape deforms easily.

To vary stroke creation when using a mouse, adjust the stiffness setting.

Spacing Controls the distance between the brush marks in a stroke. To change the spacing, type a number or use the slider to specify a percentage of the brush diameter. When this option is deselected, the speed of the cursor determines the spacing.

Angle When painting with a mouse, determines the brush tip angle.

Brush preview

Shows brush tip that reflects changes to settings above, as well as current pressure and stroke angle. Click the preview window to see the brush from different sides.

Erodible tip options

Erodible tip brushes behave similar to pencils and crayons, and wear down naturally as you draw. You can see the amount of wear with the Live Brush Tip Preview to the upper left of the image.

Size Controls the size of the brush. Enter a value in pixels or drag the slider.

Softness Controls the rate of wear. Enter a value in percentage or drag the slider.

Shape Controls the shape of the tip. Choose from a variety of tip options.

Sharpen Tip Returns the tip to the original sharpness.

Spacing Controls the distance between the brush marks in a stroke. To change the spacing, type a number or use the slider to specify a percentage of the brush diameter. When this option is deselected, the speed of the cursor determines the spacing.

Brush preview

Shows brush tip that reflects changes to settings above, as well as current pressure and stroke angle. Click the preview window to see the brush from different sides.

Airbrush tip options

Airbrush tips replicate spray cans with a 3D conical spray. With a stylus, you can alter the spread of sprayed strokes by changing pen pressure.

Size Controls the size of the brush. Enter a value in pixels or drag the slider.

Hardness Controls the size of the brush's hard center.

Distortion Controls the distortion to apply to the spray of paint.

Granularity Controls how grainy the paint drops look.

Spatter Size Controls the size of the paint droplets.

Spatter Amount Controls the number of paint droplets.

Spacing Controls the distance between the droplets. If this option is deselected, the speed of the cursor determines the spacing.

Brush preview

Shows brush tip that reflects changes to settings above, as well as current pressure and stroke angle. Click the preview window to see the brush from different sides.

Brush pose options

Brush pose options let you achieve stylus-like effects and let you control the angle and position of the brush.

Tilt X Determines the tilt angle of the brush from left to right.

Tilt Y Determines the tilt angle of the brush from front to back.

Rotation Determines the rotation angle of the bristles.

Pressure Determines the pressure the brush applies on the canvas.

Enable Override options to maintain a static brush pose.

Other brush options

Noise Adds additional randomness to individual brush tips. This option is most effective when applied to soft brush tips (brush tips that contain gray values).

Wet Edges Causes paint to build up along the edges of the brush stroke, creating a watercolor effect.

Airbrush/Build-up Applies gradual tones to an image, simulating traditional airbrush techniques. The Airbrush option in the Brush panel corresponds to the Airbrush option in the options bar.

Smoothing Produces smoother curves in brush strokes. This option is most effective when you are painting quickly with a stylus; however, it may produce a slight lag time in stroke rendering.

Protect Texture Applies the same pattern and scale to all brush presets that have a texture. Select this option to simulate a consistent canvas texture when painting with multiple, textured brush tips.

Brush scattering

Brush scattering determines the number and placement of marks in a stroke.



Scatter and Control Specifies how brush marks are distributed in a stroke. When Both Axes is selected, brush marks are distributed in a radial direction. When Both Axes is deselected, brush marks are distributed perpendicular to the stroke path.

To specify the maximum percentage of scattering, enter a value. To specify how you want to control the scattering variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the scattering variance of brush marks.

Fade Fades the scattering of brush marks from maximum scattering to no scattering in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the scattering of brush marks based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Count Specifies the number of brush marks applied at each spacing interval.

Note: *If you increase the count without increasing the spacing or scattering values, painting performance may decrease.*

Count Jitter and Control Specifies how the number of brush marks varies for each spacing interval. To specify the maximum percentage of brush marks applied at each spacing interval, enter a value. To specify how you want to control the count variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the count variance of brush marks.

Fade Fades the number of brush marks from the Count value to 1 in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the number of brush marks based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Clear brush options

You can clear all options that you changed for a brush preset (except brush shape settings) at once.

? Choose Clear Brush Controls from the Brush panel menu.

Manage paths

Paths panel overview

The Paths panel (Window > Paths) lists the name and a thumbnail image of each saved path, the current work path, and the current vector mask. Turning thumbnails off can improve performance. To view a path, you must first select it in the Paths panel.



***A** Saved path **B** Temporary work path **C** Vector mask path (appears only when shape layer is selected)*

Select a path

? Click the path name in the Paths panel. Only one path can be selected at a time.

Deselect a path

? Click in a blank area of the Paths panel or press Esc.

Change the size of path thumbnails

Choose Panel Options from the Paths panel menu, and select a size, or select None to turn off the display of thumbnails.

Change a path's stacking order

? Select the path in the Paths panel, and drag the path up or down. When the heavy black line appears in the desired location, release the mouse button.

***Note:** You cannot change the order of vector masks or working paths in the Paths panel.*

Create a new path in the Paths panel

- To create a path without naming it, click the Create New Path button at the bottom of the Paths panel.
- To create and name a path, make sure no work path is selected. Choose New Path from the Paths panel menu, or Alt-click (Windows) or Option-click (Mac OS) the New Path button at the bottom of the panel. Enter a name for the path in the New Path dialog box, and click OK.

Create a new work path

1. Select a shape tool or a pen tool, and click the Paths button in the options bar.
2. Set tool-specific options, and draw the path. For more information, see Shape tool optionsand About the Pen tools.
3. Draw additional path components if desired. You can easily switch between drawing tools by clicking a tool button in the options bar. Choose a path area option to determine how overlapping path components intersect:

   Add To Path Area Adds the new area to overlapping path areas.

   Subtract From Path Area Removes the new area from the overlapping path area.

   Intersect Path Areas Restricts the path to the intersection of the new area and the existing area.

   Exclude Overlapping Path Areas Excludes the overlap area in the consolidated path.

While drawing with a shape tool, hold down Shift to temporarily select the Add To Path Area option; hold down Alt (Windows) or Option (Mac OS) to temporarily select the Subtract From Path Area option.

Manage paths

When you use a pen or shape tool to create a work path, the new path appears as the work path in the Paths panel. The work path is temporary; you must save it to avoid losing its contents. If you deselect the work path without saving it and start drawing again, a new path will replace the existing one.

When you use a pen or shape tool to create a new shape layer, the new path appears as a vector mask in the Paths panel. Vector masks are linked to their parent layer; you must select the parent layer in the Layers panel in order to list the Vector mask in the Paths panel. You can remove a Vector mask from a layer and convert a Vector mask to a rasterized mask. For more information, see Mask layers with vector masks.

Paths saved with an image appear when you open it again. In Windows, JPEG, JPEG 2000, DCS, EPS, PDF, and TIFF formats support paths in Photoshop. In Mac OS, all available file formats support paths.

Note: *Paths in formats other than those listed here generally don't survive a transition from Mac OS to Windows and back to Mac OS.*

Save a work path

- To save without renaming, drag the *work path* name to the New Path button at the bottom of the Paths panel.
- To save and rename, choose Save Path from the Paths panel menu, enter a new path name in the Save Path dialog box, and click OK.

Rename a saved path

? Double-click the path name in the Paths panel, type a new name, and press Enter (Windows) or Return (Mac OS).

Delete a path

1 Click the path name in the Paths panel.

2 Do one of the following:

- Drag the path to the Delete icon at the bottom of the Paths panel.
- Choose Delete Path from the Paths panel menu.
- Click the Delete icon at the bottom of the Paths panel, and click Yes.

To delete a path without being asked to confirm, Alt-click (Windows) or Option-click (Mac OS) the Delete icon at the bottom of the Paths panel.

Generate a pattern using the Pattern Maker

Pattern Maker is an optional plug-in that you can download for Windows or Mac OS.

The Pattern Maker filter slices and reassembles an image to make a pattern. The Pattern Maker works in two ways:

- Fills a layer or selection with a pattern. The pattern can be made of one large tile, or multiple duplicate tiles.
- Creates tiles that you can save as a pattern preset and use with other images.

You can generate multiple patterns from the same sample until you find one that you like.

1 Pattern Maker is an optional plug-in. Download and install it for Windows or Mac OS.

Run Photoshop in 32-bit mode (64-bit Mac OS only) .

2 Do one of the following:

- Select the layer that contains the area from which you want to generate the pattern. The layer you select will be replaced by the generated pattern, so it's a good idea to make a copy of the layer first.
- To generate a pattern in a new layer or file, make a rectangular selection of the image you are using to generate the pattern, and choose Edit > Copy. Then add a layer to the image, or create a new file with the dimensions you want the final image to have.

3 Choose Filter > Pattern Maker.

4 Specify the source of the pattern.

- Choose Use Clipboard As Sample to use the contents of the clipboard if you copied an image before you opened the Pattern Maker.
- Make a selection in the preview area with the Pattern Maker's Marquee tool . To move the selection marquee, drag it to a different location.

Note: *You can use the Zoom and Hand tools to navigate in the preview area. Use Alt (Windows) or Option (Mac OS) with the Zoom tool to zoom out. The magnification appears at the bottom of the dialog box.*

5 Specify the tile size.

- Enter pixel dimensions in the Width and Height boxes.
- Click Use Image Size to generate a pattern with one tile that fills the layer.

6 Click Generate. You can press Esc to cancel the generation.

The preview area is tiled with the generated pattern.

- To switch between the generated preview and the source image, choose an option from the Show menu.
- To view the boundary of individual tiles, click Tile Boundaries.
- To offset the tiles in the generated pattern, choose a direction from the Offset pop-up menu and specify an offset amount in the Amount text box. The offset amount is a percentage of the tile dimension in the specified direction. The offset has no effect on saved pattern preset tiles.

7 Click Generate Again to generate additional patterns using the same options, or adjust the options and then click Generate Again.

Smoothness Adjusts the sharp edges in the pattern. Increase the smoothness to reduce edges.

Sample Detail Specifies the size of pattern slices in the tile. A high value maintains more of the original detail in the pattern. A low value uses smaller slices in the tile. Tiles take longer to generate when you use a high value.

8 Navigate through the generated tiles in the Tile History panel to select the tile that you want to use to fill the layer or to save as a pattern preset.

- To move through the tiles you've generated, click the First Tile button, Previous Tile button, Next Tile button, or Last Tile button. Or, type the number of the pattern preview you want to view, and press Enter (Windows) or Return (Mac OS).
- To view how the tile looks as a repeating pattern in the preview area, make sure that Update Pattern Preview is selected. If tile previewing is slow, deselect this option, find the tile you want, and then select the option.
- To delete a tile and pattern preview, navigate to the tile you want to delete, and click the Delete icon.

- To save a tile as a preset pattern, navigate to the tile you want to save, and click the Save Preset Pattern button. Enter a preset name, and click OK. When you save a tile as a preset pattern, only a single tile is saved, not the full, generated pattern.

***A** Save Preset Pattern **B** First Tile **C** Previous Tile **D** Next Tile **E** Last Tile **F** Delete icon*

9 When you are satisfied with a pattern preview and you have saved the tiles that you might want to use in the future, click OK to fill the layer or selection.

If you are creating preset patterns only, click Cancel to close the dialog box without filling the layer.

Gradients

destructive photo enhancements, make selections, cut out and mix
Phone or iPad.

Apply a gradient fill

The Gradient tool creates a gradual blend between multiple colors. You can choose from preset gradient fills or create your own.

Note: *You cannot use the Gradient tool with bitmap or indexed-color images.*

1 To fill part of the image, select the desired area. Otherwise, the gradient fill is applied to the entire active layer.

2 Select the Gradient tool . (If the tool isn't visible, hold down the Paint Bucket tool.)

3 In the options bar, choose a fill from the wide gradient sample:

- Click the triangle next to the sample to pick a preset gradient fill.
- Click inside the sample to view the Gradient Editor. Select a preset gradient fill, or create a new gradient fill. (See Create a smooth gradient.)

The Neutral Density preset provides a helpful photographic filter for sunsets and other high-contrast scenes.

4 Select an option to determine how the starting point (where the mouse is pressed) and ending point (where the mouse is released) affect gradient appearance.

Linear Gradient Shades from the starting point to the ending point in a straight line.



Radial Gradient Shades from the starting point to the ending point in a circular pattern.



Angular Gradient Shades in a counterclockwise sweep around the starting point.



Reflected Gradient Mirrors the same linear gradient on either side of the starting point.



Diamond Gradient Shades from the middle to the outer corners of a diamond pattern.



5 Do the following in the options bar:

- Specify a blending mode and opacity for the paint. (See Blending modes.)
- To reverse the order of colors in the gradient fill, select Reverse.
- To create a smoother blend with less banding, select Dither.
- To use a transparency mask for the gradient fill, select Transparency. (See Specify the gradient transparency.)

6 Position the pointer in the image where you want to set the starting point of the gradient, and drag to define the ending point. To constrain the line angle to a multiple of 45°, hold down Shift as you drag.

Manage gradient presets

Gradient presets allow you to quickly apply gradients that you use often. You can manage your presets in the Gradient Picker, Presets Manager, or Gradient Editor.

Save a set of preset gradients as a library

1 Click Save in the Gradient Editor dialog box, or choose Save Gradients from the Gradient Picker menu in the options bar.

2 Choose a location for the gradient library, enter a file name, and click Save.

You can save the library anywhere. However, if you place the library file in the Presets/Gradients folder in the default preset location, the library name will appear at the bottom of the panel menu after you restart Photoshop.

Load a library of preset gradients

? Do one of the following in the Gradient Editor dialog box:

- Click Load to add a library to the current list. Select the library file you want to use, and click Load.
- Choose Replace Gradients from the panel menu to replace the current list with a different library. Select the library file you want to use, and click Load.
- Choose a library file from the bottom of the panel menu. Click OK to replace the current list, or click Append to append the current list.

Note: *You can also choose Load Gradients, Replace Gradients, or choose a library of gradients from the Gradient Picker menu in the options bar.*

Return to the default library of preset gradients

? Choose Reset Gradients from the panel menu. You can either replace the current list or append the default library to the current list.

Change how preset gradients are displayed

? Choose a display option from the panel menu:

Text Only Displays the gradients as a list.

Small or Large Thumbnail Displays the gradients as thumbnails.

Small or Large List Displays the gradients as a list with thumbnails.

Rename a preset gradient

- If the panel is set to display gradients as thumbnails, double-click a gradient, enter a new name, and click OK.
- If the panel is set to display gradients as a list or text only, double-click a gradient, enter a new name inline, and press Enter (Windows) or Return (Mac OS).

Gradient Editor overview

To display the Gradient Editor dialog box, click the current gradient sample in the options bar. (When you hover over the gradient sample, a tool tip reading “Click to edit gradient” appears.)

The Gradient Editor dialog box lets you define a new gradient by modifying a copy of an existing gradient. You can also add intermediate colors to a gradient, creating a blend between more than two colors.



A Panel menu ***B*** *Opacity stop* ***C*** *Color stops* ***D*** *Adjust values or delete the selected opacity or color stop* ***E*** *Midpoint*

Create a smooth gradient

1 Select the Gradient tool .

2 Click inside the gradient sample in the options bar to display the Gradient Editor dialog box.

3 To base the new gradient on an existing gradient, select a gradient in the Presets section of the dialog box.

4 Choose Solid from the Gradient Type pop-up menu.

5 To define the starting color of the gradient, click the left color stop under the gradient bar. The triangle above the stop turns black , indicating that the starting color is being edited.

6 To choose a color, do one of the following:

- Double-click the color stop, or click the color swatch in the Stops section of the dialog box. Choose a color, and click OK.
- Choose an option from the Color pop-up menu in the Stops section of the dialog box.
- Position the pointer over the gradient bar (the pointer turns into the eyedropper), and click to sample a color, or click anywhere in the image to sample a color from the image.

7 To define the ending color, click the right color stop under the gradient bar. Then choose a color.

8 To adjust the location of the starting point or ending point, do one of the following:

- Drag the corresponding color stop left or right to the location you want.
- Click the corresponding color stop, and enter a value for Location in the Stops section of the dialog box. A value of 0% places the point at the far left end of the gradient bar; a value of 100%, at the far right end.

9 To adjust the location of the midpoint (where the gradient displays an even mix of the starting and ending colors), drag the diamond below the gradient bar to the left or right, or click the diamond, and enter a value for Location.

10 To add intermediate colors to a gradient, click below the gradient bar to define another color stop. Specify the color and adjust the location and midpoint for the intermediate point as you would for a starting or ending point.

11 To delete the color stop you are editing, click Delete, or drag the stop downwards until it disappears.

12 To control how gradual the transitions are between color bands in the gradient, enter a value in the Smoothness text box, or drag the Smoothness pop-up slider.

13 If desired, set transparency values for the gradient.

14 Enter a name for the new gradient.

15 To save the gradient as a preset, click New after you have finished creating the gradient.

__Note:__ New presets are saved in a Preferences file. If this file is deleted or damaged, or if you reset presets to the default library, the new presets will be lost. To permanently save new presets, save them in a library.

Specify the gradient transparency

Each gradient fill contains settings that control the opacity of the fill at different locations on the gradient. For example, you can set the starting color to 100% opacity and have the fill gradually blend into an ending color with 50% opacity. The checkerboard pattern indicates the amount of transparency in the gradient preview.

1 Create a gradient.

2 To adjust the starting opacity, click the left opacity stop above the gradient bar. The triangle below the stop turns black, indicating that the starting transparency is being edited.

3 In the Stops section of the dialog box, enter a value in the Opacity text box, or drag the Opacity pop-up slider.

4 To adjust the opacity of the end point, click the right transparency stop above the gradient bar. Then set the opacity in the Stops section.

5 To adjust the location of the starting or ending opacity, do one of the following:

- Drag the corresponding opacity stop to the left or right.
- Select the corresponding opacity stop, and enter a value for Location.

6 To adjust the location of the midpoint opacity (the point midway between the starting and ending opacities), do one of the following:

- Drag the diamond above the gradient bar to the left or right.
- Select the diamond and enter a value for Location.

7 To delete the opacity stop you are editing, click Delete.

8 To add an intermediate opacity to the mask, click above the gradient bar to define a new opacity stop. You can then adjust and move this opacity as you would for a starting or ending opacity. To remove an intermediate opacity, drag its transparency stop up and off the gradient bar.

9 To create a preset gradient, enter a name in the Name text box, and click New. This creates a new gradient preset with the transparency setting you specified.

Create a noise gradient

A noise gradient is a gradient that contains randomly distributed colors within the range of colors that you specify.

A 10% roughness *B 50% roughness* *C 90% roughness*

1 Select the Gradient tool .
2 Click in the gradient sample in the options bar to display the Gradient Editor dialog box.
3 To base the new gradient on an existing gradient, select a gradient in the Presets section of the dialog box.
4 Choose Noise from the Gradient Type pop-up menu, and set the following options:

   Roughness Controls how gradual the transitions are between color bands in the gradient.

   Color Model Changes the color components you can adjust. For each component, drag the sliders to define the range of acceptable values. For example, if you choose the HSB model, you can restrict the gradient to blue-green hues, high saturation, and medium brightness.

   Restrict Colors Prevents oversaturated colors.

   Add Transparency Adds transparency to random colors.

   Randomize Randomly creates a gradient that conforms to the settings above. Click the button until you find a setting you like.
5 To create a preset gradient with the settings you've specified, enter a name in the Name text box, and click New.

More Help topics

Work with the Preset Manager

Use the options bar

Fill and stroke selections, layers, and paths

You can fill the inside of a selection, path, or layer with a color or pattern. You can also add color to the outline of a selection or path, called stroking.

Fill with the Paint Bucket tool

The Paint Bucket tool fills adjacent pixels that are similar in color value to the pixels you click.

Note: *The Paint Bucket tool cannot be used with images in Bitmap mode.*

1 Choose a foreground color. (See Choose colors in the toolbox.)
2 Select the Paint Bucket tool .

   Note: *The Paint Bucket tool is grouped with the Gradient tool in the toolbar. If you can't find the Paint Bucket tool, click and hold the Gradient tool to access it.*
3 Specify whether to fill the selection with the foreground color or with a pattern.
4 Specify a blending mode and opacity for the paint. (See Blending modes.)
5 Enter the tolerance for the fill.

The tolerance defines how similar in color a pixel must be (to the pixel you click) to be filled. Values can range from 0 to 255. A low tolerance fills pixels within a range of color values very similar to the pixel you click. A high tolerance fills pixels within a broader range.

6 To smooth the edges of the filled selection, select Anti-aliased.

7 To fill only pixels contiguous to the one you click, select Contiguous; leave Contiguous unselected to fill all similar pixels in the image.

8 To fill pixels based on the merged color data from all visible layers, select All Layers.

9 Click the part of the image you want to fill. All specified pixels within the specified tolerance are filled with the foreground color or pattern.

If you're working on a layer and don't want to fill transparent areas, make sure that the layer's transparency is locked in the Layers panel. (See Lock layers.)

Fill a selection or layer with color

1 Choose a foreground or background color. (See Choose colors in the toolbox.)

2 Select the area you want to fill. To fill an entire layer, select the layer in the Layers panel.

3 Choose Edit > Fill to fill the selection or layer. Or to fill a path, select the path, and choose Fill Path from the Paths panel menu.

4 In the Fill dialog box, choose one of the following options for Use, or select a custom pattern:

Foreground Color, Background Color, Black, 50% Gray, or White Fills the selection with the specified color.

Note: *If you fill a CMYK image using the Black option, Photoshop fills all the channels with 100% black. This may result in more ink than is allowable by the printer. For best results when filling a CMYK image, use the Foreground option with the foreground color set to an appropriate black.*

Color Fills with a color you select from the Color Picker.

5 Specify the blending mode and opacity for the paint. (See Blending modes.)

6 If you're working in a layer and want to fill only areas containing pixels, choose Preserve Transparency.

7 Click the OK button to apply the fill.

To apply a foreground color fill only to the areas that contain pixels, press Alt+Shift+Backspace (Windows) or Option+Shift+Delete (Mac OS). This preserves the transparency of the layer. To apply a background color fill only to the areas that contain pixels, press Ctrl+Shift+Backspace (Windows) or Command+Shift+Delete (Mac OS).

Use Content-aware, pattern, or history fills

1 Select the part of the image you want to fill.

2 Choose Edit > Fill.

On the Background layer, press Delete or Backspace to quickly access the Fill dialog box.

3 From the Use menu, select one of the following:

Content-Aware Seamlessly fills the selection with similar image content nearby. For the best results, create a selection that extends slightly into the area you want to replicate. (A quick lasso or marquee selection is often sufficient.)

Content-aware fills randomly synthesize similar image content. If you don't like your original results, choose Edit > Undo, and apply another content-aware fill.

Color Adaptation Algorithmically blends the color of the fill with the surrounding color



Pattern Click the inverted arrow next to the pattern sample, and select a pattern from the pop-up panel. You can load additional patterns using the pop-up panel menu. Select the name of a library of patterns, or choose Load Patterns and navigate to the folder containing the patterns you want to use.

(CC, CS6) You can also apply one of five included Scripted Patterns to easily create a variety of geometic fill patterns. Select Scripted Patterns at the bottom of the fill dialog box, and then choose a fill pattern from the Script pop-up menu.

Note: *If Pattern is dimmed, you need to load a pattern library prior to making a selection. (See Manage pattern libraries and presets.)*

History Restores the selected area to the source state or snapshot set in the History panel.

A *Create selection that extends slightly into area you want to replicate.* ***B*** *Seamlessly replace selection with Content-aware fill.*

Fill the work canvas

The work canvas surrounds the image area. You can fill the canvas with a different color that contrasts better with a given image.

? Right-click the work canvas, and choose Gray, Black, or Custom. (To specify the custom color, choose Select Custom Color.)

Stroke a selection or layer with color

You can use the Stroke command to paint a colored border around a selection, path, or layer. When you create a border this way, it becomes a rasterized part of the current layer.

To create shape or layer borders that can be turned on or off like overlays and are anti-aliased to create softer-edged corners and edges, use the Stroke layer effect instead of the Stroke command. See Layer effects and styles.

1 Choose a foreground color.

2 Select the area or layer you want to stroke.

3 Choose Edit > Stroke.

4 In the Stroke dialog box, specify the width of the hard-edged border.

5 For Location, specify whether to place the border inside, outside, or centered over the selection or layer boundaries.

Note: *If the layer contents fill the entire image, a stroke applied outside the layer will not be visible.*

6 Specify an opacity and a blending mode. (See Blending modes.)

7 If you're working in a layer and want to stroke only areas containing pixels, select the Preserve Transparency option. (See Lock layers.)

Draw a circle or square

You can draw a circle or square using the elliptical or rectangular marquee tools, and then add a line (called a *stroke*) to the selection marquee. Stroking a selection is a quick way to add a border or frame around an object. You can stroke any selection you create with the selection tools.

1 In the Layers panel, click the New Layer button to create a new layer for the circle or square. Isolating the circle or square on its own layer makes it easier to work with.

2 Select the Elliptical Marquee tool or the Rectangular Marquee tool in the toolbox.

3 Drag in the document window to create the shape. Hold down the Shift key while dragging to constrain the shape to a circle or square.

4 Choose Edit > Stroke.

5 In the Stroke dialog box, type a value for Width, and then click the color swatch to display the Adobe Color Picker.

6 In the Adobe Color Picker, locate the color range you want using the triangle sliders on the color spectrum bar, and then click the desired color in the color field. The color you select appears in the top half of the color swatch. The original color remains in the bottom half. Click OK.

7 Set the location for the stroke in relationship to the marquee by choosing Inside, Center, or Outside. Adjust the other settings as desired, and click OK. Photoshop strokes the line using the color and stroke settings you set.

More Help topics

Video | Retouch photos with Content-Aware

Change the canvas size

Stroke paths with color

Draw with the Pen tools

About the Pen tools

Photoshop provides multiple Pen tools. The standard Pen tool draws with the greatest precision; the Freeform Pen tool draws paths as if you were drawing with pencil on paper, and the magnetic pen option lets you draw a path that snaps to the edges of defined areas in your image. You can use the pen tools in conjunction with the shape tools to create complex shapes. When you use the standard Pen tool, the following options are available in the options bar:

- Auto Add/Delete, which lets you add an anchor point when you click a line segment or delete an anchor point when you click it.
- Rubber Band, which lets you preview path segments as you move the pointer between clicks. (To access this option, click the pop-up menu to the right of the Custom Shape icon.)

Before drawing with the Pen tool, you can create a new path in the Paths panel to automatically save the work path as a named path.

For more information about the modes in which you can draw with the Pen tools, see Drawing modes.

Draw straight line segments with the Pen tool

The simplest path you can draw with the Pen tool is a straight line, made by clicking the Pen tool to create two anchor points. By continuing to click, you create a path made of straight line segments connected by corner points.





1 Select the Pen tool.

2 Position the Pen tool where you want the straight segment to begin, and click to define the first anchor point (do not drag).

   Note: *The first segment you draw will not be visible until you click a second anchor point. (Select the Rubber Band option in Photoshop to preview path segments.) Also, if direction lines appear, you've accidentally dragged the Pen tool; choose Edit > Undo, and click again.*

3 Click again where you want the segment to end (Shift-click to constrain the angle of the segment to a multiple of 45°).

4 Continue clicking to set anchor points for additional straight segments.

   The last anchor point you add always appears as a solid square, indicating that it is selected. Previously defined anchor points become hollow, and deselected, as you add more anchor points.

5 Complete the path by doing one of the following:

- To close the path, position the Pen tool over the first (hollow) anchor point. A small circle appears next to the Pen tool pointer when it is positioned correctly. Click or drag to close the path.
- To leave the path open, Ctrl-click (Windows) or Command-click (Mac OS) anywhere away from all objects.

To leave the path open, you can also select a different tool.

Draw curves with the Pen tool

You create a curve by adding an anchor point where a curve changes direction, and dragging the direction lines that shape the curve. The length and slope of the direction lines determine the shape of the curve.

Curves are easier to edit and your system can display and print them faster if you draw them using as few anchor points as possible. Using too many points can also introduce unwanted bumps in a curve. Instead, draw widely spaced anchor points, and practice shaping curves by adjusting the length and angles of the direction lines.

1 Select the Pen tool.

2 Position the Pen tool where you want the curve to begin, and hold down the mouse button.

The first anchor point appears, and the Pen tool pointer changes to an arrowhead. (In Photoshop, the pointer changes only after you've started dragging.)

3 Drag to set the slope of the curve segment you're creating, and then release the mouse button.

In general, extend the direction line about one third of the distance to the next anchor point you plan to draw. (You can adjust one or both sides of the direction line later.)

Hold down the Shift key to constrain the tool to multiples of 45°.



***A** Positioning Pen tool **B** Starting to drag (mouse button pressed) **C** Dragging to extend direction lines*

4 Position the Pen tool where you want the curve segment to end, and do one of the following:

- To create a C-shaped curve, drag in a direction opposite to the previous direction line. Then release the mouse button.



- To create an S-shaped curve, drag in the same direction as the previous direction line. Then release the mouse button.



To change the direction of the curve sharply, release the mouse button, and then Alt-drag (Windows) or Option-drag (Mac OS) the direction point in the direction of the curve. Release the Alt (Windows) or Option (Mac OS) key and the mouse button, reposition the pointer where you want the segment to end, and drag in the opposite direction to complete the curve segment.

5 Continue dragging the Pen tool from different locations to create a series of smooth curves. Note that you are placing anchor points at the beginning and end of each curve, not at the tip of the curve.

Alt-drag (Windows) or Option-drag (Mac OS) direction lines to break out the direction lines of an anchor point.

6 Complete the path by doing one of the following:

- To close the path, position the Pen tool over the first (hollow) anchor point. A small circle appears next to the Pen tool pointer when it is positioned correctly. Click or drag to close the path.
- To leave the path open, Ctrl-click (Windows) or Command-click (Mac OS) anywhere away from all objects or select a different tool.

Finish drawing a path

? Complete a path in one of the following ways:

- To close a path, position the Pen tool over the first (hollow) anchor point. A small circle appears next to the Pen tool pointer when it is positioned correctly. Click or drag to close the path.
- To leave a path open, Ctrl-click (Windows) or Command-click (Mac OS) anywhere away from all objects.

Draw with the Freeform Pen tool

The Freeform Pen tool lets you draw as if you were drawing with a pencil on paper. Anchor points are added automatically as you draw. You do not determine where the points are positioned, but you can adjust them once the path is complete. To draw with greater precision, use the Pen tool.

1 Select the Freeform Pen tool .

2 To control how sensitive the final path is to the movement of your mouse or stylus, click the inverted arrow next to the shape buttons in the options bar, and enter a value between 0.5 and 10.0 pixels for Curve Fit. A higher value creates a simpler path with fewer anchor points.

3 Drag the pointer in the image. As you drag, a path trails behind the pointer. When you release the mouse, a work path is created.

4 To continue the existing freehand path, position the pen pointer on an end point of the path, and drag.

5 To complete the path, release the mouse. To create a closed path, drag the line to the initial point of the path (a circle appears next to the pointer when it is aligned).

Draw straight lines followed by curves

1 Using the Pen tool, click corner points in two locations to create a straight segment.

2 Position the Pen tool over the selected endpoint. A small diagonal line, or slash, appears next to the Pen tool. To set the slope of the curved segment you'll create next, click the anchor point, and drag the direction line that appears.



***A** Straight segment completed **B** Positioning Pen tool over endpoint **C** Dragging direction point*

3 Position the pen where you want the next anchor point; then click (and drag, if desired) the new anchor point to complete the curve.



***A** Positioning Pen tool **B** Dragging direction line **C** New curve segment completed*

Draw curves followed by straight lines

1 Using the Pen tool, drag to create the first smooth point of the curved segment, and release the mouse button.

2 Reposition the Pen tool where you want the curved segment to end, drag to complete the curve, and release the mouse button.

3 Select the Convert Point tool from the toolbox, and then click the selected end point to convert it from a smooth point to a corner point.

Press Alt (Windows) or Option (Mac OS) to temporarily change the Pen tool to the Convert Point tool.

4 Select the Pen tool from the toolbox, position the Pen tool where you want the straight segment to end, and click to complete the straight segment.

Draw two curved segments connected by a corner

1 Using the Pen tool, drag to create the first smooth point of a curved segment.

2 Reposition the Pen tool and drag to create a curve with a second smooth point; then press and hold Alt (Windows) or Option (Mac OS) and drag the direction line toward its opposing end to set the slope of the next curve. Release the key and the mouse button.

This process converts the smooth point to a corner point by splitting the direction lines.

3 Reposition the Pen tool where you want the second curved segment to end, and drag a new smooth point to complete the second curved segment.



***A** Dragging a new smooth point **B** Pressing Alt/Option to split direction lines while dragging, and swinging direction line up **C** Result after repositioning and dragging a third time*

Draw using the magnetic pen options

The Magnetic Pen is an option of the Freeform Pen tool that lets you draw a path that snaps to the edges of defined areas in your image. You can define the range and sensitivity of the snapping behavior, as well as the complexity of the resulting path. The Magnetic Pen and Magnetic Lasso tools share many of the same options.

1 To convert the Freeform Pen tool to the Magnetic Pen tool , select Magnetic in the options bar, or click the inverted arrow next to the shape buttons in the options bar, select Magnetic, and set the following:

- For Width, enter a pixel value between 1 and 256. The Magnetic Pen detects edges only within the specified distance from the pointer.
- For Contrast, enter a percentage value between 1 and 100 to specify the contrast required between pixels for that area to be considered an edge. Use a higher value for low-contrast images.
- For Frequency, enter a value between 0 and 100 to specify the rate at which the Pen sets anchor points. A higher value anchors the path in place more quickly.
- If you are working with a stylus tablet, select or deselect Pen Pressure. When this option is selected, an increase in pen pressure causes the width to decrease.

2 Click in the image to set the first fastening point.

3 To draw a freehand segment, move the pointer or drag along the edge you want to trace.

The most recent segment of the border remains active. As you move the pointer, the active segment snaps to the strongest edge in the image, connecting the pointer to the last fastening point. Periodically, the Magnetic Pen adds fastening points to the border to anchor previous sections.



4 If the border doesn't snap to the desired edge, click once to add a fastening point manually and to keep the border from moving. Continue to trace the edge and add fastening points as needed. If you make a mistake, press Delete to remove the last fastening point.

5 To dynamically modify the properties of the Magnetic Pen, do one of the following:
- Alt-drag (Windows) or Option-drag (Mac OS) to draw a freehand path.
- Alt-click (Windows) or Option-click (Mac OS) to draw straight segments.
- Press the open square bracket key ([) to decrease the Magnetic Pen width by 1 pixel; press the close square bracket key (]) to increase the pen width by 1 pixel.

6 Complete the path:
- Press Enter (Windows) or Return (Mac OS) to end an open path.
- Double-click to close the path with a magnetic segment.
- Hold down Alt (Windows) or Option (Mac OS), and double-click to close the path with a straight segment.

More Help topics

About drawing

Draw shapes

Create a new work path

Path segments, components, and points

Brush presets

A preset brush is a saved brush tip with defined characteristics, such as size, shape, and hardness. You can save preset brushes with the characteristics you use often. You can also save tool presets for the Brush tool that you can select from the Tool Preset menu in the options bar.

When you change the size, shape, or hardness of a preset brush, the change is temporary. The next time you choose that preset, the brush uses its original settings. To make your changes permanent, you need to create a new preset. See Create a new preset brush.

Select a preset brush

1 Select a painting or editing tool, and click the Brush pop-up menu in the options bar.

2 Select a brush.

Note: You can also select a brush from the Brush panel. To view the loaded presets, click Brush Presets in the upper left of the panel.

3 Change options for the preset brush.

Diameter Temporarily changes the brush size. Drag the slider or enter a value. If the brush has a dual tip, both the primary and dual brush tips are scaled.

Use Sample Size Uses the original diameter of the brush tip if the brush tip shape is based on a sample. (Not available for round brushes.)

Hardness (Available only for round and square brushes.) Temporarily changes the amount of anti-aliasing for the brush tool. At 100%, the brush tool paints with the hardest brush tip, but is still anti-aliased. The Pencil always paints a hard edge that is not anti-aliased.

Change how preset brushes are displayed

Choose a display option from the Brush Presets panel menu ≡:

- Text Only to view the brushes as a list.
- Small or Large Thumbnail to view the brushes as thumbnails.
- Small or Large List to view the brushes as a list with thumbnails.
- Stroke Thumbnail to view a sample brush stroke with each brush thumbnail.

To dynamically preview brush strokes in the Brush panel, position the pointer over a brush in the Brush Presets panel until the tool tip appears. As you move the pointer over different brushes, the preview area at the bottom of the Brush panel will display sample brush strokes.

Load, save, and manage brush presets

You can manage libraries of preset brushes to keep your brushes organized.

Change the displayed library of preset brushes

1 To load a library of preset brushes, choose one of the following from the Brush Presets panel menu.

- Load Brushes to add a library to the current list.
- Replace Brushes to replace the current list with a different library.
- A library file (displayed at the bottom of the panel menu). Click OK to replace the current list, or click Append to append the current list.

2 To return to the default library of preset brushes, choose Reset Brushes from the Brush Presets panel menu. You can either replace the current list or append the default library to the current list.

You can also use the Preset Manager to load and reset brush libraries. For more information, see Work with the Preset Manager.

Save a set of preset brushes as a library

1 Choose Save Brushes from the Brush Presets panel menu.

2 Choose a location for the brush library, enter a file name, and click Save.

You can save the library anywhere. However, if you place the library file in the Presets/Brushes folder in the default preset location, the library name will appear at the bottom of the Brush Presets panel menu after you restart Photoshop.

Rename a preset brush

Do one of the following:

- Select a brush in the Brush Presets panel, and choose Rename Brush from the panel menu. Enter a new name, and click OK.
- In the Brush panel, double-click a brush tip, enter a new name, and click OK.

Delete a preset brush

In the Brush Presets panel, do any of the following:

- Alt-click (Windows) or Option-click (Mac OS) the brush you want to delete.
- Select a brush, and choose Delete Brush from the panel menu, or click the Delete icon .

Create a new preset brush

You can save a customized brush as a preset brush that appears in the Brush Presets panel and Preset Manager.

Note: *New preset brushes are saved in a Preferences file. If this file is deleted or damaged, or if you reset brushes to the default library, the new presets will be lost. To permanently save new preset brushes, save them in a library.*

1 Customize a brush.

2 Do one of the following in the Brush Presets panel:

- Choose New Brush Preset from the panel menu, enter a name for the preset brush, and click OK.
- Click the Create New Brush button .

More Help topics

Brush panel overview

Tool presets

Paint with the Mixer Brush

Paint with the Mixer Brush

The Mixer Brush simulates realistic painting techniques such as mixing colors on the canvas, combining colors on a brush, and varying paint wetness across a stroke.

The Mixer Brush has two paint wells, a reservoir and a pickup. The reservoir stores the final color deposited onto the canvas and has more paint capacity. The pickup well receives paint only from the canvas; its contents are continuously mixed with canvas colors.

For a video about the Mixer Brush, see Adobe Photoshop CS6 Tutorial – Using the Mixer Brush

1 Select the Mixer Brush tool . (If necessary, click and hold the standard Brush tool to reveal the Mixer Brush.)

2 To load paint into the reservoir, Alt-click (Windows) or Option-click (Mac OS) the canvas. Or, choose a foreground color.

When you load paint from the canvas, the brush tip reflects any color variation in the sampled area. If you prefer brush tips of uniform color, select Load Solid Colors Only from the Current Brush Load pop-up menu in the options bar.

3 Choose a brush from the Brush Presets panel. See Select a preset brush.

4 In the options bar, set tool options. For common options, see Paint tool options. For options unique to the Mixer Brush, see the following:

Current Brush Load swatch From the pop-up panel, click Load Brush to fill the brush with the reservoir color, or Clean Brush to remove paint from the brush. To perform these tasks after each stroke, select the automatic Load or Clean options.

Preset pop-up menu Applies popular combinations of Wet, Load, and Mix settings.

Wet Controls how much paint the brush picks up from the canvas. Higher settings produce longer paint streaks.



A B

A 0% B 100%

Load Specifies the amount of paint loaded in the reservoir. At low load rates, paint strokes dry out more quickly.



A B

A 1% B 100%

Mix Controls the ratio of canvas paint to reservoir paint. At 100%, all paint is picked up from the canvas; at 0%, all paint comes from the reservoir. (The Wet setting, however, continues to determine how paints mix on the canvas.)

Sample All Layers Picks up canvas color from all visible layers.

5 Do one or more of the following:

- Drag in the image to paint.
- To draw a straight line, click a starting point in the image. Then hold down Shift, and click an ending point.

- When using the Brush tool as an airbrush, hold down the mouse button without dragging to build up color.

More Help topics

Painting tools

Select and display tools

Standard brush tip shape options

Erodible tip options

Bristle tip shape options

Creating and managing patterns

Erasing parts of an image

Manage pattern libraries and presets

You can keep your patterns organized in libraries that you can load or remove from pattern pop-up panels.

Load a library of patterns

Choose one of the following from a Pattern pop-up panel menu:

- Load Patterns to add a library to the current list. Select the library file you want to use, and click Load.
- Replace Patterns to replace the current list with a different library. Select the library file you want to use, and click Load.
- A library file (displayed at the bottom of the panel menu). Click OK to replace the current list, or click Append to append the current list.

Save a set of preset patterns as a library

1. Choose Save Patterns from a Pattern pop-up panel menu.
2. Choose a location for the pattern library, enter a file name, and click Save.

   You can save the library anywhere. However, if you place the library file in the Presets/Patterns folder in the default location, the library name will appear at the bottom of the Pattern pop-up panel menus after you restart Photoshop.

Return to the default library of patterns

? Choose Reset Patterns from a Pattern pop-up panel menu. You can either replace the current list or append the default library to the current list.

If you receive a Pattern Stamp tool preset that uses an undefined pattern, or if you erase the preset you're using by resetting or replacing the pattern library, choose New Pattern from the Pattern pop-up panel menu to redefine the pattern.

Rename a preset pattern

1. Select the pattern you want to rename, and choose Rename Pattern from the panel menu.
2. Enter a new name for the pattern, and click OK.

Delete a preset pattern

? Do one of the following:

- Select the pattern you want to delete, and choose Delete Pattern from the panel menu.
- Hold down Alt (Windows) or Option (Mac OS), position the pointer over a pattern (the pointer turns into scissors), and click.

The pattern is deleted only from the displayed group. To display the full library again, see Work with the Preset Manager.

More Help topics

Tool presets

Create patterns

Edit paths

Path segments, components, and points

A path consists of one or more straight or curved segments. *Anchor points* mark the end points of the path segments. On curved segments, each selected anchor point displays one or two *direction lines*, ending in *direction points*. The positions of direction lines and points determine the size and shape of a curved segment. Moving these elements reshapes the curves in a path.



***A** Curved line segment **B** Direction point **C** Direction line **D** Selected anchor point **E** Unselected anchor point*

A path can be *closed*, with no beginning or end (for example, a circle), or *open*, with distinct *end points* (for example, a wavy line).

Smooth curves are connected by anchor points called *smooth points*. Sharply curved paths are connected by *corner points*.



When you move a direction line on a smooth point, the curved segments on both sides of the point are adjusted simultaneously. By comparison, when you move a direction line on a corner point, only the curve on the same side of the point as the direction line is adjusted.



A path does not have to be one connected series of segments. It can contain more than one distinct and separate path component. Each shape in a shape layer is a path component, as described by the layer's clipping path.



Select a path

Selecting a path component or path segment displays all of the anchor points on the selected portion, including any direction lines and direction points if the selected segment is curved. Direction handles appear as filled circles, selected anchor points as filled squares, and unselected anchor points as hollow squares.

1 Do one of the following:

- To select a path component (including a shape in a shape layer), select the Path Selection tool , and click anywhere inside the path component. If a path consists of several path components, only the path component under the pointer is selected.
- To select a path segment, select the Direct Selection tool , and click one of the segment's anchor points, or drag a marquee over part of the segment.

2 To select additional path components or segments, select the Path Selection tool or the Direct Selection tool, and then hold down Shift while selecting additional paths or segments.

When the Direct Selection tool is selected, you can select the entire path or path component by Alt-clicking (Windows) or Option-clicking (Mac OS) inside the path. To activate the Direct Selection tool when most other tools are selected, position the pointer over an anchor point, and press Ctrl (Windows) or Command (Mac OS).

Select multiple paths | Photoshop CC

You can select multiple paths on the same layer or across different layers.

1 In the Paths panel, do any of the following to make the paths visible:
- Shift-click to select contiguous paths.
- Ctrl-click (Windows) or Command-click (Mac OS) to select non-contiguous paths.

2 Select the Path Selection tool or the Direct Selection tool and do any of the following:
- Drag over the segments.
- Shift-click the paths.

3 To select additional path components or segments, select the Path Selection tool or the Direct Selection tool, and then hold down the Shift key while selecting additional paths or segments.

Note: *You can choose to work with paths in the isolation mode. To isolate only the layer containing a path, with the path active, double-click using a selection tool. You can also isolate single or multiple layers by using the Select/Isolate Layers menu item or by setting Layer Filtering to Selected.You can exit the isolation mode in several ways, such as:*

- Turning off Layer Filtering
- Switching Layer Filtering to something other than Selected
- Double-clicking away from a path using the path selection tools

Reorder paths

You can reorder saved paths that are not Shape, Type, or Vector Mask paths in the Paths panel.

? In the Paths panel, drag the path to the position you want. In Photoshop CC, you can select and drag more than one path simultaneously.

Duplicate paths

1 In the Paths panel, select the path you want to duplicate. In Photoshop CC, you can select more than one path.

2 Do any of the following:
   - Alt-drag (Windows) or Option-drag the paths.
   - Choose Duplicate Path from the panel menu.

Adjust path segments

You can edit a path segment at any time, but editing existing segments is slightly different from drawing them. Keep the following tips in mind when editing segments:

- If an anchor point connects two segments, moving that anchor point always changes both segments.
- When drawing with the Pen tool, you can temporarily activate the Direct Selection tool so that you can adjust segments you've already drawn; press Ctrl (Windows) or Command (Mac OS) while drawing.
- When you initially draw a smooth point with the Pen tool, dragging the direction point changes the length of the direction line on both sides of the point. However, when you edit an existing smooth point with the Direct Selection tool, you change the length of the direction line only on the side you're dragging.

Move straight segments

1 With the Direct Selection tool , select the segment you want to adjust.

2 Drag the segment to its new position.

Adjust the length or angle of straight segments

1 With the Direct Selection tool select an anchor point on the segment you want to adjust.

2 Drag the anchor point to the desired position. Shift-drag to constrain the adjustment to multiples of 45°.

Adjust the position or shape of curved segments

1 With the Direct Selection tool ,, select a curved segment, or an anchor point on either end of the curved segment. Direction lines appear, if any are present. (Some curved segments use just one direction line.)

2 Do any of the following:
   - To adjust the position of the segment, drag the segment. Shift-drag to constrain the adjustment to multiples of 45°.



   - To adjust the shape of the segment on either side of a selected anchor point, drag the anchor point or the direction point. Shift-drag to constrain movement to multiples of 45°.



Note: *Adjusting a path segment also adjusts the related segments, letting you intuitively transform path shapes. To only edit segments between the selected anchor points, similar to earlier Photoshop versions, select Constrain Path Dragging in the options bar.*

Note: *You can also apply a transformation, such as scaling or rotating, to a segment or anchor point.*

Delete a segment

1 (Optional) If you're creating an opening in a closed path, select the Add Anchor Point tool , and add two points where you want the cut to occur.

2 Select the Direct Selection tool , and select the segment you want to delete.

3 Press Backspace (Windows) or Delete (Mac OS) to delete the selected segment. Pressing Backspace or Delete again erases the rest of the path.

Delete the direction line of an anchor point

- Using the Convert Anchor Point tool, click the anchor point of the direction line.

  The smooth point becomes a corner point. For more information, see Convert between smooth points and corner points .

Extend an open path

1 Using the Pen tool, position the pointer over the endpoint of the open path you want to extend. The pointer changes when it's precisely positioned over the endpoint.

2 Click the endpoint.

3 Do one of the following:

- To create a corner point, position the Pen tool where you want to end the new segment, and click. If you are extending a path that ends at a smooth point, the new segment will be curved by the existing direction line.
- To create a smooth point, position the Pen tool where you want to end the new curved segment, and drag.

Connect two open paths

1 Using the Pen tool, position the pointer over the endpoint of the open path that you want to connect to another path. The pointer changes when it's precisely positioned over the endpoint.

2 Click the endpoint.

3 Do one of the following:

- To connect the path to another open path, click an endpoint on the other path. When you precisely position the Pen tool over the other path's endpoint, a small merge symbol appears next to the pointer.

- To connect a new path to an existing path, draw the new path near the existing path, and then move the Pen tool to the existing path's (unselected) endpoint. Click that endpoint when you see the small merge symbol that appears next to the pointer.

Move or nudge anchor points or segments using the keyboard

1 Select the anchor point or path segment.

2 Click or hold down any of the arrow keys on the keyboard to move 1 pixel at a time in the direction of the arrow.

Hold down the Shift key in addition to the arrow key to move 10 pixels at a time.

Add or delete anchor points

Adding anchor points can give you more control over a path or it can extend an open path. However try not to add more points than necessary. A path with fewer points is easier to edit, display, and print. You can reduce the complexity of a path by deleting unnecessary points.

The toolbox contains three tools for adding or deleting points: the Pen tool , the Add Anchor Point tool , and the Delete Anchor Point tool .

By default, the Pen tool changes to the Add Anchor Point tool as you position it over a selected path, or to the Delete Anchor Point tool as you position it over an anchor point. You must select Auto Add/Delete in the options bar to enable the Pen tool to automatically change to the Add Anchor Point or Delete Anchor Point tool.

You can select and edit multiple paths simultaneously. You can also reshape a path while adding anchor points by clicking and dragging as you add.

Note: *Don't use the Delete or Backspace keys or the Edit > Cut or Edit > Clear commands to delete anchor points. These keys and commands delete the point and line segments that connect to that point.*

Add or delete anchor points

1 Select the path you want to modify.

2 Select the Pen tool, the Add Anchor Point tool, or the Delete Anchor Point tool.

3 To add an anchor point, position the pointer over a path segment and click. To delete an anchor point, position the pointer over an anchor point and click.

Disable or temporarily override automatic Pen tool switching

You can override automatic switching of the Pen tool to the Add Anchor Point tool or the Delete Anchor Point tool. This is useful when you want to start a new path on top of an existing path.

- In Photoshop, deselect Auto Add/Delete in the options bar.

Convert between smooth points and corner points

1 Select the path you want to modify.

2 Select the Convert Point tool, or use the Pen tool and hold down Alt (Windows) or Option (Mac OS).

Note: *To activate the Convert Point tool while the Direct Selection tool is selected, position the pointer over an anchor point, and press Ctrl+Alt (Windows) or Command+Option (Mac OS).*

3 Position the Convert Point tool over the anchor point you want to convert, and do one of the following:

- To convert a corner point to a smooth point, drag away from the corner point to make direction lines appear.



- To convert a smooth point to a corner point without direction lines, click the smooth point.



- To convert a corner point without direction lines to a corner point with independent direction lines, first drag a direction point out of a corner point (making it a smooth point with direction lines). Release the mouse button only (don't release any keys you may have pressed to activate the Convert Anchor Point tool), and then drag either direction point.
- To convert a smooth point to a corner point with independent direction lines, drag either direction point.



Adjust path components

You can reposition a path component (including a shape in a shape layer) anywhere within an image. You can copy components within an image or between two Photoshop images. Using the Path Selection tool, you can merge overlapping components into a single component. All vector objects, whether they are described by a saved path, work path, or vector mask, can be moved, reshaped, copied, or deleted.

You can also use the Copy and Paste commands to duplicate vector objects between a Photoshop image and an image in another application, such as Adobe Illustrator.

Change the overlap mode for the selected path component

1 Using the Path Selection tool , drag a marquee to select existing path areas.

2 Choose a shape area option from the Path Operations drop-down menu in the options bar:

Combine Shapes Adds the path area to overlapping path areas.

Subtract From Shape Area Removes the path area from overlapping path areas.

Intersect Shape Areas Restricts the area to the intersection of the selected path area and overlapping path areas.

Exclude Overlapping Shape Areas Excludes the overlap area.

Show or hide the selected path component

Do one of the following:

- Choose View > Show > Target Path.
- Choose View > Extras. This command also shows or hides a grid, guides, selection edges, annotations, and slices.

Move a path or path component

1 Select the path name in the Paths panel, and use the Path Selection tool to select the path in the image. To select multiple path components, Shift-click each additional path component to add it to the selection.

2 Drag the path to its new location. If you move any part of a path beyond the canvas boundaries, the hidden part of the path is still available.



Note: *If you drag a path so that the move pointer is over another open image, the path is copied to that image.*

Reshape a path component

1 Select the path name in the Paths panel, and use the Direct Selection tool to select an anchor point in the path.

2 Drag the point or its handles to a new location.

Merge overlapping path components

1 Select the path name in the Paths panel, and select the Path Selection tool .

2 To create a single component from all overlapping components, choose Merge Shape Components from the Path Operations drop-down menu in the options bar.

Copy a path component or path

Do any of the following:

- To copy a path component as you move it, select the path name in the Paths panel, and click a path component with the Path Selection tool . Then Alt-drag (Windows) or Option-drag (Mac OS) the selected path.
- To copy a path without renaming it, drag the path name in the Paths panel to the New Path button at the bottom of the panel.
- To copy and rename a path, Alt-drag (Windows) or Option-drag (Mac OS) the path in the Paths panel to the New Path button at the bottom of the panel. Or select the path to copy, and choose Duplicate Path from the Paths panel menu. Enter a new name for the path in the Duplicate Path dialog box, and click OK.

- To copy a path or path component into another path, select the path or path component you want to copy, and choose Edit > Copy. Then select the destination path, and choose Edit > Paste.

Copy path components between two Photoshop files

1 Open both images.

2 In the source image, use the Path Selection tool to select the entire path or the path components that you want to copy.

3 To copy the path component, do any of the following:

- Drag the path component from the source image to the destination image. The path component is copied to the active path in the Paths panel.
- In the source image, select the path name in the Paths panel and choose Edit > Copy to copy the path. In the destination image, choose Edit > Paste. You can also use this method to combine paths in the same image.
- To paste the path component into the destination image, select the path component in the source image, and choose Edit > Copy. In the destination image, choose Edit > Paste.

Delete a path component

1 Select the path name in the Paths panel, and click a path component with the Path Selection tool .

2 Press Backspace (Windows) or Delete (Mac OS) to delete the selected path component.

Align and distribute path components

You can align and distribute path components that are described in a single path. For example, you can align the left edges of several shapes contained in a single layer or distribute several components in a work path along their horizontal centers.

Note: *To align shapes that are on separate layers, use the Move tool.*

- To align components, use the Path Selection tool to select the components you want to align. Then choose an option from the Path Alignment drop-down menu in the options bar.

- To distribute components, select at least three components you want to distribute. Then choose an option from the Path Arrangement drop-down menu in the options bar.



Create patterns

A pattern is an image that is repeated, or tiled, when you use it to fill a layer or selection. Photoshop comes with various preset patterns.

You can create new patterns and save them in libraries for use with different tools and commands. Preset patterns are displayed in pop-up panels in the options bar for the Paint Bucket, Pattern Stamp, Healing Brush, and Patch tools, as well as in the Layer Style dialog box. You can change how patterns are displayed in the pop-up panels by choosing a display option from the pop-up panel menu. You can also manage pattern presets using the preset manager.

Define an image as a preset pattern

1 Use the Rectangle Marquee tool on any open image to select an area to use as a pattern. Feather must be set to 0 pixels. Note that large images may become unwieldy.

2 Choose Edit > Define Pattern.

3 Enter a name for the pattern in the Pattern Name dialog box.

Note: *If you are using a pattern from one image and applying it to another, Photoshop converts the color mode.*

Photoshop comes with a set of Illustrator format files that you can use to define a preset pattern. Open the file, select any rendering option, and then define the pattern.

More Help topics

Tool presets

Manage pattern libraries and presets

Draw or paint with a graphics tablet

Change brush size and opacity with pen pressure

If you work with a graphics drawing tablet, such as the Wacom® tablet, you can control painting tools with pen pressure, angle, rotation, or the stylus wheel.

1 Select the Brush , Pencil , or other painting tool.

2 In the options bar, do either of the following:

- Click the Tablet Pressure Controls Size button .
- Click the Tablet Pressure Controls Opacity button .

Note: *Choose Window > Brush to access additional controls that vary the angle, flow, scatter, texture depth, and roundness of the stroke according to pen pressure.*

More Help topics

Create and modify brushes

Create textured brushes

Textured brush options

A textured brush uses a pattern to make strokes look as if they are painted on textured canvas.



Click the pattern sample, and select a pattern from the pop-up panel. Set one or more of the following options:

Invert Inverts the high and low points in the texture based on the tones in the pattern. When Invert is selected, the lightest areas in the pattern are the low points in the texture and therefore receive the least paint; the darkest areas in the pattern are the high points in the texture and therefore receive the most paint. When Invert is deselected, the lightest areas in the pattern receive the most paint; the darkest areas in the pattern receive the least paint.

Scale Specifies the scale of the pattern. Type a number, or use the slider to enter a value that is a percentage of the pattern size.

Texture Each Tip Applies the selected texture individually to each brush mark in a brush stroke, rather than to the brush stroke as a whole (a brush stroke is made up of many brush marks, applied continuously as you drag the brush). You must select this option to make the Depth variance options available.

Mode Specifies the blending mode used to combine the brush and the pattern. (See Blending modes.)

Depth Specifies how deeply the paint penetrates into the texture. Type a number, or use the slider to enter a value. At 100%, the low points in the texture do not receive any paint. At 0%, all points in the texture receive the same amount of paint, therefore hiding the pattern.

Minimum Depth Specifies the minimum depth to which paint can penetrate when Depth Control is set to Fade, Pen Pressure, Pen Tilt, or Stylus Wheel, and Texture Each Tip is selected.

Depth Jitter and Control Specifies how the depth varies when Texture Each Tip is selected. To specify the maximum percentage of jitter, enter a value. To specify how you want to control the depth variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the depth variance of brush marks.

Fade Fades from the Depth Jitter percentage to the Minimum Depth percentage in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the depth based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Copy textures between tools

When you specify a texture for the current tool, you can copy the texture's pattern and scale to all tools that support textures. For example, you can copy the current texture pattern and scale for the Brush tool to the Pencil, Clone Stamp, Pattern Stamp, History Brush, Art History Brush, Eraser, Dodge, Burn, and Sponge tools.

? Choose Copy Texture To Other Tools from the Brush panel menu.

Dual brushes

A dual brush combines two tips to create brush marks. The second brush texture is applied within the brush stroke of the primary brush; only the areas where both brushstrokes intersect are painted. Set options for the primary tip in the Brush Tip Shape section of the Brush panel. Select a second brush tip from the Dual Brush section of the Brush panel, and set any of the following options.

A B C

***A** Primary brush tip stroke (hard round 55). **B** Secondary brush tip stroke (grass). **C** Dual brush stroke (using both).*

Mode Sets a blending mode to use when combining brush marks from the primary tip and the dual tip. (See Blending modes.)

Diameter Controls the size of the dual tip. Enter a value in pixels, drag the slider, or click Use Sample Size to use the original diameter of the brush tip. (The Use Sample Size option is available only if the brush tip shape was created by sampling pixels in an image.)

Spacing Controls the distance between the dual tip brush marks in a stroke. To change the spacing, type a number, or use the slider to enter a percentage of the tip diameter.

Scatter Specifies how dual tip brush marks are distributed in a stroke. When Both Axes is selected, dual tip brush marks are distributed in a radial direction. When Both Axes is deselected, dual tip brush marks are distributed perpendicular to the stroke path. To specify the maximum percentage of scattering, type a number or use the slider to enter a value.

Count Specifies the number of dual tip brush marks applied at each spacing interval. Type a number, or use the slider to enter a value.

More Help topics

Create and modify brushes

Painting tools

Add dynamic elements to brushes

Add brush dynamics

The Brush panel provides many options for adding dynamic (or changing) elements to preset brush tips. For example, you can set options that vary the size, color, and opacity of brush marks over the course of a stroke.

You work with two components when adding dynamics elements to a brush:

- Jitter percentages specify the randomness of dynamic elements. At 0%, an element does not change over the course of a stroke; at 100%, an element has the maximum amount of randomness.
- Options in the Control pop-up menus specify how you want to control the variance of dynamic elements. You can choose not to control the variance of an element, to fade an element over the specified number of steps, or to vary an element based on pen pressure, pen tilt, position of the pen thumbwheel, or pen rotation.

Note: *Pen controls are available only when you're using a pressure-sensitive digitizing tablet such as the Wacom tablet, and supported pens (for rotation control and thumbwheel). A warning icon appears if you select a pen control but have not installed a tablet or are using a pen that is missing the control feature.*

Brush shape dynamics

Shape dynamics determine the variance of brush marks in a stroke.



Size Jitter and Control Specifies how the size of brush marks vary in a stroke. For more information, see Create and modify brushes.

To specify the maximum percentage of jittering, type a number or use the slider to enter a value. To specify how you want to control the size variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the size variance of brush marks.

Fade Fades the size of brush marks between the initial diameter and the minimum diameter in the specified number of steps. Each step is equal to one mark of the brush tip. The value can range from 1 to 9999. For example, entering 10 steps produces a fade in 10 increments.

Pen Pressure, Pen Tilt, Stylus Wheel Varies the size of brush marks between the initial diameter and the minimum diameter based on the pen pressure, pen tilt, or position of the pen thumbwheel.

Minimum Diameter Specifies the minimum percentage by which brush marks can scale when Size Jitter or Size Control is enabled. Type a number, or use the slider to enter a value that is a percentage of the brush tip diameter.

Tilt Scale Specifies the scale factor applied to the height of the brush prior to rotation when Size Control is set to Pen Tilt. Type a number, or use the slider to enter a value that is a percentage of the brush diameter.

Angle Jitter and Control Specifies how the angle of brush marks varies in a stroke. To specify the maximum percentage of jittering, enter a value that is a percentage of 360 degrees. To specify how you want to control the angle variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the angle variance of brush marks.

Fade Fades the angle of brush marks between 0 and 360 degrees in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the angle of brush marks between 0 and 360 degrees based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Initial Direction Bases the angle of brush marks on the initial direction of the brush stroke.

Direction Bases the angle of brush marks on the direction of the brush stroke.

Roundness Jitter and Control Specifies how the roundness of brush marks varies in a stroke. To specify the maximum percentage of jittering, enter a percentage indicating the ratio between the brush's short and long axes. To specify how you want to control the roundness variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the roundness variance of brush marks.

Fade Fades the roundness of brush marks between 100% and the Minimum Roundness value in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the roundness of brush marks between 100% and the Minimum Roundness value based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Minimum Roundness Specifies the minimum roundness for brush marks when Roundness Jitter or Roundness Control is enabled. Enter a percentage indicating the ratio between the brush's short and long axes.

Brush Projection Specifies that as you paint with a stylus, changes to tilt and rotation alter the tip shape.

Color dynamics brush options

Color dynamics determine how the color of paint changes over the course of a stroke.



Apply per tip Specifies changing color for each distinct tip stamp in a stroke.

If unchecked, dynamic changes occur once at the beginning of each stroke. You can vary color between strokes, rather than within each individual stroke.

Foreground/Background Jitter and Control Specifies how paint varies between the foreground color and background color.

To specify a percentage by which the color of the paint can vary, type a number, or use the slider to enter a value. To specify how you want to control the color variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the color variance of brush marks.

Fade Varies the color of paint between the foreground color and the background color in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel, Rotation Varies the color of paint between the foreground color and the background color based on the pen pressure, pen tilt, position of the pen thumbwheel, or rotation of the pen.

Hue Jitter Specifies a percentage by which the hue of the paint can vary in a stroke. Type a number, or use the slider to enter a value. A lower value changes the hue while maintaining a close proximity to the hue of the foreground color. A higher value increases the difference between hues.

Saturation Jitter Specifies a percentage by which the saturation of the paint can vary in a stroke. Type a number, or use the slider to enter a value. A lower value changes the saturation while maintaining a close proximity to the saturation of the foreground color. A higher value increases the difference between saturation levels.

Brightness Jitter Specifies a percentage by which the brightness of the paint can vary in a stroke. Type a number, or use the slider to enter a value. A lower value changes the brightness while maintaining a close proximity to the brightness of the foreground color. A higher value increases the difference between brightness levels.

Purity Increases or decreases the saturation of the color. Type a number, or use the slider to enter a percentage between –100 and 100. At –100%, the color is fully desaturated; at 100%, the color is fully saturated.

Transfer brush options

Transfer brush options determine how paint changes over the course of a stroke.



Opacity Jitter and Control Specifies how the opacity of paint varies in a brush stroke, up to (but not exceeding) the opacity value specified in the options bar. To specify a percentage by which the opacity of the paint can vary, type a number or use the slider to enter a value. To specify how you want to control the opacity variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the opacity variance of brush marks.

Fade Fades the opacity of paint from the opacity value in the options bar to 0, in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel Varies the opacity of paint based on the pen pressure, pen tilt, or the position of the pen thumbwheel.

Flow Jitter and Control Specifies how the flow of paint varies in a brush stroke, up to (but not exceeding) the flow value specified in the options bar.

To specify a percentage by which the flow of the paint can vary, type a number or use the slider to enter a value. To specify how you want to control the flow variance of brush marks, choose an option from the Control pop-up menu:

Off Specifies no control over the flow variance of brush marks.

Fade Fades the flow of paint from the flow value in the options bar to 0 in the specified number of steps.

Pen Pressure, Pen Tilt, Stylus Wheel Varies the flow of paint based on the pen pressure, pen tilt, or position of the pen thumbwheel.

More Help topics

Create and modify brushes

Paint stylized strokes with the Art History Brush

The Art History Brush tool paints with stylized strokes, using the source data from a specified history state or snapshot. By experimenting with different paint style, size, and tolerance options, you can simulate the texture of painting with different colors and artistic styles.

Like the History Brush tool, the Art History Brush tool uses a specified history state or snapshot as the source data. The History Brush tool, however, paints by re-creating the specified source data, while the Art History Brush tool uses that data along with the options you set to create different colors and artistic styles.

For various visual effects, experiment with applying filters or filling an image with a solid color before painting with the Art History Brush tool. Also try increasing the size of the image by a factor of 4 to soften the details.



***A** Original **B** Using a small brush **C** Using a large brush*

1. In the History panel, click the left column of the state or snapshot to use as the source for the Art History Brush tool. A brush icon appears next to the source history state.
2. Select the Art History Brush tool .
3. Do the following in the options bar:
   - Choose a brush from the Brush Presets picker, and set brush options. (See Select a preset brush.)
   - Choose a blending mode from the Mode menu. (See Blending modes.)
   - Choose an option from the Style menu to control the shape of the paint stroke.
   - For Area, enter a value to specify the area covered by the paint strokes. The greater the size, the larger the covered area and the more numerous the strokes.
   - For Tolerance, enter a value to limit the regions where paint strokes can be applied. A low tolerance lets you paint unlimited strokes anywhere in the image. A high tolerance limits paint strokes to areas that differ considerably from the color in the source state or snapshot.
4. Click and drag in the image to paint.

More Help topics

Painting tools

Select and display tools

Standard brush tip shape options

Erodible tip options

Bristle tip shape options

Creating and managing patterns

Selecting a cursor preference

Erasing parts of an image

Paint with a pattern

You can use the Pattern Stamp tool to give your photos a hand-painted look.

Paint with a pattern

The Pattern Stamp tool paints with a pattern. You can select a pattern from the pattern libraries or create your own patterns.

1 Select the Pattern Stamp tool .
2 Choose a brush from the Brush Presets panel. See Select a preset brush.
3 Set tool options for mode, opacity, etc. in the options bar. See Paint tool options.
4 Select Aligned in the options bar to maintain the pattern's continuity with your original start point, even if you release the mouse button and then continue painting. Deselect Aligned to restart the pattern each time you stop and start painting.
5 Select a pattern from the Pattern pop-up panel in the options bar.
6 If you'd like to apply the pattern with an impressionistic effect, select Impressionist.
7 Drag in the image to paint it with the pattern.

More Help topics

Painting tools

Select and display tools

Standard brush tip shape options

Erodible tip options

Bristle tip shape options

Creating and managing patterns

Erasing parts of an image

Add color to paths

Fill paths with color

A path created with the Pen tool does not become an image element until you stroke or fill it. The Fill Path command fills a path with pixels using a specified color, a state of the image, a pattern, or a fill layer.



Note: *When you fill a path, the color values appear on the active layer. Make sure that a standard or background layer is active before completing the steps below. (You cannot fill a path when a mask, text, fill, adjustment, or Smart Object layer is active.)*

Fill a path using the current Fill Path settings

1 Select the path in the Paths panel.

2 Click the Fill Path button at the bottom of the Paths panel.

Fill a path and specify options

1 Select the path in the Paths panel.

2 Fill the path:

- Alt-click (Windows) or Option-click (Mac OS) the Fill Path button at the bottom of the Paths panel.
- Alt-drag (Windows) or Option-drag (Mac OS) the path to the Fill Path button.
- Choose Fill Path from the Paths panel menu. If the selected path is a path component, this command changes to Fill Subpath.

3 For Use, choose the contents for the fill. (See Fill a selection or layer with color.)

4 Specify an opacity for the fill. To make the fill more transparent, use a low percentage. A setting of 100% makes the fill opaque.

5 Choose a blending mode for the fill. (See Blending mode descriptions.)

The Mode list includes a Clear mode that lets you erase to transparency. You must be working in a layer other than the background to use this option.

6 Choose Preserve Transparency to limit the fill to layer areas that contain pixels. (See Lock layers.)

7 Select a Rendering option:

Feather Radius Defines how far inside and outside the selection border the feather edge extends. Enter a value in pixels.

Anti-aliased Creates a finer transition between the pixels in the selection and the surrounding pixels by partially filling the edge pixels of the selection.

For more information on these options, see Soften the edges of selections.

8 Click OK.

Stroke paths with color

The Stroke Path command paints the border of a path. The Stroke Path command allows you to create a paint stroke (using the current settings for your painting tools) that follows any path. This command is completely different from the Stroke layer effect, which doesn't mimic the effect of any of the painting tools.

Note: *When you stroke a path, the color values appear on the active layer. Make sure that a standard or background layer is active before completing the steps below. (You cannot stroke a path when a mask, text, fill, adjustment, or Smart Object layer is active.)*

Stroke a path using the current Stroke Path options

1 Select the path in the Paths panel.

2 Click the Stroke Path button at the bottom of the Paths panel. Each click of the Stroke Path button builds up the opacity of the stroke and, depending upon the current brush options, makes it look thicker.

Stroke a path and specify options

1 Select the path in the Paths panel.

2 Select the painting or editing tool you want to stroke the path. In the options bar, set the tool options, and specify a brush.

For information on specific tool settings, see Smudge image areasand About painting tools, presets, and options.

3 To stroke the path, do one of the following:

- Alt-click (Windows) or Option-click (Mac OS) the Stroke Path button at the bottom of the Paths panel.
- Alt-drag (Windows) or Option-drag (Mac OS) the path to the Stroke Path button.
- Choose Stroke Path from the Paths panel menu. If the selected path is a path component, this command changes to Stroke Subpath.

4 In the Stroke Path dialog box, choose a tool if you did not select one in step 2. To simulate hand-painted strokes, select Simulate Pressure. Or, deselect this option to create more linear, even strokes.

5 Click OK.

More Help topics

Stroke a selection or layer with color

Vector Shapes

Drawing shapes in CS6

Vector Shapes

New shape, type, and design tools

Genuine vector shapes, type styles, and more.

New shape, type, and design tools

Chapter 13: Text

Format characters

You can set type attributes before you enter characters or reset them to change the appearance of selected characters in a type layer.

Before you can format individual characters, select them. You can select one character, a range of characters, or all characters in a type layer.

To quickly get up to speed with text-related Photoshop features, see Add words to your picture .

Select characters

1 Select the Horizontal Type tool or the Vertical Type tool .

2 Select the type layer in the Layers panel, or click in the text to automatically select a type layer.

3 Position the insertion point in the text, and do one of the following:

- Drag to select one or more characters.
- Click in the text, and then Shift-click to select a range of characters.
- Choose Select > All to select all the characters in the layer.
- Double-click a word to select it. Triple-click a line to select it. Quadruple-click a paragraph to select it. Quintuple-click anywhere in the text flow to select all characters in a bounding box.
- To use the arrow keys to select characters, click in the text, and then hold down Shift and press the Right Arrow or Left Arrow key. To use the keys to select words, hold down Shift+Ctrl (Windows) or Shift+Command (Mac OS) and press the Right Arrow or Left Arrow key.

4 To select all the characters in a layer without positioning the insertion point in the text flow, select the type layer in the Layers panel, and then double-click the layer's type icon.

Note: *Selecting and formatting characters in a type layer puts the Type tool into edit mode.*

Character panel and dynamic shortcuts overview

The Character panel provides options for formatting characters. Some formatting options are also available from the options bar.

You can display the Character panel by doing one of the following:

- Choose Window > Character, or click the Character panel tab if the panel is visible but not active.
- With a type tool selected, click the Panel button in the options bar.

To set an option in the Character panel, choose a value from the pop-up menu on the right side of the option. For options with numeric values, you can also use the up and down arrows to set the value, or you can edit the value directly in the text box. When you edit a value directly, press Enter or Return to apply a value, Shift+Enter or Shift+Return to apply a value and then highlight the value just edited, or Tab to apply a value and move to the next text box in the panel.



A Font Family B Font Size C Vertical Scale D Set Tsume option E Tracking F Baseline Shift G Language H Font Style I Leading J Horizontal Scale K Kerning

Note: *Select Show Asian Text Options in the Type preferences for the Set Tsume option to appear in the Character panel.*

You can access additional commands and options in the Character panel menu. To use this menu, click the triangle in the upper right corner of the panel.

Dynamic shortcuts are keyboard shortcuts accessible from the Character panel menu only when you are entering point or paragraph type, when type is selected, or when the I-beam is in text. Dynamic shortcuts are available for type options such as Faux Bold, Faux Italic, All Caps, Small Caps, Superscript, Subscript, Underline, and Strikethrough.



Specify type size and color

The type size determines how large the type appears in the image.

The default unit of measurement for type is points. One PostScript point is equal to 1/72 of an inch in a 72-ppi image; however, you can switch between using the PostScript and traditional definitions of point size. You can change the default unit of measurement for type in the Units & Rulers area of the Preferences dialog box.

The type you enter is rendered in the current foreground color; however, you can change the color before or after you enter type. When editing existing type layers, you can change the color of individual, selected characters or of all type in a layer.

Choose a type size

? In the Character panel or options bar, enter or select a new value for Size .

To use an alternate unit of measurement, enter the unit (in, cm, mm, pt, px, or pica) after the value in the Font Size text box.

To change the unit of measurement for type, choose Edit > Preferences > Units & Rulers (Windows) or Photoshop > Preferences > Units & Rulers (Mac OS), and choose a unit of measurement from the Type menu.

Define the point size unit

1 Choose Edit > Preferences > Units & Rulers (Windows) or Photoshop > Preferences > Units & Rulers (Mac OS).

2 For Point/Pica Size, select from the following options:

PostScript (72 points/inch) Sets a unit size compatible for printing to a PostScript device.

Traditional (72.27 points/inch) Uses 72.27 points per inch, as traditionally used in printing.

3 Click OK.

Change the type color

? Do one of the following:

- Click the Color selection box in the options bar or Character panel, and select a color using the Adobe Color Picker.
- Use fill shortcuts. To fill with the foreground color, press Alt+Backspace (Windows) or Option+Delete (Mac OS); to fill with the background color, press Ctrl+Backspace (Windows) or Command+Delete (Mac OS).
- Apply an overlay layer style to the type layer to apply a color, gradient, or pattern on top of the existing color. You can't apply an overlay layer style selectively; it affects all characters in the type layer.
- Click the foreground color selection box in the toolbox, and select a color using the Adobe Color Picker. Alternatively, click a color in the Color panel, or the Swatches panel. If you use this method to change the color of an existing type layer, you must first select characters on that layer.

Change the color of individual letters

1 Select the Horizontal Type tool .

2 In the Layers panel, select the layer containing the type.

3 In the document window, select the characters you want to change.

4 In the options bar at the top of the work area, click the color swatch.

5 In the Adobe Color Picker, locate the color range you want using the triangle sliders on the color spectrum bar, and then click the desired color in the color field. The color you select appears in the top half of the color swatch in the Adobe Color Picker. The original color remains in the bottom half.

6 Click OK. The new color replaces the original color in the options bar and in the selected characters.

Note: *You won't see the new color in the characters until you deselect them or select something else.*

Text treatments in the Character panel

Underline or strike through text

You can place a line under horizontal type, or to the left or right of vertical type. You can also place a line through horizontal or vertical type. The line is always the same color as the type color.

? Select the type you want to underline or strike through.

- To underline horizontal type, click the Underline button in the Character panel.
- To apply an underline to the left or right of vertical type, choose Underline Left or Underline Right from the Character panel menu. You can apply an underline to the left or right, but not to both sides. A check mark indicates that an option is selected.

Note: *The Underline Left and Underline Right options appear in the Character panel menu only when a type layer containing vertical type is selected. When working with vertical Asian type, you can add an underline on either side of the type line.*

- To apply a horizontal line through horizontal type or a vertical line through vertical type, click the Strikethrough button in the Character panel. You can also choose Strikethrough from the Character panel menu.

Apply all caps or small caps

You can enter or format type as uppercase characters, either all caps or small caps. When you format text as small caps, Photoshop automatically uses the small-cap characters designed as part of the font, if available. If the font does not include small caps, Photoshop generates faux small caps.



1 Select the type you want to change.

2 Do one of the following:

- Click the All Caps button or the Small Caps button in the Character panel.
- Choose All Caps or Small Caps from the Character panel menu. A check mark indicates that the option is selected.

Specify superscript or subscript characters

Superscript and subscript text (also called superior and inferior text) are reduced-size text that is raised or lowered in relation to a font's baseline. If the font does not include superscript or subscript characters, Photoshop generates faux superscript or subscript characters.

1 Select the type you want to change.

2 Do one of the following:

- Click the Superscript button T^1 or the Subscript button T_1 in the Character panel.
- Choose Superscript or Subscript from the Character panel menu. A check mark indicates that the option is selected.

Character styles

A character style includes character formatting attributes, and can be applied to characters, a paragraph, or even a range of paragraphs. You can create Character styles and then apply them later.

Choose **Window** > **Character Styles** to open the Character Styles panel.

- To apply a character style, select the text or text layer and click a character style.

Type styles are hierarchical: Manual overrides supersede any applied character styles, which in turn replace applied paragraph styles. This hierarchical approach lets you combine the efficiency of styles with the flexibility to customize your designs.

For a video overview, see Paragraph and Character Styles in Photoshop by Julieanne Kost.

Create a character style

1 If you want to base a new style on the formatting of existing text, select that text.

2 Choose New Character Style from the Character Styles panel menu.

Note:To create a style without first selecting text, click the Create New Style icon at the bottom of the Character Styles panel. To edit a style without applying it to text, select an image layer, such as the Background.

Edit a character style

Double-click existing styles to edit them and update all associated text in the current document. Changing the style formatting updates all text to which the style has been applied with the new format.

To edit a character style, do the following:

1 Double-click the style in the Character Styles panel.

2 To specify the formatting attributes, click a category (such as Basic Character Formats) on the left, and specify the attributes to add to the style.

3 When you've finished specifying the formatting attributes, click OK.

Specifying default type styles | Creative Cloud only

Current character and paragraph styles can be saved as type defaults. These defaults are automatically applied to new Photoshop documents and can also be applied to existing documents that don't already contain type styles. For more information, see Character styles.

To save the current character and paragraph styles as the type defaults, do any of the following:

- Choose Type > Save Default Type Styles.
- In the Character Styles or the Paragraph Styles panel, choose Save Default Type Styles from the panel menu.

To apply the default Character and Paragraph styles to a document:

1 Do any of the following:
   - Choose Type > Load Default Type Styles.
   - In the Character Styles or the Paragraph Styles panel, choose Load Default Type Styles from the panel menu.
2 If you are loading the default type styles into a document that already has an existing type style, the Import Paragraph Styles dialog box appears. You can choose whether or not to replace the existing type style with the default type style.

More Help topics

Line and character spacing

Format paragraphs

Panels and menus

About layer effects and styles

Creating type

Format paragraphs

Format paragraphs

For point type, each line is a separate paragraph. For paragraph type, each paragraph can have multiple lines, depending on the dimensions of the bounding box.

You can select paragraphs and then use the Paragraph panel to set formatting options for a single paragraph, multiple paragraphs, or all paragraphs in a type layer.

? Select the Horizontal Type tool or the Vertical Type tool .
   - To apply formatting to a single paragraph, click in a paragraph.
   - To apply formatting to multiple paragraphs, make a selection within a range of paragraphs.
   - To apply formatting to all paragraphs in the layer, select the type layer in the Layers panel.

Paragraph panel overview

You use the Paragraph panel to change the formatting of columns and paragraphs. To display the panel, choose Window > Paragraph, or click the Paragraph panel tab if the panel is visible but not active. You can also select a type tool and click the Panel button in the options bar.

To set options with numeric values in the Paragraph panel, you can use the up and down arrows or edit the value directly in the text box. When you edit a value directly, press Enter or Return to apply a value, Shift+Enter or Shift+Return to apply a value and then highlight the value just edited, or Tab to apply a value and move to the next text box in the panel.



A Alignment and justification ***B*** *Left indent* ***C*** *First line left indent* ***D*** *Space before paragraph* ***E*** *Hyphenation* ***F*** *Right indent* ***G*** *Space after paragraph*

You can access additional commands and options in the Paragraph panel menu. To use this menu, click the triangle in the upper-right corner of the panel.

Specify alignment

You can *align* type to one edge of a paragraph (left, center, or right for horizontal type; top, center, or bottom for vertical type). Alignment options are available only for paragraph type.

1 Do one of the following:
   - Select a type layer if you want all the paragraphs in that type layer to be affected.
   - Select the paragraphs you want affected.
2 In the Paragraph panel or options bar, click an alignment option.

   The options for horizontal type are:

   Left Align Text Aligns type to the left, leaving the right edge of the paragraph ragged.

   Center Text Aligns type to the center, leaving both edges of the paragraph ragged.

   Right Align Text Aligns type to right, leaving the left edge of the paragraph ragged.

   The options for vertical type are:

   Top Align Text Aligns type to the top, leaving the bottom edge of the paragraph ragged.

   Center Text Aligns type to the center, leaving both the top and bottom edges of the paragraph ragged.

   Bottom Align Text Aligns type to the bottom, leaving the top edge of the paragraph ragged.

Specify justification for paragraph type

Text is said to be *justified* when it is aligned with both edges. You can choose to justify all text in a paragraph excluding the last line, or you can justify text in a paragraph including the last line. The settings you choose for justification affect the horizontal spacing of lines and the aesthetic appeal of type on a page.

Justification options are available only for paragraph type and determine word, letter, and glyph spacing. Justification settings apply only to Roman characters; double-byte characters available in Chinese, Japanese, and Korean fonts are not affected by these settings.

1 Do one of the following:
   - Select a type layer if you want all the paragraphs in that type layer to be affected.
   - Select the paragraphs you want affected.
2 In the Paragraph panel, click a justification option.

The options for horizontal type are:

Justify Last Left Justifies all lines except the last, which is left aligned.

Justify Last Centered Justifies all lines except the last, which is center aligned.

Justify Last Right Justifies all lines except the last, which is right aligned.

Justify All Justifies all lines including the last, which is force justified.

The options for vertical type are:

Justify Last Top Justifies all lines except the last, which is top aligned.

Justify Last Centered Justifies all lines except the last, which is center aligned.

Justify Last Bottom Justifies all lines except the last, which is bottom justified.

Justify All Justifies all lines including the last, which is force justified.

Note: *Justification (right, center, and left align, and justify all) for type on a path starts at the insertion point and ends at the end of the path.*

Adjust word and letter spacing in justified text

You can precisely control how Photoshop spaces letters and words and scales characters. Adjusting spacing is especially useful with justified type, although you can also adjust spacing for unjustified type.

1 Select the paragraphs you want affected, or select a type layer if you want all the paragraphs in that type layer to be affected.

2 Choose Justification from the Paragraph panel menu.

3 Enter values for Word Spacing, Letter Spacing, and Glyph Scaling. The Minimum and Maximum values define a range of acceptable spacing for justified paragraphs only. The Desired value defines the desired spacing for both justified and unjustified paragraphs:

Word Spacing The space between words that results from pressing the spacebar. Word Spacing values can range from 0% to 1000%; at 100%, no additional space is added between words.

Letter Spacing The distance between letters, including kerning or tracking values. Letter Spacing values can range from –100% to 500%; at 0%, no space is added between letters; at 100% , an entire space width is added between letters.

Glyph Scaling The width of characters (a *glyph* is any font character). Values can range from 50% to 200%; at 100%, the height of characters is not scaled.

Spacing options are always applied to an entire paragraph. To adjust the spacing in a few characters, but not an entire paragraph, use the Tracking option.

Indent paragraphs

Indention specifies the amount of space between type and the bounding box or line that contains the type. Indention affects only the selected paragraph or paragraphs, so you can easily set different indentions for paragraphs.

1 Do one of the following:

- Select a type layer if you want all the paragraphs in that type layer to be affected.
- Select the paragraphs you want affected.

2 In the Paragraph panel, enter a value for an indention option:

Indent Left Margin Indents from the left edge of the paragraph. For vertical type, this option controls the indention from the top of the paragraph.

Indent Right Margin Indents from the right edge of the paragraph. For vertical type, this option controls the indention from the bottom of the paragraph.

Indent First Line Indents the first line of type in the paragraph. For horizontal type, the first line indent is relative to the left indent; for vertical type, the first line indent is relative to the top indent. To create a first line hanging indent, enter a negative value.

Adjust paragraph spacing

1 Select the paragraphs you want affected, or select a type layer if you want all the paragraphs in that type layer to be affected. If you don't insert the cursor in a paragraph or select a type layer, the setting applies to new text you create.

2 In the Paragraph panel, adjust the values for Add Space Before Paragraph and Add Space After Paragraph .

Specify hanging punctuation for Roman fonts

Hanging punctuation controls the alignment of punctuation marks for a specific paragraph. When Roman Hanging Punctuation is turned on, the following characters appear outside the margins: single quotes, double quotes, apostrophes, commas, periods, hyphens, em dashes, en dashes, colons, and semicolons. When a punctuation character is followed a quotation mark, both characters hang.

Keep in mind that the paragraph alignment determines the margin from which the punctuation hangs. For left-aligned and right-aligned paragraphs, punctuation hangs off the left and right margin, respectively. For top-aligned and bottom-aligned paragraphs, punctuation hangs off the top and bottom margin, respectively. For centered and justified paragraphs, punctuation hangs off both margins.



1 Do one of the following:

- Select a type layer if you want all the paragraphs in that type layer to be affected.
- Select the paragraphs you want affected.

2 Choose Roman Hanging Punctuation from the Paragraph panel menu. A check mark indicates that the option is selected.

Note: *Double-byte punctuation marks available in Chinese, Japanese, and Korean fonts in the selected range will not hang when you use Roman Hanging Punctuation. Instead, use either Burasagari Standard or Burasagari Strong. These items are available only if you select Show Asian Text Options in the Type preferences.*

Adjust hyphenation automatically

The settings you choose for hyphenation affect the horizontal spacing of lines and the aesthetic appeal of type on a page. Hyphenation options determine whether words can be hyphenated and, if so, what breaks are allowable.

1 To use automatic hyphenation, do any of the following:
   - To turn automatic hyphenation on or off, select or deselect the Hyphenate option in the Paragraph panel.
   - To apply hyphenation to specific paragraphs, first select only the paragraphs that you want to affect.
   - To choose a hyphenation dictionary, choose a language from the Language menu at the bottom of the Character panel.

2 To specify options, choose Hyphenation from the Paragraph panel menu, and specify the following options:

   Words Longer Than _ Letters Specifies the minimum number of characters for hyphenated words.

   After First _ Letters And Before Last _ Letters Specifies the minimum number of characters at the beginning or end of a word that can be broken by a hyphen. For example, by specifying 3 for these values, **aromatic** would be hyphenated as **aro- matic** instead of **ar- omatic** or **aromat- ic**.

   Hyphen Limit Specifies the maximum number of consecutive lines on which hyphenation may occur.

   Hyphenation Zone Specifies a distance from the right edge of a paragraph, demarcating a portion of the line where hyphenation is not allowed. A setting of 0 allows all hyphenation. This option applies only when you use the Adobe Single-line Composer.

   Hyphenate Capitalized Words Deselect to prevent capitalized words from being hyphenated.

Note: *Hyphenation settings apply only to Roman characters; double-byte characters available in Chinese, Japanese, and Korean fonts are not affected by these settings.*

Prevent words from breaking

You can prevent words from breaking at the end of lines—for example, proper names or words that could be misread when hyphenated. You can also keep multiple words or groups of words together—for example, clusters of initials and a last name.

1 Select the characters you want to prevent from breaking.

2 Choose No Break from the Character panel menu.

   Note: *If you apply the No Break option to too many adjacent characters, the text may wrap in the middle of a word. However, if you apply the No Break option to more than a single line of text, none of the text will appear.*

Composition methods

The appearance of type on the page depends on a complex interaction of processes called *composition*. Using the word spacing, letterspacing, glyph spacing, and hyphenation options you've selected, Adobe applications evaluate possible line breaks and choose the one that best supports the specified parameters.

You can choose between two composition methods: the Adobe Every-line Composer and the Adobe Single-line Composer. Both methods evaluate possible breaks and choose the one that best supports the hyphenation and justification options you've specified for a given paragraph. The composition method affects only the selected paragraph or paragraphs, so you can easily set different composition methods for different paragraphs.

Every-line Composer

The Every-line Composer considers a network of break points for a range of lines and thus can optimize earlier lines in the paragraph in order to eliminate especially unattractive breaks later on.

The Every-line Composer approaches composition by identifying possible break points, evaluating them, and assigning a weighted penalty based on the following principles:

- For left-, right-, or center-aligned text, lines that fall closer to the right side are favored and have a lower penalty.
- For justified text, the highest importance is given to evenness of letter and word spacing.
- Hyphenation is avoided when possible.

Single-line Composer

The Single-line composer offers a traditional approach to composing type one line at a time. This option is useful if you want manual control over how lines break. The Single-line Composer uses the following principles when considering a breakpoint:

- Longer lines are favored over shorter lines.
- In justified text, compressed or expanded word spacing is preferable to hyphenation.
- In nonjustified text, hyphenation is preferable to compressed or expanded letterspacing.
- If spacing must be adjusted, compression is better than expansion.

  To choose one of these methods, select it from the Paragraph panel menu. To apply the method to all paragraphs, first select the type object; to apply the method to the current paragraph only, first insert the cursor in that paragraph.

Paragraph styles | CC, CS6

A paragraph style includes both character and paragraph formatting attributes, and can be applied to a paragraph or range of paragraphs. You can create Paragraph styles and then apply them later.

Choose **Window** > **Paragraph Styles** to open the Paragraph Styles panel. By default, each new document contains a Basic Paragraph style that is applied to text you type. You can edit this style, but you can't rename or delete it. You can rename and delete styles that you create. You can also select a different default style to apply to text.

- To apply a paragraph style, select the text or text layer and click a paragraph style.

Type styles are hierarchical: Manual overrides supersede any applied character styles, which in turn replace applied paragraph styles. This hierarchical approach lets you combine the efficiency of styles with the flexibility to customize your designs.

For a video overview, see Paragraph and Character Styles in Photoshop CS6 by Julieanne Kost.

(Creative Cloud only) You can specify character and paragraph styles as default types styles. For more information see Specifying default type styles | Creative Cloud only.

Create a paragraph style

1. If you want to base a new style on the formatting of existing text, select that text or place the insertion point in it.
2. Choose New Paragraph Style from the Paragraph Styles panel menu.

Note:To create a style without first selecting text, click the Create New Style icon at the bottom of the Paragraph Styles panel. To edit a style without applying it to text, select an image layer, such as the Background.

Edit a paragraph style

Double-click existing styles to edit them and update all associated text in the current document. When you change the formatting of a style, all text to which the style has been applied will be updated with the new format.

To edit a paragraph style, do the following:

1. Double-click the style in the Paragraph style panel.
2. To specify the formatting attributes, click a category (such as Basic Character Formats) on the left, and specify the attributes to add to the style.
3. When specifying a Character Color in the Style Options dialog box, you can create a new color by double-clicking the fill or stroke box.
4. When you've finished specifying the formatting attributes, click OK.

More Help topics

Format characters

Line and character spacing

Editing text

Specify a burasagari option

Display and set Asian type options

Troubleshoot fonts | Photoshop CC 2014, CC, CS6, CS5

Issues

Damaged fonts can cause various problems in Photoshop, some of which don't appear to be font-related.

Solutions

These solutions are listed in order of easiest, and most likely to locate the damaged font, to more challenging or time consuming.

Important: Remove or update any third-party font plug-ins before testing your fonts.

Solution 1: Update Photoshop to the most recent version

1. Choose Help > Updates (this is the preferred update method).
2. Download the most recent update from the Adobe website: http://www.adobe.com/downloads/updates.

Solution 2: Turn off Font Preview in Photoshop preferences

Photoshop CC 2014, CC, and CS6:

1. Choose Type > Font Preview Size.
2. Select None.

Photoshop CS5:

1. Choose Photoshop > Preferences > Type (Mac OS) or Edit > Preferences > Type (Windows).
2. Deselect Font Preview Size.

Retest your issue to determine if this solution solved the problem.

Solution 3: Remove fonts

The following fonts are known to cause problems when used in Photoshop:

Bustle (Mac OS only)

- 21kannmbn_ttf
- GURAKH_S.TTF
- JH_TITLES.TTF
- SCREEN__.TTF
- SEVESBRG.TTF
- SF Tattle Tales Condensed.ttF
- ZEROGEBI.TTF
- Zippy.ttf

Solution 4: (Mac OS) Validate all fonts through the Font Book Mac OS application

1. Choose Applications > Font Book.
2. Choose All Fonts in the Collection column.
3. Select the top-most font in the Font column and press Cmd+A to select all the fonts.
4. Choose File > Validate Font.
5. Delete the damaged or duplicate font.
6. If Font Book crashes, restart Font Book, and scroll through the fonts one by one to determine which font caused the crash. Use the Down Arrow key to select the first font, then hold the key down to scroll through all your fonts.

Solution 5: Use the FontTest script to determine if there are damaged fonts on your computer

Download, install, and run the appropriate FontTest.jsx script for your version of Photoshop below. The script can determine if there are damaged fonts on your system, or if some of your fonts are causing the crash.

Download and read the appropriate FontTest_readme.pdf file.

Important: This PDF ReadMe file contains critical information on how to install and run the script, and information about the results.**Note:** If Photoshop crashes before you can run this script, the cause is most likely in the operating system, and less likely in Photoshop. In these cases, perform the other solutions in the document.

Photoshop CS6

Right-click (Windows) or Control-click (Mac OS) the FontTest.jsx.zip file below. Then save the FontTest.jsx file to a location on your hard disk, such as your Desktop. Unzip the file by double-clicking it, and if asked, choose to extract all files.

FontTest.jsx.zipFontTest_readme.pdf

Photoshop CS5

Right-click (Windows) or Control-click (Mac OS) the FontTest script . Then, save the FontTest.jsx file to a location on your hard disk, such as your Desktop.

FontTest ReadMe

Solution 6: Delete the Photoshop font cache

Mac OS

1 Quit Photoshop and the Creative Cloud desktop app (if installed).

2 Navigate to:

- Photoshop CS6 and earlier /Users/[user name]/Library/Caches/Adobe
- Photoshop CC or CC 2014 /Users/[user name]/Library/Application Support/Adobe/Adobe Photoshop CC or CC 2014 **Note:** If you're using Mac OS 10.7 or later, use this TechNote to learn how to open the hidden Library folder.

3 Drag the TypeSupport folder (Photoshop CS6 and earlier) or the CT Font Cache folder (Photoshop CC or CC 2014) to the trash and empty the trash.

Windows

1 Exit Photoshop and the Creative Cloud desktop app (if installed).

2 Navigate to the appropriate folder

- Photoshop CS6 and earlier Windows XP: \Documents and Settings\Local Settings\Application Data\Adobe Windows 7: \Users\[user name]\AppData\Local\Adobe
- Photoshop CC and CC 2014 Windows 7 and 8: \Users\[user name]\AppData\Roaming\Adobe\Adobe Photoshop CC or CC 2014

3 Delete the TypeSupport folder (Photoshop CS6 and earlier) or the CT Font Cache folder (Photoshop CC and CC 2014), and empty the trash.

Restart Photoshop and test to determine if the problem recurs.

Solution 7: Delete the system font cache

Mac OS

To delete the system font cache, run a command-line utility in the Terminal application. This command is part of the Mac OS. Be careful when using Terminal, as it affects your operating system at a low level. You can review the Atsutil manual by typing "man atsutil" (without quotes) and pressing Return in Terminal. Or you can read this article in MacWorld magazine: http://www.macworld.com/article/139383/2009/03/fontcacheclear.html

1 Quit Photoshop and the Creative Cloud desktop app (if installed).

2 Choose Applications > Utilities.

3 Open Terminal

4 Type the following command followed with Return

sudo atsutil databases –remove

Windows

Turn on hidden files and folders by accessing this TechNote.

1 Close all Adobe applications including the Creative Cloud desktop app (if installed).

2 Navigate to \Windows\ServiceProfiles\LocalService\Appdata\Local

3 Delete the *FNTCACHE*.DAT or *FontCache*.dat files. **NOTE**: The asterisk (*) indicates various numbers, letters, or words, such as FontCache-S-1-5-21.dat or COFFfntCache.dat.

It is generally a good idea to also delete the Photoshop font cache (Solution 6 above) when deleting the OS cache. Retest to determine if the problem recurs.

Solution 8: Isolate the font causing the problem (Mac OS only)

Important: Apple made the user library folder hidden by default with the release of Mac OS X 10.7. To access files in the hidden library folder to perform Adobe-related troubleshooting, use the methods in How to access hidden user library files.

Make sure that your fonts are located in only one font folder:

- /Users/[user name]/Library/Fonts
- /Library/Fonts

If your fonts are not duplicated, continue with the rest of the Step. If they are duplicated, remove them from one location.

Create two folders on the desktop, called fonttest and goodfonts.

There are three locations that can contain fonts to test. Perform this testing for all of the following folders that contain fonts:

* /Users/[user name]/Library/Fonts * /Library/Fonts * /[network drive]/Library/Fonts

To test for a damaged font, keep half your fonts in the Library/Fonts folder. Move half to the fonttest folder, and test the condition that caused the problem.

- If the problem recurs, the damaged font is still in the Font folder, and the font is not in the fonttest folder. Move the fonts from the fonttest folder to the goodfonts folder.
- If the problem does not recur, the damaged font is in the fonttest folder. Move the fonts from the official fonts folder into the goodfont folder. Move half the fonts back into the official font folder for the next round of testing.
- Continue to test half the remaining fonts, and continue to move the fonts without the problem into the goodfonts folder.
- When you've determined the one font that is causing the problem, remove it from the official fonts folder. Move all the fonts from the goodfonts folder back into the appropriate official fonts folder that you are testing. Perform these tests for each official fonts folder that contain fonts.

Important: If the same problem occurs after you remove a font, one or more fonts have the same or a similar problem. Continue to perform these steps until all damaged fonts are removed.

Required fonts in Photoshop CS6

- AdobeArabic-Bold.otf
- AdobeArabic-BoldItalic.otf
- AdobeArabic-Italic.otf
- AdobeArabic-Regular.otf
- AdobeDevanagari-Bold.otf
- AdobeDevanagari-BoldItalic.otf
- AdobeDevanagari-Italic.otf
- AdobeDevanagari-Regular.otf
- AdobeHebrew-Bold.otf
- AdobeHebrew-BoldItalic.otf
- AdobeHebrew-Italic.otf
- AdobeHebrew-Regular.otf

- AdobeMingStd-Light.otf
- AdobeMyungjoStd-Medium.otf
- AdobeSongStd-Light.otf
- KozGoPr6N-Regular.otf
- KozGoPr6N-Bold.otf
- KozGoPr6N-ExtraLight.otf
- KozGoPr6N-Heavy.otf
- KozGoPr6N-Light.otf
- KozGoPr6N-Normal.otf
- KozMinPr6N-Regular.otf
- KozMinPr6N-Bold.otf
- KozMinPr6N-ExtraLight.otf
- KozMinPr6N-Heavy.otf
- KozMinPr6N-Light.otf
- KozMinPr6N-Medium.otf
- LetterGothicStd.otf
- LetterGothicStd-Bold.otf
- LetterGothicStd-BoldSlanted.otf
- LetterGothicStd-Slanted.otf
- MinionPro-Regular.otf
- MinionPro-It.otf
- MinionPro-Bold.otf
- MinionPro-BoldIt.otf
- MyriadPro-Regular
- MyriadPro-Bold.otf
- MyriadPro-BoldCond.otf
- MyriadPro-BoldCondIt.otf
- MyriadPro-BoldIt.otf
- MyriadPro-Cond.otf
- MyriadPro-CondIt.otf
- MyriadPro-It.otf
- MyriadPro-Semibold.otf
- MyriadPro-SemiboldIt.otf
- MyriadHebrew-Bold.otf
- MyriadHebrew-BoldIt.otf
- MyriadHebrew-It.otf
- MyriadHebrew-Regular.otf

Optional fonts in Photoshop CS6

- ACaslonPro-Bold.otf
- ACaslonPro-BoldItalic.otf
- ACaslonPro-Italic.otf
- ACaslonPro-Regular.otf
- ACaslonPro-Semibold.otf
- ACaslonPro-SemiboldItalic.otf
- AdobeHeitiStd-Regular.otf
- AdobeFangsongStd-Regular.otf
- AdobeFanHeitiStd-Bold.otf
- AdobeGothicStd-Bold.otf
- AdobeKaitiStd-Regular.otf
- AGaramondPro-Bold.otf
- AGaramondPro-BoldItalic.otf
- AGaramondPro-Italic.otf
- AGaramondPro-Regular.otf
- BirchStd.otf
- BlackoakStd.otf
- BrushScriptStd.otf
- ChaparralPro-Bold.otf
- ChaparralPro-BoldIt.otf
- ChaparralPro-Italic.otf
- ChaparralPro-Regular.otf
- CharlemagneStd-Bold.otf
- CooperBlackStd.otf
- CooperBlackStd-Italic.otf
- GiddyupStd.otf
- HoboStd.otf
- KozGoPro-Regular.otf
- KozGoPro-Bold.otf
- KozGoPro-ExtraLight.otf
- KozGoPro-Heavy.otf
- KozGoPro-Light.otf
- KozGoPro-Medium.otf
- KozMinPro-Regular.otf
- KozMinPro-Bold.otf
- KozMinPro-ExtraLight.otf

- KozMinPro-Heavy.otf
- KozMinPro-Light.otf
- KozMinPro-Medium.otf
- LithosPro-Black.otf
- LithosPro-Regular.otf
- MesquiteStd.otf
- MinionPro-BoldCn.otf
- MinionPro-BoldCnIt.otf
- MinionPro-Medium.otf
- MinionPro-MediumIt.otf
- MinionPro-Semibold.otf
- MinionPro-SemiboldIt.otf
- NuevaStd-BoldCond.otf
- NuevaStd-BoldCondItalic.otf
- NuevaStd-Cond.otf
- NuevaStd-CondItalic.otf
- OCRAStd.otf
- OratorStd.otf
- OratorStd-Slanted.otf
- PoplarStd.otf
- PrestigeEliteStd-Bd.otf
- RosewoodStd-Regular.otf
- StencilStd.otf
- TektonPro-Bold.otf
- TektonPro-BoldCond.otf
- TektonPro-BoldExt.otf
- TektonPro-BoldObl.otf
- TrajanPro-Bold.otf
- TrajanPro-Regular.otf

Required fonts in Photoshop CS5

- AdobeArabic-Bold.otf
- AdobeArabic-BoldItalic.otf
- AdobeArabic-Italic.otf
- AdobeArabic-Regular.otf
- AdobeHebrew-Bold.otf
- AdobeHebrew-BoldItalic.otf

- AdobeHebrew-Italic.otf
- AdobeHebrew-Regular.otf
- AdobeMingStd-Light.otf
- AdobeMyungjoStd-Medium.otf
- AdobeSongStd-Light.otf
- KozGoPro-Regular.otf
- KozGoPro-Bold.otf
- KozGoPro-ExtraLight.otf
- KozGoPro-Heavy.otf
- KozGoPro-Light.otf
- KozGoPro-Medium.otf
- KozMinPro-Regular.otf
- KozMinPro-Bold.otf
- KozMinPro-ExtraLight.otf
- KozMinPro-Heavy.otf
- MyriadPro-Regular
- MyriadPro-BoldIt.otf
- MyriadPro-Cond.otf
- MyriadPro-CondIt.otf
- MyriadPro-It.otf
- MyriadPro-Semibold.otf
- MyriadPro-SemiboldIt.otf

Optional fonts in Photoshop CS5

Note: These fonts can influence the way templates display or affect interproduct connectivity.

- ACaslonPro-Bold.otf
- ACaslonPro-BoldItalic.otf
- ACaslonPro-Italic.otf
- ACaslonPro-Regular.otf
- ACaslonPro-Semibold.otf
- ACaslonPro-SemiboldItalic.otf
- AdobeHeitiStd-Regular.otf
- AdobeFangsongStd-Regular.otf
- AdobeFanHeitiStd-Bold.otf
- AdobeGothicStd-Bold.otf
- AdobeKaitiStd-Regular.otf
- AGaramondPro-Bold.otf

- AGaramondPro-BoldItalic.otf
- AGaramondPro-Italic.otf
- AGaramondPro-Regular.otf
- BirchStd.otf
- BlackoakStd.otf
- BrushScriptStd.otf
- ChaparralPro-Bold.otf
- ChaparralPro-BoldIt.otf
- ChaparralPro-Italic.otf
- ChaparralPro-Regular.otf
- CharlemagneStd-Bold.otf
- CooperBlackStd.otf
- CooperBlackStd-Italic.otf
- GiddyupStd.otf
- HoboStd.otf
- KozGoPr6N-Bold.otf
- KozGoPr6N-ExtraLight.otf
- KozGoPr6N-Heavy.otf
- KozGoPr6N-Light.otf
- KozGoPr6N-Medium.otf
- KozGoPr6N-Regular.otf
- KozMinPr6N-Bold.otf
- KozMinPr6N-ExtraLight.otf
- KozMinPr6N-Heavy.otf
- KozMinPr6N-Light.otf
- KozMinPr6N-Medium.otf
- KozMinPr6N-Regular.otf
- LithosPro-Black.otf
- LithosPro-Regular.otf
- MesquiteStd.otf
- MinionPro-BoldCn.otf
- MinionPro-BoldCnIt.otf
- MinionPro-Medium.otf
- MinionPro-MediumIt.otf
- MinionPro-Semibold.otf
- MinionPro-SemiboldIt.otf
- NuevaStd-BoldCond.otf

- NuevaStd-BoldCondItalic.otf
- NuevaStd-Cond.otf
- NuevaStd-CondItalic.otf
- OCRAStd.otf
- OratorStd.otf
- OratorStd-Slanted.otf
- PoplarStd.otf
- PrestigeEliteStd-Bd.otf
- RosewoodStd-Regular.otf
- StencilStd.otf
- TektonPro-Bold.otf
- TektonPro-BoldCond.otf
- TektonPro-BoldExt.otf
- TektonPro-BoldObl.otf
- TrajanPro-Bold.otf
- TrajanPro-Regular.otf

Create type effects

You can perform various operations on type to change its appearance. For example, you can warp type, convert type to shapes, or add a drop shadow to type. One of the easiest ways to create type effects is to play the default Text Effects actions that come with Photoshop on a type layer. You can access these effects by choosing Text Effects from the Actions panel menu.

Create type along or inside a path

You can enter type that flows along the edge of a work path created by a pen or a shape tool. When you enter type along a path, the type flows in the direction that anchor points were added to the path. Entering horizontal type on a path results in letters that are perpendicular to the baseline. Entering vertical type on a path results in text orientation parallel to the baseline.

You can also enter type inside a closed path. In this case, however, the type is always oriented horizontally, with line breaks occurring wherever the type reaches path boundaries.

As you move a path or change its shape, related type conforms to the new path location or shape.



Enter type along a path

1 Do one of the following:

- Select the Horizontal Type tool or the Vertical Type tool .
- Select the Horizontal Type Mask tool or the Vertical Type Mask tool .

2 Position the pointer so that the baseline indicator of the type tool is on the path and click. After you click, an insertion point appears on the path.



3 Enter the type. Horizontal type appears along the path, perpendicular to the baseline. Vertical type appears along the path, parallel to the baseline.

For more control over vertical alignment of type on a path, use the Baseline Shift option in the Character panel. For example, type a negative value in the Baseline Shift text box to lower the type.

Move or flip type along a path

? Select the Direct Selection tool or Path Selection tool and position it over the type. The pointer changes to an I-beam with an arrow .

- To move text, click and drag the type along the path. Be careful not to drag across the path.

- To flip text to the other side of the path, click and drag the type across the path.



To move type across a path without changing the direction of the type, use the Baseline Shift option in the Character panel. For example, if you created type that runs from left to right across the top of a circle, you can enter a negative number in the Baseline Shift text box to drop the type so that it flows inside the top of the circle.

Enter type inside a closed path

1 Select the Horizontal Type tool .

2 Position the pointer inside the path.

3 When the type tool is surrounded by dashed parentheses , click to insert text.

Move a path with type

? Select the Path Selection tool or the Move tool , and then click and drag the path to a new position. If you use the Path Selection tool, make sure that the pointer does not change to an I-beam with an arrow or you'll move the type along the path.

Change the shape of a path with type

1 Select the Direct Selection tool .

2 Click an anchor point on the path and use the handles to change the shape of the path.

Warp and unwarp type

You can warp type to create a special type effect. For example, you can warp type in the shape of an arc or a wave. The warp style you select is an attribute of the type layer—you can change a layer's warp style at any time to change the overall shape of the warp. Warping options give you precise control over the orientation and perspective of the warp effect.

Note: *You cannot warp type layers that include Faux Bold formatting or that use fonts without outline data (such as bitmap fonts).*



Warp type

1 Select a type layer.

2 Do one of the following:

- Select a type tool, and click the Warp button in the options bar.
- Choose Type > Warp Text.

Note: *You can use the Warp command to warp text in a type layer. Choose Edit > Transform Path > Warp.*

3 Choose a warp style from the Style pop-up menu.

4 Select the orientation of the warp effect—Horizontal or Vertical.

5 If desired, specify values for additional warping options:

- Bend to specify how much warp is applied to the layer
- Horizontal Distortion or Vertical Distortion to apply perspective to the warp

Unwarp type

1 Select a type layer that has warping applied to it.

2 Select a type tool and click the Warp button in the options bar, or choose Layer > Type > Warp Text.

3 Choose None from the Style pop-up menu, and click OK.

Create a work path from type

You can work with type characters as vector shapes by converting them to a work path. A *work path* is a temporary path that appears in the Paths panel and defines the outline of a shape. After you create a work path from a type layer, you can save and manipulate it as you do any other path. You cannot edit characters in the path as text; however, the original type layer remains intact and editable.

? Select a type layer, and choose Type > Create Work Path.

Note: *You cannot create work paths from fonts that don't include outline data (such as bitmap fonts).*

Convert type to shapes

When you convert type to shapes, the type layer is replaced by a layer with a vector mask. You can edit the vector mask and apply styles to the layer; however, you cannot edit characters in the layer as text.

? Select a type layer, and choose Type > Convert To Shape.

Note: *You cannot create shapes from fonts that don't include outline data (such as bitmap fonts).*

Create a type selection border

When you use the Horizontal Type Mask tool or Vertical Type Mask tool, you create a selection in the shape of the type. Type selections appear on the active layer, and can be moved, copied, filled, or stroked just like any other selection.

1 Select the layer on which you want the selection to appear. For best results, create the type selection border on a normal image layer, not a type layer. If you want to fill or stroke the type selection border, create it on a new blank layer.

2 Select the Horizontal Type Mask tool or the Vertical Type Mask tool .

3 Select additional type options, and enter type at a point or in a bounding box.

A red mask appears over the active layer as you enter the type. After you click the Commit button , the type selection border appears in the image on the active layer.

Add a drop shadow to text

Add a drop shadow to give depth to text in an image.

1 In the Layers panel, select the layer containing the text to which you want to add a drop shadow.

2 Click the Layer Style button fx at the bottom of the Layers panel and choose Drop Shadow from the list that appears.

3 If possible, position the Layer Style dialog box so that you can see the layer and its drop shadow.

4 Adjust the settings to your liking. You can change various aspects of the shadow, including the way it blends with the layers below it, its opacity (how much the underlying layers show through), the angle of the light, and its distance from the text or object.

5 When you're satisfied with the drop shadow, click OK.

To use the same drop shadow settings on another layer, Alt+drag the Drop Shadow layer in the Layers panel to the other layer. When you release the mouse button, Photoshop applies the drop shadow attributes to the layer.

Fill type with an image

You can fill type with an image by applying a clipping mask to an image layer placed above a type layer in the Layers panel.

1 Open the file containing the image you want to use inside the text.

2 Select the Horizontal Type tool T or the Vertical Type tool T in the toolbox.

3 Click the Character tab to bring the Character panel to the front or, if the panel isn't open, choose Window > Character.

4 In the Character panel, select the font and other type attributes for the text. Large, bold, thick letters work best.

5 Click an insertion point in the document window and type the desired text. When you are satisfied with the text, press Ctrl+Enter (Windows) or Command+Return (Mac OS).

6 Click the Layers tab to bring the Layers panel to the front or, if the panel isn't open, choose Windows > Layers.

7 (Optional) If the image layer is the background layer, double-click the image layer in the Layers panel to convert it from a background layer into a regular layer.

Note: *Background layers are locked and prevent you from moving them in the Layers panel. It's necessary to convert background layers to regular layers to unlock them.*

8 (Optional) In the New Layer dialog box, you can rename the layer. Click OK to close the dialog box and convert the image layer.

9 In the Layers panel, drag the image layer so that it is immediately above the type layer.

10 With the image layer selected, choose Layer > Create Clipping Mask. The image appears inside the text.

11 Select the Move tool , and then drag the image to adjust its placement within the text.

To move the text instead of the image, select the type layer in the Layers panel and then use the Move tool to move the text.

More Help topics

Play an action on a file

Understand shapes and paths

Shift the baseline

Warp an item

Path segments, components, and points

Understand shapes and paths

About layer effects and styles

Mask layers with clipping masks

Entering type

Formatting characters

Edit text

Edit text

1 Select the Horizontal Type tool T or the Vertical Type tool T.

2 Select the type layer in the Layers panel, or click in the text flow to automatically select a type layer.

3 Position the insertion point in the text, and do one of the following:

- Click to set the insertion point.
- Select one or more characters you want to edit.

4 Enter text as desired.

5 In the options bar, do one of the following:

- Click the Commit button ✓ to apply your changes to the type layer.
- Click the Cancel button ⊘ or press ESC.

Specify curly or straight quotes

Typographer's quotes, often called curly quotes or smart quotes, blend in with the curves of the font. Typographer's quotes are traditionally used for quotation marks and apostrophes. *Straight quotes* are traditionally used as abbreviations for feet and inches.

1 Choose Edit > Preferences > Type (Windows) or Photoshop > Preferences > Type (Mac OS).

2 Under Type Options, select or deselect Use Smart Quotes.

Apply anti-aliasing to a type layer

Anti-aliasing produces smooth-edged type by partially filling the edge pixels. As a result, the edges of the type blend into the background.



When creating type for display on the web, consider that anti-aliasing greatly increases the number of colors in the original image. This limits your ability to reduce the number of colors in the image and thus to reduce the size of the image file. Anti-aliasing may also cause stray colors to appear along the edges of the type. When reducing file size and limiting the number of colors are most important, it may be preferable to avoid anti-aliasing, despite the jagged edges. Also, consider using larger type than you would use for print. Larger type is easier to view on the web and gives you more freedom in deciding whether to apply anti-aliasing.

Note: *When you use anti-aliasing, type may be rendered inconsistently at small sizes and low resolutions (such as the resolution used for web graphics). To reduce this inconsistency, deselect the Fractional Width option in the Character panel menu.*

1 Select the type layer in the Layers panel.

2 Choose an option from the anti-aliasing menu a_a in the options bar or the Character panel. Or, choose Layer > Type, and choose an option from the submenu.

None Applies no anti-aliasing

Sharp Type appears at its sharpest

Crisp Type appears somewhat sharp

Strong Type appears heavier

Smooth Type appears smoother

Check and correct spelling

When you check the spelling in a document, Photoshop questions any words that aren't in its dictionary. If a questioned word is spelled correctly, you can confirm its spelling by adding the word to your personal dictionary. If a questioned word is misspelled, you can correct it.

1 If necessary, in the Character panel, choose a language from the pop-up menu at the bottom of the panel. This is the dictionary Photoshop uses to check spelling.

2 (Optional) Show or unlock type layers. The Check Spelling command does not check spelling in hidden or locked layers.

3 Do one of the following:

- Select a type layer.
- To check specific text, select the text.
- To check a word, place the insertion point in the word.

4 Choose Edit > Check Spelling.

5 If you selected a type layer and want to check the spelling of only that layer, deselect Check All Layers.

6 As Photoshop finds unfamiliar words and other possible errors, click one of the following:

Ignore Continues the spelling check without changing the text.

Ignore All Ignores the questioned word during the rest of the spelling check.

Change Corrects a misspelling. Make sure that the correctly spelled word is in the Change To text box and click Change. If the suggested word is not the word you want, select a different word in the Suggestions text box or enter the correct word in the Change To text box.

Change All Corrects all instances of the misspelling in the document. Make sure the correctly spelled word is in the Change To text box.

Add Stores the unrecognized word in the dictionary, so that subsequent occurrences are not flagged as misspellings.

Find and replace text

1 Do one of the following:

- Select the layer containing the text you want to find and replace. Place the insertion point at the beginning of the text you want to search.
- Select a nontype layer if you have more than one type layer and you want to search all layers in the document.

Note: *In the Layers panel, make sure the type layers you want to search are visible and unlocked. The Find And Replace Text command does not check spelling in hidden or locked layers.*

2 Choose Edit > Find And Replace Text.

3 In the Find What box, type or paste the text you want to find. To change the text, type the new text in the Change To text box.

4 Select one or more options to refine your search.

Search All Layers Searches all layers in a document. This option is available when a nontype layer is selected in the Layers panel.

Forward Searches forward from an insertion point in the text. Deselect this option to search all the text in a layer, regardless of where the insertion point is placed.

Case Sensitive Searches for a word or words that exactly match the case of the text in the Find What text box. For example, with the Case Sensitive option selected, a search for "PrePress" does not find "Prepress" or "PREPRESS."

Whole Word Only Disregards the search text if it is embedded in a larger word. For example, if you are searching for "any" as a whole word, "many" is disregarded.

5 Click Find Next to begin the search.

6 Click one of the following buttons.

Change Replaces the found text with the revised text. To repeat the search, select Find Next.

Change All Searches for and replaces all occurrences of the found text.

Change/Find Replaces the found text with the revised text, and then searches for the next occurrence.

Assign a language for text

Photoshop uses language dictionaries to check hyphenation. Language dictionaries are also used to check spelling. Each dictionary contains hundreds of thousands of words with standard syllable breaks. You can assign a language to an entire document or apply a language to selected text.



A *"Cactophiles" in English USA* ***B*** *"Cactophiles" in English UK* ***C*** *"Cactophiles" in French*

1 Do one of the following:

- To enter text using a specific language dictionary, choose the dictionary from the pop-up menu in the lower left corner of the Character panel. Then enter the text.
- To change the dictionary of existing text, select the text and choose the dictionary from the pop-up menu in the lower left corner of the Character panel.

2 In the Character panel, choose the appropriate dictionary from the pop-up menu in the lower left corner of the panel.

Note: *If you select text with multiple languages or if the type layer has multiple languages, the pop-up menu in the Character panel will be dimmed and it will display the word "Multiple."*

Scale and rotate type

Adjust the scale of type

You can specify the proportion between the height and width of the type, relative to the original width and height of the characters. Unscaled characters have a value of 100%. Some type families include a true *expanded font*, which is designed with a larger horizontal spread than the plain type style. Scaling distorts the type, so it is generally preferable to use a font that is designed as condensed or expanded, if one is available.

1 Select the characters or type objects you want to change. If you don't select any text, the scale applies to new text you create.

2 In the Character panel, set the Vertical Scaling option or the Horizontal Scaling option .

Rotate type

? Do the following:

- To rotate type, select the type layer and use any rotate command or the Free Transform command. For paragraph type, you can also select the bounding box and use a handle to rotate the type manually.
- To rotate multiple characters in vertical Asian text, use the tate-chu-yoko.

More Help topics

Use tate-chu-yoko

Apply transformations

Rotate vertical type characters

When working with vertical type, you can rotate the direction of characters by 90°. Rotated characters appear upright; unrotated characters appear sideways (perpendicular to the type line).

1 Select the vertical type you want to rotate or unrotate.

2 Choose Standard Vertical Roman Alignment from the Character panel menu. A check mark indicates that the option is selected.

Note: *You cannot rotate double-byte characters (full-width characters available only in Chinese, Japanese, and Korean fonts). Any double-byte characters in the selected range will not be rotated.*

Change the orientation of a type layer

The orientation of a type layer determines the direction of type lines in relation to the document window (for point type) or the bounding box (for paragraph type). When a type layer is vertical, the type flows up and down; when a type layer is horizontal, the type flows from left to right. Don't confuse the orientation of a type layer with the direction of characters in a type line.

1 Select the type layer in the Layers panel.

2 Do one of the following:

- Select a type tool, and click the Text Orientation button in the options bar.
- Choose Layer > Type > Horizontal, or choose Layer > Type > Vertical.
- Choose Change Text Orientation from the Character panel menu.

Rasterize type layers

Some commands and tools—such as filter effects and painting tools—are not available for type layers. You must rasterize the type before applying the command or using the tool. *Rasterizing* converts the type layer into a normal layer and makes its contents uneditable as text. A warning message appears if you choose a command or tool that requires a rasterized layer. Some warning messages provide an OK button you can click to rasterize the layer.

? Select the type layer and choose Layer > Rasterize > Type.

More Help topics

Formattingcharacters

Formattingparagraphs

Lineand character spacing

Fonts

Line and character spacing

Set leading

The vertical space between lines of type is called *leading* (rhymes with *sledding*). For Roman type, leading is measured from the baseline of one line of text to the baseline of the line above it. The *baseline* is the invisible line on which most letters sit. You can apply more than one leading amount within the same paragraph; however, the largest leading value in a line of type determines the leading value for that line.

Note: *When working with horizontal Asian type, you can specify how leading is measured, either from baseline to baseline or from the top of one line to the top of the next.*



Set the leading

1 Select the characters you want to change. If you don't select any text, the leading applies to new text you create.

2 In the Character panel, set the Leading value.

Change the default auto leading percentage

1 Choose Justification from the Paragraph panel menu.

2 For Auto Leading, enter a new default percentage.

Kern and track

Kerning is the process of adding or subtracting space between specific pairs of characters. *Tracking* is the process of loosening or tightening the spacing between the characters in selected text or an entire block of text.

Note: *Values for kerning and tracking affect Japanese text but normally these options are used to adjust the aki between Roman characters.*

You can automatically kern type using metrics kerning or optical kerning. Metrics kerning (also called auto kerning) uses kern pairs, which are included with most fonts. Kern pairs contain information about the spacing of specific pairs of letters. Some of these are: LA, P., To, Tr, Ta, Tu, Te, Ty, Wa, WA, We, Wo, Ya, and Yo. Metrics kerning is set as the default so that specific pairs are automatically kerned when you import or type text.

Some fonts include robust kern-pair specifications. However, when a font includes only minimal built-in kerning or none at all, or if you use two different typefaces or sizes in one or more words on a line, you may want to use the optical kerning option. Optical kerning adjusts the spacing between adjacent characters based on their shapes.



A *Original text* ***B*** *Text with optical kerning* ***C*** *Text with manual kerning between W and a* ***D*** *Text with tracking* ***E*** *Cumulative kerning and tracking*

You can also use *manual kerning*, which is ideal for adjusting the space between two letters. Tracking and manual kerning are cumulative, so you can first adjust individual pairs of letters, and then tighten or loosen a block of text without affecting the relative kerning of the letter pairs.

When you click to place the insertion point between two letters, kerning values appear in the Character panel. Similarly, if you select a word or a range of text, the tracking values appear in the Character panel.

Tracking and kerning are both measured in 1/1000 em, a unit of measure that is relative to the current type size. In a 6-point font, 1 em equals 6 points; in a 10-point font, 1 em equals 10 points. Kerning and tracking are strictly proportional to the current type size.

Note: *Values for kerning and tracking affect Japanese text, but normally these options are used to adjust the aki between roman characters.*

Adjust kerning

? Do any of the following:

- To use a font's built-in kerning information for selected characters, select Metrics for the Kerning option in the Character panel.
- To automatically adjust the spacing between selected characters based on their shapes, select Optical for the Kerning option in the Character panel.
- To adjust kerning manually, place an insertion point between two characters, and set the desired value for the Kerning option in the Character panel. (Note that if a range of text is selected, you can't manually kern the text. Instead, use tracking.)

Press Alt+Left/Right Arrow (Windows) or Option+Left/Right Arrow (Mac OS) to decrease or increase the kerning between two characters.

- To turn off kerning for selected characters, set the Kerning option in the Character panel to 0 (zero).

Adjust tracking

1 Select the range of characters or the type object that you want to adjust.

2 In the Character panel, set the Tracking option.

Shift the baseline

Use Baseline Shift to move selected characters up or down relative to the baseline of the surrounding text. Shifting the baseline is especially useful when you're hand-setting fractions or adjusting the position of a picture font.

1 Select the characters or type objects you want to change. If you don't select any text, the shift applies to new text you create.

2 In the Character panel, set the Baseline Shift option. Positive values move the character's baseline above the baseline of the rest of the line; negative values move it below the baseline.



Turn fractional character widths off or on

By default, the software uses *fractional character widths* between characters. This means that the spacing between characters varies, and will sometimes use only fractions of whole pixels.

In most situations, fractional character widths provide the best spacing for type appearance and readability. However, for type in small sizes (less than 20 points) displayed online, fractional character widths could cause type to run together or have too much extra space, making it difficult to read.

Turn off fractional widths when you want to fix type spacing in whole-pixel increments and prevent small type from running together. The fractional character width setting applies to all characters on a type layer—you cannot set the option for selected characters.

? Do any of the following:

- To set type spacing for the entire document in whole-pixel increments, choose System Layout from the Character panel menu.
- To re-enable fractional character widths, choose Fractional Widths from the Character panel menu.

More Help topics

Asian type

Asian type

Photoshop provides several options for working with Chinese, Japanese, and Korean type. Characters in Asian fonts are often referred to as *double-byte characters.*

Note: *Your operating system must support the languages in which you wish to work. Consult your system software manufacturer for more information.*

Display and set Asian type options

By default, non-Chinese, Japanese, or Korean versions of Photoshop hide options for Asian type that appear in the Character panel and Paragraph panel. To view and set options for working with Chinese, Japanese, and Korean type in these versions of Photoshop, you must select Show Asian Text Options in the Preferences dialog box. You can also control how font names are displayed—in English or in the native language.

1 Choose Edit > Preferences > Type (Windows) or Photoshop > Preferences > Type (Mac OS).

2 Select from the following options:

Show Font Names In English Displays Asian font names in English.

East Asian (CC, CS6) or Show Asian Text Options (CS5) Displays Asian type options in the Character and Paragraph panels.

Reduce spacing around Asian type characters

Tsume reduces the space around a character by a specified percentage value. As a result, the character itself is not stretched or squeezed. Instead, the space between the character's bounding box and the em box is compressed. When tsume is added to a character, spacing around both sides of the character is reduced by an equal percentage.

1 Select the characters you want to adjust.

2 In the Character panel, enter or select a percentage for Tsume . The greater the percentage, the tighter the compression between characters. At 100% (the maximum value), there is no space between the character's bounding box and its em box.

Specify how leading is measured in Asian type

1 Select the paragraphs you want to adjust.

2 Choose a leading option from the Paragraph panel menu.

Top-to-top Leading Measures the spacing between lines of type from the top of one line to the top of the next line. When you use top-to-top leading, the first line of type in a paragraph is aligned flush with the top of the bounding box.

Bottom-to-bottom Leading For horizontal type, measures the space between lines of type from the type baseline. When you use bottom-to-bottom leading, space appears between the first line of type and the bounding box. A check mark indicates which option is selected.

Note: *The leading option you choose does not affect the amount of leading between lines, only how the leading is measured.*

Use tate-chu-yoko

Tate-chu-yoko (also called *kumimoji* and *renmoji*) is a block of horizontal type laid out within vertical type lines. Using tate-chu-yoko makes it easier to read half-width characters such as numbers, dates, and short foreign words in vertical text.

1 Select the characters you want to rotate.

2 Choose Tate-Chu-Yoko from the Character panel menu. A check mark indicates that the option is turned on.

Note: *Using tate-chu-yoko does not prevent you from editing and formatting type; you can edit and apply formatting options to rotated characters just as you do to other characters.*

Align Asian characters with mojisoroe

Mojisoroe is the alignment of characters in Asian type. When a line of text contains different sizes of characters, you can specify how to align text to the largest characters in the line: to the top, center, or bottom of the em box (right, center, and left for vertical frames), to the roman baseline, or to the top or bottom of the ICF box (right or left for vertical frames). ICF (Ideographic Character Space) is the average height and width used by the font designer to design the ideographic characters that comprise a font.

***A** Small characters aligned to the bottom **B** Small characters aligned to the center **C** Small characters aligned to the top*

? In the Character panel menu, choose an option from the Character Alignment submenu:

Roman Baseline Aligns the small characters in a line to the large character.

Em box Top/Right, Em box Center, or Em box Bottom/Left Aligns the small characters in a line to the specified position of the large character's em box. In vertical text frames, Em box Top/Right aligns the text to the right of the em box, and Em box Bottom/Left aligns the text to the left of the em box.

ICF Top/Right and ICF Bottom/Left Aligns the small characters in a line to the ICF specified by the large characters. In vertical text frames, ICF Top/Right aligns the text to the right of the ICF, and ICF Bottom/Left aligns the text to the left of the ICF.

Specify left and right underlining with Asian type

1 Select vertical type.

2 Choose either Underline Left or Underline Right from the Character panel menu.

Set Asian OpenType font attributes

Asian OpenType fonts may include a number of features that aren't available in current PostScript and TrueType fonts. It is usually best to use any weights of KozMinPro and KozGoPro OpenType fonts. These fonts have the largest collection of glyphs of the Asian fonts produced by Adobe.

1 With the Type tool selected, do one of the following:

- On an existing type layer, select the characters or type objects to which you want to apply the setting.
- Click on the image to create a new type layer.

2 In the Character panel, make sure that an Asian OpenType Pro font is selected.

3 From the Character panel menu, choose an OpenType option.

4 Turn on the MSIME (Windows) or Kotoeri (Mac OS) input method. Do one of the following:

- (Windows) From the Windows Start menu, choose Programs > Accessories > System Tools > Character Map.
- (Mac OS) From the Input pop-up menu at the right side of the menu bar, choose Show Character Viewer.

***Note:** (Mac OS) If the Input menu does not display in the menu bar, choose Apple menu > System Preferences > Language & Text, then click Input Sources, and select Keyboard & Character Viewer.*

5 Do one of the following:

- (Windows) In Character Map, select the Advanced View option, choose All from the Group By menu, and then choose Unicode for Character Set.

- (Mac OS) In the Kotoeri Character panel, select Glyph from the View menu.

A View menu B Font menu C Character Information D Insert With Font button

6 Choose an Asian OpenType font from the Font menu.

7 Do one of the following:

- (Windows) Select the character you want to use, click Select, click Copy, and then paste it in Photoshop.
- (Mac OS) Double-click the character you want to use to insert it into your document.

Asian OpenType options

Additional OpenType options are available, depending on the font.

Japanese 78 Substitutes the standard glyph with the jp78-variant glyph.

Japanese Expert Substitutes the standard glyph with the expert-variant glyphs.

Japanese Traditional Substitutes the standard glyph with the traditional-variant glyph.

Proportional Metrics Substitutes the half-width and the full-width glyphs with the proportional glyph.

Kana Substitutes the standard kana glyph with the horizontally optimized kana glyph for horizontal layout. However, the differences are often very subtle.

Roman Italics Substitutes the standard proportional glyph with the italic glyph.

For more information, see .

Choose a mojikumi set

Mojikumi specifies Japanese text composition for spacing of Japanese characters, roman characters, punctuation, special characters, line start, line end, and numbers. Photoshop includes several predefined mojikumi sets based on the Japanese Industrial Standard (JIS) X 4051-1995.

? In the Paragraph panel, choose an option from the Mojikumi pop-up menu:

None Turns off the use of mojikumi.

Mojikumi Set 1 Uses half-width spacing for punctuation.

Mojikumi Set 2 Uses full-width spacing for most characters except the last character in the line.





Mojikumi Set 3 Uses full-width spacing for most characters and the last character in the line.

Mojikumi Set 4 Uses full-width spacing for all characters.





Set kinsoku shori options

Kinsoku shori specifies line breaks for Japanese text. Characters that cannot begin a line or end a line are known as *kinsoku* characters. Photoshop includes weak and maximum kinsoku sets based on the Japanese Industrial Standard (JIS) X 4051-1995. Weak kinsoku sets omit long vowel symbols and small hiragana characters.

Disable or enable kinsoku shori for a paragraph

? In the Paragraph panel, choose an option from the Kinsoku Shori pop-up menu:

None Turns off the use of kinsoku shori.

JIS Weak or JIS Maximum Prevents the following characters from beginning or ending a line:

JIS Weak Set	
Characters that can't begin a line	’ ” 、 。 々 〉 》 」 』 】 〕 ゝ ゞ ・ ヽ ヾ !) , . : ; ?] }
Characters that can't end a line	‘ “ 〈 《 「 『 【 〔 ([{

JIS Maximum Set	
Characters that can't begin a line	!) , . : ; ?] } ¢ — ’ ” ‰ ℃ ℉ 、 。 々 〉 》 」 』 】 〕 ぁ ぃ ぅ ぇ ぉ っ ゃ ゅ ょ ゎ ゛ ゜ ゝ ゞ ァ ィ ゥ ェ ォ ッ ャ ュ ョ ヮ ヵ ヶ ・ — ヽ ヾ ! %) , . : ; ?] }
Characters that can't end a line	([{ £ § ‘ “ 〈 《 「 『 【 〒 〔 # $ (@ [{ ¥

Specify a kinsoku line-breaking option

Kinsoku shori or mojikumi must be selected to use the following line-breaking options.

? From the Paragraph panel menu, choose Kinsoku Shori Type and then choose one of the following methods:

Push In First Moves characters up to the previous line to prevent prohibited characters from ending or beginning a line.

Push Out First Moves characters down to the next line to prevent prohibited characters from ending or beginning a line.

Push Out Only Always moves characters down to the next line to prevent prohibited characters from ending or beginning a line. A push-in is not attempted.

A check mark indicates which method is selected.

Specify a burasagari option

Burasagari lets single-byte periods, double-byte periods, single-byte commas, and double-byte commas fall outside the paragraph bounding box.

1 In the Paragraph panel, choose Burasagari from the panel menu.

2 Choose an option from the submenu:

None Turns off hanging punctuation.

Regular Turns on hanging punctuation without forcing ragged lines to the bounding box edge.

Force Forces punctuation outside the bounding box by spreading lines that end within the bounding box and end with one of the hanging characters.

Note: *The Burasagari options are not available when Kinsoku Shori is set to None.*

Arabic and Hebrew type

Enable Middle Eastern features

To reveal Middle Eastern type options in the Photoshop interface, do the following:

1 Choose Edit > Preferences > Type (Windows) or Photoshop > Preferences > Type (Mac OS).

2 In the Choose Text Engine Options section, select Middle Eastern.

3 Click OK, and restart Photoshop.

4 Choose Type > Language Options > Middle Eastern features.

Text direction

To create content in Arabic and Hebrew, you can make the right-to-left (RTL) direction the default text direction. However, for documents that include left-to-right (LTR) text, you can now seamlessly switch between the two directions.

Select the paragraph direction from the Paragraph panel.



Digit types

When you are working in Arabic or Hebrew, you can select the type of digits you want to use. You can choose between Arabic, Hindi, and Farsi.

By default, in Arabic versions of Photoshop, Hindi digits are auto-selected; in Hebrew versions, Arabic digits are selected. However, you can manually change digit types if necessary:

1 Select the digits in the text.

2 In the Character panel, use the Digits menu to select the appropriate font.



Legacy font support

Fonts that have been traditionally used (for example, AXT fonts) can continue to be used in this release of the software. However, it is recommended that newer Open Type fonts be used for text-based elements.

Missing Glyph Protection (Edit > Preferences > Advanced Type) is enabled by default. Text is handled automatically, where glyphs are not available in the font you are using.

Default fonts

When you install a Middle Eastern or North African version, the default typing font is set to the installation-specific language, by default. For example, if you have installed the English/Arabic-enabled version, the default typing font is set to Adobe Arabic. Similarly, if you have installed the English/Hebrew-enabled version, the default typing font is set to Adobe Hebrew (or Myriad Hebrew in Photoshop).

Automatic Kashida insertion

In Arabic, text is justified by adding Kashidas. Kashidas are added to Arabic characters to lengthen them. Whitespace is not modified. Use automatic Kashida insertion to justify paragraphs of Arabic text.

Select the paragraph, and at the lower-right of the Paragraph panel, choose an option from the Insert Kashidas pop-up menu: None, Short, Medium, Long, or Stylistic.

Note: Kashidas are inserted only in paragraphs with fully justified margins.

To apply Kashidas to a group of characters, select the characters in the document, and then choose Type > Language Options > Kashidas.

Ligatures (OpenType fonts)

With some OpenType fonts, you can automatically apply ligatures to character pairs in Arabic and Hebrew. Ligatures are typographic replacement characters for certain letter pairs.

1 Select text.

2 In the Character panel, above the language and anti-aliasing menus, click the Standard or Discretionary Ligatures icon.

Discretionary ligatures provide more ornate options that some fonts support.

Hyphenation

Sentences that have more words that can fit into one line of text automatically wrap into the next line. The type of text justification when wrapping occurs sometimes causes unnecessary spaces to appear in the line that are not aesthetically pleasing or linguistically correct. Hyphenation enables you to split the word at the end of a line, using a hyphen. This fragmentation causes the sentence to wrap into the next line in a better way.

Mixed text: The Kashida insertion feature affects how hyphenation occurs in mixed text. When enabled, Kashidas are inserted where applicable, and non-Arabic text is not hyphenated. When the Kashida feature is disabled, only non-Arabic text is considered for hyphenation.

Hebrew text: Hyphenation is allowed. To enable hyphenation and customize settings, choose Paragraph panel > Panel menu > Hyphenation Settings.



Diacritical marks

In the Arabic script, a diacritic or a diacritical mark is a glyph used to indicate consonant length or short vowels. A diacritical mark is placed above or below the script. For better styling of text, or improved readability of certain fonts, you can control the vertical or horizontal position of diacritical marks:

1 Select text that has diacritical marks

2 In the Character panel, modify the position of the diacritic marks relative to the script. Values you can change are, Adjust Horizontal Diacritic Position, and the Adjust Vertical Diacritic Position.

Justification alternates

A font can provide alternative shapes for certain letters, typically for stylistic or calligraphy purposes. In rare cases, justification alternates are used to justify and align paragraphs containing these shapes.

Justification alternates can be turned on at a character level, but only if a font supports this feature. At the bottom of the Character panel, select Justification Alternates.

These Arabic fonts contain justification alternates: Adobe Arabic, Myriad Arabic, and Adobe Naskh.

These Hebrew fonts contain justification alternates: Adobe Hebrew and Myriad Hebrew.

Text Engine error using type tool in Photoshop CC | Windows 8

Issue

When you use the Type tool, you receive the following error:

"Could not complete your request because something prevented the text engine from being initialized."

Solution

Close Photoshop, clear the font cache, and restart.

1 Exit Photoshop.

2 In Windows Explorer, navigate to the Users/[user name]/AppData/Roaming/Adobe/Adobe Photoshop CC/CT Font Cache folder.

3 Move these two files to the Recycle Bin:

- AdobeFnt_CMaps.lst
- AdobeFnt_OSFonts.lst

4 Empty the Recycle Bin.

5 Restart Photoshop.

Additional information

This issue can occur after you uninstall and reinstall Photoshop several times.

Chapter 14: Video and animation

Video editing | CC, CS6

Timeline video creation

The redesigned, clip-based Timeline panel reflects video editors like Adobe Premiere, including transitions and effects that give finished videos professional polish.

Video tutorials:

Intuitive video Workflow: How to add video clips, trim video clips, add a music track, and render your movie for playback by your audience. By RC Conception (8:18)

How to edit video in Photoshop. By Matthew Gore (10:42)

Slip editing to adjust the in and out points of a video without changing the clip duration. By Meredith Payne-Stotzner (1:20)

Frame skipping and caching to improve playback performance. By Meredith Payne-Stotzner (2:07)

Changing clip speed: Slow and Fast Motion. By Jeff Sengstack (9:45). How to put clips into slow motion or speed them up. By Jeff Sengstack (9:45)

Video Groups

Video Groups combine multiple video clips and other content such as text, images, and shapes on a single track in the Timeline.

Create a Video Group

- Import a video file; it's automatically added as a new Video Group.
- To create an empty group for adding content to, click a filmstrip icon on the left of the Timeline panel, and choose New Video Group from the pop-up menu.

Edit a Video Group

- To reposition clips, drag them in the Timeline.
- To change in and out points, drag clip borders in the Timeline.
- To move items from one group to another, drag them up or down in the Timeline or Layers panel.
- To divide a selected clip and edit the resulting parts separately, position the Timeline playhead where you want to split the clip. Then click the Split At Playhead button in the upper-left corner of the Timeline panel.

Audio tracks and controls

Separate audio tracks in the Timeline allow for easy editing and adjusting.

Adjust audio in clips

- Right-click audio clips to mute them, adjust volume, or fade in and out.
- Right-click video clips, and click the musical notes to adjust audio they contain.

Adjusting audio: Video tutorial by Richard Harrington. (3:31)

Create or delete audio tracks

- To the right of audio track names in the Timeline, click the musical notes, and select either New Audio Track or Delete Track.

Add, duplicate, delete, or replace audio clips

- To the right of audio track names in the Timeline, click the musical notes. Then select Add Audio to place another clip on the track.
- Select an audio clip in the Timeline, and click the musical notes to the right of the track name. Then select Duplicate, Delete, or Replace Audio Clip.

Video transitions

Transitions create professional fade and cross-fade effects. Click the transitions icon in the upper left of the Timeline panel. Then choose a duration, and drag a transition type to the start or end of clips. (Place the transition between clips to cross-fade.) Drag the edges of the transition preview in the Timeline to precisely set in and out points.

Right-click transitions in the Timeline to replace them with another transition type or specify a precise numeric duration.

Change video clip duration and speed

Right-click video clips to access Duration and Speed sliders. These controls interact; for example, a Speed of 400% limits the maximum duration to one-quarter of the original.

Apply filters to video layers

To apply filters across all frames in a video layer, first convert the layer into a Smart Object. Any subsequent filters you apply become Smart Filters, which provide total flexibility, letting you readjust filter settings at any time.

1. Select the video layer in the Timeline or Layers panel.
2. Choose Layer > Smart Objects > Convert to Smart Object.
3. Apply filters from the Filter menu. To later readjust settings, view the Layers panel, and double-click the filter in the Smart Filters list for the video layer.

For more information, see Nondestructive editing.

Apply motion effects to text, still images, and Smart Objects

Right-click text, still-image, and Smart Object clips to access pan, zoom, and rotate presets, quickly applying sophisticated animation. Drag the resulting Transform keyframes in the Timeline to fine-tune the results.

To create dramatic effects as you pan, scale, and rotate clips over time, convert your clip to a Smart Object and use Transform keyframes with the Free Transform tool.

Video tutorials:

Transforming Layers over time. Julieanne Kost (3:52)

Creating masks to move over time. Julieanne Kost (3:17)

How to pan and zoom video in Photoshop. Julieanne Kost (18:06)

Create animations with audio. Tutorial article by Rafiq Elmansy.

Import a wider range of file formats

With a redesigned video engine, you can import a wider range of video, audio, and image sequence files. Easily work with file types such as 3GP, 3G2, AVI, DV, FLV and F4V, MPEG-1, MPEG-4, QuickTime MOV(in Windows, full support requires separate QuickTime installation).

For the complete list, see .

Export final video with the Adobe Media Encoder

Choose File > Export > Render Video. From the first pop-up menu, select Adobe Media Encoder to choose from the following Format options:

- DPX (Digital Picture Exchange) format is designed primarily for frame sequences that you plan to incorporate into professional video projects using an editor such as Adobe Premiere Pro.
- H.264 (MPEG-4) format is the most versatile, including presets for high-definition and widescreen video, and output optimized for tablet devices or web delivery.
- QuickTime (MOV) format is required for export of alpha channels and uncompressed video. The Preset menu provides additional compression options.

More Help topics

Video and animation overview

Edit video and animation layers

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Transform video layers

You can transform a video layer as you transform any other layer in Photoshop. However, you must convert video layers to Smart Objects before you can transform them.

1. In the Timeline or Layers panel, select the video layer.
2. Do any of the following:
   - Choose Edit > Free Transform to use handles in the document window to transform the video.
   - Choose Edit > Transform and choose a specific transformation from the submenu.

   If the video layer is not a Smart Object, Photoshop asks you to convert it.

Create new video layers

You can create new video layers by adding a video file as a new layer or creating a blank layer.

Open a video file

? Choose File > Open, select a video file, and click Open.

The video appears on a video layer in a new document.

Add a video file as a new video layer

1 For the active document, make sure that the Timeline panel is displayed in timeline mode.

2 Choose Layer > Video Layers > New Video Layer From File.

3 Select a video or image sequence file and click Open.

Add a blank video layer

1 For the active document, make sure that the Timeline panel is displayed in the timeline mode.

2 Choose Layer > Video Layers > New Blank Video Layer.

Specify when a layer appears in a video or animation

You can use various methods to specify when a layer appears in a video or animation. For example, you can trim (hide) frames at the beginning or end of a layer. This changes the layer's start and end points in a video or animation. (The first frame to appear is called the In point, and the last frame is called the Out point.) You can also drag the entire layer duration bar to a different portion of the timeline.

1 In the Timeline panel, select the layer.

2 Do any of the following:

- To specify the In and Out points of a layer, drag the beginning and end of the layer duration bar.
- Drag the layer duration bar to the section of the timeline where you want the layer to appear.

Note: *For best results, drag the layer duration bar after the bar has been trimmed.*



- Move the current-time indicator to the frame you want as the new In or Out point, and from the panel menu, choose Trim Layer Start To Current Time or Trim Layer End To Current Time.

This shortens the layer duration by hiding the frames between the current-time indicator and either the start or the end of the layer. (Re-extending the ends of the layer duration bar reveals the hidden frames.)

- Use keyframes to change the layer's opacity at specific times or frames.

Note: *To delete footage in one or more layers, use the Lift Work Area command. To delete a specific duration from all video or animated layers, use the Extract Work Area command.*

Trim or move a video layer

To hide frames at the start or end of a video or animation layer, trim the layer. To start or end video at a different time point, move the video layer.

If you move video layers, changes become permanent when you save the file. If you trim video, however, you can restore it by re-extending the ends of the layer duration bar.

1 In the Timeline or Layers panel, select the layer you want to edit.

2 Move the current-time indicator to the frame (or time) you want as the new In point or Out point.

3 From the Timeline panel menu, choose one of the following options:

Move Layer In Point To Current Time Permanently moves the start of the layer to the current-time indicator.

Move Layer End Point To Current Time Permanently moves the end of the layer to the current-time indicator.

Trim Layer Start To Current Time Temporarily hides section from the current-time indicator to the start of the layer.

Trim Layer End To Current Time Temporarily hides section from the current-time indicator to the end of the layer.

Note: *You can also use the Lift Work Area command to hide frames in one or more layers, or the Extract Work Area command to hide a specific duration in all layers of a video or animation.*

Lift work area

A section of the footage in selected layers can be deleted, leaving a gap of the same duration as the removed section.

1 Select the layers you want to edit.

2 In the Timeline panel, set the work area to specify the duration of the selected layers you want to omit.

3 From the panel menu, choose Lift Work Area.





Extract work area

To delete portions of video and automatically remove the time gap, use the Extract Work Area command. The remaining content is copied to new video layers.

1 Select the layers you want to edit.

2 In the Timeline panel, set the work area to specify the duration of the video or animation that you want to omit.

3 From the panel menu, choose Extract Work Area.

Split video layers

A video layer can be split into two new video layers at the frame you specify.

1 Select a video layer in the Timeline panel.

2 Move the current-time indicator to the time or frame number where you want to split the video layer.

3 Click the panel menu icon , and choose Split Layer.

The selected video layer is duplicated and appears immediately above the original in the Timeline panel. The original layer is trimmed from the start to the current time, and the duplicate layer is trimmed from the end to the current time.





Group layers in a video or animation

As you add more layers to your video or animation, you might want to organize them into a hierarchy by grouping the layers. Photoshop preserves the frames in your video or animation in grouped layers.

You can also group a group of layers. Besides nesting your layers in a more complex hierarchy, grouping a group of layers lets you simultaneously animate the opacity of all the grouped layers. The Animation panel displays a group of grouped layers with a common opacity layer property.

Grouping video layers in Photoshop is similar to precomposing in Adobe After Effects.

? In the Layers panel, select two or more layers and do one of the following:

- Choose Layer > Group Layers.
- Choose Layer > Smart Objects > Convert to Smart Object.

Rasterize video layers

When you rasterize video layers, the selected layer is flattened to a composite of the current frame selected in the Animation panel. Although it's possible to rasterize more than one video layer at a time, you'll only be able to specify the current frame for the topmost video layer.

1 In the Layers panel, select the video layer.

2 In the Timeline panel, move the current-time indicator to the frame that you want preserved when you rasterize the video layer.

3 Do either of the following:

- Choose Layer > Rasterize > Video.
- Choose Layer > Rasterize > Layer.

Note: *To rasterize more than one video layer at a time, select the layers in the Layers panel, set the current-time indicator to the frame you want to preserve in the topmost video layer, and then choose Layer > Rasterize > Layers.*

More Help topics

Transform objects

About Smart Objects

Importing video files and image sequences

Place a video or image sequence

Replace footage in a video layer

Audio doesn't play in video files encoded with Dolby Digital AC3

Issue

The audio doesn't play in video files that are encoded as Dolby Digital and Dolby AC3 in Adobe Photoshop.

Solutions

Solution 1: Install Adobe Premiere Pro.

While Photoshop does not have a license that allows Dolby encoded audio to play, Adobe Premiere Pro does. Photoshop can use this license when Adobe Premiere Pro is installed.

Solution 2: Re-encode your video files in an application that can open these files, so the audio is encoded with a different codec.

See these Photoshop Help topics for a list of the supported video formats:

- Video editing

- Supported file formats in Photoshop

Video and animation overview

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

About video layers

You can use Photoshop to edit individual frames of video and image sequence files. In addition to using any Photoshop tool to edit and paint on video, you can also apply filters, masks, transformations, layers styles, and blending modes. After making edits, you can save the document as a PSD file (that can be played back in other Adobe applications such as Premiere Pro and After Effects or accessed as a static file in other applications), or you can render it as a QuickTime movie or image sequence.

Note: *You can work only with the visual images in a video file, not the audio.*

When you open a video file or image sequence in Photoshop, the frames are contained within a video layer. In the Layers panel, a video layer is identified with a filmstrip icon . Video layers let you paint and clone on individual frames using the brush tools and stamp tools. Like working with regular layers, you can create selections or apply masks to restrict your edits to specific areas of a frame. You navigate through the frames using the timeline mode in the Animation panel (Window > Animation).

Note: *Video layers do not work when the Animation panel is in Frame mode.*

You work with video layers just like regular layers by adjusting the blending mode, opacity, position, and layer style. You can also group video layers in the Layers panel. Adjustment layers let you apply color and tonal adjustments non-destructively to the video layers.

If you prefer to make your frame edits on a separate layer, you can create a blank video layer. Blank video layers also let you create hand-drawn animations.

Note: *A video layer references the original file, so that edits to the video layer don't alter the original video or image sequence file. To maintain the link to the original file, ensure that it remains in the same location relative to the PSD file. For more information, see Replace footage in a video layer.*

Supported video and image sequence formats

You can open video files and image sequences in the following formats.

QuickTime video formats

- MPEG-1 (.mpg or .mpeg)
- MPEG-4 (.mp4 or .m4v)
- MOV
- AVI
- MPEG-2 is supported if an MPEG-2 encoder is installed on your computer.

Image sequence formats

- BMP

- DICOM
- JPEG
- OpenEXR
- PNG
- PSD
- Targa
- TIFF
- Cineon and JPEG 2000 are supported if the plug-ins are installed.

Color mode and bit depth

Video layers can contain files in the following color modes and bits per channel (bpc):

- Grayscale: 8, 16, or 32 bpc
- RGB: 8, 16, or 32 bpc
- CMYK: 8 or 16 bpc
- Lab: 8 or 16 bpc

Animation panel overview

An animation is a sequence of images, or frames, that is displayed over time. Each frame varies slightly from the preceding frame, creating the illusion of movement or other changes when the frames are viewed in quick succession.

In the standard edition of earlier versions of Photoshop, the Animation panel (Window > Animation) appears in frame mode, showing a thumbnail of each frame in your animation. Use the tools at the bottom of the panel to navigate through the frames, set looping options, add and delete frames, and preview the animation.

The Animation panel menu contains additional commands for editing frames or timeline durations, and for configuring the panel display. Click the panel menu icon to view available commands.



A Selects the first frame B Selects the previous frame C Plays animation D Selects the next frame E Tweens animation frames F Duplicates selected frames G Deletes selected frames H Converts to timeline mode I Animation panel menu

You can use the Animation panel in either frame mode or timeline mode. Timeline mode shows the frame duration and animation properties for document layers. Use the tools at the bottom of the panel to navigate through frames, zoom the time display in or out, toggle onion skin mode, delete keyframes, and preview the video. You can use controls on the timeline itself to adjust frame duration for a layer, set keyframes for layer properties, and designate a section of the video as the working area.



A Enable audio playback ***B*** *Zoom out* ***C*** *Zoom slider* ***D*** *Zoom in* ***E*** *Toggle onion skins* ***F*** *Delete keyframes* ***G*** *Convert to frame animation*

In timeline mode, the Animation panel displays each layer in a Photoshop document (except the background layer) and is synchronized with the Layers panel. Whenever a layer is added, deleted, renamed, grouped, duplicated, or assigned a color, the changes are updated in both panels.

Note: *When animated layers are grouped as a Smart Object, the animation information from the Animation panel is stored in the Smart Object. See also Work with Smart Objects.*

Frame mode controls

In frame mode, the Animation panel includes the following controls:

Looping Options Sets the number of times an animation plays when exported as an animated GIF file.

Frame Delay Time Sets the duration of a frame during playback.

Tween Animation Frames

Adds a series of frames between two existing frames, *interpolating* (varying) the layer properties evenly between the new frames.

Duplicate Selected Frames

Adds a frame to the animation by duplicating the selected frame in the Animation panel.

Convert To Timeline Animation

Converts a frame animation to timeline animation using keyframes to animate layer properties.

Timeline mode controls

In timeline mode, the Animation panel includes the following features and controls:

Cached frames indicator Displays a green bar to indicate the frames that are cached for playback.

Comments track Choose Edit Timeline Comment from the panel menu to insert a text comment at the current time. Comments appear as icons in the comments track. Move the pointer over these icons to display comments as tool tips. Double-click these icons to revise comments. To navigate from one comment to the next, click the Go To Previous or Go To Next buttons at the far left of the Comments track.

To create an HTML table listing the time, frame number, and text of each comment, choose Export Timeline Comments from the panel menu.

Convert To Frame Animation Converts a timeline animation using keyframes to frame animation.

Timecode Or frame number display Shows the timecode or frame number (depending on panel options) for the current frame.

Current-time indicator

Drag the current-time indicator to navigate frames or change the current time or frame.

Global Lighting track Displays keyframes where you set and change the master lighting angle for layer effects such as Drop Shadow, Inner Shadow, and Bevel and Emboss.

Keyframe navigator

Arrow buttons to the left of a track label move the current-time indicator to the previous or next keyframe from its current position. Click the center button to add or delete a keyframe at the current time.

Layer duration bar Specifies a layer's place in time within a video or animation. To move the layer to another place in time, drag the bar. To trim (adjust the duration of) a layer, drag either end of the bar.

Altered Video track For video layers, displays a duration bar for altered frames. To jump to altered frames, use the keyframe navigator to the left of the track label.

Time ruler Measures duration (or frame count) horizontally, according to the document's duration and frame rate. (Choose Document Settings from the panel menu to change duration or frame rate.) Tick marks and numbers appear along the ruler and change in spacing with the zoom setting of the timeline.

Time-Vary stopwatch

Enables or disables keyframing for a layer property. Select this option to insert a keyframe and enable keyframing for a layer property. Deselect to remove all keyframes and disable keyframing for a layer property.

Animation panel menu Includes functions affecting keyframes, layers, panel appearance, onion skinning, and document settings.

Work area indicators Drag the blue tab at either end of the topmost track to mark the specific portion of the animation or video that you want to preview or export.

Change thumbnail size

In the Animation panel, you can change the size of the thumbnails that represent each frame or layer.

1 Choose Panel Options from the Animation panel menu.

2 Do one of the following:

- Select a size option.
- In timeline mode, select None to display only layer names.

Switch timeline units

You can display the Animation panel timeline in either frame number or timecode units.

- To select units to display, choose Panel Options from the Animation panel menu and select Frame Numbers or Timecode.
- To toggle between units, Alt-click (Windows) or Option-click (Mac OS) the current-time display in the upper-left corner of the timeline.

Show or hide layer properties in the timeline

As you add layers to a document, they appear as tracks in the timeline. Expand layer tracks to show layer properties that can be animated.

? To show or hide layer properties, click the triangle to the left of the layer name.

Show or hide layers in the timeline

All document layers appear in the timeline by default. To show only a subset of layers, first set them as favorites.

1 In timeline mode, select one or more layers from the Animation panel, then choose Show > Set Favorite Layers in the Animation panel menu.

2 To specify which layers are displayed, choose Show from the Animation panel menu, then select All Layers or Favorite Layers.

Navigate the timeline

? With the Animation panel in timeline mode, do any of the following:

- Drag the current-time indicator .
- Click a number or location in the time ruler where you want to position the current-time indicator.
- Drag the current-time display (in the upper-left corner of the timeline).
- Double-click the current-time display and enter a frame number or time in the Set Current Time dialog box.
- Use the playback controls in the Animation panel.
- Choose Go To in the Animation panel menu, and then choose a timeline option.

Switch animation modes

You can use the Animation panel in either frame or timeline animation mode. Frame mode shows each separate frame, letting you set unique duration and layer properties for each. Timeline mode shows frames in a continuous timeline, letting you animate properties with keyframes and play video layers.

Ideally, you should select the mode you want before starting an animation. However, it's possible to switch animation modes in an open document, converting a frame animation to a timeline animation, or vice versa.

Note: *You may lose some interpolated keyframes when converting a timeline animation to a frame animation. The animation appearance doesn't change, however.*

? In the Animation panel, do any of the following:

- Click the Convert To Frame Animation icon .
- Click the Convert To Timeline Animation icon .
- From the Animation panel menu, choose either Convert To Frame Animation or Convert To Timeline.

Specify timeline duration and frame rate

When you are working in timeline mode, you can specify the duration and frame rate of a document containing video or animation. *Duration* is the overall time length of the video clip, from the first frame you specify to the last. *Frame rate* or frames per second (fps), is usually determined by the type of output you produce: NTSC video has a frame rate of 29.97 fps; PAL video has a frame rate of 25 fps; and motion picture film has a frame rate of 24 fps. Depending on the broadcast system, DVD video can have the same frame rate as NTSC video or PAL video, or a frame rate of 23.976. Video intended for CD-ROM or the web typically has a frame rate of 10 to 15 fps.

When you create a new document, the default timeline duration is 10 seconds. The frame rate depends on the chosen document preset. For non-video presets (like International Paper), the default rate is 30 fps. For video presets, the rate is 25 fps for PAL and 29.97 for NTSC.

1 From the Animation panel menu, choose Document Settings.

2 Enter or choose values for Duration and Frame Rate.

Note: Reducing the duration of an existing video or animation has the effect of trimming frames (and any keyframes) from the end of the document.

More Help topics

Creating images for video

Load video actions

Adjustment and fill layers

Set the timeline area to preview

Preview video and animations

Note: For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.

Preview a frame animation

1 Do one of the following:

- Click the Play button ▶ in the Timeline panel.
- Use the spacebar to play and pause the animation.

The animation is displayed in the document window. The animation repeats indefinitely unless you specified another repeat value in the Play Options dialog box.

2 To stop the animation, click the Stop button ■.

3 To rewind the animation, click the Selects First Frame button ◀◀.

Note: To see a more accurate preview of the animation and timing, preview the animation in a web browser. In Photoshop, open the Save For Web dialog box and click the Preview In Browser button. Use the browser's Stop and Reload commands to stop or replay the animation.

Set the timeline area to preview

1 To set the timeline duration you want to export or preview, do any of the following in the Timeline panel:

- Drag either end of work area bar.



- Drag the work area bar over the section you want to preview.
- Move the current-time indicator to the time or frame you want. From the panel menu, choose either Work Area > Set Start At Playhead or Work Area > Set End At Playhead.

2 To remove the portions of the timeline not in the work area, choose Trim Document Duration To Work Area from the panel menu.

Previewing video or timeline animations

Your video or animation can be previewed in the document window. Photoshop uses RAM to preview the video or animation during your editing session. When you play or drag to preview frames, they are automatically cached for faster playback the next time they're played. The cached frames are indicated by the green bar in the work area of the Timeline panel. The number of frames cached depends on the amount of RAM available to Photoshop.

Preview a video or timeline animation

? Do any of the following:

- In the timeline, drag the current-time indicator.
- Use the playback buttons at the bottom of the Animation panel Timeline panel.
- Press the spacebar to play or stop playback. For additional shortcuts, see .

To see a more accurate preview of an animation created for the web, preview the animation in a web browser. Use the browser's Stop and Reload commands to stop or replay the animation. Open the Save For Web dialog box, and click the Preview In Browser button.

Preview audio for video layers

When you enable audio previews for video layers, Photoshop includes the audio in files exported to QuickTime Movie format. (See Export video files or image sequences.)

In the Timeline panel, do either of the following:

- To enable or disable audio previews for a specific video layer, click the speaker icon for that layer.
- To enable or disable audio previews for an entire document, click the speaker icon to the right of the playback buttons at the bottom of the panel.

Enable frame skipping

Photoshop can skip uncached frames to achieve real-time playback.

? With Timeline panel in timeline animation mode, choose Allow Frame Skipping from the panel menu.

Preview your document on a video monitor

The Video Preview plug-in lets you preview the current frame specified in the animation timeline (or any image open in Photoshop) through FireWire (IEEE 1394) on a display device, such as a video monitor. You can also adjust the aspect ratio for proper display of images.

Note: *On 64-bit operating systems, you must use the 32-bit version of Photoshop to access the Video Preview plug-in.*

The Video Preview plug-in supports RGB, grayscale, and indexed images. (The plug-in converts 16-bpc images to 8-bpc images.) The Video Preview plug-in does not support alpha channels. Transparency is displayed as black.

Note: *The Video Preview plug-in does not lock the display device. When Photoshop is in the background on your computer and another application moves into the foreground, the preview turns off and the device is unlocked so other applications can use it for preview purposes.*

1 Connect a display device, such as a video monitor, to your computer via FireWire (IEEE 1394).

2 With a document open in Photoshop, do one of the following:

- If you don't want to set output options for viewing your document on a device, choose File > Export > Send Video Preview To Device. You can skip the rest of the steps in this procedure.
- To set output options before viewing your document on the device, choose File > Export > Video Preview.

The Video Preview dialog box opens. If your document's pixel aspect ratio doesn't match the aspect ratio settings of the display device, you will see an alert.

Note: *The Send Video Preview To Device command uses the previous settings in the Video Preview dialog box.*

3 Under Device Settings, specify options for the device that will display the image:

- (Mac OS) To specify an output mode, select NTSC or PAL. If the output mode and the device do not match (for example, specifying NTSC for the output mode and connecting to a device in PAL mode), black patches appear on previewing.
- To specify the aspect ratio of the display device, choose either Standard (4:3) or Widescreen (16:9) from the Aspect Ratio menu.

Note: *The Aspect Ratio setting determines which placement options are available.*

4 Under Image Options, choose a placement option to determine how the image appears in the display device:

Center Places the center of the image at the center of the screen, cropping the portions that fall outside the display edges of the video preview device.

Pillarbox Displays a 4:3 image on a 16:9 display with the center of the image at the center of the screen and gray bands on the left and right sides of the image. This option is available only if you chose Widescreen (16:9) for the device aspect ratio.

Crop to 4:3 Displays a 16:9 image on a 4:3 display with the center of the image at the center of the screen and without distortion by cropping the left and right edges of the frame that fall outside the display edges of the video preview device. This option is available only if you chose Standard (4:3) for the device aspect ratio.

Letterbox Scales a 16:9 image to fit on a 4:3 display. Gray bands appear on the top and bottom of the image due the difference in aspect ratio between the 16:9 image and the 4:3 display. This maintains the display aspect ratio without cropping or distorting the image. This option is available only if you chose Standard (4:3) for the device aspect ratio.

Crop To 14:9/Letterbox Displays a widescreen image cropped to a 14:9 aspect ratio with black bands on either the top and bottom of the image (when viewed on a 4:3 display) or on the left and right sides (when viewed on a 16:9 display). This maintains the display aspect ratio without distorting the image.

5 Choose an option from the Image Size menu to control whether the document pixels are scaled to the device display:

Do Not Scale Applies no vertical scaling to the image. The image is cropped if its height is greater than that of the video display.

Scale To Fit Within Frame Increases or decreases the image height and width proportionally to fit in the video frame. With this option, a 16:9 image appears on a 4:3 display as letterbox, and a 4:3 image appears on a 16:9 display as pillarbox.

6 Select the Apply Pixel Aspect Ratio To Preview check box to display the image using the document's (nonsquare) pixel aspect ratio. Deselect this option to display the image as it appears on your computer (square pixel) monitor.

By default, the Apply Pixel Aspect Ratio To Preview check box is selected to maintain the image's pixel aspect ratio. In general, you would deselect this option if the document's pixel aspect ratio is assumed to be square and you want to view the image as it would appear on a computer (square pixel) monitor.

7 Click OK to export the document to the device display.

More Help topics

Preview optimized images in a web browser

Specify timeline duration and frame rate

Paint frames in video layers

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Paint frames in video layers

You can edit or paint on individual video frames to create an animation, add content, or to remove unwanted details. In addition to using any brush tool, you can paint using the Clone Stamp, Pattern Stamp, Healing Brush, or Spot Healing Brush. You can also edit video frames using the Patch tool.

Note: *Painting (or using any other tool) on video frames is often called rotoscoping; although traditionally, rotoscoping involves the frame-by-frame tracing of live action images for use in animation.*

1. In the Timeline or Layers panel, select the video layer.
2. Move the current time indicator to the video frame you want to edit.
3. (Optional) If you want your edits to be on a separate layer, choose Layers > Video Layers > New Blank Video Layer.
4. Select the brush tool that you want to use and apply your edits to the frame.

   Painting on a video layer is nondestructive. To discard the altered pixels on a specific frame or video layer, choose the Restore Frame or Restore All Frames command. To toggle on and off the visibility of altered video layers, choose the Hide Altered Video command (or click the eyeball next to the altered video track in the timeline).

Cloning content in video and animation frames

In Photoshop you can use the Clone Stamp and Healing Brush tools to retouch or duplicate objects in video or animation frames. Use the Clone Stamp to sample content from one part of a frame (the source) and paint it over another part of the same or different frame (the target). You can also use a separate document as the sampling source, instead of a frame. The Healing Brush includes options for blending the sampled content with the target frame.

Note: *You can also clone content with the Spot Healing Brush and the Patch tools. However, the Clone Stamp and the Healing Brush tools let you store up to five samples in the Clone Source panel, and set overlay, scaling, and frame offset options.*

After you sample content from a frame and paint with it, and then move to another frame, the source frame changes relative to the frame you initially sampled from. You can lock in the source frame you first sampled, or enter a frame offset value to change the source to a different frame, relative to the frame you first sampled.

Clone video or animation content

1. Select the Clone Stamp tool or Healing Brush tool , and then set the tool options you want.
2. Do one of the following:
   - Select a video layer in the Layers panel or Timeline panel, and then move the current-time indicator to the frame you want to sample.

- Open the image you want to sample.

3 Position the pointer in an open image or frame, and Alt-click (Windows) or Option-click (Mac OS) to set the sampling point.

4 To set additional sampling points, click each clone source button in the Clone Source panel.

5 Select the target video layer and move the current-time indicator to the frame you want to paint.

If you want to paint on a separate layer, you can add a blank video layer. Make sure you choose the appropriate Sample option to clone content onto the blank video layer.

6 If you have set multiple sampling points, select the source you want to use in the Clone Source panel.

7 Do any of the following in the Clone Source panel:

- To scale or rotate the source that you're cloning, enter a value for W (width) or H (height), or the rotation in degrees .
- To show an overlay of the source that you're cloning, select Show Overlay and specify the overlay options. (The Clipped option restricts the overlay to the brush size. Deselect this option to overlay the entire source image).

To move the source overlay to an offset position, Shift + Alt-drag (Windows) or Shift + Option-drag (Mac OS). To temporarily show overlays, deselect Show Overlay, and press Shift + Alt (Windows) or Shift + Option (Mac OS).

8 Drag over the area of the frame you want to paint.

Painting on a video layer is nondestructive. You can choose the Restore Frame or Restore All Frames command to discard the altered pixels on a specific frame or video layer.

Change frame offset for cloning or healing

? In the Clone Source panel:

- To always paint using the same frame you initially sampled from, select Lock Frame.
- To paint using a frame relative to the frame you initially sampled from, enter the number of frames in the Frame Offset box. If the frame you want to use is after the frame you initially sampled, enter a positive value. If the frame you want to use is before the frame you initially sampled, enter a negative value.

Restore frames in video layers

You can discard edits made to frame video layers and blank video layers.

? In the Timeline panel, select a video layer and do one of the following:

- To restore a specific frame, move the current-time indicator to the video frame and choose Layer > Video Layers > Restore Frame.
- To restore all the frames in a video layer or blank video layer, choose Layer > Video Layers > Restore All Frames.

Managing color in video layers

In Photoshop you can paint on video layers using tools such as a brush tool or the Clone Stamp tool. If no color profile is assigned to the video layer, these pixel edits are stored using the document file's color space, and the video footage itself is left unchanged. If the color space of the imported footage is different from the color space of your Photoshop document, you may need to make adjustments. For example, a standard definition video movie may be in SDTV 601 NTSC, while the Photoshop document is in Adobe RGB. Your final exported video or document might not have the colors you expect due to the color space mismatch.

Before investing a lot of time painting or editing video layers, test your complete workflow to understand your color management needs and find the approach that works best for your workflow.

Often, you can solve a mismatch by assigning a color profile to the document that corresponds to the imported footage, and leaving the video layer unmanaged. For example, with standard definition video, you can leave the video layer unmanaged and assign the document the SDTV (Rec. 601 NTSC) color profile. In this case, the imported frame pixels are stored directly in the video layer without color conversion.

Conversely, you can assign the document's color profile to the video layer using the Convert Edited Frame Content option (Layers > Video Layers > Interpret Footage). This option converts the pixel edits to the document's color space, but does not convert the colors of the video frames.

The Convert To Profile command (Edit > Convert To Profile) also converts all pixel edits to the document's color space. However, using the Assign Profile command (Edit > Assign Profile) does not convert the pixel edits to a video layer. Use the Assign Profile command with care, especially when you've painted on or edited video frames. If the video layer has a color profile, applying the Assign Profile command to the document may cause a color space mismatch between the pixel edits and the imported frames.

Some combinations of video footage and document color spaces require color conversion:

- A grayscale movie in an RGB, CMYK, or Lab mode document requires color conversion.
- Using 8- or 16-bpc footage in a 32-bpc document requires color conversion.

More Help topics

Paint with the Brush tool or Pencil tool

Retouching and repairing images

Create hand-drawn animations

Retouch with the Clone Stamp tool

Retouch with the Healing Brush tool

Set sample sources for cloning and healing

Create new video layers

Understanding color management

Assign or remove a color profile

Convert document colors to another profile

Create timeline animations

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Timeline animation workflow

To animate layer content in timeline mode, you set keyframes in the Timeline panel, as you move the current-time indicator to a different time/frame, and then modify the position, opacity, or style of the layer content. Photoshop automatically adds or modifies a series of frames between two existing frames—varying the layer properties (position, opacity, and styles) evenly between the new frames to create the appearance of movement or transformation.

For example, if you want to fade out a layer, set the opacity of the layer in the starting frame to 100% and click the Opacity stopwatch for the layer. Then move the current-time indicator to the time/frame for the ending frame and set the opacity for the same layer to 0%. Photoshop automatically interpolates frames between the start and end frames, and the opacity of the layer is reduced evenly across the new frames.

In addition to letting Photoshop interpolate frames in an animation, you can also create a hand-drawn frame-by-frame animation by painting on a blank video layer.

If you want to create a SWF format animation, use Adobe Flash, Adobe After Effects, or Adobe Illustrator.

To create a timeline-based animation, use the following general workflow.

1. Create a new document.

Specify the size and background contents. Make sure the pixel aspect ratio and dimensions are appropriate for the output of your animation. The color mode should be RGB. Unless you have special reasons for making changes, leave the resolution at 72 pixels/inch, the bit depth at 8 bpc, and the pixel aspect ratio at square.

Make sure the Timeline panel is open. If necessary, click the downpointing arrow in the middle of the panel, choose Create Video Timeline from the menu, and then, click the button to the left of the arrow. If the Timeline panel is in frame animation mode, click the Convert To Video Timeline icon in the lower-left corner of the panel.

2. Specify the Set Timeline Frame Rate in the panel menu.

Specify the duration and frame rate. See Specify timeline duration and frame rate.

3. Add a layer.

Background layers cannot be animated. If you want to animate content, either convert the background layer to a normal layer or add any of the following:

- A new layer for adding content.
- A new video layer for adding video content.
- A new blank video layer for cloning content to or creating hand-drawn animations.

4. Add content to the layer.

5. (Optional) Add a layer mask.

A layer mask can be used to reveal a portion of the layer's content. You can animate the layer mask to reveal different portions of the layer's content over time. See Add layer masks.

6. Move the current time indicator to the time or frame where you want to set the first keyframe.

See Use keyframes to animate layer properties.

7. Turn on keyframing for a layer property.

Click the triangle next to the layer name. A down-pointing triangle displays the layer's properties. Then, click the stopwatch to set the first keyframe for the layer property you want to animate. You can set keyframes for more than one layer property at a time.

8. Move the current time indicator and change a layer property.

Move the current-time indicator to the time or frame where the layer's property changes. You can do one or more of the following:

- Change the position of the layer to make layer content move.
- Change layer opacity to make content fade in or out.
- Change the position of a layer mask to reveal different parts of the layer.
- Turn a layer mask on or off.

For some types of animation, such as changing the color of an object, or completely changing the content in a frame, you need additional layers with the new content.

Note: *To animate shapes, you animate the vector mask rather than the shape layer, using the Time-Vary stopwatch for Vector Mask Position or Vector Mask Enable.*

9. Add additional layers with content and edit their layer properties as needed.

10. Move or trim the layer duration bar to specify when a layer appears in an animation.

See Specify when a layer appears in a video or animation and Set the timeline area to preview.

11. Preview the animation.

Use the controls in the Timeline panel to play the animation as you create it. Then preview the animation in your web browser. You can also preview the animation in the Save For Web dialog box. See Previewing video or timeline animations.

12. Save the animation.

You can save the animation as an animated GIF using the Save for Web command, or as an image sequence or video using the Render Video command. You can also save it in PSD format, which can be imported into Adobe After Effects.

Use keyframes to animate layer properties

You can animate different layer properties, such as Position, Opacity, and Style. Each change can occur independently of, or simultaneously with, other changes. If you want to animate different objects independently, it's best to create them on separate layers.

For a video on animating layer properties, see Use keyframes with transform properties .

Here are some examples of how you can animate layer properties:

- You can animate position by adding a keyframe to the Position property, then moving the current time indicator and dragging the layer in the document window.
- You can animate a layer's opacity by adding a keyframe to the Opacity property, then moving the current time indicator and changing the layer's opacity in the Layers panel.
- You can animate 3D properties, such as object and camera position. (For more information, see Create 3D animations .)

To animate a property using keyframes, you must set at least two keyframes for that property. Otherwise, changes that you make to the layer property remain in effect for the duration of the layer.

Each layer property has a Time-Vary stopwatch icon that you click to begin animating. When the stopwatch is active for a specific property, Photoshop automatically sets new keyframes whenever you change the current time and the property value. When the stopwatch is inactive for a property, the property has no keyframes. If you type a value for a layer property while the stopwatch is inactive, the value remains in effect for the duration of the layer. If you deselect the stopwatch, you will permanently delete all of the keyframes for that property.

Choose interpolation method

Interpolation (sometimes called tweening) describes the process of filling in unknown values between two known values. In digital video and film, interpolation usually means generating new values between two keyframes. For example, to move a graphic element 50 pixels to the left in 15 frames, you'd set the position of the graphic in the first and 15th frames, and mark them both as keyframes. Photoshop interpolates the frames between the two keyframes. Interpolation between keyframes can be used to animate movement, opacity, styles, and global lighting.

In the Timeline panel, the appearance of a keyframe depends on the interpolation method you choose for the interval between keyframes.

Linear keyframe

Evenly changes the animated property from one keyframe to another. (The one exception is the Layer Mask Position property which switches between enabled and disabled states abruptly.)

Hold keyframe

Maintains the current property setting. This interpolation method is useful for strobe effects, or when you want layers to appear or disappear suddenly.

To choose the interpolation method for a keyframe, do the following:

1 In the Timeline panel, select one or more keyframes.

2 Do one of the following:

- Right-click a selected keyframe and choose either Linear Interpolation or Hold Interpolation from the Context menu.
- Open the panel menu and choose either Keyframe Interpolation > Linear or Keyframe Interpolation > Hold.

Move the current-time indicator to a keyframe

After you set the initial keyframe for a property, Photoshop displays the keyframe navigator, which you can use to move from keyframe to keyframe or to set or remove keyframes. When the keyframe navigator diamond is active (yellow), the current-time indicator lies precisely at a keyframe for that layer property. When the keyframe navigator diamond is inactive (gray), the current-time indicator lies between keyframes. When arrows appear on each side of the keyframe navigator box, other keyframes for that property exist on both sides of the current time.

? In the Timeline panel, click a keyframe navigator arrow. The arrow to the left moves the current-time indicator to the previous keyframe. The arrow to the right moves the current-time indicator to the next keyframe.

Select keyframes

? In the Timeline panel, do any of the following:

- To select a keyframe, click the keyframe icon.
- To select multiple keyframes, Shift-click the keyframes or drag a selection marquee around the keyframes.
- To select all keyframes for a layer property, click the layer property name next to the stopwatch icon.

Move keyframes

1 In the Timeline panel, select one or more keyframes.

2 Drag any of the selected keyframe icons to the desired time. (If you selected multiple keyframes, they move as a group and maintain the same time spacing.)

To expand or compress the spacing of multiple keyframes, Alt-drag (Windows) or Option-drag (Mac OS) the first or last keyframe in the selection. The keyframe at the opposite end of the selection remains in place as you drag, slowing down or speeding up the animation.

Copy and paste keyframes

You can copy keyframes for a property (such as Position) to the same property in any layer. When you paste keyframes, they reflect the copied offset from the current-time indicator.

You can copy keyframes from only one layer at a time. When you paste keyframes into another layer, they appear in the corresponding property in the destination layer. The earliest keyframe appears at the current time, and the other keyframes follow in relative order. The keyframes remain selected after pasting, so you can immediately move them in the timeline.

Note: *You can copy and paste keyframes between more than one property at a time.*

1 In the Timeline panel, display the layer property containing the keyframes you want to copy.

2 Select one or more keyframes.

3 Right-click a selected keyframe, and choose Copy Keyframes.

4 In the Timeline panel containing the destination layer, move the current-time indicator to the point in time where you want the keyframes to appear.

5 Select the destination layer.

6 Open the panel menu and choose Paste Keyframes.

Delete keyframes

? In the Timeline panel, select one or more keyframes and do one of the following:

- Right-click (Windows) or Control-click (Mac OS) a selected keyframe, and choose Delete Keyframes from the context menu.
- From the panel menu, choose Delete Keyframes.

Create hand-drawn animations

You can add a blank video layer to your document when you want to create frame-by-frame hand-drawn animations. Adding a blank video layer above a video layer and then adjusting the opacity of the blank video layer allows you to see the contents of the video layer below. You can then rotoscope the video layer content by painting or drawing on the blank video layer. See also Paint frames in video layers.

Note: *If you're animating several independent elements, create separate content on different blank video layers.*

1 Create a new document.

2 Add a blank video layer.

3 Paint or add content to the layer.

4 (Optional) In the Timeline panel, choose Enable Onion Skins from the panel menu to enable the onion skin mode.

5 Move the current-time indicator to the next frame.

6 Paint or add content to the layer in a slightly different position from the content in the previous frame.

You can add a blank video frame, duplicate a frame, or delete a frame from the blank video layer by choosing Layer > Video Layers and then choosing the appropriate command.

As you create more hand-drawn frames, you can either drag the current time indicator or use the playback controls to preview your animation.

Insert, delete, or duplicate blank video frames

A blank video frame can be added to or removed from a blank video layer. You can also duplicate existing (painted) frames in blank video layers.

1 In the Timeline panel, select the blank video layer and then move the current-time indicator to the desired frame.

2 Choose Layer > Video Layers and then choose one of the following:

Insert Blank Frame Inserts a blank video frame in the selected blank video layer at the current time.

Delete Frame Deletes the video frame in the selected blank video layer at the current time.

Duplicate Frame Adds a copy of the video frame at the current time in the selected blank video layer.

Specify onion skin settings

Onion skin mode displays content drawn on the current frame plus content drawn on the surrounding frames. These additional frames appear at the opacity you specify to distinguish them from the current frame. Onion skin mode is useful for drawing frame-by-frame animations because it gives you reference points for stroke positions and other edits.

Onion skin settings specify how previous and later frames appear when onion skins are enabled. (See Animation panel overview.)

1 Open the Timeline panel and choose Onion Skin Settings.

2 Specify options for the following:

Onion Skin Count Specifies how many previous and forward frames are displayed. Enter the Frames Before (previous frames) and Frames After (forward frames) values in the text boxes.

Frame Spacing Specifies the number of frames between the displayed frames. For example, a value of 1 displays consecutive frames, and a value of 2 displays strokes that are two frames apart.

Max Opacity Sets the percentage of opacity for the frames immediately before and after the current time.

Min Opacity Sets the percentage of opacity for the last frames of the before and after sets of onion-skin frames.

Blend Mode Sets the appearance of the areas where the frames overlap.



A Current frame with one frame after ***B*** *Current frame with both one frame before and after* ***C*** *Current frame with one frame before*

Open a multilayer animation

You can open animations that were saved in older versions of Photoshop as multilayer Photoshop (PSD) files. The layers are placed in the Timeline panel in their stacking order, with the bottom layer becoming the first frame.

1 Choose File > Open, and select the Photoshop file to open.

2 In the Layers panel, select the layers you want for the animation, and choose Make Frames From Layers from the panel menu.

   You can edit the animation, use the Save For Web command to save an animated GIF, or use the Render Video command to save the animation as a QuickTime movie.

More Help topics

Switch animation modes

Blending mode descriptions

Create images for video

About creating images for video

Photoshop can create images of various aspect ratios so that they appear properly on devices such as video monitors. You can select a specific video option (using the New dialog box) to compensate for scaling when the final image is incorporated into video.

Safe zones

The Film & Video preset also creates a document with nonprinting guides that delineate the action-safe and title-safe areas of the image. Using the options in the Size menu, you can produce images for specific video systems—NTSC, PAL, or HDTV.

Safe zones are useful when you edit for broadcast and videotape. Most consumer TV sets use a process called overscan, which cuts off a portion of the outer edges of the picture, allowing the center of the picture to be enlarged. The amount of overscan is not consistent across TVs. To ensure that everything fits within the area that most TVs display, keep text within the title-safe margins, and all other important elements within the action-safe margins.



A *Action safe area (outer rectangle)* ***B*** *Title safe area (inner rectangle)*

Note: *If you are creating content for the web or for CD, the title-safe and action-safe margins do not apply to your project because the entire image is displayed in these media.*

Preview options

To help you create images for video, Photoshop has a Pixel Aspect Ratio Correction viewing mode that displays images at the specified aspect ratio. For more accurate previews, Photoshop also has a Video Preview command that lets you immediately preview your work on a display device, such as a video monitor. To use this feature, you must have the device connected to your computer via FireWire (IEEE 1394). See also Preview your document on a video monitor. For more information on FireWire (IEEE 1394), see Apple's website.

Other considerations

Both Adobe AfterEffects and Adobe Premiere Pro support PSD files created in Photoshop. However, if you're using other film and video applications, you might consider these details when you create images for use in video:

- Some video-editing programs can import individual layers from a multilayer PSD file.
- If the file has transparency, some video-editing programs preserve it.
- If the file uses a layer mask or multiple layers, you might not have to flatten the layers, but you might want to include a flattened copy of the file in PSD format to maximize backward compatibility.

Aspect ratio

Frame aspect ratio describes the ratio of width to height in the dimensions of an image. For example, DV NTSC has a frame aspect ratio of 4:3 (or 4 width by 3 height) and a typical widescreen frame has a frame aspect ratio of 16:9. Some video cameras can record various frame aspect ratios. Many cameras that have a widescreen mode use the 16:9 aspect ratio. Many professional films have been shot using even wider aspect ratios.



Pixel aspect ratio describes the ratio of width to height of a single pixel in a frame. Different video standards use different pixel aspect ratios. For example, many computer video standards define a 4:3 aspect ratio frame as 640 pixels wide by 480 pixels high, which results in square pixels. The computer video pixels in this example have a pixel aspect ratio of 1:1 (square), whereas the DV NTSC pixels have a pixel aspect ratio of 0.91 (nonsquare). DV pixels, which are always rectangular, are vertically oriented in systems producing NTSC video and horizontally oriented in systems producing PAL video.

If you display rectangular pixels on a square-pixel monitor without alteration, images appear distorted; for example, circles distort into ovals. However, when displayed on a broadcast monitor, the images appear correctly proportioned because broadcast monitors use rectangular pixels.

Note: *When copying or importing images into a nonsquare pixel document, Photoshop automatically converts and scales the image to the pixel aspect ratio of the document. Images imported from Adobe Illustrator are also properly scaled.*



A *4:3 square-pixel image displayed on 4:3 square-pixel (computer) monitor* ***B*** *4:3 square-pixel image interpreted correctly for display on 4:3 non-square pixel (TV) monitor* ***C*** *4:3 square-pixel image interpreted incorrectly for display on 4:3 non-square pixel (TV) monitor*

Create an image for use in video

1 Create a new document.

2 From the Preset menu in the New dialog box, choose the Film & Video preset.

3 Choose the size that's appropriate for the video system on which the image will be shown.

4 Click Advanced to specify a color profile and specific pixel aspect ratio.

Note: *By default, nonsquare pixel documents open with Pixel Aspect Ratio Correction enabled. This setting scales the image so it appears as it would on the nonsquare-pixel output device (usually a video monitor).*

5 To view the image as it would appear on a computer monitor (square pixel), choose View > Pixel Aspect Ratio Correction.



You can simultaneously view an image with the Pixel Aspect Ratio Correction turned on and off. With the nonsquare pixel image open and Pixel Aspect Ratio Correction enabled, choose Window > Arrange > New Window For [name of document]. With the new window active, choose View > Pixel Aspect Ratio Correction to turn off the correction.

6 If you have a display device, such as a video monitor, connected to your computer via FireWire, you can preview the document on the device:

- To set output options before previewing the image, choose File > Export > Video Preview.
- To view the image without setting output options, choose File > Export > Send Video Preview To Device.

When creating images for video, you can load a set of video actions (included with Photoshop) that automate certain tasks—such as scaling images to fit video pixel dimensions and setting the pixel aspect ratio.

Load video actions

For video images, actions automate tasks such as constraining the luminance range and saturation levels to comply with broadcast standards, resizing and converting to nonsquare pixels for use in DVD slide shows (NTSC and PAL, standard and widescreen aspect ratios), creating an alpha channel from all currently visible layers, adjusting image areas (especially thin lines) that are likely to cause interlace flicker, and generating a title-safe overlay.

1 Choose Window > Actions to display the Actions panel.

2 Click the triangle in the upper right corner of the panel, and choose Video Actions from the menu.

Adjust pixel aspect ratio

You can create a custom pixel aspect ratio in existing documents, or delete or reset pixel aspect ratios previously assigned to a document.

Assign a pixel aspect ratio value to an existing document

? With a document open, choose View > Pixel Aspect Ratio and then choose a pixel aspect ratio that's compatible with the video format that you'll be using your Photoshop file with.

Create a custom pixel aspect ratio

1 With a document open, choose View > Pixel Aspect Ratio > Custom Pixel Aspect Ratio.

2 In the Save Pixel Aspect Ratio dialog box, enter a value in the Factor text box, name the custom pixel aspect ratio, and click OK.

The new custom pixel aspect ratio appears in both the Pixel Aspect Ratio menu of the New dialog box and in the View > Pixel Aspect Ratio menu.

Delete a pixel aspect ratio

1 With the document open, choose View > Pixel Aspect Ratio > Delete Pixel Aspect Ratio.

2 In the Delete Pixel Aspect Ratio dialog box, choose the item to delete from the Pixel Aspect Ratio menu, and click Delete.

Reset the pixel aspect ratios

1 With the document open, choose View > Pixel Aspect Ratio > Reset Pixel Aspect Ratios.

2 In the dialog box, choose one of the following:

Append Replaces the current pixel aspect ratios with the default values plus any custom pixel aspect ratios. This option is useful if you deleted a default value and want to restore it to the menu but also want to retain any custom values.

OK Replaces the current pixel aspect ratios with the default values. Custom pixel aspect ratios are discarded.

Cancel Cancels the command.

Prepare images for use in After Effects

You can import a Photoshop (PSD) file directly into an After Effects project with the option of preserving individual layers, layer styles, transparent areas and layer masks, and adjustment layers (preserving the individual elements for animation).

Note: For best results, work in RGB mode, which After Effects uses. After Effects CS3 and later can convert files from CMYK to RGB. After Effects 7 and earlier cannot.

Before you export a layered Photoshop file for use in After Effects, do the following to reduce preview and rendering time and to avoid problems with importing and updating Photoshop layers.

- Organize and name layers. If you change a layer name or delete a layer in a Photoshop document after you import it into After Effects, After Effects won't be able to find the renamed or deleted layer. The After Effects Project panel lists that layer as missing. (You can also group layers into Smart Objects. For example: If you used a set of layers to make a foreground object and a set of layers to make a background, you can group them as one Smart Object each, and easily animate one to fly in front of the other).
- Make sure that each layer has a unique name. Duplicate layer names can cause confusion.
- Choose Always from the Maximize PSD And PSB File Compatibility menu in the File Handling Preferences dialog box.
- Use the appropriate pixel dimension preset for video and film in the New Document dialog box.
- Do any required color correction, scaling, cropping, or other edits in Photoshop so that After Effects doesn't have to do extra image-processing work. (You can also assign a color profile to the image that corresponds to the intended output type, such as Rec. 601 NTSC or Rec. 709. After Effects can read embedded color profiles and interpret the image's colors accordingly. For more information on color profiles, see Working with color profiles.

More Help topics

Preview your document on a video monitor

Create frame animations

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

Frame animation workflow

In Photoshop, you use the Timeline panel to create animation frames. Each frame represents a configuration of layers.

Note: *You can also create animations using a timeline and keyframes. See Create timeline animations.*



To create frame-based animations in Photoshop, use the following general workflow.

Open a new document.

If they are not already visible, open the Timeline, and Layers panels. Make sure the Timeline panel is in frame animation mode. In the middle of the Timeline panel, click the downpointing arrow to choose Create Frame Animation and then click the button next to the arrow.

Add a layer or convert the background layer.

Because a background layer cannot be animated, add a new layer or convert the background layer to a regular layer. See Convert background and Photoshop layers.

Add content to your animation.

If your animation includes several objects that are animated independently, or if you want to change the color of an object or completely change the content in a frame, create the objects on separate layers.

Add a frame to the Timeline panel.

See Add frames to an animation.

Select a frame.

See Select animation frames.

Edit the layers for the selected frame.

Do any of the following:

- Turn visibility on and off for different layers.
- Change the position of objects or layers to make layer content move.
- Change layer opacity to make content fade in or out.
- Change the blending mode of layers.
- Add a style to layers.

  Photoshop provides tools for keeping characteristics of a layer the same across frames. See Unify layer properties in animation frames.

Add more frames and edit layers as needed.

The number of frames you can create is limited only by the amount of system memory available to Photoshop.

You can generate new frames with intermediate changes between two existing frames in the panel using the Tween command. This is a quick way to make an object move across the screen or to fade in or out. See Create frames using tweening.

Set frame delay and looping options.

You can assign a delay time to each frame and specify looping so that the animation runs once, a certain number of times, or continuously. See Specify a delay time in frame animationsand Specify looping in frame animations.

Preview the animation.

Use the controls in the Timeline panel to play the animation as you create it. Then use the Save For Web command to preview the animation in your web browser. See Preview optimized images in a web browser.

Optimize the animation for efficient download.

See Optimize animation frames.

Save the animation.

There are different options for saving your frame animation:

- Save as an animated GIF using the Save For Web command.
- Save in Photoshop (PSD) format so you can do more work on the animation later.
- Save as an image sequence, QuickTime movie, or as separate files. See also Export video files or image sequences.

Add frames to an animation

Adding frames is the first step in creating an animation. If you have an image open, the Timeline panel displays the image as the first frame in a new animation. Each frame you add starts as a duplicate of the preceding frame. You then make changes to the frame using the Layers panel.

1 Make sure the Timeline panel is in frame animation mode.

2 Click the Duplicate Selected Frames button .

Select animation frames

Before you can work with a frame, you must select it as the current frame. The contents of the current frame appear in the document window.

In the Timeline panel, the current frame is indicated by a narrow border (inside the shaded selection highlight) around the frame thumbnail. Selected frames are indicated by a shaded highlight around the frame thumbnails.

Select one animation frame

? Do one of the following in the Timeline panel:

- Click a frame.
- Click the Select Next Frame button to select the next frame in the series as the current frame.
- Click the Select Previous Frame button to select the previous frame in the series as the current frame.
- Click the Select First Frame button to select the first frame in the series as the current frame.

Select multiple animation frames

? In the Timeline panel, do one of the following:

- To select contiguous multiple frames, Shift-click a second frame. The second frame and all frames between the first and second are added to the selection.
- To select discontiguous multiple frames, Ctrl-click (Windows) or Command-click (Mac OS) additional frames to add those frames to the selection.
- To select all frames, choose Select All Frames from the panel menu.
- To deselect a frame in a multiframe selection, Ctrl-click (Windows) or Command-click (Mac OS) that frame.

Edit animation frames

1 In the Timeline panel, select one or more frames.

2 Do any of the following:

- To edit the content of objects in animation frames, use the Layers panel to modify the layers in the image that affect that frame.
- To change the position of an object in an animation frame, select the layer containing the object in the Layers panel and drag it to a new position.

Note: *You can select and change the position of multiple frames. However, if you drag multiple discontiguous frames, the frames are placed contiguously in the new position.*

- To reverse the order of animation frames, choose Reverse Frames from the panel menu.

Note: *The frames you want to reverse do not have to be contiguous; you can reverse any selected frames.*

- To delete selected frames, choose Delete Frame from the Timeline panel menu or click the Delete icon , then click Yes to confirm the deletion. You can also drag the selected frame onto the Delete icon.

Unify layer properties in animation frames

The unify buttons (Unify Layer Position, Unify Layer Visibility, and Unify Layer Style) in the Layers panel determine how the changes you make to attributes in the active animation frame apply to the other frames in the same layer. When a unify button is selected, that attribute is changed in all the frames in the active layer; when that button is deselected, changes apply to only the active frame.

The Propagate Frame 1 option in the Layers panel also determines how the changes you make to attributes in the first frame will apply to the other frames in the same layer. When it is selected, you can change an attribute in the first frame, and all subsequent frames in the active layer will change in relation to the first frame (and preserve the animation you have already created).

Unify layer properties

1. In the Timeline panel, change the attribute to one frame.
2. In the Layers panel, click Unify Layer Position , Unify Layer Visibility , or Unify Layer Style to have the changed attribute apply to all other frames in the active layer.

Propagate Frame 1

1. In the Layers panel, select the Propagate Frame 1 option.
2. In the Timeline panel, change the attribute for the first frame.

   The changed attribute is applied (in relation) to all subsequent frames in a layer.

You can also propagate frames by Shift-selecting any consecutive group of frames in the layer and changing an attribute in any of the selected frames.

Show or hide unify layers buttons

? Choose Animation Options from the Layers panel menu, and then choose one of the following:

Automatic Displays the unify layers buttons when the Timeline panel is open.

Always Show Displays the unify layers buttons whether the Timeline panel is open or closed.

Always Hide Hides the unify layers buttons whether the Timeline panel is open or closed.

Copy frames with layer properties

To understand what happens when you copy and paste a frame, think of a frame as a duplicate version of an image with a given layer configuration. When you copy a frame, you copy the configurations of layers (including each layer's visibility setting, position, and other properties). When you paste a frame, you apply that layer configuration to the destination frame.

1. Select one or more frames you want to copy in the Timeline panel.
2. Choose Copy Frame(s) from the panel menu.
3. Select a destination frame or frames in the current animation or another animation.
4. Choose Paste Frame(s) from the panel menu.

5 Select a Paste method:

Replace Frames Replaces the selected frames with the copied frames. No new layers are added. The properties of each existing layer in the destination frames are replaced by those of each copied layer. When you paste frames between images, new layers are added to the image; however, only the pasted layers are visible in the destination frames (the existing layers are hidden).

Paste Over Selection Adds the contents of the pasted frames as new layers in the image. When you paste frames into the same image, using this option doubles the number of layers in the image. In the destination frames, the newly pasted layers are visible, and the original layers are hidden. In the non-destination frames, the newly pasted layers are hidden.

Paste Before Selection or Paste After Selection Adds the copied frames before or after the destination frame. When you paste frames between images, new layers are added to the image; however, only the pasted layers are visible in the new frames (the existing layers are hidden).

6 (Optional) To link pasted layers in the Layers panel, select Link Added Layers.

This option works only when pasting frames into another document. Select it when you plan to reposition the pasted layers as a unit.

7 Click OK.

Create frames using tweening

The term *tweening* is derived from "in betweening," the traditional animation term used to describe this process. Tweening (also called *interpolating*) significantly reduces the time required to create animation effects such as fading in or fading out, or moving an element across a frame. You can edit tweened frames individually after you create them.

You use the Tween command to automatically add or modify a series of frames between two existing frames—varying the layer properties (position, opacity, or effect parameters) evenly between the new frames to create the appearance of movement. For example, if you want to fade out a layer, set the opacity of the layer in the starting frame to 100%; then set the opacity of the same layer in the ending frame to 0%. When you tween between the two frames, the opacity of the layer is reduced evenly across the new frames.



1 To apply tweening to a specific layer, select it in the Layers panel.

2 Select a single frame or multiple contiguous frames.

- If you select a single frame, you choose whether to tween the frame with the previous frame or the next frame.
- If you select two contiguous frames, new frames are added between the frames.
- If you select more than two frames, existing frames between the first and last selected frames are altered by the tweening operation.
- If you select the first and last frames in an animation, these frames are treated as contiguous, and tweened frames are added after the last frame. (This tweening method is useful when the animation is set to loop multiple times.)

3 Do one of the following:

- Click the Tweens button in the Timeline panel.

- Choose Tween from the panel menu.

4 Specify the layer or layers to be varied in the added frames:

All Layers Varies all layers in the selected frame or frames.

Selected Layer Varies only the currently selected layer in the selected frame or frames.

5 Specify layer properties to be varied:

Position Varies the position of the layer's content in the new frames evenly between the beginning and ending frames.

Opacity Varies the opacity of the new frames evenly between the beginning and ending frames.

Effects Varies the parameter settings of layer effects evenly between the beginning and ending frames.

6 If you selected a single frame in step 2, choose where to add frames from the Tween With menu:

Next Frame Adds frames between the selected frame and the following frame. This option is not available when you select the last frame in the Timeline panel.

First Frame Adds frames between the last frame and first frame. This option is available only if you select the last frame in the Timeline panel.

Previous Frame Adds frames between the selected frame and the preceding frame. This option is not available when you select the first frame in the Timeline panel.

Last Frame Adds frames between the first frame and last frame. This option is available only if you select the first frame in the Timeline panel.

7 In the Frames To Add box, enter a value, or use the Up or Down Arrow key to choose the number of frames. (This option is not available if you selected more than two frames.)

8 Click OK.

Add a new layer for each new frame

The Create New Layer For Each New Frame command automatically adds a new layer visible in the new frame but hidden in other frames. This option saves time when you are creating an animation that requires you to add a new visual element to each frame.

? Choose Create New Layer For Each New Frame from the Timeline panel menu.

A check mark indicates that the option is turned on.

Hide layers in animation frames

When you create a new layer, it is visible in all animation frames by default.

- To show new layers only in active frames, deselect New Layers Visible In All Frames from the Timeline panel menu.
- To hide a layer in a specific frame, select the frame, and then hide the desired layer in the Layers panel.

Specify a delay time in frame animations

You can specify a *delay*—the time that a frame is displayed—for single frames or for multiple frames in an animation. Delay time is displayed in seconds. Fractions of a second are displayed as decimal values. For example, one-quarter of a second is specified as .25. If you set a delay on the current frame, every frame you create after that will remember and apply that delay value.

1 Select one or more frames in the Timeline panel.

2 Click the Delay value below the selected frame to view the pop-up menu.

3 Specify the delay:

- Choose a value from the pop-up menu. (The last value used appears at the bottom of the menu.)
- Choose Other, enter a value in the Set Frame Delay dialog box, and click OK. If you selected multiple frames, specifying a delay value for one frame applies the value to all frames.

Choose a frame disposal method

The frame disposal method specifies whether to discard the current frame before displaying the next frame. You select a disposal method for animations that include background transparency to specify whether the current frame will be visible through the transparent areas of the next frame.

***A** Frame with background transparency with Restore To Background option **B** Frame with background transparency with Do Not Dispose option*

The Disposal Method icon indicates whether the frame is set to Do Not Dispose or Dispose . (No icon appears when Disposal Method is set to Automatic.)

1 Select a frame or frames for which you want to choose a disposal method.

2 Right-click (Windows) or Control-click (Mac OS) the frame thumbnail to view the Disposal Method context menu.

3 Choose a disposal method:

Automatic Determines a disposal method for the current frame automatically, discarding the current frame if the next frame contains layer transparency. For most animations, the Automatic option (default) yields the desired results.

Note: *To preserve frames that include transparency, select the Automatic disposal option when you are using the Redundant Pixel Removal optimization option.*

Do Not Dispose Preserves the current frame as the next frame is added to the display. The current frame (and preceding frames) may show through transparent areas of the next frame. Use a browser to see an accurate preview of an animation using the Do Not Dispose option.

Dispose Discards the current frame from the display before the next frame is displayed. Only a single frame is displayed at any time (and the current frame does not appear through the transparent areas of the next frame).

Specify looping in frame animations

You select a looping option to specify how many times the animation sequence repeats when played.

1 Click the Looping Option Selection box at the lower-left corner of the Timeline panel.

2 Select a looping option: Once, 3 Times, Forever, or Other.

3 If you selected Other, enter a value in the Set Loop Count dialog box, and click OK.

__Note:__ Looping options can also be set in the Save for Web dialog box. For more information, see Save For Web & Devices overview.

Delete an entire animation

? Choose Delete Animation from the Timeline panel menu.

More Help topics

Save in GIF format

Photoshop format (PSD)

Import video files and image sequences

__Note:__ For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.

Open or import a video file

In Photoshop, you can open a video file directly or add video to an open document. When you import video, the image frames are referenced in a video layer.

1 Do one of the following:

- To open a video file directly, choose File > Open.
- To import video into an open document, choose Layer > Video Layers > New Video Layer From File.

2 In the Open dialog box, for Files Of Type (Windows) or Enable (Mac OS), choose either All Readable Documents or QuickTime Movie.

3 Select a video file and then click Open.

You can also open video directly from Bridge: Select a video file and then choose File > Open With > Adobe Photoshop.

Import image sequences

In Photoshop, when you import a folder of sequenced image files, each image becomes a frame in a video layer.

1 Make sure that the image files are in one folder and are named sequentially.

The folder should contain only those images you want to use as frames. The resulting animation will be more successful if all files have the same pixel dimensions. To order frames correctly for the animation, name the files in alphabetical or numeric order. For example, *filename001*, *filename002*, *filename003*, and so forth.

2 Do one of the following:
   - To open an image sequence directly, choose File > Open.
   - To import an image sequence into an open document, choose Layer > Video Layers > New Video Layer From File.
3 In the Open dialog box, navigate to the folder with image sequence files.
4 Select one file, choose the Image Sequence option, and then click Open.

   Note: *Selecting more than one file in an image sequence disables the Image Sequence option.*
5 Specify the frame rate, and click OK.

Place a video or image sequence

In Photoshop, use the Place command if you want to transform the video or image sequence as you import it into a document. Once placed, the video frames are contained within a Smart Object. When video is contained by a Smart Object, you can navigate through the frames using the Animation panel, and you can also apply Smart Filters.

Note: *You can't paint or clone directly on video frames contained by a Smart Object. However, you can add a blank video layer above the Smart Object, and paint on the blank frames. You can also use the Clone tool with the Sample All Layers option to paint on blank frames. This lets you use the video in the Smart Object as a cloning source.*

1 With a document open, choose File > Place.
2 In the Place dialog box, do one of the following:
   - Select a video file and click Place.
   - Select one image sequence file, select the Image Sequence option, and then click Place.

   Note: *Make sure all the image sequence files are in one folder.*
3 (Optional) Use the control points to scale, rotate, move, or warp the imported content.
4 Click the Commit Transform button ✓ in the options bar to place the file.

You can also place video directly from Adobe Bridge. Select the video file and then choose File > Place > In Photoshop.

Reload footage in a video layer

If the source file for a video layer is modified in a different application, Photoshop generally reloads and updates the footage, when you open the document containing the video layer referencing the changed source file. If your document is already open and the source file has been modified, use the Reload Frame command to reload and update the current frame in the Animation panel. Navigating through the video layer using the Previous/Next Frame or Play button in the Animation panel should also reload and update the footage.

Replace footage in a video layer

Photoshop tries to maintain the link between the video layer and source file even if you move or rename the source. If the link breaks for some reason, an alert icon appears on the layer in the Layers panel. To relink the video layer to the source file, use the Replace Footage command. This command can also replace the video or image sequence frames in a video layer with frames from a different video or image sequence source.

1 In the Timeline, or Layers panel, select the video layer that you want to relink to the source file or to replace the content.

2 Choose Layer > Video Layers > Replace Footage.

3 In the Open dialog box, select a video or image sequence file, and then click Open.

Interpreting video footage

Interpret video footage

You can specify how Photoshop interprets the alpha channel and frame rate of the video you've opened or imported.

1 In the Timeline, or Layers panel, select the video layer that you want to interpret.

2 Choose Layer > Video Layers > Interpret Footage.

3 In the Interpret Footage dialog box, do any of the following:

- To specify how the alpha channel in the video layer is interpreted, select an Alpha Channel option. The footage must have an alpha channel for this option to be available. If Premultiplied-Matte is selected, you can specify the matte color with which the channels are premultiplied.
- To specify the number of video frames played per second, enter a Frame Rate.
- To color-manage the frames or images in a video layer, choose a profile from the Color Profile menu.

Alpha channel interpretation in video and image sequences

Video and image sequences with alpha channels can be straight or premultiplied. If you're working with video or image sequences containing alpha channels, it's important to specify how Photoshop interprets the alpha channel to get the results you expect. When premultiplied video or images are in a document with certain background colors, it's possible to get undesirable ghosting or halos. You can specify a matte color so the semi-transparent pixels blend (multiply) with the background without producing halos.

Ignore Ignores the alpha channel in the video.

Straight-Unmatted Interprets the alpha channel as straight alpha transparency. If the application you used to create the video doesn't premultiply the color channels, select this option.

Premultiplied-Matte Uses the alpha channel to determine how much of the matte color to mix with the color channels. If necessary, click the color swatch in the Interpret Footage dialog box to specify the matte color.



More Help topics

Supported video and image sequence formats

Understand Smart Objects

Transform video layers

About Smart Filters

Create new video layers

Video workflow

Intuitive editing for video DSLRs and other sources.

Video workflow

Chapter 15: Filters and effects

Use the Blur Gallery

Use the Blur Gallery to quickly create distinct photographic blur effects with intuitive on-image controls.

Each blur tool provides intuitive on-image controls to apply and control the blur effect. With the blur adjustments complete, use the Bokeh controls to style the overall blur effect. Photoshop provides a full-size, live preview when you work with the Blur Gallery effects.

Choose Filter > Blur Gallery and then select the desired effect.

For information on other blur effects, see Adjust image sharpness and blur.

For Lens blurs (Field blur, Iris blur, and Tilt/Shift blur), press the M key to view the blur mask applied to the image. The black areas are not blurred, while lighter areas indicate the amount of blurring applied to the image.

Field blur

Use Field Blur to build a gradient of blurs, by defining multiple blur points with different amounts of blur. Add multiple pins to the image and specify a blur amount for each pin.

The final result is combined effect of all blur pins on the image. You can even add a pin outside the image, to apply the blur at corners.

1 Choose Filter > Blur Gallery > Field Blur.

   A Field blur pin is placed on the image. Click the image to add additional blur pins.

2 Click a pin to select it, and do one of the following:

   - Drag the blur handle to increase or decrease the blur. You can also use the Blur Tools panel to specify a blur value.
   - Drag the pin to a new location.
   - Press Delete to remove it.

***A** Unselected blur pin **B** Selected blur pin*

Iris blur

Use the Iris blur to simulate a shallow depth-of-field effect to your picture, irrespective of the camera or lens used. You can also define multiple focus points, an effect almost impossible to achieve using traditional camera techniques.

1 Choose Filter > Blur Gallery > Iris Blur.

   The default Iris blur pin is placed on the image. Click the image to add additional blur pins.



A Sharp area ***B*** *Fade area* ***C*** *Blur area*

2 Drag the handles to move them to redefine the various areas.

3 Drag the blur handle to increase or decrease the blur. You can also use the Blur Tools panel to specify a blur value.

Tilt-Shift

Use the Tilt-Shift effect to simulate an image taken with a tilt-shift lens. This special effect blur defines area of sharpness, and then fades to a blur at the edges. The Tilt-Shift effect can be used to simulate photos of miniature objects.

1 Choose Filter > BlurGallery > Tilt-Shift.

The default Tilt-Shift blur pin is placed on the image. Click the image to add additional blur pins.



A Sharp area ***B*** *Fade area* ***C*** *Blur area*

2 Drag the blur handle to increase or decrease the blur. You can also use the Blur Tools panel to specify a blur value.

3 To define the different areas, do the following:

- Drag the lines to move them.
- Drag the handles and rotate.

Path blur

Using the Path Blur effects, you can create motion blurs along paths. You can also control the shape and amount of blurring. Photoshop automatically composites the effects of multiple path blurs applied to an image.



Follow the steps below:

1 Choose Filter > Blur Gallery > Path Blur.

2 In the Blur Tools panel, under the Path Blur section, specify whether you want to apply a Basic Blur or a Rear Sync Flash blur. A Rear Sync Flash blur simulates the effect of a flash fired at the end of an exposure.

1 Use the on-image controls in conjunction with steps 4-8 of this procedure.

2 Specify the following settings:

Speed Adjust the Speed slider to specify the amount of path blur you want to apply to the image. The Speed setting is applied to all plath blurs in the image.

Taper Adjust the slider to specify a taper value. A higher taper value lets the blur trail off gradually.

? If necessary, deselect Centered Blur. You may want to deselect this option if you want to apply a more directed motion blur. The Centered Blur option helps create stable blurs by centering the blur shape for any pixel on that pixel.

? In the Motion Blur Effects tab, specify the following settings:

Strobe Flashes Set the number of exposures of the virtual strobe flash light.

Strobe Strength Determine how much blurring is displayed between strobe flash exposures. Strobe Strength controls the balance between ambient light and the virtual strobe flash light.

No strobe effect is displayed if you set Strobe Strength to 0%; only continuous blur is shown. On the other hand, when you set Strobe Strength to 100%, the strobe flashes are produced in full strength but no continuous blur is displayed between flash exposures. Intermediate Strobe Strength values produce a mixture of individual strobe flashes along with continuous blur.

1 If necessary, adjust the blur amounts at the endpoints.

2 Optionally, adjust the blur shape guides. Select Edit Blur Shapes to view the guides.

3 In the blur tool Options bar, click OK to commit the Path Blur effect.

Tips for working with the on-image controls

You can use the overlay controls to conveniently create path blurs.

Using the controls, you first define a path for the blur (blue). You can then define a curve for the path, thereby creating new curve points in the path. Once the path has been defined, you can define blur shape guides (red).

***A** Beginning point for the path **B** Curve point created while defining a path **C** Endpoint for the path along with the blur amount wheel control*

This image is a derivative of the public domain work "Deer Running in the Snow" by Gustave Courbet (1819-1877).

A *Blur shape guides*

Manipulate blur paths and blur shape guides

- Click an endpoint to select it.
- Double-click an endpoint to view the red blur shape guides. Alternatively, select Edit Blur Shapes in the Blur Tools panel to view the guides.
- Drag endpoints to lengthen the blur path.
- Cmd/Ctrl-click an endpoint to reduce its blur shape guide to zero.
- Hover the mouse pointer near a selected endpoint to view the blur amount wheel control.
- Opt/Alt-click a curve point along the blur path to convert it into a corner point. Opt/Alt-click a corner point to convert it back to a curve point.
- Shift-drag the red blur shape to move both blur shapes for the path together.
- Use the Cmd/Ctrl+drag combination to move a path blur.
- Use the Opt/Alt+Cmd/Ctrl+drag combination to duplicate a path blur.
- To delete a path blur, with an endpoint selected, press the Delete key.

Spin blur

Using the Spin Blur effect, you can rotate and blur the image around one or more points. The spin blur is a radial blur measured in degrees. Photoshop lets you work with center points, blur size and shape, and other settings, all while viewing a live preview of the changes.



A Original image ***B*** *Spin Blur (Blur Angle: 15°; Strobe Strength: 50%; Strobe Flashes: 2; Strobe Flash Duration: 10°)* ***C*** *Spin Blur (Blur Angle: 60°; Strobe Strength: 100%; Strobe Flashes: 4; Strobe Flash Duration: 10°)*

Follow these steps:

1 Choose Filter > Blur Gallery > Spin Blur.

2 In the Blur Tools panel, under the Spin Blur section, use the Blur Angle control to vary the amount of blurring. You can either specify an angular value (0-360°) or adjust the slider. Alternatively, you can also adjust the blur amount using overlay controls.



? In the Blur Effects panel, on the Motion Blur Effects tab, specify the following settings:

Strobe Flashes Set the number of exposures of the virtual strobe flash light

Strobe Strength Determine how much blurring is displayed between strobe flash exposures. Strobe Strength controls the balance between ambient light and the virtual strobe flash light.

No strobe effect is displayed if you set Strobe Strength to 0%; only continuous blur is shown. On the other hand, when you set Strobe Strength to 100%, the strobe flashes are produced in full strength but no continuous blur is displayed between flash exposures. Intermediate Strobe Strength values produce a mixture of individual strobe flashes along with continuous blur.

Strobe Flash Duration Lets you specify, in degrees, the length of a strobe flash exposure. Strobe Flash Duration controls the length of the blur for each flash exposure in terms of angular distance along the circumference.

? In the blur tool Options bar, click OK to commit the Spin Blur effect.

You can disable preview from the blur tool Options bar.

Note: *Photoshop automatically blends effects of multiple spin blurs defined for an image.*

Tips for working with the overlay controls

Overlay controls depicted in the illustration below are available for the Spin Blur effect.



A *Rotation point* ***B*** *Blur ring* ***C*** *Feather handles* ***D*** *Ellipse handles*

- To add a new spin blur, click a desired location in the image.
- To duplicate a spin blur, use the following keyboard combinations:(Windows) Alt+Ctrl+drag(Mac) Opt+Cmd+drag
- To resize the ellipse uniformly, drag an ellipse boundary.
- To delete a spin blur, press the Delete key while the spin blur is selected.
- To move a rotation point off-center, use the following keyboard combination:(Windows) Alt+drag(Mac) Opt+drag Repositioning the rotation point is helpful while working with objects viewed at an angle.
- Hold down the H key to temporarily hide the overlay controls.

Blur effects

You can enhance the overall image, by controlling the appearance of out-of-focus or blurred parts. Specify the bokeh parameters to ensure an overall pleasing effect.

In the Blur Effects panel, specify a value for the following:

Light Bokeh Brightens the out-of-focus, or blurred areas in the picture.

Bokeh Color Adds more vivid color to lightened areas that are not blown out to white.

Light Range Determines the range of tones the settings affect.

Restore noise in blurred areas

Sometimes, after applying a Blur Gallery effect, you may notice that the blurred area of the image looks synthetic or unnatural. You can restore noise/grain to such a blurred image area to give it a more realistic appearance.



After using blur controls to achieve the initial effect, follow these steps to restore noise:

1 In the blur Effects panel, on the Noise tab, ensure that the checkbox in the top-right corner is selected. You may deselect this checkbox at any time to revert any noise previously added to the blurred image area.

2 Select the type of noise that you want to apply to the blurred area:**Uniform:** Same as the noise added through the Filter > Noise > Add Noise > Uniform option.**Gaussian:** Same as the noise added through the Filter > Noise > Add Noise > Gaussian option.**Grain:** Same as the noise added through the Add Grain option in Camera Raw.

3 Specify the following settings:**Amount:** Matches the amount of noise with the noise in the not-blurred areas of the image. Adjust the slider between 0-100%.**Size:**(Only for Grain-type noise) Controls the particle size for the noise**Roughness:**(Only available for Grain-type noise) Controls the regularity of the grain. Drag to the left (below 50%) to make the grain more uniform. Drag to the right (above 50%) to make the grain less even.**Color**: Graduated slider controlling the degree to which the noise is colored. To make the noise monochromatic, similar to the effect achieved by enabling the Monochromatic option on the Add Noise dialog (Filter > Noise > Add Noise), drag the slider to 0%. Highlight: For better shadow/highlight matching, reduces noise in the highlighted areas of the image. Adjust the slider between 0-100%.

Once you specify the settings for a noise type, Photoshop remembers it if you switch back and forth between noise types. For example, when you switch from Grain-type noise to Gaussian-type noise and then back to Grain-type noise.

Applying Blur Gallery effects as Smart Filters

The blur effects in the Blur Gallery now support Smart Objects and can be applied non-destructively as Smart Filters. This feature also supports Smart Object video layers. To apply a Blur Gallery effect as a Smart Filter:

1 In the Layers panel, select a Smart Object layer.

2 Choose Filter > Blur Gallery, and then choose the appropriate effect.

For more information about Smart Filters, see Apply Smart Filters.

Adobe also recommends

- Filter effects reference
- Adobe Camera Raw | Vignette and grain effects
- Video | Add creative blur to photos

Filter basics

Note: *For detailed instructions, click the links below. To ask questions, request features, or report problems, visit feedback.photoshop.com.*

Using filters

You can use filters to clean up or retouch your photos, apply special art effects that give your image the appearance of a sketch or impressionistic painting, or create unique transformations using distortions and lighting effects. The filters provided by Adobe appear in the Filter menu. Some filters provided by third-party developers are available as plug-ins. Once installed, these plug-in filters appear at the bottom of the Filter menu.

Smart Filters, applied to Smart Objects, let you use filters non-destructively. Smart Filters are stored as layer effects in the Layers panel and can be readjusted at any time, working from the original image data contained in the Smart Object. For more information on Smart Filter Effects and nondestructive editing, see Nondestructive editing.

To use a filter, choose the appropriate submenu command from the Filter menu. These guidelines can help you in choosing filters:

- Filters are applied to the active, visible layer or a selection.
- For 8-bits per-channel images, most filters can be applied cumulatively through the Filter Gallery. All filters can be applied individually.
- Filters cannot be applied to Bitmap-mode or indexed-color images.
- Some filters work only on RGB images.
- All filters can be applied to 8-bit images.
- The following filters can be applied to 16-bit images: Liquify, Vanishing Point, Average Blur, Blur, Blur More, Box Blur, Gaussian Blur, Lens Blur, Motion Blur, Radial Blur, Surface Blur, Shape Blur, Lens Correction, Add Noise, Despeckle, Dust & Scratches, Median, Reduce Noise, Fibers, Clouds, Difference Clouds, Lens Flare, Sharpen, Sharpen Edges, Sharpen More, Smart Sharpen, Unsharp Mask, Emboss, Find Edges, Solarize, De-Interlace, NTSC Colors, Custom, High Pass, Maximum, Minimum, and Offset.
- The following filters can be applied to 32-bit images: Average Blur, Box Blur, Gaussian Blur, Motion Blur, Radial Blur, Shape Blur, Surface Blur, Add Noise, Clouds, Lens Flare, Smart Sharpen, Unsharp Mask, De-Interlace, NTSC Colors, Emboss, High Pass, Maximum, Minimum, and Offset.
- Some filters are processed entirely in RAM. If you don't have enough available RAM to process a filter effect, you may get an error message.

Apply a filter from the Filter menu

You can apply a filter to the active layer, or to a Smart Object. Filters applied to a Smart Object are nondestructive and can be readjusted at any time.

1 Do one of the following:
   - To apply a filter to an entire layer, make sure the layer is active or selected.
   - To apply a filter to an area of a layer, select that area.
   - To apply a filter nondestructively so you can change your filter settings later, select the Smart Object that contains the image content you want to filter.

2 Choose a filter from the submenus in the Filter menu.

   If no dialog box appears, the filter effect is applied.

3 If a dialog box or the Filter Gallery appears, enter values or select options, and then click OK.

Applying filters to large images can be time consuming, but you can preview the effect in the filter dialog box. Drag in the preview window to center a specific area of the image. In some filters, you can click in the image to center it where you click. Click the + or – buttons under the preview window to zoom in or out.

Filter Gallery overview

The Filter Gallery provides a preview of many of the special effects filters. You can apply multiple filters, turn on or off the effect of a filter, reset options for a filter, and change the order in which filters are applied. When you are satisfied with the preview, you can then apply it to your image. Not all filters in the Filter menu are available in the Filter Gallery.



A Preview B Filter category C Thumbnail of selected filter D Show/Hide filter thumbnails E Filters pop-up menu F Options for selected filter G List of filter effects to apply or arrange H Filter effect selected but not applied I Filter effects applied cumulatively but not selected J Hidden filter effect

Display the Filter Gallery

? Choose Filter > Filter Gallery. Clicking a filter category name displays thumbnails of available filter effects.

Zoom in or out of the preview

? Click the + or – button under the preview area, or choose a zoom percentage.

View another area of the preview

? Drag in the preview area with the Hand tool.

Hide filter thumbnails

? Click the Show/Hide button at the top of the gallery.

Apply filters from the Filter Gallery

Filter effects are applied in the order you select them. You can rearrange filters after you apply them by dragging a filter name to another position in the list of applied filters. Rearranging filter effects can dramatically change the way your image looks. Click the eye icon next to a filter to hide the effect in the preview image. You can also delete applied filters by selecting the filter and clicking the Delete Layer icon .

To save time when trying various filters, experiment by selecting a small, representative part of your image.

1 Do one of the following:
   - To apply a filter to an entire layer, make sure that the layer is active or selected.
   - To apply a filter to an area of a layer, select that area.
   - To apply a filter non-destructively, so you can change your filter settings later, select the Smart Object that contains the image content that you want to filter.
2 Choose Filter > Filter Gallery.
3 Click a filter name to add the first filter. You may need to click the inverted triangle next to the filter category to see the complete list of filters. Once added, the filter appears in the applied filter list in the lower right corner of the Filter Gallery dialog box.
4 Enter values or select options for the filter you selected.
5 Do any of the following:
   - To apply filters cumulatively, click the New Effect Layer icon , and choose an additional filter to apply. Repeat this procedure to add more filters.
   - To rearrange applied filters, drag the filter to a new position in the applied filter list in the lower right corner of the Filter Gallery dialog box.
   - To remove applied filters, select a filter in the applied filter list, and click the Delete Layer icon .
6 When you're satisfied with the results, click OK.

Blend and fade filter effects

The Fade command changes the opacity and blending mode of any filter, painting tool, erasing tool, or color adjustment. The Fade command blending modes are a subset of those in the painting and editing tools options (excluding the Behind and Clear modes). Applying the Fade command is similar to applying the filter effect on a separate layer and then using the layer opacity and blending mode controls.

Note: *The Fade command can also modify the effects of using the Liquify command and Brush Strokes filters.*

1 Apply a filter, painting tool, or color adjustment to an image or selection.

2 Choose Edit > Fade. Select the Preview option to preview the effect.

3 Drag the slider to adjust the opacity, from 0% (transparent) to 100%.

4 Choose a blending mode from the Mode menu.

Note: The Color Dodge, Color Burn, Lighten, Darken, Difference, and Exclusion blending modes do not work on Lab images.

5 Click OK.

Tips for creating special effects

Creating edge effects You can use various techniques to treat the edges of an effect applied to only part of an image. To leave a distinct edge, simply apply the filter. For a soft edge, feather the edge, and then apply the filter. For a transparent effect, apply the filter, and then use the Fade command to adjust the selection's blending mode and opacity.

Applying filters to layers You can apply filters to individual layers or to several layers in succession to build up an effect. For a filter to affect a layer, the layer must be visible and must contain pixels—for example, a neutral fill color.

Applying filters to individual channels You can apply a filter to an individual channel, apply a different effect to each color channel, or apply the same filter but with different settings.

Creating backgrounds By applying effects to solid-color or grayscale shapes, you can generate a variety of backgrounds and textures. You might then blur these textures. Although some filters have little or no visible effect when applied to solid colors (for example, Glass), others produce interesting effects.

Combining multiple effects with masks or duplicate images Using masks to create selection areas gives you more control over transitions from one effect to another. For example, you can filter the selection created with a mask.

You can also use the History Brush tool to paint a filter effect onto part of the image. First, apply the filter to an entire image. Next, step back in the History panel to the image state before the filter was applied, and set the history brush source to the filtered state by clicking in the well at the left side of the history state. Then paint the image.

Improving image quality and consistency You can disguise faults, alter or enhance images, or create a relationship among images by applying the same effect to each. Use the Actions panel to record the steps you take to modify one image, and then apply this action to the other images.

Improve filter performance

Some filter effects can be memory-intensive, especially when applied to a high-resolution image.

? You can do any of the following to improve performance:

- Try out filters and settings on a small portion of an image.
- Apply the effect to individual channels—for example, to each RGB channel—if the image is large and you're having problems with insufficient memory. (With some filters, effects vary if applied to the individual channel rather than the composite channel, especially if the filter randomly modifies pixels.)
- Free up memory before running the filter by using the Purge command.
- Allocate more RAM to Photoshop. If necessary, exit other applications to make more memory available to Photoshop.
- Try changing settings to improve the speed of memory-intensive filters, such as Lighting Effects, Cutout, Stained Glass, Chrome, Ripple, Spatter, Sprayed Strokes, and Glass filters. (For example, with the Stained Glass filter, increase cell size. With the Cutout filter, increase Edge Simplicity, decrease Edge Fidelity, or both.)

- If you plan to print to a grayscale printer, convert a copy of the image to grayscale before applying filters. However, applying a filter to a color image, and then converting to grayscale, may not have the same effect as applying the filter to a grayscale version of the image.

More Help topics

About plug-in modules

Blending modes

About adjustment and fill layers

Filter effects reference

Note: *Complete information on using some filters is available in other sections. Search Adobe Help for information on the sharpening, blurring, Lens Correction, Lens Blur, Noise Reduction, Liquify, and Vanishing Point filters.*

List of filters supporting 16-bit/channel and 32-bit/channel documents

The following filters support 16-bit/channel and 32-bit/channel documents:

- All Blur filters (except for Lens Blur and Smart Blur)
- All Distort filters
- The Noise > Add Noise filter
- All Pixelate filters
- All Render filters (except for Lighting Effects)
- All Sharpen filters (except for Sharpen Edges)
- The following filters under Filter > Stylize:
  - Diffuse
  - Emboss
  - Trace Contour
- All Video filters
- All filters under Filter > Other

Artistic filters

Filters from the Artistic submenu help you achieve painterly and artistic effects for a fine arts or commercial project. For example, use the Cutout filter for collages or typography. These filters replicate natural or traditional media effects. All the Artistic filters can be applied through the Filter Gallery.

Colored Pencil Draws an image using colored pencils on a solid background. Edges are retained and given a rough crosshatch appearance; the solid background color shows through the smoother areas.

For a parchment effect, change the background color just before applying the Colored Pencil filter to a selected area.

Cutout Makes an image appear as though it were constructed from roughly cut pieces of colored paper. High-contrast images appear as if in silhouette, and colored images are built up from several layers of colored paper.

Dry Brush Paints the edges of the image using a dry brush technique (between oil and watercolor). The filter simplifies an image by reducing its range of colors to areas of common color.

Film Grain Applies an even pattern to the shadow tones and midtones. A smoother, more saturated pattern is added to the lighter areas. This filter is useful for eliminating banding in blends and visually unifying elements from various sources.

Fresco Paints an image in a coarse style using short, rounded, and hastily applied daubs.

Neon Glow Adds various types of glows to the objects in an image. This filter is useful for colorizing an image while softening its look. To select a glow color, click the glow box, and select a color from the Color Picker.

Paint Daubs Lets you choose from various brush sizes (from 1 to 50) and types for a painterly effect. Brush types include Simple, Light Rough, Dark Rough, Wide Sharp, Wide Blurry, and Sparkle.

Palette Knife Reduces detail in an image to give the effect of a thinly painted canvas that reveals the texture underneath.

Plastic Wrap Coats the image in shiny plastic, accentuating the surface detail.

Poster Edges Reduces the number of colors in an image (posterizes it) according to the posterization option you set, and finds the edges of the image and draws black lines on them. Large broad areas have simple shading, and fine dark detail is distributed throughout the image.

Rough Pastels Applies strokes of pastel chalk on a textured background. In areas of bright color, the chalk appears thick with little texture; in darker areas, the chalk appears scraped off to reveal the texture.

Smudge Stick Softens an image using short diagonal strokes to smudge or smear the darker areas. Lighter areas become brighter and lose detail.

Sponge Creates images with highly textured areas of contrasting color, simulating the effect of sponge painting.

Underpainting Paints the image on a textured background, and then paints the final image over it.

Watercolor Paints the image in a watercolor style using a medium brush loaded with water and color, simplifying details. Where significant tonal changes occur at the edges, the filter saturates the color.

Blur filters

The Blur filters soften a selection or an entire image, and are useful for retouching. They smooth transitions by averaging the pixels next to the hard edges of defined lines and shaded areas in an image.

Note: *To apply a Blur filter to the edges of a layer, deselect the Lock Transparent Pixel option in the Layers panel.*

Average Finds the average color of an image or selection, and then fills the image or selection with the color to create a smooth look. For example, if you select an area of grass, the filter changes the area into a homogeneous patch of green.

Blur and Blur More Eliminate noise where significant color transitions occur in an image. Blur filters smooth transitions by averaging the pixels next to the hard edges of defined lines and shaded areas. The effect of the Blur More filter is three or four times stronger than that of the Blur filter.

Box Blur Blurs an image based on the average color value of neighboring pixels. This filter is useful for creating special effects. You can adjust the size of the area used to calculate the average value for a given pixel; a larger radius results in greater blurring.

Gaussian Blur Quickly blurs a selection by an adjustable amount. Gaussian refers to the bell-shaped curve that is generated when Photoshop applies a weighted average to the pixels. The Gaussian Blur filter adds low-frequency detail and can produce a hazy effect.

Note: When Gaussian Blur, Box Blur, Motion Blur, or Shape Blur are applied to a selected image area, they will sometimes produce visually unexpected results near the edges of the selection. This is because these blur filters will use image data from outside the selected area to create the new, blurred pixels inside the selected area. For example, if the selection represents a background area that you want to blur while keeping the foreground sharp, the edges of the blurred background area will be contaminated with colors from the foreground, producing a fuzzy, muddy-looking outline around the foreground. To avoid this effect in such cases, you can use Smart Blur or Lens Blur.

Lens Blur Adds blur to an image to give the effect of a narrower depth of field so that some objects in the image stay in focus and others areas are blurred. See Add lens blur.

Motion Blur Blurs in the specified direction (from –360º to +360º) and at a specified intensity (from 1 to 999). The filter's effect is analogous to taking a picture of a moving object with a fixed exposure time.

Radial Blur Simulates the blur of a zooming or rotating camera to produce a soft blur. Choose Spin to blur along concentric circular lines, and then specify a degree of rotation. Choose Zoom to blur along radial lines, as if zooming into or out of the image, and specify a value from 1 to 100. Blur quality ranges from Draft (for fast but grainy results) or Good and Best for smoother results, which are indistinguishable from each other except on a large selection. Specify the origin of the blur by dragging the pattern in the Blur Center box.

Shape Blur Uses the specified kernel to create the blur. Choose a kernel from the list of custom shape presets, and use the radius slider to adjust its size. You can load different shape libraries by clicking the triangle and choosing from the list. Radius determines the size of the kernel; the larger the kernel, the greater the blur.

Smart Blur Blurs an image with precision. You can specify a radius, a threshold, and a blur quality. The Radius value determines the size of the area searched for dissimilar pixels. The Threshold value determines how dissimilar the pixels must be before they are affected. You also can set a mode for the entire selection (Normal) or for the edges of color transitions (Edge Only and Overlay Edge). Where significant contrast occurs, Edge Only applies black-and-white edges, and Overlay Edge applies white.

Surface Blur Blurs an image while preserving edges. This filter is useful for creating special effects and for removing noise or graininess. The Radius option specifies the size of the area sampled for the blur. The Threshold option controls how much the tonal values of neighboring pixels must diverge from the center pixel value before being part of the blur. Pixels with tonal value differences less than the Threshold value are excluded from the blur.

Brush Stroke filters

Like the Artistic filters, the Brush Stroke filters give a painterly or fine-arts look using different brush and ink stroke effects. Some of the filters add grain, paint, noise, edge detail, or texture. All the Brush Stroke filters can be applied through the Filter Gallery.

Accented Edges Accentuates the edges of an image. When the edge brightness control is set to a high value, the accents resemble white chalk; when set to a low value, the accents resemble black ink.

Angled Strokes Repaints an image using diagonal strokes, with lighter and darker areas painted in strokes going in opposite directions.

Crosshatch Preserves the details and features of the original image while adding texture and roughening the edges of the colored areas with simulated pencil hatching. The Strength option (with values from 1 to 3) determines the number of hatching passes.

Dark Strokes Paints dark areas with short, tight, dark strokes, and lighter areas with long, white strokes.

Ink Outlines Redraws an image with fine narrow lines over the original details, in pen-and-ink style.

Spatter Replicates the effect of a spatter airbrush. Increasing the options simplifies the overall effect.

Sprayed Strokes Repaints an image, using its dominant colors, with angled, sprayed strokes of color.

Sumi-e Paints an image in Japanese style, as if with a fully saturated brush applied to rice paper. Sumi-e creates soft, blurred edges with rich, inky blacks.

Distort filters

The Distort filters geometrically distort an image, creating 3D or other reshaping effects. Note that these filters can be very memory-intensive. The Diffuse Glow, Glass, and Ocean Ripple filters can be applied through the Filter Gallery.

Diffuse Glow Renders an image as though it were viewed through a soft diffusion filter. The filter adds see-through white noise, with the glow fading from the center of a selection.

Displace Uses an image, called a *displacement map*, to determine how to distort a selection. For example, using a parabola-shaped displacement map, you can create an image that appears to be printed on a cloth held up by its corners.

Glass Makes an image appear as if it were being viewed through different types of glass. You can choose a glass effect or create your own glass surface as a Photoshop file and apply it. You can adjust scaling, distortion, and smoothness settings. When using surface controls with a file, follow the instructions for the Displace filter.

Ocean Ripple Adds randomly spaced ripples to the surface of the image so that it appears to be underwater.

Pinch Squeezes a selection. A positive value up to 100% shifts a selection toward its center; a negative value up to –100% shifts a selection outward.

Polar Coordinates Converts a selection from its rectangular to polar coordinates, and vice versa, according to a selected option. You can use this filter to create a cylinder anamorphosis—an art form popular in the 18th century—in which the distorted image appears normal when viewed in a mirrored cylinder.

Ripple Creates an undulating pattern on a selection, like ripples on the surface of a pond. For greater control, use the Wave filter. Options include the number and size of ripples.

Shear Distorts an image along a curve. Specify the curve by dragging the line in the box. You can adjust any point along the curve. Click Default to change the curve back to a straight line. In addition, you choose how to treat undistorted areas.

Spherize Gives objects a 3D effect by wrapping a selection around a spherical shape, distorting the image and stretching it to fit the selected curve.

Twirl Rotates a selection more sharply in the center than at the edges. Specifying an angle produces a twirl pattern.

Wave Works much as the Ripple filter does, but with greater control. Options include the number of wave generators, wavelength (distance from one wave crest to the next), height of the wave, and wave type: Sine (rolling), Triangle, or Square. The Randomize option applies random values. You can also define undistorted areas.

ZigZag Distorts a selection radially, depending on the radius of the pixels in your selection. The Ridges option sets the number of direction reversals of the zigzag from the center of the selection to its edge. You also specify how to displace the pixels: Pond Ripples displaces pixels to the upper-left or lower right, Out From Center displaces pixels toward or away from the center of the selection, and Around Center rotates pixels around the center.

Noise filters

The Noise filters add or remove *noise*, or pixels with randomly distributed color levels. This helps to blend a selection into the surrounding pixels. Noise filters can create unusual textures or remove problem areas, such as dust and scratches.

Add Noise Applies random pixels to an image, simulating the effect of shooting pictures on high-speed film. You can also use the Add Noise filter to reduce banding in feathered selections or graduated fills or to give a more realistic look to heavily retouched areas. Options for noise distribution include Uniform and Gaussian. Uniform distributes color values of noise using random numbers between 0 and plus or minus the specified value, creating a subtle effect. Gaussian distributes color values of noise along a bell-shaped curve, creating a speckled effect. The Monochromatic option applies the filter to only the tonal elements in the image without changing the colors.

Despeckle Detects the edges in an image (areas where significant color changes occur) and blurs all of the selection except those edges. This blurring removes noise while preserving detail.

Dust & Scratches Reduces noise by changing dissimilar pixels. To achieve a balance between sharpening the image and hiding defects, try various combinations of Radius and Threshold settings. Or apply the filter to selected areas in the image. See also Apply the Dust And Scratches filter .

Median Reduces noise in an image by blending the brightness of pixels within a selection. The filter searches the radius of a pixel selection for pixels of similar brightness, discarding pixels that differ too much from adjacent pixels, and replaces the center pixel with the median brightness value of the searched pixels. This filter is useful for eliminating or reducing the effect of motion on an image.

Reduce Noise Reduces noise while preserving edges based on user settings affecting the overall image or individual channels. See Reduce image noise and JPEG artifacts.

Pixelate filters

The filters in the Pixelate submenu sharply define a selection by clumping pixels of similar color values in cells.

Color Halftone Simulates the effect of using an enlarged halftone screen on each channel of the image. For each channel, the filter divides the image into rectangles and replaces each rectangle with a circle. The circle size is proportional to the brightness of the rectangle. See Apply the Color Halftone filter .

Crystallize Clumps pixels into a solid color in a polygon shape.

Facet Clumps pixels of solid or similar colors into blocks of like-colored pixels. You can use this filter to make a scanned image look hand-painted or to make a realistic image resemble an abstract painting.

Fragment Creates four copies of the pixels in the selection, averages them, and offsets them from each other.

Mezzotint Converts an image to a random pattern of black-and-white areas or of fully saturated colors in a color image. To use the filter, choose a dot pattern from the Type menu in the Mezzotint dialog box.

Mosaic Clumps pixels into square blocks. The pixels in a given block are the same color, and the colors of the blocks represent the colors in the selection.

Pointillize Breaks up the color in an image into randomly placed dots, as in a pointillist painting, and uses the background color as a canvas area between the dots.

Render filters

The Render filters create 3D shapes, cloud patterns, refraction patterns, and simulated light reflections in an image. You can also manipulate objects in 3D space, create 3D objects (cubes, spheres, and cylinders), and create texture fills from grayscale files to produce 3D-like effects for lighting.

Clouds Generates a soft cloud pattern using random values that vary between the foreground and the background colors. To generate a more stark cloud pattern, hold down Alt (Windows) or Option (Mac OS) as you choose Filter > Render > Clouds. When you apply the Clouds filter, the image data on the active layer is replaced.

Difference Clouds Uses randomly generated values that vary between the foreground and background color to produce a cloud pattern. The filter blends the cloud data with the existing pixels in the same way the Difference mode blends colors. The first time you choose this filter, portions of the image are inverted in a cloud pattern. Applying the filter several times creates rib and vein patterns that resemble a marble texture. When you apply the Difference Clouds filter, the image data on the active layer is replaced.

Fibers Creates the look of woven fibers using the foreground and background colors. You use the Variance slider to control how the colors vary (a low value produces long streaks of color, and a high value results in very short fibers with more varied distribution of color). The Strength slider controls how each fiber looks. A low setting produces a loose weave, and a high setting produces short, stringy fibers. Click the Randomize button to change how the pattern looks; you can click the button a number of times until you find a pattern you like. When you apply the Fibers filter, the image data on the active layer is replaced.

Try adding a gradient map adjustment layer to colorize the fibers.

Lens Flare Simulates the refraction caused by shining a bright light into a camera lens. Specify a location for the center of the flare by clicking anywhere inside the image thumbnail or by dragging its cross hair.

Lighting Effects Lets you produce myriad lighting effects on RGB images by varying 17 light styles, three light types, and four sets of light properties. You can also use textures from grayscale files (called bump maps) to produce 3D-like effects and save your own styles for use in other images. See Add Lighting Effects .

Note: Lighting Effects is unavailable in 64-bit versions of Mac OS.

Sharpen filters

The Sharpen filters focus blurred images by increasing the contrast of adjacent pixels.

Sharpen and Sharpen More Focus a selection and improve its clarity. The Sharpen More filter applies a stronger sharpening effect than does the Sharpen filter.

Sharpen Edges and Unsharp Mask Find the areas in the image where significant color changes occur and sharpen them. The Sharpen Edges filter sharpens only edges while preserving the overall smoothness of the image. Use this filter to sharpen edges without specifying an amount. For professional color correction, use the Unsharp Mask filter to adjust the contrast of edge detail and produce a lighter and darker line on each side of the edge. This process emphasizes the edge and creates the illusion of a sharper image.

Smart Sharpen Sharpens an image by letting you set the sharpening algorithm or control the amount of sharpening that occurs in shadows and highlights. This is the recommended way to sharpen if you don't have a particular sharpening filter in mind. See Sharpen using Smart Sharpen.

In Photoshop CC, the enhanced Smart Sharpen filter empowers you to produce high-quality results through adaptive sharpening technology that minimizes noise and halo effects. The streamlined UI design for this filter offers optimized controls for targeted sharpening. Use the sliders for quick adjustments and advanced controls to fine-tune your results.

Smart sharpening in Photoshop CC supports CMYK. Additionally, you can sharpen arbitrary channels. For example, you can choose to sharpen just the blue channel, green channel, or the alpha channel.



Here is a recommended approach to sharpening images with Photoshop CC:

1 To begin, set Amount to a high value.

2 Increase the Radius to a value that introduces a halo effect.

3 Decrease the Radius until the halo effect disappers. You've arrived at the optimal value for Radius.

4 Now, decrease the Amount value as necessary.

5 Adjust the Reduce Noise slider, such that the noise in the image looks similar to how it was before you began sharpening the image. Too much noise reduction can result in a plasticy look. Higher Amount values require greater noise reduction.

Sketch filters

Filters in the Sketch submenu add texture to images, often for a 3D effect. The filters also are useful for creating a fine-arts or hand-drawn look. Many of the Sketch filters use the foreground and background color as they redraw the image. All the Sketch filters can be applied through the Filter Gallery.

Bas Relief Transforms an image so that it appears carved in low relief and lit to accent the surface variations. Dark areas of the image take on the foreground color, and light colors use the background color.

Chalk & Charcoal Redraws highlights and midtones with a solid midtone gray background drawn in coarse chalk. Shadow areas are replaced with black diagonal charcoal lines. The charcoal is drawn in the foreground color; the chalk, in the background color.

Charcoal Creates a posterized, smudged effect. Major edges are boldly drawn, and midtones are sketched using a diagonal stroke. Charcoal is the foreground color, and the background is the color of the paper.

Chrome Renders the image as if it had a polished chrome surface. Highlights are high points, and shadows are low points in the reflecting surface. After applying the filter, use the Levels dialog box to add more contrast to the image.

Conté Crayon Replicates the texture of dense dark and pure white Conté crayons on an image. The Conté Crayon filter uses the foreground color for dark areas and the background color for light areas. For a truer effect, change the foreground color to one of the common Conté Crayon colors (black, sepia, or sanguine) before applying the filter. For a muted effect, change the background color to white, add some of the foreground color to the white background, and then apply the filter.

Graphic Pen Uses fine, linear ink strokes to capture the details in the original image. The effect is especially striking with scanned images. The filter replaces color in the original image, using the foreground color for ink and the background color for paper.

Halftone Pattern Simulates the effect of a halftone screen while maintaining the continuous range of tones.

Note Paper Creates an image that appears to be constructed of handmade paper. This filter simplifies images and combines the effects of the Stylize > Emboss and Texture > Grain filters. Dark areas of the image appear as holes in the top layer of paper, revealing the background color.

Photocopy Simulates the effect of photocopying an image. Large dark areas tend to be copied only around their edges, and midtones fall away to either solid black or solid white.

Plaster Molds an image from 3D plaster, and then colorizes the result using the foreground and background color. Dark areas are raised, and light areas are recessed.

Reticulation Simulates the controlled shrinking and distortion of film emulsion to create an image that appears clumped in the shadows and lightly grained in the highlights.

Stamp Simplifies the image so that it appears to be created with a rubber or wood stamp. This filter is best used with black-and-white images.

Torn Edges Reconstructs the image so that it appears composed of ragged, torn pieces of paper, and then colorizes the image using the foreground and background colors. This filter is particularly useful for text or high-contrast objects.

Water Paper Uses blotchy daubs that appear painted onto fibrous, damp paper, causing the colors to flow and blend.

Stylize filters

The Stylize filters produce a painted or impressionistic effect on a selection by displacing pixels and by finding and heightening contrast in an image. After using filters like Find Edges and Trace Contour that highlight edges, you can apply the Invert command to outline the edges of a color image with colored lines or to outline the edges of a grayscale image with white lines.

Diffuse Shuffles pixels in a selection to soften focus according to the selected option: Normal moves pixels randomly (ignoring color values), Darken Only replaces light pixels with darker ones, and Lighten Only replaces dark pixels with lighter ones. Anisotropic shuffles pixels in the direction of the least change in color.

Emboss Makes a selection appear raised or stamped by converting its fill color to gray and tracing the edges with the original fill color. Options include an embossing angle (from –360° to recess the surface, to +360° to raise the surface), height, and a percentage (1% to 500%) for the amount of color within the selection. To retain color and detail when embossing, use the Fade command after applying the Emboss filter.

Extrude Gives a 3D texture to a selection or layer. See Apply the Extrude filter .

Find Edges Identifies the areas of the image with significant transitions and emphasizes the edges. Like the Trace Counter filter, Find Edges outlines the edges of an image with dark lines against a white background and is useful for creating a border around an image.

Glowing Edges Identifies the edges of color and adds a neon-like glow to them. This filter can be applied cumulatively.

Solarize Blends a negative and a positive image—similar to exposing a photographic print briefly to light during development.

Tiles Breaks up an image into a series of tiles, creating an offset between the selection and its original position. You can choose one of the following to fill the area between the tiles: the background color, the foreground color, a reverse version of the image, or an unaltered version of the image, which puts the tiled version on top of the original and reveals part of the original image underneath the tiled edges.

Trace Contour Finds the transitions of major brightness areas and thinly outlines them for each color channel, for an effect similar to the lines in a contour map. See Apply the Trace Contour filter .

Wind Places tiny horizontal lines in the image to create a windblown effect. Methods include Wind; Blast, for a more dramatic wind effect; and Stagger, which offsets the lines in the image.

Texture filters

Use the Texture filters to simulate the appearance of depth or substance, or to add an organic look.

Craquelure Paints an image onto a high-relief plaster surface, producing a fine network of cracks that follow the contours of the image. Use this filter to create an embossing effect with images that contain a broad range of color or grayscale values.

Grain Adds texture to an image by simulating different kinds of grain—Regular, Soft, Sprinkles, Clumped, Contrasty, Enlarged, Stippled, Horizontal, Vertical, and Speckle, available from the Grain Type menu.

Mosaic Tiles Renders the image so that it appears to be made up of small chips or tiles and adds grout between the tiles. (In contrast, the Pixelate > Mosaic filter breaks up an image into blocks of different-colored pixels.)

Patchwork Breaks up an image into squares filled with the predominant color in that area of the image. The filter randomly reduces or increases the tile depth to replicate the highlights and shadows.

Stained Glass Repaints an image as single-colored adjacent cells outlined in the foreground color.

Texturizer Applies a texture you select or create to an image.

Video filters

The Video submenu contains the De-Interlace and NTSC Colors filters.

De-Interlace Smooths moving images captured on video by removing either the odd or even interlaced lines in a video image. You can choose to replace the discarded lines by duplication or interpolation.

NTSC Colors Restricts the gamut of colors to those acceptable for television reproduction, to prevent oversaturated colors from bleeding across television scan lines.

Other filters

Filters in the Other submenu let you create your own filters, use filters to modify masks, offset a selection within an image, and make quick color adjustments.

Custom Lets you design your own filter effect. With the Custom filter, you can change the brightness values of each pixel in the image according to a predefined mathematical operation known as convolution. Each pixel is reassigned a

value based on the values of surrounding pixels. This operation is similar to the Add and Subtract calculations for channels.

You can save the custom filters you create and use them with other Photoshop images. See Create a custom filter .

High Pass Retains edge details in the specified radius where sharp color transitions occur and suppresses the rest of the image. (A radius of 0.1 pixel keeps only edge pixels.) The filter removes low-frequency detail from an image and has an effect opposite to that of the Gaussian Blur filter.

It is helpful to apply the High Pass filter to a continuous-tone image before using the Threshold command or converting the image to Bitmap mode. The filter is useful for extracting line art and large black-and-white areas from scanned images.

Maximum and Minimum The Maximum and Minimum filters are useful for modifying masks. The Maximum filter has the effect of applying a spread (dilation)—spreading out white areas and choking in black areas. The Minimum filter has the effect of applying a choke (erosion)—shrinking white areas and spreading out the black areas. Like the Median filter, the Maximum and Minimum filters operate on selected pixels. Within a specified radius, the Maximum and Minimum filters replace the current pixel's brightness value with the highest or lowest brightness value of the surrounding pixels.

These filters, especially with larger radii, tend to promote either corners or curves in the image contours. In Photoshop CC, you can choose from the Preserve menu to favor squareness or roundness as you specify the radius value.



Offset Moves a selection a specified horizontal or vertical amount, leaving an empty space at the selection's original location. You can fill the empty area with the current background color, with another part of the image, or with your choice of fill if the selection is near the edge of an image.

Digimarc filters

The Digimarc filters embed a digital watermark into an image to store copyright information.

Note: *Digimarc plug-ins require a 32-bit operating system. They are unsupported in 64-bit versions of Windows and Mac OS.*

Vanishing Point

The Vanishing Point feature preserves correct perspective in edits of images that contain perspective planes (for instance, the sides of a building or any rectangular object).

More Help topics

Tutorial: Turn a photo into a painting

Tutorial: Blur the background for a focal point

Adjust image sharpness and blur

Work in Vanishing Point

Add Lighting Effects

Apply the Lighting Effects filter

The Lighting Effects filter lets you produce myriad lighting effects on RGB images. You can also use textures from grayscale files (called *bump maps*) to produce 3D-like effects and save your own styles for use in other images.

Note: *The Lighting Effects filter works only on 8-bit RGB images in Photoshop CC. You must have a supported video card to use Lighting Effects. For more information, see this FAQ .*

1 Choose Filter > Render > Lighting Effects.

2 From the Presets menu at upper left, choose a style.

3 In the preview window, select individual lights you want to adjust. Then, in the upper half of the Properties panel, do any of the following:

- Choose a light type (Spot, Infinite, or Point) from the top menu.
- Adjust color, intensity, and hotspot size.

To duplicate a light, Alt-drag (Windows) or Option-drag (Mac OS) the light within the preview window.

4 In the lower half of the Properties panel, adjust the entire set of lights with these options:

Colorize Click to tint the overall lighting.

Exposure Controls highlight and shadow detail.

Gloss Determines how much surfaces reflects light.

Metallic Determines which is more reflective: the light or the object on which the light is cast.

Ambience Diffuses the light as if it were combined with other light in a room, such as sunlight or fluorescent light. Choose a value of 100 to use only the light source, or a value of –100 to remove the light source.

Texture Applies a Apply a Texture channel.

From an Expert: Lighting Effects tutorials

Quickly master the dedicated Lighting Effects workspace. This tutorial from Dan Moughamian gives you a step-by-step tour.

Also, see this Lighting Effects overview video by Matt Kloskowski.

Lighting Effects types

You can choose from several lighting types:

Point Shines light in all directions from directly above the image—like a light bulb.

Infinite Shines light across an entire plane—like the sun.

Spot Casts an elliptical beam of light. The line in the preview window defines the light direction and angle, and the handles define the edges of the ellipse.

Adjust a Point light in the preview window

1 In the Properties panel, choose Point from the top menu.

2 In the preview window, adjust the light:

- To move the light, drag anywhere on the canvas.
- To change the spread of light (reflecting a light moving closer or farther away), drag the white section of the Intensity ring at the center.

An Intensity value of 100 is brightest, normal lighting is about 50, negative intensity takes away light, and –100 intensity produces no light.

Adjust an Infinite light in the preview window

1 In the Properties panel, choose Infinite from the top menu.

2 Adjust the light:

- To change the direction, drag the handle at the end of the line.
- To change brightness, drag the white section of the Intensity ring at the center of the light controls.

Adjust a Spot light in the preview window

1 At the top of the Properties panel, choose Spot.

2 In the preview window, adjust the light:

- To move the light, drag within the outer ellipse.
- To rotate the light, drag beyond the outer ellipse.
- To change the hotspot angle, drag the edge of the interior ellipse.
- To extend or shrink the ellipse, drag one of the four outer handles.
- To change how much of the ellipse is filled with light, drag the white section of the Intensity ring in the center.

Lighting Effects presets

Use the Presets menu in the Lighting Effects workspace to choose from 17 light styles. You can also create your own presets by adding lights to the Default setting. The Lighting Effects filter requires at least one light source. Only one light can be edited at a time, but all added lights are used to create the effect.

2 o'clock Spotlight A yellow spotlight of medium (17) intensity with a wide (91) focus.

Blue Omni A blue overhead omni light of full (85) intensity with no focus.

Circle Of Light Four spotlights. White has full (100) intensity and a concentrated (8) focus. Yellow has strong intensity (88) and a concentrated focus (3). Red has medium (50) intensity and a concentrated (0) focus. Blue has full (100) intensity and medium (25) focus.

Crossing A white spotlight of medium (35) intensity with a wide (69) focus.

Crossing Down Two white spotlights of medium (35) intensity with a wide (100) focus.

Default A white spotlight of medium intensity (35) with a wide focus (69).

Five Lights Down/Five Lights Up Five white spotlights, down or up, of full (100) intensity with a wide (60) focus.

Flashlight An omni yellow light of medium (46) intensity.

Flood Light A white spotlight of medium (35) intensity with a wide (69) focus.

Parallel Directional A directional blue light of full (98) intensity with no focus.

RGB Lights Red, blue, and green lights that produce a light of medium (60) intensity with a wide (96) focus.

Soft Direct Lights Two unfocused white and blue directional lights. White has a soft (20) intensity. Blue has a medium (67) intensity.

Soft Omni A soft omni light of medium (50) intensity.

Soft Spotlight A white spotlight of full (98) intensity with a wide (100) focus.

Three Down Three white spotlights of soft (35) intensity with a wide (96) focus.

Triple Spotlight Three spotlights of slight (35) intensity with a wide (100) focus.

Add or delete a light

? In the Lighting Effects workspace, do one of the following:

- At upper left, click the Lights icons to add Point, Spot, and Infinite types. Repeat as desired for a maximum of 16 lights.
- In the Lights panel (at lower right by default), drag a light to the Trash icon to delete it.

Create, save, or delete a Lighting Effects preset

? In the Lighting Effects dialog box, do one of the following:

- To create a preset, choose Custom from the Preset menu, and click the Lights icons to add Point, Spot, and Infinite types. Repeat as desired for a maximum of 16 lights.
- To save a preset, click Save, name the style, and click OK. Saved presets include all the settings for each light and appear in the Style menu whenever you open the image.
- To delete a preset, choose it, and then click Delete.

Apply a Texture channel

In the Lighting Effects workspace, the Texture channel lets you control lighting effects using grayscale images (called bump maps). You add bump maps to the image as alpha channels. You can add any grayscale image to your image as an alpha channel, or create an alpha channel and add texture to it. For an embossed text effect, use a channel with white text on a black background, or vice versa.

1 If necessary, add an alpha channel to your image. Do one of the following:
   - To use a texture based on another image (for example, fabric or water), convert that image to grayscale, then drag the grayscale channel from that image into the current image.
   - Drag an existing alpha channel from another image into the current image.
   - Create an alpha channel in your image, then add texture to it.
2 In the Lighting Effects workspace, choose a channel from the Texture menu in the Properties dialog box. (Choose either an alpha channel you've added or the image's Red, Green, or Blue channel.)
3 Drag the Height slider to vary the texture from Flat (0) to Mountainous (100).

More Help topics

Create and edit alpha channel masks

Add Lighting Effects

Use the Adaptive Wide Angle filter

Use the Adaptive Wide Angle filter to correct lens distortions due to using wide angle lenses. You can quickly straighten lines that appear curved in panoramas, or photos taken with fish-eye and wide angle lenses. For example, buildings seem to be leaning inwards when captured using a wide-angle lens.

The filter detects the camera and lens model and uses the lens characteristics to straighten the images. You can add multiple constraints to indicate straight lines in different parts of the picture. Using this information, the Adaptive Wide Angle filter removes the distortions.

You can also use this filter on images that do not contain camera and lens information, though it's some extra work.

If you want to edit the filter settings later, convert the layer to a smart object. Select the layer and choose Layers > Smart Objects > Convert to Smart Object.

Focal Length Specify the focal length of the lens. This value is automatically populated if the lens information is detected in the photograph.

Crop Factor Specify a value to determine how the final image is cropped. Use this value in combination with Scale to compensate for any blank areas that are introduced while applying the filter.

1 Choose Filter > Adaptive Wide Angle.
2 Choose a correction type:

   Fisheye Corrects extreme curvature caused by a fisheye lens.

   Perspective Corrects converging lines caused by angle of view and camera tilt.

   Panorama Corrects a Photomerge panorama.

   Full Spherical Corrects 360-degree panoramas. The panoramas must have a 2:1 aspect ratio.

Auto Detects the appropriate correction automatically.

3 Specify additional settings for filter. If the image has lens data, these values are automatically detected, and some options are not displayed.

Scale Specify a value to scale the image. Use this value to minimize the blank areas that are introduced after applying the filter.

Focal Length Specify the focal length of the lens. This value is automatically populated if the lens information is detected in the photograph.

Crop Factor Specify a value to determine how the final image is cropped. Use this value in combination with Scale to compensate for any blank areas that are introduced while applying the filter.

As Shot Enable this option to use the values as defined in the lens profile. This option is disabled if no lens information is found.

4 Define the constraints to indicate straight lines in the picture.

Do one of the following:

- Choose the **Constraint** tool, and drag a line across a key object to straighten.
- Choose the **Polygon Constraint** tool, and draw a polygon along the object to straighten.

The filter detects the curvature and draws a line that follows the contour of the object.

To constrain vertically or horizontally, press Shift while dragging the line. To define the orientation for an existing line, right-click the constraint line in the image, and choose an orientation from the pop-up menu.

After the wide-angle correction is complete, the picture may have several blank areas. You can Crop or remove part of an imageto remove such areas, or even use Fill and stroke selections, layers, and pathsto add content into that area.

More Help topics

Video | Lens Aware Adjustments by RC Conception

Video | Adaptive Wide Angle filter by Russell Brown

Use the Oil Paint filter

The Oil Paint filter lets you transform a photo into an image with the visual appearance of a classic oil painting. With a few simple sliders, you can adjust the amount of stylization, brush scale, cleanliness, and other parameters.

Work with the Oil Paint filter

Select Filter > Stylize > Oil Paint to use the filter. You can adjust the following settings for the filter:

Brush sliders

Stylization Adjusts the style of the strokes, ranging from a daubed look at 0 to smooth strokes at 10

Cleanliness Adjusts the length of the strokes, ranging from shortest & choppiest at 0 to longest & fluid at 10

Scale Adjusts the relief or apparent thickness of the paint, moving from a thin coat at 0 to a thick coat, giving luscious Vincent van Gogh-style paint globs, at 10

Bristle Detail Adjusts how much of the paintbrush-hair indentation is apparent, moving from soft at 0 to leaving strong grooves at 10

Lighting sliders

Angle Adjusts the incidence angle of the light (not the brushstroke). This setting is important if you are incorporating the oil painting into another scene.

Shine Adjusts the brightness of the light source and the amount of bounce off the paint's surface.

If the Oil Paint filter is disabled, check if your computer supports OpenCL v1.1 or higher. For more information, see the GPU FAQ .

Smudge image areas

The Smudge tool simulates the effect you see when you drag a finger through wet paint. The tool picks up color where the stroke begins and pushes it in the direction you drag.

1 Select the Smudge tool .
2 Choose a brush tip and options for the blending mode in the options bar.
3 Select Sample All Layers in the options bar to smudge using color data from all visible layers. If this is deselected, the Smudge tool uses colors from only the active layer.
4 Select Finger Painting in the options bar to smudge using the foreground color at the beginning of each stroke. If this is deselected, the Smudge tool uses the color under the pointer at the beginning of each stroke.
5 Drag in the image to smudge the pixels.

Press Alt (Windows) or Option (Mac OS) as you drag with the Smudge tool to use the Finger Painting option.

More Help topics

Retouching tools gallery

Chapter 16: Save and export

Supported file formats

Asterisks (*) indicate formats whose support was introduced in CS6.

The following formats can now be opened in Photoshop CC, CS6, and CS6 Extended.

Audio import formats

AAC* AIFF* M2A* M4A* MP2* MP3*

Video import formats

.264* 3GP, 3GPP* AVC* AVI F4V* FLV* MOV (QuickTime) MPE* MPEG-1 MPEG-4 MPEG-2 if a decoder is installed (for example, with an Adobe video suite) MTS* MXF* R3D* TS* VOB*

Video export formats

DPX* MOV (QuickTime) MP4

Graphic file formats

Photoshop PSD Large Document Format PSB BMP Cineon CompuServe GIF Photoshop DCS 1.0 Photoshop DCS 2.0 DICOM Photoshop EPS IFF format JPEG JPEG2000 OpenEXR PCX Photoshop PDF Pixar PNG Portable Bit Map Photoshop Raw Scitex CT Targa TIFF Wireless Bitmap Photoshop 2.0 (Mac only) PICT (read only) PICT Resource (Mac only, can open only) Radiance

3D-related formats

3D Studio (import only) DAE (Collada) Flash 3D* (export only) JPS* (JPEG Stereo) KMZ (Google Earth 4) MPO* (Multi-Picture format) U3D Wavefront|OBJ

Save files in graphics formats

As of the 2015 release of Photoshop CC, the File > Save For Web option has been moved to File > Export > Save For Web (Legacy) alongside newer export options.

To learn more about these new export options, see Export artboards, layers, and more.

You can easily save your Photoshop image files to a wide array of popular image formats.

Save in TIFF format

TIFF is a flexible raster (bitmap) image format supported by virtually all paint, image-editing, and page-layout applications.

1 Choose File > Save As, choose TIFF from the Format menu, and click Save.

2 In the TIFF Options dialog box, select the options you want, and click OK.

Bit depth (32-bit only) Specifies the bit depth (16, 24, or 32-bit) of the saved image.

Image Compression Specifies a method for compressing the composite image data. If you're saving a 32-bit TIFF file, you can specify that the file be saved with predictor compression, but you don't have the option to use JPEG compression. Predictor compression offers improved compression by rearranging floating point values, and works with both LZW and ZIP compression.

Note: *JPEG compression is available only for opaque RGB and grayscale images that are 8-bits-per-channel and no more than 30,000 pixels wide or high.*

Pixel Order Writes the TIFF file with the channels data interleaved or organized by plane. Previously, Photoshop always wrote TIFF files with the channel order interleaved. Theoretically, the Planar order file can be read and written faster, and offers a little better compression. Both channel orders are backward compatible with earlier versions of Photoshop.

Byte Order Selects the platform on which the file can be read. This option is useful when you don't know what program the file may be opened in. Photoshop and most recent applications can read files using either IBM PC or Macintosh byte order.

Save Image Pyramid Preserves multiresolution information. Photoshop does not provide options for opening multiresolution files; the image opens at the highest resolution within the file. However, Adobe InDesign and some image servers provide support for opening multiresolution formats.

Save Transparency Preserves transparency as an additional alpha channel when the file is opened in another application. Transparency is always preserved when the file is reopened in Photoshop.

Layer Compression Specifies a method for compressing data for pixels in layers (as opposed to composite data). Many applications cannot read layer data and skip over it when opening a TIFF file. Photoshop, however, can read layer data in TIFF files. Although files that include layer data are larger than those that don't, saving layer data eliminates the need to save and manage a separate PSD file to hold the layer data. Choose Discard Layers And Save A Copy if you want to flatten the image.

Note: *To have Photoshop prompt you before saving an image with multiple layers, select Ask Before Saving Layered TIFF Files in the File Handling area of the Preferences dialog box.*

Save in JPEG format

You can use the Save As command to save CMYK, RGB, and grayscale images in JPEG (*.jpg) format. JPEG compresses file size by selectively discarding data. You can also save an image as one or more JPEGs using the File > Export > Save For Web (Legacy) command.

JPEG supports only 8-bit images. If you save a 16-bit image to this format, Photoshop automatically lowers the bit depth.

To quickly save a medium-quality JPEG, play the Save As JPEG Medium action on the file. You can access this action by choosing Production from the Actions panel menu.

1 Choose File > Save As, and choose JPEG from the Format menu.

2 In the JPEG Options dialog box, select the options you want, and click OK.

Matte Offers matte color choices to simulate the appearance of background transparency in images that contain transparency.

Image Options Specifies the image quality. Choose an option from the Quality menu, drag the Quality pop-up slider, or enter a value between 0 and 12 in the Quality text box.

Format Options Specifies the format of your JPEG file. Baseline ("Standard") uses a format recognized by most web browsers. Baseline Optimized creates a file with optimized color and a slightly smaller file size. Progressive displays a series of increasingly detailed versions of the image (you specify how many) as it downloads. (Not all web browsers support optimized and Progressive JPEG images.)

Note: *Some applications may not be able to read a CMYK file saved in JPEG format. Likewise, if you find that a Java application can't read a JPEG file, try saving the file without a thumbnail preview.*

Save in PNG format

You can use the Save As command to save RGB, Indexed Color, Grayscale, and Bitmap mode images in PNG format.

1 Choose File > Save As, and choose PNG from the Format menu.

2 Select an Interlace option:

None Displays the image in a browser only when download is complete.

Interlaced Displays low-resolution versions of the image in a browser as the file downloads. Interlacing makes download time seem shorter, but it also increases file size.

3 Click OK.

Note: *Beginning with the Photoshop CC 2015 release, you can export artboards, layers, layer groups, or documents as JPEG, GIF, PNG, PNG-8, or SVG images. Select the items in the Layers panel, right-click the selection, and then select Quick Export or Export As from the context menu.*

Save in GIF format

You can use the Save As command to save RGB, Indexed Color, Grayscale, or Bitmap mode images directly in CompuServe GIF (known as GIF) format. The image is automatically converted to Indexed Color mode.

Note: *GIF is only available when the image is 8 Bits/Channel (it only supports 8 Bit/Channel).*

1 Choose File > Save As, and choose CompuServe GIF from the Format menu.

2 For RGB images, the Indexed Color dialog box appears. Specify conversion options and click OK.

3 Select a row order for the GIF file, and click OK:

Normal Displays the image in a browser only when download is complete.

Interlaced Displays low-resolution versions of the image in a browser as the file downloads. Interlacing makes download time seem shorter, but it also increases file size.

Note: *Beginning with the Photoshop CC 2015 release, you can export artboards, layers, layer groups, or documents as JPEG, GIF, PNG, PNG-8, or SVG images. Select the items in the Layers panel, right-click the selection, and then select Quick Export or Export As from the context menu.*

Save in Photoshop EPS format

Virtually all page-layout, word-processing, and graphics applications accept imported or placed EPS (Encapsulated PostScript) files. To print EPS files, you should use a PostScript printer. Non-PostScript printers will print only the screen-resolution preview.

1 Choose File > Save As, and choose Photoshop EPS from the Format menu.

2 In the EPS Options dialog box, select the options you want, and click OK:

Preview Creates a low-resolution image to view in the destination application. Choose TIFF to share an EPS file between Windows and Mac OS systems. An 8-bit preview is in color and a 1-bit preview is in black and white with a jagged appearance. An 8-bit preview creates a larger file size than a 1-bit preview. See also Bit depth.

Encoding Determines the way image data is delivered to a PostScript output device. Encoding options are described below.

Include Halftone Screen and Include Transfer Function Control print specifications for high-end commercial print jobs. Consult your printer before selecting these options.

Transparent Whites Displays white areas as transparent. This option is available only for images in Bitmap mode.

PostScript Color Management Converts file data to the printer's color space. Do not select this option if you plan to place the image in another color-managed document.

Note: *Only PostScript Level 3 printers support PostScript Color Management for CMYK images. To print a CMYK image using PostScript Color Management on a Level 2 printer, convert the image to Lab mode before saving in EPS format.*

Include Vector Data Preserves any vector graphics (such as shapes and type) in the file. However, vector data in EPS and DCS files is available only to other applications; vector data is rasterized if you reopen the file in Photoshop. This option is only available if your file contains vector data.

Image Interpolation Applies bicubic interpolation to smooth the low-resolution preview if printed.

Photoshop EPS encoding options

ASCII or ASCII85 Encodes if you're printing from a Windows system, or if you experience printing errors or other difficulties.

Binary Produces a smaller file and leaves the original data intact. However, some page-layout applications and some commercial print spooling and network printing software may not support binary Photoshop EPS files.

JPEG Compresses the file by discarding some image data. You can choose the amount of JPEG compression from very little (JPEG Maximum Quality) to a lot (JPEG Low Quality). Files with JPEG encoding can be printed only on Level 2 (or later) PostScript printers and may not separate into individual plates.

Save in Photoshop DCS format

DCS (Desktop Color Separations) format is a version of EPS that lets you save color separations of CMYK or multichannel files.

1 Choose File > Save As, and choose Photoshop DCS 1.0 or Photoshop DCS 2.0 from the Format menu.

2 In the DCS Format dialog box, select the options you want, and click OK.

The dialog box includes all the options available for Photoshop EPS files. Additionally, the DCS menu gives you the option of creating a 72-ppi composite file that can be placed in a page-layout application or used to proof the image:

DCS 1.0 format Creates one file for each color channel in a CMYK image. You can also create a fifth file: a grayscale or color composite. To view the composite file, you must keep all five files in the same folder.

DCS 2.0 format Retains spot color channels in the image. You can save the color channels as multiple files (as for DCS 1.0) or as a single file. The single-file option saves disk space. You can also include a grayscale or color composite.

Save in Photoshop Raw format

The Photoshop Raw format is a file format for transferring images between applications and computer platforms. The Photoshop Raw format is not the same as camera raw.

1 Choose File > Save As, and choose Photoshop Raw from the Format menu.

2 In the Photoshop Raw Options dialog box, do the following:

- (Mac OS) Specify values for File Type and File Creator, or accept the default values.
- Specify a Header parameter.
- Select whether to save the channels in an interleaved or non-interleaved order.

Save in BMP format

The BMP format is an image format for the Windows operating system. The images can range from black-and-white (1 bit per pixel) up to 24-bit color (16.7 million colors).

1 Choose File > Save As, and choose BMP from the Format menu.

2 Specify a filename and location, and click Save.

3 In the BMP Options dialog box, select a file format, specify the bit depth and, if necessary, select Flip Row Order. For more options, click Advanced Modes and specify the BMP options.

4 Click OK.

Save in Cineon format (16-bit images only)

RGB images that are 16 bits per channel can be saved in Cineon format for use in the Kodak Cineon Film System.

? Choose File > Save As and choose Cineon from the Format menu.

Save in Targa format

The Targa (TGA) format supports bitmap and RGB images with 8 Bits/Channel. It is designed for Truevision® hardware, but it is also used in other applications.

1 Choose File > Save As, and choose Targa from the Format menu.

2 Specify a filename and location, and click Save.

3 In the Targa Options dialog box, select a resolution, select the Compress (RLE) option if you want to compress the file, and then click OK.

More Help topics

About file compression

Extract assets

Convert a grayscale or RGB image to indexed color

TIFF

JPEG format

PNG format

GIF

Photoshop EPS format

Photoshop DCS 1.0 and 2.0 formats

Photoshop Raw format

BMP format

Cineon format

Targa

Save images

As of the 2015 release of Photoshop CC, the File > Save For Web option has been moved to File > Export > Save For Web (Legacy) alongside newer export options.

To learn about these new export options, see Export artboards, layers, and more.

Save a file

Use the Save command to save changes to the current file or the Save As command to save changes to a different file.

Save changes to the current file

? Choose File > Save.

The file remains in the current format.

Save a file with a different name, location, or format

1 Choose File > Save As.

Note: The Camera Raw plug-in can save camera raw image files in a different file format, such as Digital Negative (DNG).

2 Choose a format from the Format menu.

Note: If you choose a format that does not support all the features of the document, a warning will appear at the bottom of the dialog box. If you see this warning, it's best to save a copy of the file in Photoshop format or in another format that supports all of the image data.

3 Specify a filename and location.

4 In the Save As dialog box, select saving options.

5 Click Save.

A dialog box appears for choosing options when saving in some image formats.

To copy an image without saving it to your hard disk, use the Duplicate command. To store a temporary version of the image in memory, use the History panel to create a snapshot.

File saving options

You can set a variety of file saving options in the Save As dialog box. The availability of options depends on the image you are saving and the selected file format.

As A Copy Saves a copy of the file while keeping the current file open on your desktop.

Alpha Channels Saves alpha channel information with the image. Disabling this option removes the alpha channels from the saved image.

Layers Preserves all layers in the image. If this option is disabled or unavailable, all visible layers are flattened or merged (depending on the selected format).

Notes Saves notes with the image.

Spot Colors Saves spot channel information with the image. Disabling this option removes spot colors from the saved image.

Use Proof Setup, ICC Profile (Windows), or Embed Color Profile (Mac OS) Creates a color-managed document.

Note: *The following image preview and file extension options are available only if Ask When Saving is selected for the Image Previews and Append File Extension (Mac OS) options in the File Handling Preferences dialog box.*

Thumbnail (Windows) Saves thumbnail data for the file.

Use Lower Case Extension (Windows) Makes the file extension lowercase.

Image Previews options (Mac OS) Saves thumbnail data for the file. Thumbnails appear in the Open dialog box.

File Extension options (Mac OS) Specifies the format for file extensions. Select Append to add the format's extension to a filename and Use Lower Case to make the extension lowercase.

Set file saving preferences

1 Do one of the following:

- (Windows) Choose Edit > Preferences > File Handling.
- (Mac OS) Choose Photoshop > Preferences > File Handling.

2 Set the following options:

Image Previews Choose an option for saving image previews: Never Save to save files without previews, Always Save to save files with specified previews, or Ask When Saving to assign previews on a file-by-file basis. In Mac OS, you can select one or more preview types. (See Mac OS image preview options.)

File Extension (Windows) Choose an option for the three-character file extensions that indicate a file's format: Use Upper Case to append file extensions using uppercase characters, or Use Lower Case to append file extensions using lowercase characters.

Append File Extension (Mac OS) File extensions are necessary for files that you want to use on or transfer to a Windows system. Choose an option for appending extensions to filenames: Never to save files without file extensions, Always to append file extensions to filenames, or Ask When Saving to append file extensions on a file-by-file basis. Select Use Lower Case to append file extensions using lowercase characters.

Save As to Original Folder When saving, defaults to the folder images originated from. Deselect this option to instead default to the folder you last saved in.

Save in Background Background saving lets you keep working in Photoshop after you choose a Save command. You don't have to wait for Photoshop to finish saving the file.

Automatically Save Recovery Information Photoshop automatically stores crash-recovery information at the interval that you specify. If you experience a crash, Photoshop recovers your work when you restart it.

Mac OS image preview options

In Mac OS, you can select one or more of the following preview types (to speed the saving of files and minimize file size, select only the previews you need).

Icon Uses the preview as a file icon on the desktop.

Full Size Saves a 72-ppi version of the file for use in applications that can open only low-resolution Photoshop images. For non-EPS files, this is a PICT preview.

Macintosh Thumbnail Displays the preview in the Open dialog box.

Windows Thumbnail Saves a preview that Windows systems can display.

Save large documents

Photoshop supports documents up to 300,000 pixels in either dimension and offers three file formats for saving documents with images having more than 30,000 pixels in either dimension. Keep in mind that most other applications, including versions of Photoshop earlier than Photoshop CS, cannot handle files larger than 2 GB or images exceeding 30,000 pixels in either dimension.

? Choose File > Save As, and choose one of the following file formats:

Large Document Format (PSB) Supports documents of any file size. All Photoshop features are preserved in PSB files (though some plug-in filters are unavailable if documents exceed 30,000 pixels in width or height). Currently, PSB files are supported only by Photoshop CS and later.

Photoshop Raw Supports documents of any pixel dimension or file size, but does not support layers. Large documents saved in the Photoshop Raw format are flattened.

TIFF Supports files up to 4 GB in size. Documents larger than 4 GB cannot be saved in TIFF format.

Export layers to files

You can export and save layers as individual files using a variety of formats, including PSD, BMP, JPEG, PDF, Targa, and TIFF. Layers are named automatically as they are saved. You can set options to control the generation of names.

1. Choose File > Export > Export Layers To Files.
2. In the Export Layers To Files dialog box, under Destination, click Browse to select a destination for the exported files. By default, the generated files are saved in the sample folder as the source file.
3. Enter a name in the File Name Prefix text box to specify a common name for the files.
4. Select the Visible Layers Only option if you want to export only those layers that have visibility enabled in the Layers panel. Use this option if you don't want all the layers exported. Turn off visibility for layers that you don't want exported.
5. Choose a file format from the File Type menu. Set options as necessary.
6. Select the Include ICC Profile option if you want the working space profile embedded in the exported file. This is important for color-managed workflows.
7. Click Run.

More Help topics

Duplicate an image

Large Document Format (PSB)

Photoshop Raw format

TIFF

File formats

Note: *If a supported file format does not appear in the appropriate dialog box or submenu, you may need to install the format's plug-in module.*

Choosing a file format

Graphics file formats differ in the way they represent image data (as pixels or vectors), and support different compression techniques and Photoshop features. To preserve all Photoshop features (layers, effects, masks, and so on), save a copy of your image in Photoshop format (PSD).

Like most file formats, PSD supports files up to 2 GB in size. For files larger than 2 GB, save in Large Document Format (PSB), Photoshop Raw (flattened image only), TIFF (up to 4 GB), or DICOM format.

The standard bit depth for images is 8 bits per channel. To achieve greater dynamic range with 16- or 32-bit images, use the following formats:

Formats for 16-bit images (requires Save As command)

Photoshop, Large Document Format (PSB), Cineon, DICOM, IFF, JPEG, JPEG 2000, Photoshop PDF, Photoshop Raw, PNG, Portable Bit Map, and TIFF.

Note: *The Save For Web & Devices command automatically converts 16-bit images to 8-bit.*

Formats for 32-bit images (requires Save As command)

Photoshop, Large Document Format (PSB), OpenEXR, Portable Bitmap, Radiance, and TIFF.

About file compression

Many file formats use compression to reduce the file size of bitmap images. *Lossless* techniques compress the file without removing image detail or color information; *lossy* techniques remove detail. The following are commonly used compression techniques:

RLE (Run Length Encoding) Lossless compression; supported by some common Windows file formats.

LZW (Lemple-Zif-Welch) Lossless compression; supported by TIFF, PDF, GIF, and PostScript language file formats. Most useful for images with large areas of single color.

JPEG (Joint Photographic Experts Group) Lossy compression; supported by JPEG, TIFF, PDF, and PostScript language file formats. Recommended for continuous-tone images, such as photographs. JPEG uses lossy compression. To specify image quality, choose an option from the Quality menu, drag the Quality pop-up slider, or enter a value between 0 and 12 in the Quality text box. For the best printed results, choose maximum-quality compression. JPEG files can be printed only on Level 2 (or later) PostScript printers and may not separate into individual plates.

CCITT A family of lossless compression techniques for black-and-white images, supported by the PDF and PostScript language file formats. (CCITT is an abbreviation for the French spelling of International Telegraph and Telekeyed Consultive Committee.)

ZIP Lossless compression; supported by PDF and TIFF file formats. Like LZW, ZIP compression is most effective for images that contain large areas of single color.

Maximize compatibility for PSD and PSB files

If you work with PSD and PSB files in older versions of Photoshop or applications that don't support layers, you can add a flattened version of the image to the saved file.

Note: *If you save an image in an earlier version of Photoshop, features that version doesn't support are discarded.*

1 Choose Edit > Preferences > File Handling (Windows) or Photoshop > Preferences > File Handling (Mac OS).

2 From the Maximize PSD and PSB File Compatibility menu, choose any of the following:

Always Saves a composite (flattened) image along with the layers of your document.

Ask Asks whether to maximize compatibility when you save.

Never Saves only a layered image.

Choose Ask or Never if you want to significantly reduce file size.

Photoshop format (PSD)

Photoshop format (PSD) is the default file format and the only format, besides the Large Document Format (PSB), that supports all Photoshop features. Because of the tight integration between Adobe products, other Adobe applications, such as Adobe Illustrator, Adobe InDesign, Adobe Premiere, Adobe After Effects, and Adobe GoLive, can directly import PSD files and preserve many Photoshop features. For more information, see Help for the specific Adobe applications.

When saving a PSD, you can set a preference to maximize file compatibility. This saves a composite version of a layered image in the file so it can be read by other applications, including previous versions of Photoshop. It also maintains the appearance of the document, just in case future versions of Photoshop change the behavior of some features. Including the composite also makes the image much faster to load and use in applications other than Photoshop, and may sometimes be required to make the image readable in other applications.

You can save 16-bits-per-channel and high dynamic range (HDR) 32-bits-per-channel images as PSD files.

Photoshop 2.0 format

(Mac OS) You can use this format to open an image in Photoshop 2.0 or to export an image to an application supporting only Photoshop 2.0 files. Saving in Photoshop 2.0 format flattens your image and discards layer information.

Photoshop DCS 1.0 and 2.0 formats

Desktop Color Separations (DCS) format is a version of the standard EPS format that lets you save color separations of CMYK images. You can use DCS 2.0 format to export images containing spot channels. To print DCS files, you must use a PostScript printer.

Photoshop EPS format

Encapsulated PostScript (EPS) language file format can contain both vector and bitmap graphics and is supported by virtually all graphics, illustration, and page-layout programs. EPS format is used to transfer PostScript artwork between applications. When you open an EPS file containing vector graphics, Photoshop rasterizes the image, converting the vector graphics to pixels.

EPS format supports Lab, CMYK, RGB, Indexed Color, Duotone, Grayscale, and Bitmap color modes, and does not support alpha channels. EPS does support clipping paths. Desktop Color Separations (DCS) format, a version of the standard EPS format, lets you save color separations of CMYK images. You use DCS 2.0 format to export images containing spot channels. To print EPS files, you must use a PostScript printer.

Photoshop uses the EPS TIFF and EPS PICT formats to let you open images saved in file formats that create previews but are not supported by Photoshop (such as QuarkXPress). You can edit and use an opened preview image just as any other low-resolution file. An EPS PICT preview is available only in Mac OS.

Note: *EPS TIFF format and EPS PICT format are more relevant to earlier versions of Photoshop. The current version of Photoshop includes rasterization features for opening files that include vector data.*

Photoshop Raw format

The Photoshop Raw format is a flexible file format for transferring images between applications and computer platforms. This format supports CMYK, RGB, and grayscale images with alpha channels, and multichannel and Lab images without alpha channels. Documents saved in the Photoshop Raw format can be of any pixel or file size, but they cannot contain layers.

The Photoshop Raw format consists of a stream of bytes describing the color information in the image. Each pixel is described in binary format, with 0 representing black and 255 white (for images with 16-bit channels, the white value is 65535). Photoshop designates the number of channels needed to describe the image, plus any additional channels in the image. You can specify the file extension (Windows), file type (Mac OS), file creator (Mac OS), and header information.

In Mac OS, the file type is generally a four-character ID that identifies the file—for example, TEXT identifies the file as an ASCII text file. The file creator is also generally a four-character ID. Most Mac OS applications have a unique file creator ID that is registered with the Apple Computer Developer Services group.

The Header parameter specifies how many bytes of information appear in the file before actual image information begins. This value determines the number of zeroes inserted at the beginning of the file as placeholders. By default, there is no header (header size = 0). You can enter a header when you open the file in Raw format. You can also save the file without a header and then use a file-editing program, such as HEdit (Windows) or Norton Utilities (Mac OS), to replace the zeroes with header information.

You can save the image in an interleaved or non-interleaved format. If you choose interleaved, the color values (red, green, and blue, for example) are stored sequentially. Your choice depends on requirements of the application that will open the file.

Note: *A Photoshop Raw image is not in the same file format as a camera raw image file from a digital camera. A camera raw image file is in a camera-specific proprietary format that is essentially a "digital negative," with no filtering, white balance adjustments, or other in-camera processing.*

Digital Negative format (DNG)

Digital Negative (DNG) is a file format that contains the raw image data from a digital camera and metadata that defines what the data means. DNG, Adobe's publicly available, archival format for camera raw files, is designed to provide compatibility and decrease the current proliferation of camera raw file formats. The Camera Raw plug-in can save camera raw image data in the DNG format. For more information about the Digital Negative (DNG) file format, visit www.adobe.com and search for the term "Digital Negative." You'll find comprehensive information and a link to a user forum.

BMP format

BMP is a standard Windows image format on Windows-compatible computers. BMP format supports RGB, Indexed Color, Grayscale, and Bitmap color modes. You can specify either Windows or OS/2 format and a bit depth of 8 bits/channel. For 4-bit and 8-bit images using Windows format, you can also specify RLE compression.

BMP images are normally written bottom to top; however, you can select the Flip Row Order option to write them from top to bottom. You can also select an alternate encoding method by clicking Advanced Modes. (Flip Row Order and Advanced Modes are most relevant to game programmers and others using DirectX.)

Cineon format

Developed by Kodak, Cineon is a 10-bits-per-channel digital format suitable for electronic composition, manipulation, and enhancement. Using the Cineon format, you can output back to film with no loss of image quality. The format is used in the Cineon Digital Film System, which transfers images originated on film to the Cineon format and back to film.

DICOM format

The DICOM (Digital Imaging and Communications in Medicine) format is commonly used for the transfer and storage of medical images, such as ultrasounds and scans. DICOM files contain both image data and headers, which store information about the patient and the medical image.

GIF

Graphics Interchange Format (GIF) is the file format commonly used to display indexed-color graphics and images in HTML documents. GIF is an LZW-compressed format designed to minimize file size and electronic transfer time. GIF format preserves transparency in indexed-color images; however, it does not support alpha channels.

IFF

IFF (Interchange File Format) is a general-purpose data storage format that can associate and store multiple types of data. IFF is portable and has extensions that support still-picture, sound, music, video, and textual data. The IFF format includes Maya IFF and IFF (formerly Amiga IFF).

JPEG format

Joint Photographic Experts Group (JPEG) format is commonly used to display photographs and other continuous-tone images in HTML documents. JPEG format supports CMYK, RGB, and Grayscale color modes, and does not support transparency. Unlike GIF format, JPEG retains all color information in an RGB image but compresses file size by selectively discarding data.

A JPEG image is automatically decompressed when opened. A higher level of compression results in lower image quality, and a lower level of compression results in better image quality. In most cases, the Maximum quality option produces a result indistinguishable from the original.

Large Document Format (PSB)

The Large Document Format (PSB) supports documents up to 300,000 pixels in any dimension. All Photoshop features, such as layers, effects, and filters, are supported. (With documents larger than 30,000 pixels in width or height, some plug-in filters are unavailable.)

You can save HDR, 32-bits-per-channel images as PSB files.

Note: *Most other applications and older versions of Photoshop cannot support documents with file sizes larger than 2 GB.*

OpenEXR format

OpenEXR (EXR) is a file format used by the visual effects industry for HDR images. The film format has high color fidelity and a dynamic range suitable for use in motion picture production. Developed by Industrial Light and Magic, OpenEXR supports multiple lossless or lossy compression methods. An OpenEXR file supports transparency and works only with 32 bits/channel images; the file format stores the values as 16 bits/channel floating point.

PDF

Portable Document Format (PDF) is a flexible, cross-platform, cross-application file format. Based on the PostScript imaging model, PDF files accurately display and preserve fonts, page layouts, and both vector and bitmap graphics. In addition, PDF files can contain electronic document search and navigation features such as electronic links. PDF supports 16-bits-per-channel images. Adobe Acrobat also has a Touch Up Object tool for minor editing of images in a PDF. For more information about working with images in PDFs, see Acrobat Help.

Note: *The Touch Up Object tool is mainly for last-minute revisions to images and objects. It's best to do image editing in Photoshop before saving as PDF.*

Photoshop recognizes two types of PDF files:

Photoshop PDF files Created when Preserve Photoshop Editing Capabilities is selected in the Save Adobe PDF dialog box. Photoshop PDF files can contain only a single image.

Photoshop PDF format supports all color modes (except Multichannel) and features that are supported in standard Photoshop format. Photoshop PDF also supports JPEG and ZIP compression, except for Bitmap-mode images, which use CCITT Group 4 compression.

Standard PDF files Created when Preserve Photoshop Editing Capabilities is *deselected* in the Save Adobe PDF dialog box, or by using another application such as Adobe Acrobat or Illustrator. Standard PDF files can contain multiple pages and images.

When you open a standard PDF file, Photoshop rasterizes vector and text content, while preserving pixel content.

PICT File

PICT format is used in Mac OS graphics and page-layout applications as an intermediary file format for transferring images between applications. PICT format supports RGB images with a single alpha channel and Indexed Color, Grayscale, and Bitmap mode images without alpha channels.

Though Photoshop can open raster PICT files, it cannot open QuickDraw PICTs or save to PICT format.

PICT Resource

(Mac OS) A PICT resource is a PICT file but takes a name and resource ID number. The PICT Resource format supports RGB images with a single alpha channel, and Indexed Color, Grayscale, and Bitmap mode images without alpha channels.

You can use the Import command or the Open command to open a PICT resource. However, Photoshop cannot save to this format.

Pixar format

The Pixar format is designed specifically for high-end graphics applications, such as those used for rendering three-dimensional images and animation. Pixar format supports RGB and grayscale images with a single alpha channel.

PNG format

Developed as a patent-free alternative to GIF, Portable Network Graphics (PNG) format is used for lossless compression and for display of images on the web. Unlike GIF, PNG supports 24-bit images and produces background transparency without jagged edges; however, some web browsers do not support PNG images. PNG format supports RGB, Indexed Color, Grayscale, and Bitmap mode images without alpha channels. PNG preserves transparency in grayscale and RGB images.

Portable Bit Map format

The Portable Bit Map (PBM) file format, also known as Portable Bitmap Library and Portable Binary Map, supports monochrome bitmaps (1 bit per pixel). The format can be used for lossless data transfer because many applications support this format. You can even edit or create such files within a simple text editor.

The Portable Bit Map format serves as the common language of a large family of bitmap conversion filters including Portable FloatMap (PFM), Portable Graymap (PGM), Portable Pixmap (PPM), and Portable Anymap (PNM). While the PBM file format stores monochrome bitmaps, PGM additionally stores grayscale bitmaps, and PPM can also store color bitmaps. PNM is not a different file format in itself, but a PNM file can hold PBM, PGM, or PPM files. PFM is a floating-point image format that can be used for 32-bits-per-channel HDR files.

Radiance format

Radiance (HDR) is a 32-bits-per-channel file format used for HDR images. This format was originally developed for the Radiance system, a professional tool for visualizing lighting in virtual environments. The file format stores the quantity of light per pixel instead of just the colors to be displayed onscreen. The levels of luminosity accommodated by the Radiance format are far higher than the 256 levels in 8-bits-per-channel image file formats. Radiance (HDR) files are often used in 3D modeling.

Scitex CT

Scitex Continuous Tone (CT) format is used for high-end image processing on Scitex computers. Contact Creo to obtain utilities for transferring files saved in Scitex CT format to a Scitex system. Scitex CT format supports CMYK, RGB, and grayscale images and does not support alpha channels.

CMYK images saved in Scitex CT format often have extremely large file sizes. These files are generated for input using a Scitex scanner. Images saved in Scitex CT format are printed to film using a Scitex rasterizing unit, which produces separations using a patented Scitex halftoning system. This system produces very few moiré patterns and is often demanded in professional color work—for example, ads in magazines.

TIFF

Tagged-Image File Format (TIFF, TIF) is used to exchange files between applications and computer platforms. TIFF is a flexible bitmap image format supported by virtually all paint, image-editing, and page-layout applications. Also, virtually all desktop scanners can produce TIFF images. TIFF documents have a maximum file size of 4 GB.

TIFF format supports CMYK, RGB, Lab, Indexed Color, and Grayscale images with alpha channels and Bitmap mode images without alpha channels. Photoshop can save layers in a TIFF file; however, if you open the file in another application, only the flattened image is visible. Photoshop can also save notes, transparency, and multiresolution pyramid data in TIFF format.

In Photoshop, TIFF image files have a bit depth of 8, 16, or 32 bits per channel. You can save HDR images as 32-bits-per-channel TIFF files.

WBMP format

WBMP format is the standard format for optimizing images for mobile devices, such as cell phones. WBMP supports 1-bit color, which means that WBMP images contain only black and white pixels.

More Help topics

Save large documents

About plug-in modules

Save a camera raw image in another format

DICOM files

Save and export video and animations

Note: *For Photoshop versions earlier than Photoshop CC, some functionality discussed in this article may be available only if you have Photoshop Extended. Photoshop CC does not have a separate Extended offering. All features in Photoshop Extended are part of Photoshop CC.*

After you've created video or animation content in Photoshop, you can easily optimize, render, and export it.

Video and animation export formats

You can save animations as GIF files for viewing on the web. Videos and animations can be saved as QuickTime movies or PSD files. If you're not rendering your work to video, then saving the file as PSD is best because it preserves the edits and saves the file in a format that's supported by Adobe digital video applications and many motion picture editing applications.

Optimize animation frames

After you complete your animation, optimize it for efficient download to a web browser. You optimize an animation in two ways:

- Optimize the frames to include only areas that change from frame to frame. This greatly reduces the file size of the animated GIF file.

- If you are saving your animation as a GIF image, optimize it as you would any GIF image. A special dithering technique is applied to animations to ensure that dither patterns are consistent across all frames and to prevent flickering during playback. Due to these additional optimization functions, more time may be required to optimize an animated GIF than to optimize a standard GIF.

When optimizing the colors in an animation, use the Adaptive, Perceptual, or Selective palette. This ensures that the colors are consistent across frames.

1 Make sure that the Timeline panel is in the frame animation mode.

2 Choose Optimize Animation from the panel menu.

3 Set the following options:

Bounding Box Crops each frame to the area that has changed from the preceding frame. Animation files created using this option are smaller but are incompatible with GIF editors that do not support the option. (This option is selected by default and is recommended.)

Redundant Pixel Removal Makes all pixels transparent in a frame that are unchanged from the preceding frame. The Transparency option in the Optimize panel must be selected for redundant pixel removal to work. (This option is selected by default and is recommended.)

Note: *Set the frame disposal method to Automatic when using the Redundant Pixel Removal option. (See Choose a frame disposal method.)*

4 Click OK.

Flatten frames into layers

When you flatten frames into layers, a single layer is created for each frame in a video layer. This can be useful, for example, if you're exporting the individual video frames as separate image files, or if you're planning to use the video of a static object in an image stack.

1 In the Timeline or Layers panel, select the video layer.

2 In the Timeline panel, choose Flatten Frames Into Layers from the panel menu.

Export video files or image sequences

1 Choose File > Export > Render Video.

2 In the Render Video dialog box, enter a name for the video or image sequence.

3 Click the Select Folder button, and navigate to the location for the exported files.

To create a folder to contain your exported file, select the Create New Subfolder option and enter a name for the subfolder.

4 Choose either Adobe Media Encoder or Photoshop Image Sequence from the menu below the Location section of the Render Video dialog box. Then choose a file format from the pop-up menu. If you chose Adobe Media Encoder, you have the choice of CPS, H.264, and QuickTime formats.

5 (Optional) Specify format-specific options from the menus below the file format menu.

6 (Optional) If you chose Image Sequence in step 4, specify the Starting and Digits numbers. (These options specify the numbering system for the exported files.) Then do any of the following if necessary:

- Choose from the Size pop-up menu to specify the pixel dimensions for the exported files.
- Click the Settings button and specify the format-specific options.

- Choose a frame rate from the Document Frame Rate menu.

7 Under Range, select one of the following options:

All Frames Renders all the frames in the Photoshop document.

Start Frame and End Frame Specify the sequence of frames to render.

Work Area Renders the frames selected by the work area bar in the Timeline panel.

In Frame and Out Frame (Photoshop Extended) Specify the sequence of frames to render.

Currently Selected Frames (Photoshop Extended) Renders the frames selected by the work area bar in the Animation panel.

Note: *The available Range options depend on the file format you chose.*

8 (Optional) Specify render options:

Alpha Channel Specifies how alpha channels are rendered. (This option is available only with formats that support alpha channels, such as PSD or TIFF). Select None to ignore the alpha channel, Straight-Unmatted to include the channel, or one of the Premultiplied options to mix a matte color with the color channels.

3D Quality Controls how surfaces are rendered if your project includes 3D objects. Interactive is suitable for video games and similar uses. Ray Traced Draft is low quality but lets the video render qucikly. Ray Traced Final is high quality but the video takes a long time to render.

Frame Rate Determines how many frames are created for each second of the video or animation. The Document Frame Rate option reflects the rate in Photoshop. If you're exporting to a different video standard (from NTSC to PAL, for example), choose the appropriate rate from the pop-up menu.

9 Click Render.

QuickTime export file formats (Photoshop Extended)

3G A file format developed for third-generation mobile devices.

FLC An animation format for playback of computer-generated animations on workstations, Windows, and Mac OS. This format is also referred to as FLI.

Flash Video (FLV) Adobe Flash Video is the Adobe format for streaming audio and video over the web and other networks. (To use this format, you must first install an FLV QuickTime encoder).

QuickTime Movie The Apple Computer multimedia architecture that includes a number of codecs. (To export audio, you must use this format.)

AVI Audio Video Interleave (AVI) is a standard format for audio and video data on Windows computers.

DV Stream A video format with intraframe compression that uses FireWire (IEEE 1394) interface to transfer video to nonlinear editing systems.

Image Sequence A sequence of still images that can reside within one folder and use the same numeric or alphabetic filename pattern (such as Sequence1, Sequence2, Sequence3, and so on).

MPEG-4 A multimedia standard for delivering audio and video streams over a range of bandwidths.

Note: *Photoshop also supports other third-party formats such as Avid AVR codecs; however, the necessary QuickTime codecs must be installed.*

Understanding QuickTime key frames

In QuickTime terminology, the term *key frames* refers to something different than the animation keyframes in Photoshop. In QuickTime, key frames occur at regular intervals in the movie and are stored as complete frames. Each intermediate frame that separates them is compared to the previous frame, and only changed data is stored. Using key frames greatly reduces movie size and greatly increases the memory required to edit and render a movie. Shorter intervals between key frames enable faster seeking and reverse playback, but can significantly increase the size of the file.

3G export settings (Photoshop Extended)

For more information on 3G settings, search for 3G on the Apple Computer website.

File Format 3GPP and 3GPP2 are standards for the creation, delivery, and playback of multimedia over third-generation high-speed wireless networks. 3GPP is for GSM networks and 3GPP2 is for CDMA 2000 networks. 3GPP (Mobile MP4), 3GPP2 (EZmovie), and AMC (EZmovie) are for specific networks. 3GPP (Mobile MP4) is for NTT DoCoMo's i-motion 3G service. 3GPP2 (EZmovie) is for KDDI's 3G network service. AMC (EZmovie) is for KDDI subscribers with AMC-capable phones.

Video Choose Video from the pop-up menu below the File Format menu and specify the following:

Video Format Selects the codec used during video export. If your source movie has only one video track and it is already compressed, you can choose Pass Through so that the video doesn't get compressed again.

Data Rate Specifies the kilobits per second (kbps) during playback. A higher kbps rate usually improves movie playback quality; however, don't choose a data rate higher than the available bandwidth.

Optimized For Specifies the intended delivery method if you choose H.264 from the Video Format menu, click Video Options, and select Best Quality. This setting tells the codec how much the data rate can vary above and below the data rate you choose.

Image Size Specifies a standard for sending the file to a mobile phone. Current maintains the source material size; the resulting file may not play on a mobile phone. Choose Custom to specify a size not listed in the menu.

Preserve Aspect Ratio Using Specifies an option when you're changing the image size and the movie must be scaled to the new dimensions. Letterbox scales the source proportionally to fit into the clean aperture, adding black bars to the top and bottom or sides as necessary. Crop centers, scales, and trims to the clean aperture.

Frame Rate Specifies the frames per second (fps) during playback. In most cases, your video looks better if you choose a number that your source fps is exactly divisible by. For example, if your source is captured at 30 fps, choose a frame rate of 10 or 15. Don't choose a rate larger than that of your source material.

Key Frame Specifies how frequently key frames are created in the exported video. A higher key frame rate (lower number) improves video quality, but increases the file size.

Video Options If available, click the Video Options button to open the 3G Advanced Video Settings dialog box. Depending on the video, you can specify whether to add re-sync markers inside the video frames to help with packet loss recovery when streaming. With H.264 video, you can also speed up the compression process (for preview purposes, for example) by choosing Faster Encode (Single-pass). The default option, Best Quality (Multi-pass), allows the codec to determine how many passes are needed to compress the data for the best quality.

Audio All audio options are disabled because Photoshop Extended does not include audio in exported 3G files.

Text All text options are disabled because Photoshop Extended does not include text tracks in exported 3G files.

Streaming Choose Streaming from the pop-up menu below the File Format menu and specify the following:

Enable Streaming Creates a file for RTSP streaming to QuickTime Player. This option creates a hint track (instructions necessary for streaming a file).

Optimize For Server Helps the server to process the file faster, but increases the file size.

Advanced Choose Advanced from the pop-up menu below the File Format menu and specify the following:

Restrict Distribution Specifies how many times the file can play back on the handset once downloaded. Also specifies file expiration options: set the file to expire in a number of days or enter a date. If your file is in Mobile MP4 or EZmovie format, you can restrict distribution so that once the file is on a handset it can't be sent or copied elsewhere.

Fragment Movie Enables the file to download via HTTP in small pieces so that playback can start faster and so that larger files can be played on the handset (only the fragment, not the entire movie, must fit on the handset at one time).

FLC export settings (Photoshop Extended)

The following options are available in the FLC Export Settings dialog box:

Color Table Specifies the color table using the Windows system colors or Mac OS system colors in the exported movie.

Motion Sets the playback frame rate.

Specify AVI export settings (Photoshop Extended)

1. In the Render Video dialog box, select QuickTime Export and then choose AVI from the pop-up menu.
2. Click the Settings button.
3. In the AVI Settings dialog box, make sure Video is selected.

   Note: *Sound options are disabled because Photoshop Extended does not include audio in exported AVI files.*

4. Under Video, click the Settings button and set the following:

   Compression Type Chooses the video compressor (codec) to compress your video.

   Frame Per Second Specifies the number of individual images shown every second. NTSC is generally the standard video format and is 29.97 fps. PAL is a European video format that is 25 fps. The standard for film is 24 fps. QuickTime movies are sometimes created with a slower frame rate to reduce bandwidth and CPU requirements.

   Movies with higher frame rates display motion better, but have larger file sizes. If you choose a frame rate that's lower than the movie's current frame rate, frames are deleted. If you choose a number that's higher than the movie's current frame rate, existing frames are duplicated (not recommended, since it increases file size without improving quality). In most cases, your video will look better if you choose a number that your source fps is exactly divisible by. For example, if your source is captured at 30 fps, choose a frame rate of 10 or 15. Don't choose a rate larger than that of your source material.

   Key Frame Every Specifies the key frame frequency. A higher key frame rate (lower number) improves video quality, but increases the file size. With some compressors, an additional key frame is inserted automatically if too much of the image has changed from one frame to the next. In general, one key frame every 5 seconds (multiply the frames per second by 5) is usually sufficient. If you are creating a file for RTSP streaming and have concerns about the reliability of the delivery network, you may want to increase key frame frequency to one key frame every 1 or 2 seconds.

   Limit Data Rate To Specifies the kilobits per second (kbps) during playback. A higher kbps rate usually improves movie playback quality; however, don't choose a data rate higher than the available bandwidth.

   Depth Specifies the number of colors to include in video that you export. This menu is not available if the selected codec supports only one color depth.

   Quality If available, drag the slider or type a value to adjust the exported video's picture quality and, consequently, its file size. If you are using the same codec to capture and export, and you've rendered previews of a sequence, you

can save rendering time by matching the export quality setting with your original capture quality setting. Increasing quality above the original capture quality does not increase quality, but may result in longer rendering times.

Scan Mode Specifies whether the exported movie has fields (Interlaced) or no fields (Progressive).

Aspect Ratio Specifies a 4:3 or 16:9 aspect ratio for the exported movie.

Options (Intel Indeo® Video 4.4 only) Sets compression, transparency options, and access for the Intel Indeo® Video 4.4 codec.

DV Stream export settings (Photoshop Extended)

The following options are available in the DV Export Settings dialog box:

DV Format Specifies either the DV or DVCPRO format for your exported video.

Video Format Specifies either NTSC or PAL video broadcast standard.

Scan Mode Specifies whether the exported video has interlaced fields or no fields (Progressive Scan).

Aspect Ratio Specifies an aspect ratio of 4:3 or 16:9.

Preserve Aspect Ratio Using Specifies an option if the movie is scaled to new pixel dimensions. Letterbox scales the source proportionally to fit into the clean aperture, adding black bars to the top and bottom or sides as necessary. Crop centers, scales, and trims to the clean aperture.

Note: *Although the DV Export Settings dialog box has Audio Format options, Photoshop Extended does not export audio in DV files.*

Image sequence settings for QuickTime export (Photoshop Extended)

Typically, QuickTime is used to export video files. However, you can also select Image Sequence from the QuickTime Export pop-up menu. Click Settings to access the following options:

Format Chooses a file format for the exported images.

Frames Per Second Sets the frame rate for the image sequence.

Insert Space Before Number Inserts a space between the name and generated number in the image's filename.

Options If available, click the Options button and set format-specific options.

For more information on the specific file formats and their options, see also Saving and exporting images and File formats.

Specify MPEG4 export settings (Photoshop Extended)

1. In the Render Video dialog box, select QuickTime Export, and choose MPEG-4 from the pop-up menu. Then click Settings.
2. In the MPEG-4 Export Settings dialog box, choose MP4 or MP4 (ISMA) from the File Format menu. The MP4 (ISMA) format ensures operability with devices made by ISMA members.
3. Under Video, specify the following:

   Video Format Chooses the codec to compress your video. For the highest quality at the lowest data rate (or the smallest file), H.264 is recommended. If you need the file to play on a device that supports MPEG-4 video, choose MPEG-4 Basic or MPEG-4 Improved, depending on the target device. If your source movie's video track is already compressed, you can choose Pass Through so that the video doesn't get compressed again.

   Data Rate Specifies the kilobits per second (kbps) during playback. A higher kbps rate usually improves movie playback quality; however, don't choose a data rate higher than the available bandwidth.

Optimized For Specifies how much the data rate can vary above and below the data rate you choose. This option becomes available if you choose MP4 from the File Format menu, choose H.264 from the Video Format menu, click Video Options, and select Best Quality.

Image Size Specifies the pixel dimensions of your exported video. Current maintains the source material size. To specify a size not listed in the Image Size menu, choose Custom.

Preserve Aspect Ratio Using Specifies an option if the movie needs to be scaled to the new pixel dimensions. Letterbox scales the source proportionally to fit into the clean aperture, adding black bars to the top and bottom or sides as necessary. Crop centers, scales, and trims to the clean aperture. Fit Within Size adjusts to the destination size by fitting to the longest side, scaling if necessary.

Frame Rate Specifies the frame rate for the playback of your exported video. Usually, your video looks better if you choose a number that is exactly divisible by the frames per second (fps) of your source. For example, if your source is captured at 30 fps, choose a frame rate of 10 or 15. Don't choose a rate greater than that of your source material.

Key Frame Specifies that key frames are generated automatically or specifies how frequently key frames are created in the exported video. A higher key frame rate (lower number) improves video quality, but increases the file size.

4 (MP4 file format only) Click the Video Options button and specify the following:

Re-sync Markers (MPEG-4 Basic and MPEG-4 Improved only) Uses re-sync markers in the video bit-stream. This can help regain synchronization due to transmission errors.

Restrict Profile(s) To (H.264 only) Selects profiles for playing video files on a device that conforms to one or more of the standard's profiles.

Encoding Mode (H.264 only) Specifies whether you want the best quality or faster encoding.

Specify QuickTime Movie settings (Photoshop Extended)

1 In the Render Video dialog box, select QuickTime Export and then choose QuickTime Movie from the pop-up menu.

2 Click the Settings button.

3 In the Movie Settings dialog box, make sure Video is selected.

Note: *Although the Movie Settings dialog box displays Sound options, you cannot adjust the current audio settings. To include audio in exported files, see Previewing video or timeline animations.*

4 Under Video, click the appropriate button to set the following:

Settings Opens the Standard Video Compression Settings dialog box so you can set the video compression and accompanying options.

Filter Opens the Choose Video Filter dialog box, where you can apply built-in QuickTime video effects.

Size Opens the Export Size Settings dialog box to specify pixel dimensions for your exported video.

5 (Optional) If your movie is being delivered over the Internet, select Prepare For Internet Streaming and choose any of the following:

Fast Start Sets up the movie to start playing from a web server before the movie has completely downloaded to a user's computer hard drive.

Fast Start-Compressed Header Compresses the movie's header losslessly and sets up the movie to start playing from a web server before the movie has completely downloaded to a user's computer hard drive.

Hinted Streaming Sets up the movie to be streamed by a QuickTime Streaming Server.

QuickTime standard video compression settings (Photoshop Extended)

The following options are available in the Standard Video Compression Settings dialog box:

Compression Type Choose the codec to apply when exporting a file.

Motion Specify the frame rate for your video by choosing the number of frames per second (fps). Some codecs support a specific set of frame rates. Increasing the frame rate may produce smoother motion (depending on the original frame rates of the source clips) but uses more disk space. If available, specify how often the key frames are generated. (See Understanding QuickTime key frames.)

Data Rate Select (if available for the selected compressor) and type a data rate to place an upper limit on the amount of video data produced by the exported video when it is played back.

Compressor Set compressor options specific to the selected codec. Click the Option button (if available) to specify further compressor options. If the Depth menu is available, choose the number of colors to include in exported video. (This menu is not available if the selected codec supports only one color depth.)

If the Quality slider is available under Compressor, drag the slider or type a value to adjust the exported video's picture quality and, consequently, its file size. If you are using the same codec to capture and export, and you've rendered previews of a sequence, you can save rendering time by matching the export quality setting with your original capture quality setting. Increasing quality above the original capture quality does not increase quality, but may result in longer rendering times.

Note: *Compressor options are not available for the Component Video codec.*

QuickTime movie size settings (Photoshop Extended)

The following settings are available in the Export Size Settings dialog box:

Dimensions Specifies the frame size for your exported movie. If you want to specify a frame size not included in the Dimensions menu, choose Custom and enter values for Width and Height.

Preserve Aspect Ratio Using Specifies an option if the movie is scaled to a new frame size. Letterbox scales the source proportionally to fit into the clean aperture, adding black bars to the top and bottom or sides as necessary. Crop centers, scales, and trims to the clean aperture. Fit Within Dimensions adjusts to the destination size by fitting to the longest side, scaling if necessary.

Deinterlace Source Video Deinterlaces the two fields in each interlaced video frame.

More Help topics

Save images

Interpreting video footage

Save PDF files

About Photoshop PDF format

You can use the Save As command to save RGB, indexed-color, CMYK, grayscale, Bitmap-mode, Lab color, and duotone images in Photoshop PDF format. Because the Photoshop PDF document can preserve Photoshop data, such as layers, alpha channels, notes, and spot color, you can open the document and edit the images in Photoshop CS2 or later.

You can quickly save a file as Photoshop PDF by playing the Save As Photoshop PDF action on the file. You can access this action by choosing Production from the Actions panel menu.

For advanced users, the Photoshop PDF format offers options for making the document PDF/X compliant, which is essential, for example, when you send your document to a large commercial press. PDF/X (Portable Document Format Exchange) is a subset of Adobe PDF that eliminates color, font, and trapping variables that lead to printing problems.

You can also specify security options for restricting access to the PDF document. The 128-bit RC4 (Acrobat 6 and later) encryption has an option for letting users view metadata and thumbnails in a secure PDF document using Adobe Bridge.

You can save your PDF settings as a PDF preset for creating consistent Photoshop PDF files. Adobe PDF presets and settings are shared across Adobe components, including Photoshop, InDesign, Illustrator, and Acrobat.

Save in Photoshop PDF format

1. Choose File > Save As, and then choose Photoshop PDF from the Format menu. You can select a Color option if you want to embed a color profile or use the profile specified with the Proof Setup command. You can also include layers, notes, spot color, or alpha channels. Click Save.
2. In the Save Adobe PDF dialog box, choose an Adobe PDF preset specifying whether the Photoshop PDF file will be printed on a desktop printer or proofer, sent to a commercial printer, distributed by e-mail, displayed on the web, and so on. For details, see Adobe PDF presets.

   Choosing a preset is the easiest way to set options for your Photoshop PDF file. After you choose a preset, click Save PDF to generate your Photoshop PDF file. If you want to add security options or fine-tune the saving options for the PDF, follow the remaining steps in this procedure.
3. (Optional) Choose options from the Standard menu and the Compatibility menu to specify the PDF/X compliance and the Acrobat version compatibility for the PDF document. For more information, see PDF compatibility levels.
4. (Optional) Select General in the left pane of the Save Adobe PDF dialog box to set general PDF file saving options. For details of each option, see General options for Adobe PDF.

   Note: *Users of Photoshop 7.0 and earlier can open a Photoshop PDF as a generic PDF with flattened layers. Choose File > Open As and then choose Generic PDF from the Files Of Type menu (Windows), or choose File > Open and choose Generic PDF from the Format menu (Mac OS).*
5. (Optional) Select Compression in the left pane of the Save Adobe PDF dialog box to specify the compression and downsampling options for the PDF file. For more information, see Compression and downsampling options for Adobe PDF.
6. (Optional) Select Output in the left pane of the Save Adobe PDF dialog box to specify color management and PDF/X options. For more information, see Color management and PDF/X options for Adobe PDF.
7. (Optional) To add security to your PDF document, select Security in the left pane of the Save Adobe PDF dialog box. Specify the password and permissions options for your PDF document. See also Add security to PDF files.

   Note: *The Encryption Level depends on the Compatibility setting of your PDF document. Choose a different Compatibility setting to specify a higher or lower Encryption Level.*
8. (Optional) Select Summary in the left pane of the Save Adobe PDF dialog box. You can review the options you specified.
9. (Optional) If you want to reuse the PDF save settings, click Save Preset and save your settings as a PDF preset. The new preset appears in the Adobe PDF Preset menu the next time you save a Photoshop PDF file and in any product in the Adobe Creative Cloud. See also Save an Adobe PDF preset.
10. Click Save PDF. Photoshop closes the Save Adobe PDF dialog box and creates the PDF document file.

Adobe PDF presets

A PDF preset is a group of settings that affect the process of creating a PDF. These settings are designed to balance file size with quality, depending on how the PDF will be used. Most predefined presets are shared across Adobe components, including InDesign, Illustrator, Photoshop, and Acrobat. You can also create and share custom presets for your unique output requirements.

A few of the presets listed below are not available until you move them—as needed—from the Extras folder (where they are installed by default) to the Settings folder. Typically, the Extras and Settings folders are found in (Windows Vista and Windows 7) ProgramData\Adobe\AdobePDF, (Windows XP) Documents and Settings\All Users\Application Data\Adobe\Adobe PDF, or (Mac OS) Library/Application Support/Adobe PDF. Some presets are not available in some Creative Suite components.

The custom settings are found in (Windows XP) Documents and Settings/[username]/Application Data/Adobe/Adobe PDF/Settings, (Windows Vista and Windows 7) Users/[username]/AppData/Roaming/Adobe/Adobe PDF/Settings, or (Mac OS) Users/[username]/Library/Application Support/Adobe/Adobe PDF/Settings.

Review your PDF settings periodically. The settings do not automatically revert to the default settings. Applications and utilities that create PDFs use the last set of PDF settings defined or selected.

High Quality Print Creates PDFs for quality printing on desktop printers and proofing devices. This preset uses PDF 1.4, downsamples color and grayscale images to 300 ppi and monochrome images to 1200 ppi, embeds subsets of all fonts, leaves color unchanged, and does not flatten transparency (for file types capable of transparency). These PDFs can be opened in Acrobat 5.0 and Acrobat Reader 5.0 and later. In InDesign, this preset also creates tagged PDFs.

Illustrator Default (Illustrator only) Creates a PDF in which all Illustrator data is preserved. PDFs created with this preset can be reopened in Illustrator without any loss of data.

Oversized Pages (Acrobat only) Creates PDFs suitable for viewing and printing of engineering drawings larger than 200 x 200 inches. These PDFs can be opened in Acrobat and Reader 7.0 and later.

PDF/A-1b: 2005 (CMYK and RGB) (Acrobat only) Used for long-term preservation (archival) of electronic documents. PDF/A-1b uses PDF 1.4 and converts all colors to either CMYK or RGB, depending on which standard you choose. These PDFs can be opened in Acrobat and Reader versions 5.0 and later.

PDF/X-1a (2001 and 2003) PDF/X-1a requires all fonts to be embedded, the appropriate marks and bleeds to be specified, and color to appear as CMYK, spot colors, or both. Compliant files must contain information describing the printing condition for which they are prepared. PDF files created with PDF/X-1a compliance can be opened in Acrobat 4.0 and Acrobat Reader 4.0 and later.

PDF/X-1a uses PDF 1.3, downsamples color and grayscale images to 300 ppi and monochrome images to 1200 ppi, embeds subsets of all fonts, creates untagged PDFs, and flattens transparency using the High Resolution setting.

Note: *The PDF/X1-a:2003 and PDF/X-3 (2003) presets are placed on your computer during installation but are not available until you move them from the Extras folder to the Settings folder.*

PDF/X-3 This preset creates a PDF based on the ISO standard PDF/X-3:2002. The PDF created in this setting can be opened in Acrobat 4.0 and Acrobat Reader 4.0 or later.

PDF/X-4 (2008) This preset creating ISO PDF/X-4:2008 files supports live transparency (transparency is not flattened) and ICC color management. PDF files exported with this preset are in PDF 1.4 format. Images are downsampled and compressed and fonts are embedded in the same manner as with the PDF/X-1a and PDF/X-3 settings. You can create PDF/X-4:2008-compliant PDF files directly from Creative Suite 4 and 5 components including Illustrator, InDesign, and Photoshop. Acrobat 9 Pro provides facilities to validate and preflight PDF files for PDF/X-4:2008 compliance as well as convert non-PDF/X files to PDF/X-4:2008 if possible.

Adobe recommends PDF/X-4:2008 as the optimal PDF file format for reliable PDF print publishing workflows.

Press Quality Creates PDF files for high-quality print production (for example, for digital printing or for separations to an imagesetter or platesetter), but does not create files that are PDF/X-compliant. In this case, the quality of the content is the highest consideration. The objective is to maintain all the information in a PDF file that a commercial printer or print service provider needs in order to print the document correctly. This set of options uses PDF 1.4, converts colors to CMYK, downsamples color and grayscale images to 300 ppi and monochrome images to 1200 ppi, embeds subsets of all fonts, and preserves transparency (for file types capable of transparency).

These PDF files can be opened in Acrobat 5.0 and Acrobat Reader 5.0 and later.

Note: *Before creating an Adobe PDF file to send to a commercial printer or print service provider, find out what the output resolution and other settings should be, or ask for a .joboptions file with the recommended settings. You might need to customize the Adobe PDF settings for a particular provider and then provide a .joboptions file of your own.*

Rich Content PDF Creates accessible PDF files that include tags, hyperlinks, bookmarks, interactive elements, and layers. This set of options uses PDF 1.5 and embeds subsets of all fonts. It also optimizes files for byte serving. These PDF files can be opened in Acrobat 6.0 and Adobe Reader 6.0 and later. (The Rich Content PDF preset is in the Extras folder.)

Note: *This preset was called eBook in earlier versions of some applications.*

Smallest File Size Creates PDF files for displaying on the web, an intranet, or for email distribution. This set of options uses compression, downsampling, and a relatively low image resolution. It converts all colors to sRGB and embeds fonts. It also optimizes files for byte serving. For best results, avoid using this preset if you intend to print the PDF file.

These PDF files can be opened in Acrobat 5.0 and Acrobat Reader 5.0 and later.

Magazine Ads 2006 (Japan) This preset creates a PDF based on the creation rules designed by Digital Data Delivery committee.

Standard (Acrobat only) Creates PDF files to be printed to desktop printers or digital copiers, published on a CD, or sent to a client as a publishing proof. This set of options uses compression and downsampling to keep the file size down, but also embeds subsets of all (allowed) fonts used in the file, converts all colors to sRGB, and prints to a medium resolution. Note that Windows font subsets are not embedded by default. PDF files created with this settings file can be opened in Acrobat 5.0 and Acrobat Reader 5.0 and later.

For more information on creating and saving a custom preset, see Save an Adobe PDF preset.

About PDF/X and PDF/A standards

PDF/X and PDF/A standards are defined by the International Organization for Standardization (ISO). PDF/X standards apply to graphic content exchange; PDF/A standards apply to long-term archiving of electronic documents. During PDF conversion, the file that is being processed is checked against the specified standard. If the PDF will not meet the selected ISO standard, a message appears, asking you to choose between canceling the conversion or going ahead with the creation of a noncompliant file.

The most widely used standards for a print publishing workflow are several PDF/X formats: PDF/X-1a, PDF/X-3, and (in 2007) PDF/X-4. The most widely used standards for PDF archiving are PDF/A-1a, and PDF/A-1b (for less stringent requirements).

Note: *For more information on PDF/X and PDF/A standards, see the ISO website.*

PDF compatibility levels

When you create PDFs, you need to decide which PDF version to use. You can change the PDF version by switching to a different preset or choosing a compatibility option when you save as PDF or edit a PDF preset.

Generally speaking, unless there's a specific need for backward compatibility, you should use the most recent version (in this case version 1.7). The latest version will include all the newest features and functionality. However, if you're creating documents that will be distributed widely, consider choosing Acrobat 5.0 (PDF 1.4) or Acrobat 6.0 (PDF 1.5) to ensure that all users can view and print the document.

The following table compares some of the functionality in PDFs created using the different compatibility settings.

Note: *Acrobat 8.0 and 9.0 also use PDF 1.7.*

Acrobat 3.0 (PDF 1.3)	**Acrobat 5.0 (PDF 1.4)**	**Acrobat 6.0 (PDF 1.5)**	**Acrobat 7.0 (PDF 1.6) and Acrobat X (PDF 1.7)**
PDFs can be opened with Acrobat 3.0 and Acrobat Reader 3.0 and later.	PDFs can be opened with Acrobat 3.0 and Acrobat Reader 3.0 and later. However, features specific to later versions may be lost or not viewable.	Most PDFs can be opened with Acrobat 4.0 and Acrobat Reader 4.0 and later. However, features specific to later versions may be lost or not viewable.	Most PDFs can be opened with Acrobat 4.0 and Acrobat Reader 4.0 and later. However, features specific to later versions may be lost or not viewable.
Cannot contain artwork that uses live transparency effects. Any transparency must be flattened prior to converting to PDF 1.3.	Supports the use of live transparency in artwork. (The Acrobat Distiller feature flattens transparency.)	Supports the use of live transparency in artwork. (The Acrobat Distiller feature flattens transparency.)	Supports the use of live transparency in artwork. (The Acrobat Distiller feature flattens transparency.)
Layers are not supported.	Layers are not supported.	Preserves layers when creating PDFs from applications that support the generation of layered PDF documents, such as Illustrator CS and later or InDesign CS and later.	Preserves layers when creating PDFs from applications that support the generation of layered PDF documents, such as Illustrator CS and later or InDesign CS and later.
DeviceN color space with 8 colorants is supported.	DeviceN color space with 8 colorants is supported.	DeviceN color space with up to 31 colorants is supported.	DeviceN color space with up to 31 colorants is supported.
Multibyte fonts can be embedded. (Distiller converts the fonts when embedding.)	Multibyte fonts can be embedded.	Multibyte fonts can be embedded.	Multibyte fonts can be embedded.
40-bit RC4 security supported.	128-bit RC4 security supported.	128-bit RC4 security supported.	128-bit RC4 and 128-bit AES (Advanced Encryption Standard) security supported.

General options for Adobe PDF

You can set the following options in the General section of the Adobe PDF Options dialog box:

Description Displays the description from the selected preset, and provides a place for you to edit the description. You can paste a description from the clipboard. If you edit the description of a preset, the word "(Modified)" is added at the end of the preset name.

Preserve Photoshop Editing Capabilities Preserves Photoshop data in the PDF, such as layers, alpha channels, and spot colors. Photoshop PDF documents with this option can be opened only in Photoshop CS2 and later.

Embed Page Thumbnails Creates a thumbnail image of artwork.

Optimize For Fast Web View Optimizes the PDF file for faster viewing in a web browser.

View PDF After Saving Opens the newly created PDF file in the default PDF viewing application.

Compression and downsampling options for Adobe PDF

When saving artwork in Adobe PDF, you can compress text and line art, and compress and downsample bitmap images. Depending on the settings you choose, compression and downsampling can significantly reduce the size of a PDF file with little or no loss of detail and precision.

The Compression area of the Adobe PDF Options dialog box is divided into three sections. Each section provides the following options for compressing and resampling images in your artwork.

Downsampling If you plan to use the PDF file on the web, use downsampling to allow for higher compression. If you plan to print the PDF file at high resolution, do not use downsampling. Select the Do Not Downsample option to disable all downsampling options.

Downsampling refers to decreasing the number of pixels in an image. To downsample images, choose an *interpolation method*—average downsampling, subsampling, or bicubic downsampling—and enter the desired resolution (in pixels per inch). Then enter a resolution in the For Images Above box. All images with resolution above this threshold are downsampled.

The interpolation method you choose determines how pixels are deleted:

Average Downsampling To Averages the pixels in a sample area and replaces the entire area with the average pixel color at the specified resolution. Average downsampling is the same as Bilinear resampling.

Subsampling To Chooses a pixel in the center of the sample area and replaces the entire area with that pixel color. Subsampling significantly reduces the conversion time compared with downsampling but results in images that are less smooth and continuous. Subsampling is the same as Nearest Neighbor resampling.

Bicubic Downsampling To Uses a weighted average to determine pixel color, which usually yields better results than the simple averaging method of downsampling. Bicubic is the slowest but most precise method, resulting in the smoothest gradations.

Compression Determines the type of compression that is used.

ZIP compression Works well on images with large areas of single colors or repeating patterns, and for black-and-white images that contain repeating patterns. ZIP compression is lossless.

JPEG compression Is suitable for grayscale or color images. JPEG compression is *lossy*, which means that it removes image data and may reduce image quality; however, it attempts to reduce file size with a minimal loss of information. Because JPEG compression eliminates data, it can achieve much smaller file sizes than ZIP compression.

JPEG2000 Is the new international standard for the compression and packaging of image data. Like JPEG compression, JPEG2000 compression is suitable for grayscale or color images. It also provides additional advantages, such as progressive display and lossless compression not available with JPEG. JPEG2000 is only available if Acrobat 6 (PDF 1.5) or later is selected from the Compatibility menu.

Image Quality Determines the amount of compression that is applied. The available options depend on the compression method. For JPEG2000 compression, Photoshop provides Lossless, Maximum, High, Medium, Low, and Minimum options. For JPEG compression, Photoshop provides Minimum, Low, Medium, High, and Maximum options. For ZIP compression, Photoshop provides an 8-bit Image Quality option. The 8-bit Image Quality option is lossless; that is, data is not removed to reduce file size, so image quality is not affected.

Tile Size Specifies the size of the tiles used in images with JPEG 2000 compression. When low Image Quality values are used to optimize images smaller than 1024 x 1024 pixels, using the largest tile size produces better results. In general, a tile size of 1024 is best for most images. Lower tile sizes are generally used for images with small dimensions (for viewing on devices such as mobile phones).

Convert 16 Bit/Channel Image To 8 Bit/Channel Converts 16-bits-per-channel images to 8-bits-per-channel images (selected by default). ZIP is the only compression method available if the Convert 16 Bits option is unselected. If your

document's Compatibility setting is Acrobat 5 (PDF 1.4) or earlier, the Convert 16 Bits option is unavailable, and images are automatically converted to 8 bits per channel.

Color management and PDF/X options for Adobe PDF

You can set the following options in the Output section of the Adobe PDF Options dialog box. Interactions between Output options change depending on whether Color Management is on or off and which PDF standard is selected.

Color Conversion Specifies how to represent color information in the Adobe PDF file. When you convert color objects to RGB or CMYK, also select a destination profile from the pop-up menu. All spot color information is preserved during color conversion; only the process color equivalents convert to the designated color space.

No Conversion Preserves color data as is.

Convert To Destination Converts all colors to the profile selected for Destination. Whether the profile is included or not is determined by the Profile Inclusion Policy.

Destination Describes the gamut of the final RGB or CMYK output device, such as your monitor or a SWOP standard. Using this profile, Photoshop converts the document's color information (defined by the source profile in the Working Spaces section of the Color Settings dialog box) to the color space of the target output device.

Profile Inclusion Policy Determines whether a color profile is included in the file.

Output Intent Profile Name Specifies the characterized printing condition for the document. An output intent profile is required for creating PDF/X-compliant files. This menu is available only if a PDF/X standard (or preset) is selected in the Adobe PDF Options dialog box.

Output Condition Describes the intended printing condition. This entry can be useful for the intended receiver of the PDF document.

Output Condition Identifier A pointer to more information on the intended printing condition. The identifier is automatically entered for printing conditions that are included in the ICC registry.

Registry Name Indicates the web address for more information on the registry. The URL is automatically entered for ICC registry names.

Add security to PDF files

When saving as PDF, you can add password protection and security restrictions, limiting not only who can open the file, but also who can copy or extract contents, print the document, and more.

A PDF file can require passwords to open a document (document open password) and to change security settings (permissions password). If you set any security restrictions in your file, you should set both passwords; otherwise, anyone who opens the file could remove the restrictions. If a file is opened with a permissions password, the security restrictions are temporarily disabled.

The RC4 method of security from RSA Corporation is used to password-protect PDF files. Depending on the Compatibility setting (in the General category), the encryption level will be high or low.

Note: *Adobe PDF presets don't support passwords and security settings. If you select passwords and security settings in the Export Adobe PDF dialog box, and then click Save Preset, the passwords and security settings won't be preserved.*

Save an Adobe PDF preset

Although the default PDF presets are based on best practices, you may discover that your workflow requires specialized PDF settings that aren't available using any of the built-in presets. In this case, you can create and save your own custom presets for reuse in Photoshop or any product in the Adobe Creative Cloud.

In Photoshop, you can save the preset using the Adobe PDF Presets command or clicking the Save Preset button in the Save Adobe PDF dialog box. Adobe PDF presets are saved as files with a .joboptions extension. This is useful, for example, if you want your vendor or printer to send you a .joboptions file with the Adobe PDF presets that work best with their workflow.

1 Do one of the following:
   - Choose Edit > Adobe PDF Presets.
   - If you're saving a Photoshop PDF document, click the Save Preset button in the Save Adobe PDF dialog box after you specify your PDF settings. Skip steps 2 and 3.
2 If you chose the Adobe PDF Presets command, do one of the following in the Adobe PDF Presets dialog box:
   - To create a new preset, click the New button in the Adobe PDF Presets dialog box. In the New PDF Preset dialog box, type a name for the preset in the Preset text box.
   - To edit an existing custom preset, select the preset and click Edit. (You can't edit the default presets.)
3 Set the PDF options.
4 Save your preset by doing one of the following:
   - In the New PDF Preset or the Edit PDF Preset dialog box, click OK. The new preset appears in the Adobe PDF Presets list. Click Done when you finish creating presets.
   - In the Save dialog box, type a name for the preset in the File Name text box and click Save.

   Adobe PDF presets are stored in the following folders:
   - (Windows Vista) Users/[user name]/AppData/Roaming/Adobe/Adobe PDF/Settings
   - (Windows XP) Documents and Settings/[user name]/Application Data/Adobe/Adobe PDF/Settings
   - (Mac OS) Users/[user name]/Library/Application Support/Adobe/Adobe PDF/Settings

   All the Adobe PDF presets you save in these locations are available in your other Adobe applications.

   Note: *To save the PDF preset in a location other than the default, click the Save As button in the Adobe PDF Presets dialog box and browse to the destination, or in the Save dialog box, browse to the destination and click Save.*

Load, edit, or delete Adobe PDF presets

Adobe PDF presets (creation settings) are available in Photoshop and other Adobe products. From the Adobe PDF Presets dialog box, you save, load, edit, or delete Adobe PDF presets.

? Choose Edit > Adobe PDF Presets and do any of the following:
   - To save settings as a new preset, click the New button, specify settings in the New PDF Preset dialog box, and click OK.
   - To edit an Adobe PDF preset, select the preset in the Preset window, click the Edit button, and change settings in the Edit PDF Preset dialog box.

   Note: *Although you can't edit the Adobe PDF presets that were installed with Photoshop (the names of presets installed with Photoshop are enclosed in square brackets), you can select one of them and click the New button. In the New PDF Preset dialog box, you can modify the settings and save them as a new preset.*

   - To delete an Adobe PDF preset, select the preset in the Preset window and click the Delete button. You can't delete the Adobe PDF presets that were installed with Photoshop.
   - To load an Adobe PDF preset, click the Load button, select the preset file, and click the Load button. The preset is added to the Presets window.

When you browse for an Adobe PDF preset to load, only files with the .joboptions extension are visible in the Load dialog box.

- To close the PDF Options Preset dialog box, click the Done button.
- To save a preset in a location other than the default, click the Save As button, give the preset a new name (if necessary), browse to the destination, and click Save.

More Help topics

Contact sheets and PDF presentations

Play an action on a file

About file compression

Digimarc copyright protection

Note: *The Digimarc plug-in is preinstalled in Photoshop CC. For earlier Photoshop versions, be sure to download the proper plug-in for your system.*

Digimarc digital watermark technology allows for embedded information into Photoshop image files. The marks are frequently used for image and video copyright protection.

Read a Digimarc watermark

1. Choose Filter > Digimarc > Read Watermark. If the filter finds a watermark, a dialog box displays the Digimarc ID, creator information, and image attributes.
2. Click OK, or for more information, click Web Lookup. The Digimarc website is displayed in your web browser, where contact details appear for the given creator ID.

Adding digital copyright information

You can add copyright information to Photoshop images and notify users that an image is copyright protected via a digital watermark that uses Digimarc ImageBridge technology. The watermark—a digital code added as noise to the image—is virtually imperceptible to the human eye. The Digimarc watermark is durable in both digital and printed forms, surviving typical image edits and file format conversions.

Embedding a digital watermark in an image lets viewers obtain information about the creator of the image. This feature is particularly valuable to image creators who license their work to others. Copying an image with an embedded watermark also copies the watermark and any information associated with it.

For more detailed information on embedding Digimarc digital watermarks, refer to the Digimarc website.

Before adding a digital watermark

Keep in mind the following considerations before embedding a digital watermark in your image.

Color variation The image must contain some degree of variation or randomness in color to embed the digital watermark effectively and imperceptibly. The image cannot consist mostly or entirely of a single flat color.

Pixel dimensions The Digimarc technology requires a minimum number of pixels to work. Digimarc recommends the following minimum pixel dimensions for the image to be watermarked:

- 100 pixels by 100 pixels, if you don't expect the image to be modified or compressed prior to its actual use.
- 256 pixels by 256 pixels, if you expect the image to be cropped, rotated, compressed, or otherwise modified after watermarking.
- 750 pixels by 750 pixels, if you expect the image to appear ultimately in printed form at 300 dpi or greater.

  There is no upper limit on pixel dimensions for watermarking.

File compression In general, a Digimarc watermark will survive lossy compression methods, such as JPEG, though it is advisable to favor image quality over file size (a JPEG compression setting of 4 or higher works best). In addition, the higher the Watermark Durability setting you choose when embedding the watermark, the better the chances that the digital watermark will survive compression.

Workflow Digital watermarking should be one of the very last tasks you perform on an image, except for file compression.

Use the following recommended workflow:

- Make all necessary modifications to your image until you are satisfied with its final appearance (this includes resizing and color correction).
- Embed the Digimarc watermark.
- If needed, compress the image by saving it in JPEG or GIF format.
- If the image is intended for printed output, perform the color separation.
- Read the watermark and use the signal strength meter to verify that the image contains a watermark of sufficient strength for your purposes.
- Publish the digital watermarked image.

Embed a watermark

To embed a digital watermark, you must first register with Digimarc Corporation—which maintains a database of artists, designers, and photographers and their contact information—to get a unique Digimarc ID. You can then embed the Digimarc ID in your images, along with information such as the copyright year or a restricted-use identifier.

1. Open the image that you want to watermark. You can embed only one digital watermark per image. The Embed Watermark filter won't work on an image that has been previously watermarked.

   If you're working with a layered image, you should flatten the image before watermarking it; otherwise, the watermark will affect the active layer only.

   Note: *You can add a digital watermark to an indexed-color image by first converting the image to RGB mode, embedding the watermark, and then converting the image back to Indexed Color mode. However, the results may be inconsistent. To make sure that the watermark was embedded, run the Read Watermark filter.*

2. Choose Filter > Digimarc > Embed Watermark.
3. If you are using the filter for the first time, click the Personalize button. Get a Digimarc ID by clicking Info to launch your web browser and visit the Digimarc website. Enter your PIN and ID number in the Digimarc ID text box, and click OK.

   After you enter a Digimarc ID, the Personalize button becomes a Change button, allowing you to enter a new Digimarc ID.

4. Enter a copyright year, transaction ID, or image ID for the image.

5 Select any of the following image attributes:

Restricted Use Limits the use of the image.

Do Not Copy Specifies that the image should not be copied.

Adult Content Labels the image contents as suitable for adults only. (Within Photoshop, this option does not limit access to adult-only images, but future versions of other applications may limit their display.)

6 For Watermark Durability, drag the slider or enter a value, as described in the next section.

7 Select Verify to automatically assess the watermark's durability after it is embedded.

8 Click OK.

Using the Watermark Durability setting

The default Watermark Durability setting is designed to strike a balance between watermark durability and visibility in most images. However, you can adjust the Watermark Durability setting yourself to suit the needs of your images. Low values are less visible in an image but less durable, and may be damaged by applying filters or by performing some image editing, printing, and scanning operations. High values are more durable but may display some visible noise in the image.

Your setting should depend on the intended use of the image and the goals you've set for your watermarks. For example, it may be quite acceptable to use a higher Watermark Durability setting with JPEG images posted on a website. The higher durability helps to ensure the persistence of the watermark, and the increased visibility often is not noticeable with medium-resolution JPEG images. Digimarc recommends experimenting with various settings as part of your testing process to determine which setting works best for the majority of your images.

Check the signal strength meter

The signal strength meter helps you determine whether a watermark is durable enough to survive the intended use of the image.

? Choose Filter > Digimarc > Read Watermark. The signal strength meter appears at the bottom of the dialog box. You can also display the meter automatically by selecting Verify while embedding the watermark.

The signal strength meter is available only for images containing digital watermarks that you yourself have embedded.

Digimarc recommends that you check the signal strength meter before publishing your images. For example, if you often compress watermarked images for inclusion in a website, check the meter before posting the images. You can also use the signal strength meter to gauge the effectiveness of different Watermark Durability settings that you are experimenting with.

Chapter 17: Printing

Print 3D objects

With Photoshop, you can print any compatible 3D model without worrying about 3D printer limitations. In preparation for printing, Photoshop automatically makes 3D models watertight. Photoshop also generates the necessary support structures—scaffolding and rafts—to ensure that your 3D prints are successful.

Preparing to print 3D objects

1 Select Window > Workspace > 3D to switch to the 3D workspace.

2 Open the 3D model in Photoshop. If necessary, customize the size of the 3D model while opening it.

3 Select 3D > 3D Print Settings.



? In the 3D Print Settings panel, choose whether you want to print to a printer connected to your computer through a USB port (local printer) or use an online 3D printing service, such as Shapeways.com or Sculpteo.

Note: *Shapeways.com and Sculpteo are leading 3D printing marketplaces. For information about these companies, see:*

- Shapeways.com FAQ
- Sculpteo FAQ

To refresh the list of supported printers or online profiles, select Get Latest Printers from the Print To pop-up menu.

? Select a local printer or a Shapeways.com printer profile.

To view estimated prices for printing the 3D model using available Shapeways.com profiles, select Printer > Estimate Price.

? Select a unit for the printer volume—inch, centimeter, millimeter, or pixel. The unit is reflected in the Printer Volume dimensions as well as the print plate measurements.



***A** 3D model **B** Print plate **C** Printer volume overlay*

1 Select a Detail Level—Low, Medium, or High—for the 3D print. The time required to print the 3D object depends on the detail level that you choose.

2 If you don't want to see the 3D printer volume overlaid on the 3D model, deselect Show Printer Volume Overlay.

? Adjust the Scene Volume dimensions to specify the desired size of the printed 3D object. When you change a value (X, Y, or Z), the other two values are scaled proportionately. As you modify the Scene Volume dimensions, notice that the print plate under the 3D model scales in proportion.

You can scrub the value of a Scene Volume dimension by clicking the dimension label (X, Y, or Z) and then dragging the mouse left or right. Hold down the Shift key to make the value scrub faster.



1 Choose Scale To Print Volume if you want Photoshop to auto-scale your 3D model, such that it fills up the available print volume of the selected printer.

2 If the 3D model has normal maps, bump maps, or opacity maps; you can choose to ignore one of more types of these maps while printing the model. You'll notice that the 3D model updates in real time when you change these Surface Detail settings.

3 You may choose to not print the support structures (scaffolds or rafts) required for the 3D object. Use this option with caution, since the printing of the 3D model may fail if you don't print a necessary support structure.

4 If your printer supports multiple materials, choose the material that you want to use for printing the 3D object.

(Experimental) Enable multitone printing for MakerBot Replicator 2x

You can enable an experimental feature that lets you print continuous tones using your MakerBot Replicator 2x 3D printer.

Prerequisite: Enable experimental features

As a prerequisite to multitone printing, you must enable experimental features in Photoshop:

1 Select Preferences > Experimental Features.

2 Select Enable Multitone Printing.

3 Click OK.

4 Restart Photoshop.

Note: *Experimental features are not yet production-ready. Use these features with discretion.*

Select the multitone surface material

1 Select the MakerBot Replicator 2x printer in the 3D Print Settings panel.

2 Under Material, select Multitone Surface. If this option is not available for selection, ensure that the Multitone 3D Printing experimental feature is already enabled.

1 Select other options relevant to the 3D object that you're printing.

2 Select 3D > 3D Print to preview and print the 3D object.

Previewing and printing the 3D object

Once you're done specifying the 3D print settings, follow these steps:

1 Click the Start Print icon ( ) or select 3D > 3D Print. Photoshop unifies the 3D scene and prepares it for the printing process.

2 If you chose to print using a Shapeways.com profile, Photoshop prompts you that the actual cost of printing may differ from the displayed estimates. Click OK.

3 In the preview window that appears, use the 3D camera tools to rotate, zoom, or move the 3D object. Rotate the 3D camera Roll the 3D camera Pan the 3D camera Slide the 3D camera Reset the 3D camera to its original location



? If necessary, select Show Repair. Photoshop displays the Original Mesh, Wall Thickness, and Closed Hole repairs using appropriate color coding:





? Optionally, enable Raytrace Preview. Raytrace previews represent the printed output more accurately.



1 If you want to export the 3D print settings to an STL file, click Export and save the file to an appropriate location on your computer. You can upload the STL file to an online service or put it on an SD card for local printing.

2 Review the 3D print summary and click Print.

You can cancel an in-progress 3D print by selecting 3D > Cancel 3D Print.

3D print utilities

Photoshop provides interactive wizard-based utilities that you can use for configuring, calibrating, and maintaining your 3D printer. You can use these utilities only when the 3D printer is powered on and connected to your computer.

1 Select 3D > 3D Printer Utilities.

2 Select the utility that you want to launch.

Calibrate Print Plate Helps level the print plate. This utility performs the following broad steps:

- Prompts you to remove any leftover printing material from the 3D printer
- Initializes the print head
- Lets you adjust/finetune the gap between the print plate and the print head for nine nozzle positions

You can use this utility in the wizard mode or in the manual mode.

Load Filament Helps load a filament into a fused deposition modeling (FDM) 3D printer. Photoshop initiates the head-heating process and the filament-loading mechanism for easy filament loading.

Remove Filament Helps remove a filament from an FDM 3D printer. Photoshop initiates the head-heating process and the filament-loading mechanism for easy filament removal.

Change Filament Helps replace the filament of an FDM 3D printer with a new filament. Photoshop initiates the head-heating process and the filament-loading mechanism for easy filament changing.

? Follow the onscreen instructions.

Pack objects on the ground plane

At times, you may want to print multiple instances of the same object on the same build plate. Follow these steps:

1 Select the required objects in the 3D Panel.

2 Select 3D > Pack Objects On Ground Plane.

3 Proceed with printing the objects.

FAQ

- **What 3D printers are supported?**

  Photoshop currently supports the following local 3D printers:

  - MakerBot Replicator 2
  - MakerBot Replicator 2x
  - ZCorp Full Color
  - Mcor Iris
  - MakerBot Replicator 5th Generation

  Additionally, Photoshop supports several Shapeways.com and Sculpteo profiles.

  Note: *Direct USB printing with the MakerBot Replicator 5th Generation printer profile is not supported yet. You can export the files you want to print to a USB stick and then print them locally.*

- **Can I apply a cross section to a 3D model before printing it?**

  Yes. You can define cross sections to slice away parts of a 3D model before printing. Follow these broad steps:

  1. Select Window > Workspace > 3D to switch to the 3D workspace.
  2. Open the 3D object you want to print.
  3. Select Scene in the 3D panel.
  4. In the Properties panel, select Cross Section.
  5. Specify settings for the cross section in the Properties panel.
  6. Select 3D > Apply Cross Section To Scene.
  7. Print the 3D scene.

  Before printing, you must bake the cross section you've defined.



- **Can I apply bump/opacity/normal maps to a 3D model before printing it?**

  Yes. Follow these broad steps:

  1. Select a material in the Scene panel.

2 In the Properties panel, click the folder icon ( ) next to Bump/Opacity/Normal and load a texture. You can also define a new texture that you want to apply to the 3D model.

3 If you're defining a new texture, save the texture. The texture is applied to the 3D model as a bump/opacity map.

4 Print the 3D model.





- **Can I print 3D models in two colors?**

  If your 3D printer is equipped with two heads, you can print 3D models in two colors. The Print Properties panel displays pop-up options for the additional heads available. The 3D workspace and the 3D print preview display the model in two colors.



- **How are 3D models having multiple layers printed?**

  From a printing standpoint, each layer in the 3D model is treated as a 3D object. If necessary, you can merge two or more layers (3D > Merge 3D Layers).

More Help topics

How to print a 3D object in Photoshop

3D painting

3D panel enhancements | Photoshop CC

Photoshop 3D documentation

Print from Photoshop

Printing basics

Whether you are printing an image to your desktop printer or sending it to a prepress facility, knowing a few basics about printing makes the print job go more smoothly and helps ensure that the finished image appears as intended.

Types of printing For many Photoshop users, printing a file means sending the image to an inkjet printer. Photoshop can send your image to a variety of devices to be printed directly onto paper or converted to a positive or negative image on film. In the latter case, you can use the film to create a master plate for printing by a mechanical press.

Types of images The simplest images, such as line art, use only one color in one level of gray. A more complex image, such as a photograph, has varying color tones. This type of image is known as a *continuous-tone image*.

Color separation Artwork intended for commercial reproduction and containing more than one color must be printed on separate master plates, one for each color. This process, called color separation, generally calls for the use of cyan, magenta, yellow, and black (CMYK) inks. In Photoshop, you can adjust how the various plates are generated.

Quality of detail The detail in a printed image depends on image resolution (pixels per inch) and printer resolution (dots per inch). Most PostScript laser printers have a resolution of 600 dpi, while PostScript imagesetters have a resolution of 1200 dpi or higher. Inkjet printers produce a microscopic spray of ink, not actual dots, resulting in an approximate resolution of 300 to 720 dpi.

About desktop printing

Unless you work in a commercial printing company or service bureau, you probably print images to a desktop printer, such as an inkjet, dye sublimation, or laser printer, not to an imagesetter. Photoshop lets you control how your image is printed.

Monitors display images using light, whereas desktop printers reproduce images using inks, dyes, or pigments. For this reason, a desktop printer can't reproduce all the colors displayed on a monitor. However, by incorporating certain procedures (such as a color management system) into your workflow, you can achieve predictable results when printing your images to a desktop printer. Keep these considerations in mind when working with an image you intend to print:

- If your image is in RGB mode, do not convert the document to CMYK mode when printing to a desktop printer. Work entirely in RGB mode. As a rule, desktop printers are configured to accept RGB data and use internal software to convert to CMYK. If you send CMYK data, most desktop printers apply a conversion anyway, with unpredictable results.
- If you want to preview an image as printed to any device for which you have a profile, use the Proof Colors command.

- To reproduce screen colors accurately on the printed page, you must incorporate color management into your workflow. Work with a monitor that is calibrated and characterized. Ideally, you should also create a custom profile specifically for your printer and the paper you print on, though the profile supplied with your printer can produce acceptable results.

Print images

Photoshop provides the following printing commands in the File menu:

Print Displays the Print dialog box, where you can preview the print and set options. (Customized settings are saved as new defaults when you click Done or Print.)

Print One Copy Prints one copy of a file without displaying a dialog box.

For maximum efficiency, you can include the Print command in actions. (Photoshop provides all print settings in one dialog box.)

Set Photoshop print options and print

1 Choose File > Print.

2 Select the printer, number of copies, and layout orientation.

3 In the preview area at left, visually adjust the position and scale of the image relative to the selected paper size and orientation. Or to the right, set detailed options for Position And Size, Color Management, Printing Marks, and so on.

For more details, see Position and scale imagesand Print with color management.

In Mac OS, expand the Color Management section, and select Send 16-bit Data to produce the highest possible quality in subtle graduated tones, such as bright skies.

4 Do one of the following:

- To print the image, click Print.
- To close the dialog box without saving the options, click Cancel.
- To preserve the options and close the dialog box, click Done.

Position and scale images

You can adjust the position and scale of an image using options in the Print dialog box. The shaded border at the edge of the paper represents the margins of the selected paper; the printable area is white.

The base output size of an image is determined by the document size settings in the Image Size dialog box. Scaling an image in the Print dialog box changes the size and resolution of the printed image only. For example, if you scale a 72-ppi image to 50% in the Print dialog box, the image will print at 144 ppi; however, the document size settings in the Image Size dialog box will not change. In the Print dialog box, the Print Resolution field at the bottom of the Position And Size section shows the print resolution at the current scaling setting.

Many third-party printer drivers provide a scaling option in the Print Settings dialog box. This scaling affects everything on the page, including the size of all page marks, such as crop marks and captions, whereas the scaling percentage provided by the Print command affects only the size of the printed image (and not the size of page marks).

Note: *To avoid inaccurate scaling, specify scaling using the Print dialog box rather than the Print Settings dialog box; do not enter a scaling percentage in both dialog boxes.*

Reposition an image on the paper

? Choose File > Print, and expand the Position And Size settings at right. Then do one of the following:

- To center the image in the printable area, select Center Image.
- To position the image numerically, deselect Center Image, and then enter values for Top and Left.
- Deselect Center Image, and drag the image in the preview area.

Scale the print size of an image

? Choose File > Print, and expand the Position And Size settings at right. Then do one of the following:

- To fit the image within the printable area of the selected paper, click Scale To Fit Media.
- To rescale the image numerically, deselect Scale To Fit Media, then enter values for Scale, Height and Width.
- To achieve the desired scale, drag the bounding box around the image in the preview area.

Note: *If you get a warning that your image is larger than the printable area of the paper, click Cancel. Then choose File > Print, expand the Position And Size settings at right, and select Scale To Fit Media.*

Print part of an image

1. With the Rectangle Marquee tool, select the part of the image you want to print.
2. Choose File > Print, and select Print Selected Area.
3. If desired, adjust the selected area by dragging the triangular handles on the perimeter of the print preview.
4. Click Print.

Print vector data

If an image includes vector graphics, such as shapes and type, Photoshop can send the vector data to a PostScript printer. When you choose to include vector data, Photoshop sends the printer a separate image for each type layer and each vector shape layer. These additional images are printed on top of the base image, and clipped using their vector outline. Consequently, the edges of vector graphics print at the printer's full resolution, even though the content of each layer is limited to the resolution of your image file.

Note: *Some blending modes and layer effects require rasterized vector data.*

1. Choose File > Print.
2. In the options box at right, scroll to the bottom, and expand PostScript Options.
3. Select Include Vector Data.

More Help topics

Image size and resolution

About soft-proofing colors

About color profiles

Print with color management

In Photoshop you can make best use of your custom color profiles by allowing Photoshop to handle color management. You can also choose to let your printer(s) manage color.

To better understand color management concepts and workflows, see Understanding Color Management.

Let Photoshop determine printed colors

If you have a custom color profile for a specific printer, ink, and paper combination, letting Photoshop manage colors often produces better results than letting the printer manage colors.

1 Choose File > Print.

2 Expand the Color Management section at right.

3 For Color Handling, choose Photoshop Manages Colors.

4 For Printer Profile, select the profile that best matches your output device and paper type. If there are any profiles associated with the current printer, they are placed at the top of the menu, with the default profile selected.

The more accurately the profile describes the behavior of the output device and printing conditions (such as paper type), the more accurately the color management system can translate the numeric values of the actual colors in a document. (See Install a color profile.)

5 (Optional) Set any of the following options:

Rendering Intent Specifies how Photoshop converts colors to the destination color space. (See About rendering intents.)

Black Point Compensation Preserves the shadow detail in the image by simulating the full dynamic range of the output device.

6 (Optional) Below the print preview, select any of the following:

Match Print Colors Select to view image colors in the preview area as they will actually print.

Gamut Warning Enabled when Match Print Colors is selected. Select to highlight out-of-gamut colors in the image, as determined by the selected printer profile. A gamut is the range of colors that a color system can display or print. A color that can be displayed in RGB may be out of gamut for your current printer profile.

Show Paper White Sets the color white in the preview to the color of the paper in the selected printer profile. This produces a more accurate print preview if you're printing on off-white paper such as newsprint or art papers that are more beige than white. Since absolute white and black create contrast, less white in the paper will lower the overall contrast of your image. Off-white paper can also change the overall color cast of the image, so yellows printed on beige paper may appear more brown.

7 Access the color management options for the printer driver from the Print Settings dialog box, which automatically appears after you click Print.

- In Windows, click the Print Settings button to access the printer driver options.
- In Mac OS, use the pop-up menu from the Print Settings dialog box to access the printer driver options.

8 Turn off color management for the printer, so the printer profile settings won't override your profile settings.

Every printer driver has different color management options. If it's not clear how to turn off color management, consult your printer documentation.

9 Click Print.

Let printer determine printed colors

If you don't have a custom profile for your printer and paper type, you can let the printer driver handle the color conversion.

1 Choose File > Print.

2 Expand the Color Management section at right.

Note: The Document Profile entry shows the profile embedded in the image.

3 For Color Handling, choose Printer Manages Colors.

4 (Optional) For Rendering Intent, specify how to convert colors to the destination color space. A summary of each option appears in the Description area at bottom.

Many non-PostScript printer drivers ignore this option and use the Perceptual rendering intent. (For more information, see About rendering intents.)

5 Access the color management options for the printer driver from the Print Settings dialog box, which automatically appears after you click Print:

- In Windows, click Print Settings to access the printer driver options.
- In Mac OS, use the pop-up menu from the Print Settings dialog box to access the printer driver options.

Every printer driver has different color management options. If it's not clear how to turn on color management, consult your printer documentation.

6 Click Print.

Print a hard proof

A hard proof (sometimes called a proof print or match print) is a printed simulation of your final output on a printing press. A hard proof is produced on an output device that's less expensive than a printing press. Some inkjet printers have the resolution necessary to produce inexpensive prints that can be used as hard proofs.

1 Choose View > Proof Setup, and select the output conditions you want to simulate. You can do this using a preset or by creating a custom proof setup. See Soft-proof colors.

The view changes automatically according to the proof you choose. Choose Custom to create custom proof settings, which you must save so you can select them in the Proof Setup menu of the Print dialog box.

2 After you select a proof, choose File > Print.

3 Expand the Color Management section at right.

4 For Color Handling, choose Photoshop Manages Colors.

5 For Printer Profile, select the profile for your output device.

6 From the menu above the Proof Setup menu or Rendering Intent menu, select Hard Proofing.

The Proofing Profile entry below should match the proof setup you selected earlier.

7 (Optional) Set any of the following options:

Proof Setup Choose any customized proofs that exist locally on your hard drive.

Simulate Paper Color Simulates what colors look like on the paper of the simulated device. Using this option produces the most accurate proof, but it is not available for all profiles.

Simulate Black Ink Simulates the brightness of dark colors for the simulated device. Using this option results in more accurate proofs of dark colors, but it is not available for all profiles.

8 Access the color management options for the printer driver from the Print Settings dialog box, which automatically appears after you click Print.
   - In Windows, click the Preferences button to access the printer driver options.
   - In Mac OS, use the pop-up menu from the Print Settings dialog box to access the printer driver options.
9 Turn off color management for the printer so that the printer profile settings don't override your profile settings.

   Every printer driver has different color management options. If it's not clear how to turn off color management, consult your printer documentation.
10 Click Print.

Contact Sheets and PDF Presentations

Contact Sheet II and PDF Presentation plug-ins in Photoshop CS6 and Photoshop CC are 64-bit compatible for optimal performance on modern systems.

Some procedures in this article are applicable to Adobe Bridge. Adobe Bridge is not installed by default with Photoshop CC. To download Bridge CC, sign in to Creative Cloud with your Adobe ID , then navigate to Apps.

Creating a contact sheet

1 Do either of the following:
   - (Photoshop) Choose File > Automate > Contact Sheet II.
   - (Bridge) Select a folder of images or specific image files. From the Bridge menu, choose Tools > Photoshop > Contact Sheet II. Unless you select specific images, the contact sheet will include all the images currently displayed in Adobe Bridge. You can select a different images after the Contact Sheet II dialog box opens.
2 In the Contact Sheet II dialog box, specify the images to include by choosing an option from the Use menu.

   Note: *If you select Bridge, all images currently in Bridge are used unless you selected images before choosing the Contact Sheet II command. Images in subfolders are not included.*
3 In the Document area, specify the dimensions and color data for the contact sheet. Select Flatten All Layers to create a contact sheet with all images and text on a single layer. Deselect Flatten All Layers to create a contact sheet in which each image is on a separate layer and each caption is on a separate text layer.
4 In the Thumbnails area, specify layout options for the thumbnail previews.
   - For Place, choose whether to arrange thumbnails across first (from left to right, then top to bottom) or down first (from top to bottom, then left to right).
   - Enter the number of columns and rows that you want per contact sheet.
   - Select Use Auto-Spacing to let Photoshop automatically space the thumbnails in the contact sheet. If you deselect Use Auto-Spacing, you can specify the vertical and horizontal space around the thumbnails.
   - Select Rotate For Best Fit to rotate the images, regardless of their orientation, so they fit efficiently on a contact sheet.
5 Select Use Filename As Caption to label the thumbnails using their source image filenames. Use the menu to specify a caption font and font size.
6 Click OK.

Creating a PDF presentation

The PDF Presentation command lets you use a variety of images to create a multipage document or slideshow presentation.

1 Choose File > Automate > PDF Presentation.

2 In the PDF Presentation dialog box, click Browse and navigate to add files to the PDF presentation. Select Add Open Files to add files already open in Photoshop.

Note: Drag files up or down to reorder them in the presentation. If you want a file to appear more than once, select the file and click Duplicate.

3 Set Output and Presentation options. Then click Save.

Note: PDF presentations are saved as generic PDF files, not Photoshop PDF files, and are rasterized when you reopen them in Photoshop.

Print photos in a picture package layout

(32-bit CS6 and below only) Place multiple photos into a picture package

To use the optional Picture Package plug-in described below, first download it for Windows or Mac OS. You can also create picture and custom packages in Photoshop Lightroom, if you have it. See Choose a print template in Lightroom Help.

With the optional Picture Package plug-in, you can place multiple copies of an image on a single page, much as portrait studios do with school photos. You can also place different images on the same page. You can choose from a variety of size and placement options to customize your package layout.

1 Picture Package is an optional plug-in. Download and install it for Windows or Mac OS.

Run Photoshop in 32-bit mode (64-bit Mac OS only) .

2 Do one of the following:

- (Photoshop) Choose File > Automate > Picture Package. If you have multiple images open, Picture Package uses the frontmost image.

- (Bridge) Choose Tools > Photoshop > Picture Package. The Picture Package command uses the first image listed in Bridge unless you select a specific image before giving the Picture Package command.

If you're using only the frontmost image or a selected image from Bridge, skip to step 3.

3 Add one or more images to the layout by doing one of the following:

- In the Source Images area of the Picture Package dialog box, choose either File or Folder from the Use menu and click Browse (Windows) or Choose (Mac OS). If you choose Folder, you can select Include All Subfolders to include images inside any subfolders.
- Click a placeholder in the preview layout and browse to select an image.



- Drag an image from the desktop or a folder into a placeholder.



You can change any image in the layout by clicking a placeholder and browsing to select an image.

4 In the Document area of the Picture Package dialog box, select page size, layout, resolution, and color mode. A thumbnail of the chosen layout appears on the right side of the dialog box.

5 Select Flatten All Layers to create a picture package with all images and label text on a single layer. Deselect Flatten All Layers to create a picture package with separate image layers and text layers (for labels). If you place each image and label on a separate layer, you can update your picture package after it's been saved. However, the layers increase the file size of your picture package.

6 In the Label area, choose the source for label text from the Content menu or choose None. If you choose Custom Text, enter the text for the label in the Custom Text field.

7 Specify font, font size, color, opacity, position, and rotation for the labels.

8 Click OK.

Customize a picture package layout

You can modify existing layouts or create new layouts using the Picture Package Edit Layout feature. Custom layouts are saved as text files and stored in the Layouts folder inside the Presets folder. You can then reuse your saved layouts. The Picture Package Edit Layout feature uses a graphic interface that eliminates the need to write text files to create or modify layouts.

1 Do one of the following:
   - (Photoshop) Choose File > Automate > Picture Package.
   - (Bridge) Choose Tools > Photoshop > Picture Package.
2 In the Picture Package dialog box, choose a layout from the Layout menu if you're creating a layout or customizing an existing one.
3 Click the Edit Layout button.
4 In the Picture Package Edit Layout dialog box, enter a name for the custom layout in the Name text box.
5 (Optional) In the Layout area of the Picture Package Edit Layout dialog box, choose a size from the Page Size menu or enter values in the Width and Height text boxes. You can use the Units menu to specify inches, centimeters, pixels, or millimeters.



6 In the Grid area of the Picture Package Edit Layout dialog box, select the Snap To option to display a grid to help you position the elements in the custom layout. Enter a value in the Size text box to change the appearance of the grid.
7 To add or delete a placeholder, do one of the following:
   - Click Add Zone to add a placeholder to the layout.
   - Select a placeholder and click Delete Zone to delete it from the layout.
8 To modify a placeholder, select a placeholder and do any of the following:
   - Enter values in the Width and Height text boxes to resize a placeholder.
   - Click and drag a handle to resize a placeholder. If you resize a rectangle placeholder with an image in it, Picture Package will snap the image within the vertical or horizontal placeholder, depending on the way the zone is being resized.
   - Enter values in the X and Y text boxes to move a placeholder.
   - Click and drag a placeholder to the location you want in the layout.
9 Click Save.

Printing spot colors

About spot colors

Spot colors are special premixed inks used instead of, or in addition to, the process color (CMYK) inks. Each spot color requires its own plate on the press. (Because a varnish requires a separate plate, it is considered a spot color, too.)

If you are planning to print an image with spot colors, you need to create spot channels to store the colors. To export spot channels, save the file in DCS 2.0 format or PDF.

Note the following when working with spot colors:

- For spot color graphics that have crisp edges and knock out the underlying image, consider creating the additional artwork in a page layout or illustration application.
- To apply spot color as a tint throughout an image, convert the image to Duotone mode and apply the spot color to one of the duotone plates. You can use up to four spot colors, one per plate.
- The names of the spot colors are printed on the separations.
- Spot colors are overprinted on top of the fully composited image. Each spot color is printed in the order it appears in the Channels panel, with the topmost channel printing as the topmost spot color.
- You cannot move spot colors above a default channel in the Channels panel except in Multichannel mode.
- You cannot apply spot colors to individual layers.
- Printing an image with a spot color channel to a composite color printer will print the spot color at an opacity indicated by the Solidity setting.
- You can merge spot channels with color channels, splitting the spot color into its color channel components.

Create a new spot channel

You can create a new spot channel or convert an existing alpha channel to a spot channel.

1. Choose Window > Channels to display the Channels panel.
2. To fill a selected area with a spot color, make or load a selection.
3. Do one of the following to create a channel:
   - Ctrl-click (Windows) or Command-click (Mac OS) the New Channel button in the Channels panel.
   - Choose New Spot Channel from the Channels panel menu.

   If you made a selection, that area is filled with the currently specified spot color.
4. In the New Spot Channel dialog box, click the Color box. Then in the Color Picker, click Color Libraries to choose from a custom color system such as PANTONE or TOYO and choose a color. See Choose a spot color.

   If you select a custom color, your print service provider can more easily provide the proper ink to reproduce the image.
5. Enter a name for the spot channel. If you choose a custom color, the channel automatically takes the name of that color.

   Be sure to name spot colors so they'll be recognized by other applications reading your file. Otherwise the file might not print.

6 For Solidity, enter a value between 0% and 100%.

This option lets you simulate on-screen the density of the printed spot color. A value of 100% simulates an ink that completely covers the inks beneath (such as a metallic ink); 0% simulates a transparent ink that completely reveals the inks beneath (such as a clear varnish). You can also use this option to see where an otherwise transparent spot color (such as a varnish) will appear.



Note: *The Solidity and color choice options affect only on-screen previews and composite prints. They have no effect on printed separations.*

Convert an alpha channel to a spot channel

1 If a selection is active in the image, choose Select > Deselect.

2 Do one of the following:

- Double-click the alpha channel thumbnail in the Channels panel.
- Select the alpha channel in the Channels panel, and choose Channel Options from the panel menu.

3 Select Spot Color.

4 Click the color box, then choose a color in the Color Picker or click Color Libraries and choose a custom color. Click OK.

5 Rename the channel if needed.

6 Click OK.

The areas of the channel containing grayscale values are converted to spot color.

7 To apply the color to the selected area of the channel, choose Image > Adjustments > Invert.

Edit a spot channel to add or remove color

1 Select the spot channel in the Channels panel.

2 Use a painting or editing tool to paint in the image. Paint with black to add more spot color at 100% opacity; paint with gray to add spot color with lower opacity.

Note: *Unlike the Solidity option in the Spot Channel Options dialog box, the Opacity option in the painting or editing tool's options determines the actual density of ink used in the printed output.*

Change a spot channel's color or solidity

1 Double-click the spot channel thumbnail in the Channels panel.

2 Click the color box, and choose a color. Click Color Libraries to choose from a custom color system such as PANTONE or TOYO.

3 Enter a Solidity value between 0% and 100% to adjust ink opacity for the spot color.

Note: The Solidity and color choice options affect only on-screen previews and composite prints. They have no effect on printed separations.

Merge spot channels

In RGB or CMYK color mode, you can remove spot channels and merge them into the standard color channels. When you merge spot channels in CMYK mode, the resulting colors usually don't precisely match the original spot colors, because CMYK inks can't produce the range of colors available from spot color inks.

1 Select the spot channel in the Channels panel.

2 Choose Merge Spot Channel from the panel menu.

The spot color is converted to and merged with the color channels. The spot channel is deleted from the panel.

Merging spot channels flattens layered images. The merged composite reflects the preview spot color information, including the Solidity settings. For example, a spot channel with a solidity of 50% will produce different merged results than the same channel with a solidity of 100%.

Adjust overlapping spot colors

To prevent overlapping spot colors from either printing over or knocking out the underlying spot color, remove one of the spot colors where they overlap.

Use a printed sample of the overprinted inks to adjust your screen display to help you predict how colors will look when printed.

Note: In some cases, such as when you use varnish and bump plates, you may want colors to overprint.

1 In the Channels panel, select the spot channel with the color you want to print.

2 Choose Select > Load Selection.

To quickly select an image in a channel, hold down Ctrl (Windows) or Command (Mac OS), and click the channel in the Channels panel.

3 For Channel, choose the spot channel from step 1, and click OK.

4 To create a trap when knocking out the underlying color, choose Select > Modify > Expand or Contract, depending on whether the overlapping spot color is darker or lighter than the spot color beneath it. In the Channels panel, select the underlying spot channel that contains the areas you want to knock out. Press Backspace (Windows) or Delete (Mac OS).

You can use this method to knock out areas from any channels under a spot color, such as the CMYK channels.

5 If a spot color in one channel overlaps more than one other spot color, repeat this process for each channel that contains the areas you want removed.

More Help topics

About channels

Print separations from Photoshop

Choose a spot color

Create a color trap

Print images to a commercial printing press

Preparing images for press

From Photoshop, you can prepare image files for offset lithography, digital printing, gravure, and other commercial printing processes.

Generally, your workflow depends on the capabilities of the prepress facility. Before you begin a workflow for commercial printing, contact the prepress staff to learn their requirements. For example, they may not want you to convert to CMYK at any point because they may need to use prepress-specific settings. Here are some possible scenarios for preparing your image files to achieve predictable printing results:

- Work entirely in RGB mode and make sure that the image file is tagged with the RGB working space profile. If your printer or prepress staff use a color management system, they should be able to use your file's profile to make an accurate conversion to CMYK before producing the film and printing plates.
- Work in RGB mode until you finish editing your image. Then convert the image to CMYK mode and make any additional color and tonal adjustments. Especially check the highlights and shadows of the image. Use Levels, Curves, or Hue/Saturation adjustment layers to make corrections. These adjustments should be very minor. Flatten the file if necessary, then send the CMYK file to the professional printer.
- Place your RGB or CMYK image in Adobe InDesign or Adobe Illustrator. In general, most images printed on a commercial press are not printed directly from Photoshop but from a page-layout program like Adobe InDesign or an illustration program like Adobe Illustrator. For more information on importing Photoshop files into Adobe InDesign or Adobe Illustrator, see Adobe InDesign Help or the Adobe Illustrator Help.

Here are a few issues to keep in mind when you work on an image intended for commercial printing:

- If you know the characteristics of the press, you can specify the highlight and shadow output to preserve certain details.
- If you use a desktop printer to preview the appearance of the final printed piece, keep in mind that a desktop printer cannot faithfully replicate the output of a commercial printing press. A professional color proof gives a more accurate preview of the final printed piece.
- If you have a profile from a commercial press, you can choose it with the Proof Setup command and then view a soft proof using the Proof Colors command. Use this method to preview the final printed piece on your monitor.

Note: *Some printers may prefer to receive your documents in PDF format, especially if the documents need to conform to PDF/X standards. See Save in Photoshop PDF format.*

Set output options

If you are preparing your images for commercial printing directly from Photoshop, you can select and preview a variety of page marks and other output options using the Print command. Generally, these output options should be specified only by prepress professionals or people knowledgeable about the commercial printing process.

A Gradient tint bar B Label C Registration marks D Progressive color bar E Corner crop mark F Center crop mark G Description H Star target

1 Choose File > Print.

2 Choose Output from the pop-up menu.

3 Set one or more of the following options:

Calibration Bars Prints an 11-step grayscale, a transition in density from 0 to 100% in 10% increments. With a CMYK color separation, a gradient tint bar is printed to the left of each CMYK plate, and a progressive color bar to the right.

Note: *Calibration bars, registration marks, crop marks, and labels are printed only if the paper is larger than the printed image.*

Registration Marks Prints registration marks on the image (including bull's-eyes and star targets). These marks are used primarily for aligning color separations on PostScript printers.

Corner Crop Marks Prints crop marks where the page is to be trimmed. You can print crop marks at the corners. On PostScript printers, selecting this option will also print star targets.

Center Crop Marks Prints crop marks where the page is to be trimmed. You can print crop marks at the center of each edge.

Description Prints any description text entered in the File Info dialog box, up to about 300 characters. Description text is always printed in 9-point Helvetica plain type.

Labels Prints the file name above the image. If printing separations, the separation name is printed as part of the label.

Emulsion Down Makes type readable when the emulsion is down—that is, when the photosensitive layer on a piece of film or photographic paper is facing away from you. Normally, images printed on paper are printed with emulsion up, with type readable when the photosensitive layer faces you. Images printed on film are often printed with emulsion down.

Negative Prints an inverted version of the entire output, including all masks and any background color. Unlike the Invert command in the Image menu, the Negative option converts the output, not the on-screen image, to a negative. If you print separations directly to film, you probably want a negative, although in many countries film positives are common. Check with your print shop to determine which is required. To determine the emulsion side, examine the

film under a bright light after it has been developed. The dull side is the emulsion; the shiny side is the base. Check whether your print shop requires film with positive emulsion up, negative emulsion up, positive emulsion down, or negative emulsion down.

Background Selects a background color to be printed on the page outside the image area. For example, a black or colored background may be desirable for slides printed to a film recorder. To use this option, click Background, and then select a color from the Color Picker. This is a printing option only; it does not affect the image itself.

Border Prints a black border around an image. Type a number and choose a unit value to specify the width of the border.

Bleed Prints crop marks inside rather than outside the image. Use this option to trim the image within the graphic. Type a number and choose a unit value to specify the width of the bleed.

Interpolation Reduces the jagged appearance of a low-resolution image by automatically resampling up while printing (on PostScript printers). Resampling may reduce the sharpness of the image quality.

For information on the Include Vector Data option, see Print vector data.

Print separations from Photoshop

When preparing your image for prepress and working with CMYK images or images with spot colors, you can print each color channel as a separate page.

Note: *Separations from CMYK, Duotone, or multi-channel documents printed on non-PostScript printers may not be identical to those printed on PostScript printers.*

Note: *If you are printing an image from another application and want to print spot channels to spot color plates, you must first save the file in DCS 2.0 format. DCS 2.0 preserves spot channels. This format is supported by applications such as Adobe InDesign and QuarkXPress.*

1 Make sure that your document is in CMYK Color, Multichannel, or Duotone mode, and then choose File > Print.

2 Choose Separations from the Color Handling drop-down menu.

   Note: *Depending on the designated printer and printer drivers on your computer, these options may also appear in the Print Settings dialog box. In Windows, click the Properties button to access the printer driver options; in Mac OS, use the pop-up menu in the Print Settings dialog box that appears.*

3 Click Print. Separations are printed for each of the colors in the image.

Prepare an image with spot channels for printing from another application

1 If the image is a duotone, convert it to Multichannel color mode.

2 Save the image in DCS 2.0 format.

3 In the DCS 2.0 Format dialog box, deselect the Include Halftone Screen and the Include Transfer Function options.

4 Open or import the image in Photoshop, and set your screen angles. Make sure that you've communicated to the printer the spot color you want for each of the color plates.

Note: *You can place a PSD file containing spot colors directly in Illustrator or InDesign without special preparation.*

Create a color trap

A *trap* is an overlap that prevents tiny gaps in the printed image caused by a slight misregistration on press. Contact your service provider before you do any trapping. In most cases, your print shop determines whether trapping is needed. If so, the print shop staff will tell you what values to enter in the Trap dialog box.



A *Misregistration with no trap* ***B*** *Misregistration with trap*

Trapping is intended to correct the misalignment of solid colors. In general, you don't need traps for continuous-tone images such as photographs. Excessive trapping may produce an outline effect. These problems may not be visible on-screen and might show up only in print. Photoshop uses standard rules for trapping:

- All colors spread under black.
- Lighter colors spread under darker colors.
- Yellow spreads under cyan, magenta, and black.
- Pure cyan and pure magenta spread under each other equally.

1 Choose Edit > Convert To Profile to view the image in the color space of the output device. See Convert document colors to another profile (Photoshop) .

2 Choose Image > Trap.

3 For Width, enter the trapping value provided by your print shop. Then select a unit of measurement, and click OK. Consult your print shop to determine how much misregistration to expect.

Determine scan resolution for printing

You can use a number of techniques to determine the resolution at which to scan a photograph. If you are scanning photos to be printed, and you know the exact size and the printing screen frequency, you can use the following techniques to determine the scanning resolution. Often it is easiest to scan at your scanner's maximum optical resolution and then resize the image in Photoshop later.

Estimate scan resolution

You can determine the resolution for your scan using the original and final image dimensions and the resolution of your output device. Scan resolution translates into image resolution when you open the scanned image in Photoshop.

1 Do one of the following:

- For laser printers and imagesetters, multiply the printer's screen frequency by 2. To determine your printer's screen frequency, check your printer documentation or consult your service provider.
- For inkjet printers, check your printer documentation for the optimal resolution. Many dye sublimation printers and devices that print directly onto photographic paper have an optimal resolution of 300 to 400 dpi.

2 Determine the ratio of the final image dimensions to the original image dimensions. For example, the ratio of a 6-by-9-inch final image to a 2-by-3-inch original image is 3:1.

3 Multiply the result of step 1 by the result of step 2.

For example, suppose you are printing to an imagesetter with a screen frequency of 85 lpi and the ratio of the final image to the original is 3:1. First multiply 85 (the screen frequency) by 2 to get 170. Then multiply 170 by 3 to get a scan resolution of 510 ppi. If you are printing to an inkjet printer with an optimal resolution of 300 dpi, multiply 300 by 3 to get a scan resolution of 900.

Note: *Different color separation procedures might require different ratios of image resolution to screen frequency. It's a good idea to check with your service provider or print shop before you scan the image.*

Calculate the file size before scanning an image

You can create a dummy file to predict the file size needed for the final output of your scan.

1 In Photoshop, choose File > New.

2 Enter the width, height, and resolution of your final printed image. The resolution should be 1.5 to 2 times the screen frequency you will use to print. Make sure that the mode you plan to scan in is selected. The New dialog box displays the file size.

For example, suppose you want the final image to be 4 inches wide and 5 inches high. You plan to print it with a 150-line screen using a 2:1 ratio, so you set the resolution to 300. The resulting file size is 5.15 MB.

To produce the scan, enter the resulting file size in your scanner settings. Don't worry about resolution or image dimensions. After you have scanned the image and imported it into Photoshop, use the Image Size command (with the Resample Image option deselected) to enter the correct width and height for the image.

More Help topics

Soft-proof colors

Resampling

Save in Photoshop EPS format

Duotones

About duotones

In Photoshop, *duotone* refers to monotones, tritones, and quadtones as well as duotones. Monotones are grayscale images printed with a single, non-black ink. Duotones, tritones, and quadtones are grayscale images printed with two, three, and four inks. In these images, colored inks, rather than different shades of gray, are used to reproduce tinted grays.

Duotones increase the tonal range of a grayscale image. Although a grayscale reproduction can display up to 256 levels of gray, a printing press can reproduce only about 50 levels of gray per ink. For this reason, a grayscale image printed with only black ink can look significantly coarser than the same image printed with two, three, or four inks, each individual ink reproducing up to 50 levels of gray.

Sometimes duotones are printed using a black ink and a gray ink—the black for shadows and the gray for midtones and highlights. More frequently, duotones are printed using a colored ink for the highlight color. This technique produces an image with a slight tint and significantly increases the dynamic range of the image. Duotones are ideal for two-color print jobs with a spot color (such as a PANTONE Color) used for accent.

Because duotones use different color inks to reproduce different gray levels, they are treated in Photoshop as single-channel, 8-bit, grayscale images. In Duotone mode, you do not have direct access to the individual image channels (as in RGB, CMYK, and Lab modes). Instead, you manipulate the channels through the curves in the Duotone Options dialog box.

Convert an image to duotone

1. Convert the image to grayscale by choosing Image > Mode > Grayscale. Only 8-bit grayscale images can be converted to duotones.
2. Choose Image > Mode > Duotone.
3. In the Duotone Options dialog box, select Preview to preview the image.
4. For the Type option, select Monotone, Duotone, Tritone, or Quadtone.
5. Click the color box (the solid square) to open the color picker, then click the Color Libraries button and select an ink book and color from the dialog box.

   Note: *To produce fully saturated colors, specify inks in descending order—darkest at the top, lightest at the bottom.*
6. Click the curve box next to the color ink box and adjust the duotone curve for each ink color.
7. Set overprint colors, if necessary.
8. Click OK.

To apply a duotone effect to only part of an image, convert the duotone image to Multichannel mode—this converts the duotone curves to spot channels. You can then erase part of the spot channel for areas that you want printed as standard grayscale.

Modify the duotone curve for a given ink

In a duotone image, each ink has a separate curve that specifies how the color is distributed across the shadows and highlights. This curve maps each grayscale value in the original image to a specific ink percentage.

1 To preview any adjustments, select the Preview option in the Duotones Options dialog box.

2 Click the curve box next to the ink color box.

The default duotone curve, a straight diagonal line, indicates that the grayscale values in the original image map to an equal percentage of ink. At this setting, a 50% midtone pixel is rendered with a 50% tint of the ink, a 100% shadow is rendered in 100% color, and so on.

3 Adjust the duotone curve for each ink by dragging a point on the graph or by entering values for the different ink percentages.

- In the curve graph, the horizontal axis moves from highlights (at the left) to shadows (at the right). Ink density increases as you move up the vertical axis. You can specify up to 13 points on the curve. When you specify two values along the curve, Photoshop calculates intermediate values. As you adjust the curve, values are automatically entered in the percentage text boxes.
- The value you enter in the text box indicates the percentage of the ink color used to represent the grayscale value in the original image. For example, if you enter 70 in the 100% text box, a 70% tint of that ink color is used to print the 100% shadows.

4 Click Save in the Duotone Curve dialog box to save curves created with this dialog box.

5 Click Load to load these curves or curves created in the Curves dialog box, including curves created using the Arbitrary Map option.

You can use the Info panel to display ink percentages when you're working with duotone images. Set the readout mode to Actual Color to determine what ink percentages will be applied when the image is printed. These values reflect any changes you've entered in the Duotone Curve dialog box.

Specifying overprint colors

Overprint colors are two unscreened inks printed on top of each other. For example, when you print a cyan ink over a yellow ink, the resulting overprint color is green. The order in which inks are printed, as well as variations in the inks and paper, can significantly affect the final results.

To predict how colors will look when printed, use a printed sample of the overprinted inks and adjust your screen display accordingly. Keep in mind that this adjustment affects only how the overprint colors appear on-screen, not when printed. Before adjusting these colors, make sure to calibrate your monitor.

Adjust the display of overprint colors

1 Choose Image > Mode > Duotone.

2 Click Overprint Colors. The Overprint Colors dialog box shows how the combined inks will look when printed.

3 Click the color swatch of the ink combination that you want to adjust.

4 Select the desired color in the Color Picker, and click OK.

5 Repeat steps 3 and 4 until you are satisfied with the ink combination. Then click OK.

Saving and loading duotone settings

Use the Save button in the Duotone Options dialog box to save a set of duotone curves, ink settings, and overprint colors. Use the Load button to load a set of duotone curves, ink settings, and overprint colors. You can then apply these settings to other grayscale images.

Photoshop includes several sample sets of duotone, tritone, and quadtone curves. These sets include some commonly used curves and colors. Use these sets as starting points when you create your own combinations.

View the individual colors of a duotone image

Because duotones are single-channel images, your adjustments to individual printing inks are displayed as part of the final composite image. In some cases, you may want to view the individual "printing plates" to see how the individual colors will separate when printed (as you can with CMYK images).

1 After specifying your ink colors, choose Image > Mode > Multichannel.

   The image is converted to Multichannel mode, with each channel represented as a spot color channel. The contents of each spot channel accurately reflect the duotone settings, but the on-screen composite preview may not be as accurate as the preview in Duotone mode.

   Note: *If you make any changes to the image in Multichannel mode, you can't revert to the original duotone state (unless you can access the duotone state in the History panel). To adjust the distribution of ink and view its effect on the individual printing plates, make the adjustments in the Duotone Curves dialog box before converting to Multichannel mode.*

2 Select the channel you want to examine in the Channels panel.

3 Choose Edit > Undo Multichannel to revert to Duotone mode.

Printing duotones

When creating duotones, keep in mind that both the order in which the inks are printed and the screen angles you use have a significant effect on the final output. (If needed, change the halftone screen angles on the printer's RIP.)

You do not have to convert duotone images to CMYK to print separations—simply choose Separations from the Profile pop-up menu in the Color Management section of the Print dialog box (for setting printer options). Converting to CMYK mode converts any custom colors to their CMYK equivalents.

Exporting duotone images to other applications

To export a duotone image to a page-layout application, you must first save the image in EPS or PDF format. (However, if the image contains spot channels, convert it to Multichannel mode and save it in DCS 2.0 format.) Remember to name custom colors using the appropriate suffix so that the importing application can recognize them. Otherwise, the application may not print the colors correctly, or it may not print the image at all.

More Help topics

About spot colors

Curves overview

Troubleshoot printing problems | Photoshop

This document provides troubleshooting steps to help you resolve general printing problems in Adobe Photoshop.

For solutions to a specific printing problem, try searching the Adobe Support knowledgebase.

Before you begin

Before you can troubleshoot the problem, determine its cause.

Determine the cause of the printing problem

1 Create a 2x2 inch RGB, 72-ppi image, paint a line in the image, and print it.

- If that image prints correctly, it's possible that your file is damaged. See Resolve problems printing a specific image from Photoshop in this document.
- If the image doesn't print correctly, go to Step 2.

Island Girl.jpg

2 Print another type of file (for example, a plain text file) from another application (such as Microsoft Word or TextEdit).

- If that file prints correctly, the problem isn't system-wide. It's specific to Photoshop. However, the way Photoshop interacts with the system can affect printing performance. Go to Step 3 to eliminate some system-related causes of the problem.
- If the file doesn't print correctly, the problem is system-wide. It isn't specific to Photoshop or your files. The problem could be low system resources, insufficient memory on your printer, or a poor connection between your computer and the printer. Go to Step 3 to eliminate some likely causes of the problem.

3 Restart your computer, and then print your image.

- If the image prints correctly, your system could have been out of memory or resources.
- If the image doesn't print correctly, go to Step 4.

4 Turn off your printer for at least 15 seconds to flush its memory, and then turn it back on and print your image.

- If the image prints correctly, the printer's memory was too full.
- If the image doesn't print correctly, go to Step 5.

5 If you are using a network printer, print from another computer.

- If the image prints correctly, the computer you first tried to print from could be unable to connect to the printer or the network correctly. Contact your network administrator, consult your network documentation, or contact the printer manufacturer to help resolve your problem.
- If the file doesn't print correctly, go to Step 6.

6 Print your image to another printer.

- If the image prints correctly, the first computer you printed from could be unable to connect to the printer. Communication, hardware, or memory problems can prevent a computer from connecting to a printer. Make sure that the printer is turned on and connected properly, and then run a self-test on it to make sure that it's working correctly. For instructions, see the documentation that came with the printer or contact the printer manufacturer. If you are using a network printer, consider contacting your network administrator for assistance.
- If the file doesn't print correctly, see Resolve problems printing any file from any application in this document.

Resolve problems printing a specific image from Photoshop

If you have problems printing an individual image from Photoshop, work through this next set of tasks in the order they are presented. Print after each one.

1. Reset the printer preferences in the image.

Press the Spacebar on your keyboard before you click File > Print. This process resets printer preferences that have been written into the image.

2. Check these options in the printer driver.

- In Print Settings, make that sure the Paper Size is accurate.
- Choose the correct paper feeding option for how your paper is actually being fed into the printer. If you select the incorrect option for how the paper is being fed, your image can be cut off, or print in part, or print on the wrong part of the page.
- Check for appropriate paper handling. Using some Epson drivers as an example, select Paper Handling, and make sure that the Destination Paper Size is accurate to your paper. If not, select Scale to fit paper size, and change the Destination Paper Size to the appropriate size. Then deselect Scale to fit paper size if desired. Other printer manufacturers can have something similar.
- Check Printer Settings to make sure that the media type is correct.
- Deselect 16 Bit Output, in case your driver doesn't support 16-bit printing.

3. Save the image as a new file.

Resave the document by choosing File > Save As, and giving the file a new name. The Save As command causes Photoshop to rewrite the file.

4. Rasterize layers or flatten your image.

When you print an image from Photoshop, only the content that is visible onscreen is printed. Rasterize layers or flatten your image to improve performance when printing.

Important: Rasterizing layers or flattening your image removes editable content, such as type and Smart Objects. Before proceeding with this task, make a backup of your existing image.

To rasterize layers:

1. Select the layers that you want to rasterize.
2. Choose Layer > Rasterize, and then choose an option from the submenu.

For more information about rasterizing layers, see Rasterize layers.

To flatten your image, choose Layer > Flatten Image.

For more information about flattening your image, see Merge and stamp layers.

5. Print a composite of the file.

If you encounter problems printing an image with color separations, print a composite of the file to determine if a color plate is the problem. When you print a composite, all the colors print on one plate, regardless of whether individual colors have been selected.

If the problem with your specific image persists after performing the above steps, your file could be damaged. It is also possible that the way that Photoshop interacts with your system is causing the problem. Proceed to Resolve problems printing to any printer from Photoshopfor further troubleshooting steps.

Resolve problems printing any file from any application

If you have problems printing any file from the computer, contact Apple Support, Microsoft Technical Support, or the printer manufacturer. Make sure that the printer is on and check the physical connections between the printer and the computer. The solution could be as simple as reconnecting a loose cable.

Also, note any recent changes to the computer system that can affect printing, such as the following:

- Updates of your hardware or software
- New hardware or software
- Removal of software
- Installing or removing fonts
- Connecting to a network, or other changes to your network configuration
- Rearranging or cleaning up of files on your hard drive

Keep a record of changes made to the system to help you troubleshoot printing and other problems. If the problem persists, work through the other sections in this document, as applicable.

Resolve problems printing to any printer from Photoshop

If you have problems printing from Photoshop, work through this set of tasks in the order they are presented, printing after each one.

1. Verify that you meet or exceed the minimum system requirements for Photoshop.

For an updated list of system requirements, visit System requirements | Photoshop .

2. Use an updated printer driver.

Many printer manufacturers frequently update their software drivers. If you haven't updated the printer driver recently, contact the printer manufacturer for an updated driver, or download one from the manufacturer's website.

3. Delete temporary files from the system (Windows only).

Excess temporary files can cause Photoshop to freeze or appear to freeze when you print.

See the following for details:

- Delete temporary files using the Disk Cleanup utility (Windows XP)
- Delete temporary files using the Disk Cleanup utility (Windows 7 and Vista)

4. Ensure that the printer has enough memory.

Ensure that the printer has enough memory to print all page elements. To print at 300 dpi, make sure that the printer has at least 2 MB of available RAM. To print at 600 dpi, make sure that the printer has at least 4 - 6 MB of RAM. For instructions on determining available printer memory, see the printer documentation.

5. Re-create the instance of the printer (Mac only).

To re-create the instance of the printer:

1. Go to Print & Scan in the System Preferences.
2. Select the printer, and click the Minus (-) button.
3. Click the Plus (+) button.

4 Select a printer or enter the printer's IP address and click Add.

6. Re-create the Photoshop preferences file.

Re-create the Photoshop preferences file to eliminate problems that a damaged preferences file can cause.

For instructions on how to re-create the preferences, watch this tutorial Video: How to Reset Photoshop CS6's Preferences File

Note: When you use this solution, Photoshop creates a preferences file and you lose custom settings associated with your current preferences file. However, the file you rename in step 3 is your original preferences file. If you determine that the preferences file is not causing the problem, then you can restore your custom settings by following the instructions below.

7. Move the image to a local hard disk.

If the file is on a removable drive (for example, a USB hard drive) or network drive, move it to a local hard disk. Adobe recommends storing files on a local hard disk when you open, save. Or, print them to reduce potential problems and damage to your files.

8. Create additional free disk space.

Make sure that plenty of free hard disk space is available on your system drive, or the drive on which you have the file stored. Adobe recommends that free space is equivalent to three to five times the size of the file you print.

To create more space, search for and delete temporary (.tmp) files on your computer, clear your temporary Internet files, or remove unnecessary programs from the computer. For instructions about clearing the temporary Internet files, see the documentation for your Internet browser. For instructions on removing programs, see the documentation for each program.

You can also free up disk space by bypassing the spool file on Windows, which stores temporary files to the system drive during printing. For instructions for bypassing the spool file, see the documentation included with Windows or contact Microsoft Technical Support.

9. Print to a local printer.

If you print to a network printer, try printing the file from a computer that is connected directly to a local printer.

If the file prints correctly, network-related issues or problems with your printer or its device drivers could be the cause. Contact your network administrator, consult the documentation for your printer, or contact the printer manufacturer for assistance.

10. Run Photoshop while no other applications are running.

Some applications or services could cause problems when running concurrently with Photoshop. Before printing from Photoshop, disable startup items that run when your computer starts up.

For Mac, start up into Safe Boot. Safe Boot mode maximizes available RAM and reduces the possibility that another application or background service conflicts with Photoshop. For instructions or assistance starting your computer into Safe Boot mode, see "Mac OS X: Starting up in Safe Mode" (Apple Support Article HT1455). Or contact Apple support.

For Windows, see: Disable startup items, services | Windows for details.

11. Optimize the performance of Photoshop.

See Optimize performance.

Resolve problems printing to a PostScript printer

If you have problems printing from Photoshop to a PostScript printer, work through the tasks below in the order they are presented, printing after each one.

Disclaimer: Some of these solutions require you to change the printer driver properties. The locations for specific properties vary by printer and by printer driver. Therefore, Adobe Technical Support cannot provide detailed information about the location for each property. Contact the printer manufacturer or refer to the printer documentation for more information.

1. Use an updated PPD file.

A PostScript Printer Description (PPD) file describes the capabilities of a PostScript printer for settings such as margins, color, and resolution. Incorrect or outdated PPD files can increase print times or cause other problems. Configure your printer in the Printers Control Panel with the PPD file that the printer manufacturer recommends.

To obtain a PPD file for your device, contact the printer manufacturer.

2. Set up the printer driver to output optimized PostScript code (Windows only).

If you set up the printer driver to output PostScript code that's optimized for portability and in binary format, the amount of scaling the driver must do is minimized, thus preventing it from losing portions of images.

To set your printer driver to output optimized PostScript code, do the following:

1. Choose Start > Control Panel, and then open Printers.
2. Right-click the printer, and choose Properties from the context menu.
3. Select the General tab.
4. Select Printing Preferences, and then click Advanced.
5. Expand the Document Options, and then expand the PostScript Options.
6. Set the PostScript Output option to Optimize For Portability.

3. Install a printer driver that's compatible with your operating system (Windows only).

If you use a network printer, install a printer driver that's compatible with your operating system. Print servers don't always provide drivers for operating systems running on client computers. So, you could be using a printer driver that's appropriate for the print server's operating system but not for your computer's operating system.

To install a printer driver that's compatible with your operating system:

1. Choose Start > Control Panel, and then open Printers.
2. Right-click the network printer, and then choose Delete.
3. Double-click Add Printer, and then click Next.
4. Select Add A Local Printer, and then click Next.
5. Select Create A New Port.
6. Choose Local Port from the Type Of Port menu, and then click Next.
7. In the Port Name dialog box, type the path for the print server and printer (for example, \\printservername\printername), and then click OK.
8. Follow the remaining onscreen instructions to install a driver that matches the brand and model of your network printer.

Resolve problems printing to a non-PostScript printer

If you have problems printing from Photoshop to a non-PostScript printer, work through the tasks below in the order they are presented, printing after each one.

1. Ensure that the printer has enough memory.

Ensure that the printer has enough memory to print all page elements. To print at 300 dpi, make sure that the printer has at least 2 MB of available RAM. To print at 600 dpi, make sure that the printer has at least 4 – 6 MB of RAM.

For instructions on determining available printer memory, see the printer documentation.

2. Enable VGA mode for your video card (Windows only)

VGA mode is a startup option that forces the system into standard 640 x 480 16-color VGA mode by using a video driver that is compatible with any video adapter. Enable VGA mode for your video card to resolve problems related to your video card and it drivers.

To restart Windows into VGA mode:

1. Quit all applications.
2. Choose Start, type **msconfig** in the Search text box, and press Enter.
3. Click the Boot tab.
4. In the Boot Options section, select Base Video.
5. Click OK, and restart Windows.

Note: Upon restart, you could be notified that the System Configuration utility has changed the way that Windows starts. If so, click OK and, when the System Configuration utility appears, click Cancel to exit the utility.

1. To re-enable your original video card driver:
2. Choose Start, type **msconfig** in the Search text box, and press Enter.
3. Click the Boot tab.
4. In the Boot Options section, deselect Base Video.
5. Click OK, and restart Windows.

If you can print correctly from Photoshop using the Windows VGA driver, then the driver for your video card could be damaged, outdated, or incompatible with your printer driver or Photoshop. To obtain an updated video card driver, contact the manufacturer of your video card.

3. Use the printer's PostScript mode

If the printer has a PostScript option, use the PostScript mode. For details, see the printer documentation.

Improve color prints from Photoshop

Who Is This Document For?

This document provides basic instructions for people who:

- work with RGB images, whether created in Photoshop or captured with a digital camera or scanner,

- wish to print their images on an inkjet printer.

This document does not address the needs of people who:

- need measurable color accuracy,
- only wish to post their images to the web,
- print their images by sending them to an online service,
- are preparing images for a printing press,
- work with images in the CMYK color mode.

What Is Color Management?

Color Management refers to the technology and processes used to insure that colors are presented as closely as possible to the way they're intended on multiple devices. No display device or printer can show the range of brightness and color that the human eye can see, and no two devices (including different kinds of printing paper) display exactly the same range of brightness and color.

Further, different devices of the same kind respond differently: if you unplug one model of monitor and plug in another without changing any software settings, images will look different on the new monitor. If you change paper in your printer without changing any software settings, images will look different on the new paper.

Color management addresses these issues. You can get quite good results with minimal equipment and a small investment of time in some simple procedures. If you require results with extreme and measurable accuracy, more complex procedures and equipment are required. This document is biased strongly toward the simple end of that scale. Color management can get you as close as physics allows, but there will always be a difference between monitor and print (see below). Most importantly, color management makes that difference consistent and predictable. Your prints won't be green sometimes and pink other times, or unpredictably dark or light.

What Are Color Profiles?

Color management is based on the use of color profiles. For our purposes, there are two kinds of color profiles:

1. Device profiles are associated with a device such as a display or a printer and specific ink and paper. They describe how that device displays color, including which colors it can and can't display.
2. Working profiles are associated with a document in Photoshop, such as an image captured by a digital camera. They describe how the RGB values in the document correspond to the actual colors that we see, and determines which colors can be represented in the document. The working profile of a document is set when that document is created, whether it's a JPEG file from a digital camera or scanner, a new document created in Photoshop, or a document created by opening a digital camera RAW image in Adobe Camera Raw. The two most common working profiles are sRGB and AdobeRGB.

1. The ProPhotoRGB. This color space is used by people who want to make sure they are retaining all the color information possible from their image captures. It's one of those "you probably only want to use it if you already know why you want to use it" features, and is more appropriate for highest-end printers. The most important thing to know about using ProPhotoRGB as a working space is that to avoid paying for those extra colors with a greater risk of banding (visible steps between colors) in your images, you should work in 16 bit mode. ProPhotoRGB can represent many more colors than even AdobeRGB, including a relatively small slice of colors that high end inkjet printers can print that cannot be represented in AdobeRGB. It also includes a huge number of colors that digital cameras can capture but that can't be displayed on any output device or printer, and even more colors that humans can see but that can't be captured with any input device or displayed by any output device. What's the use of all these colors if you can't display or print them? First, you can be sure you haven't thrown away any information that your camera captured until you absolutely

must (when you output the file). For example, you could make a big hue / saturation change that moves previously unviewable and unprintable range of purplish reds into a range of deep blues that can be displayed. Or you might perform a sequence of editing steps that temporarily create extreme, unprintable colors and then later restore them to a printable range (say, by boosting overall color saturation and then cutting it back in specific areas). Having all those extra colors lets you do this without destroying color differences in the image. But ProPhotoRGB comes with a cost: To avoid banding you should work in 16 bit mode, which doubles file sizes, memory requirements, and operation times. Most Photoshop operations are available in 16 bit mode, but many of the creative filter operations are not.

AdobeRGB can represent more colors than sRGB — specifically including more saturated colors that inkjet printers can print. This profile is most appropriate for mid-range printers. So if you plan to print your images on an inkjet printer, you may wish to use AdobeRGB as your working space. You do this by setting your digital camera or scanner software to output AdobeRGB files, setting the output settings within Adobe Camera Raw to output AdobeRGB files, or, if creating documents from scratch in Photoshop, selecting Adobe RGB from the Color Profile pop-up in the advanced section of the New Document dialog.

sRGB can represent fewer colors than AdobeRGB, and inkjet printers can print many of those colors. This profile is best for all-in-one printers (that include a scanner and/or fax). So if you use sRGB, you will never see some of the more saturated colors that your digital camera or scanner can capture and your printer could print. But sRGB does include the vast majority of colors in the vast majority of images. Most monitors connected to the Internet are not color managed in any way, but they have device profiles that are close to sRGB, and many online print services require files that they print to have a working profile of sRGB. That means that for files to be posted on the internet or sent to such an online service, you should either use a working space of sRGB, or convert the file to sRGB before posting or sending it. You can convert a document to sRGB either by choosing Edit >Convert to Profile, and choosing sRGB as the Destination Space (leave other settings as they are), or by selecting the Convert To sRGB checkbox in the Save For Web And Devices dialog when saving a JPEG for the web.

Tips for Better Color Prints:

Here are some fundamental tips for color management (the first two being the most important):

Set up a reasonable and consistent lighting environment for the monitor you use for editing.

- Low lighting that doesn't vary much by time of day and has no light sources falling directly on the screen is ideal (you don't want to see reflections of lights or bright objects in the screen when it's off). Conversely, the worst possible setup would be one in which the sun shines on your monitor in the morning and in your face in the afternoon.

Profile and calibrate the monitor every 6 months or so.

- Even the least expensive modern monitor calibrators (under $150) will produce more accurate and consistent results than the software calibration functions built into the Mac and Windows operating systems. In turn, those will produce better results than not calibrating your monitor at all.

Whichever method you use, the result will be a profile of your monitor with those settings. The next time you launch Photoshop, it will use your newly created profile. Do not change the settings on your monitor after you profile it — specifically do not change brightness, contrast, or color settings. If you do change settings or significantly change the lighting environment, you should repeat the profiling process.

The built-in screens of laptops are not ideal for obtaining good color matches with prints.

- Good color management requires a monitor that has been profiled; its controls must be set the same way as when the profile was created. Laptop screens can be more non-uniform (with different color and brightness in different parts of the screen) than high-quality desktop monitors, and they are set very bright and/or with brightness automatically varying based on the ambient light. That is great for web browsing in bright light and coffee shops, but your prints will always look dark — or worse, sometimes OK, sometimes a little too dark, and sometimes far too dark.

- Laptop screens, however, have improved greatly over the last several years. If you plan to use your laptop screen for editing images to be printed, and if the calibration device or built-in software doesn't guide you to a particular brightness level, try about one-third to one-half the maximum brightness level. Whenever you edit images, return the display to those settings, or you will be frustrated by poor and unpredictable results.

Make sure you have profiles for the printer and paper combinations you'll be using (do this when you first start using a new kind of printer paper)

- Most inkjet printers today — especially ones meant for imaging rather than business use — come with reasonably good profiles for various types of paper made by the printer manufacturer, and those profiles are installed along with the printer software. If you're using a new kind of paper, or a paper that isn't made by the printer manufacturer, you will have to obtain a profile from the paper manufacturer's website or another source.

Do not use cheap ink in your inkjet printer

- Inkjet ink is expensive — but for low volume, high quality printing there is no easy budget alternative to the printer manufacturer's ink. Save budget replacement ink for word processing documents and spreadsheets with graphics. For color accuracy and consistency, use either the printer manufacturer's ink or specialty imaging ink such as that made by Lyson (use of specialty ink will also require custom profiles — a printer profile is specific to the combination of printer, ink, and paper). Inexpensive store brand inks carry a high risk of poor and variable color results and significantly lowered print longevity.

Prepare a lighting environment near your monitor for viewing prints (do this once when you set up your computer workspace).

- You need a space near your monitor that has light suitable for viewing the print — preferably similar to the light in which it will eventually be viewed, and preferably near the monitor so you can look from one to the other. Generally that won't be direct sunlight (which would make it hard to see your monitor anyway), and it won't be pitch darkness (which might be tempting for viewing your monitor, but then you can't see your prints). It's often best not to hold the print up right next to the monitor because if there's good light for print viewing in that position, there's probably light reflecting off the monitor, which is bad. On the desk to one side is ideal.

  No matter what you do, your prints will never match your monitor exactly, because:

  - The monitor is emitting light and the print is reflecting light.
  - The print will look somewhat different depending on the light in which it is viewed: it will look different under incandescent light, indirect sunlight, and fluorescents.
  - The monitor and the print can't represent all the same colors nor the same range of brightness from light to dark. For example, the monitor can likely produce some deep blues and reddish-purples that your printer can't print — especially if you're printing on matte paper. The monitor can show a hugely greater brightness difference from black to white than can the printer (again, especially if you're printing on matte paper). The printer can probably print middle tone and deep blue-greens and greens that the monitor can't display. The color management software modifies many of the colors in the document to provide the best overall result on each device. It doesn't just take the colors that are too saturated to represent on a particular device and replace them with the closest color that can be shown. That would eliminate all detail in colors near the extremes of the device's capabilities. Instead, it shifts many colors subtly to preserve overall appearance.

Use soft proofing to get a better idea of what your print will look like (do this as desired, or each time before you print)

- If you've calibrated your monitor, what Photoshop is showing you on the screen is the most accurate representation possible of your document. If you then print that document using an appropriate profile, it will print the most accurate representation of your document that the printer can print. Because of the factors listed above, those will usually be quite different.

- Instead of having Photoshop show the most accurate possible representation of your document on the screen, it can show the most accurate possible representation of what the print will look like — taking into account the colors your printer can't print, and the decreased range of dark to light tones that the printer can produce. Because of these differences, a soft proof (onscreen preview of print colors) will always look duller than the original image. You may want to use this information to increase the contrast or saturation of certain areas of your image to compensate, though obviously if a color isn't there because the printer can't print it, nothing you can do to the file will create that color in the print. This preview is still limited by the lighting environment, plus the fact that there are colors the printer can print that the monitor can't display. But it'll give you a better idea of what the print will look like than the normal ("best possible image of the document") display.

To see a soft proof of your document, choose View > Proof Setup > Custom and set the dialog items as follows:

- Device to Simulate: Pick the profile for the printer and paper combination you want to proof.
- Preserve RGB Numbers: Deselected
- Rendering Intent: Perceptual or Relative Colorimetric (you usually won't see much difference between these, but the one you choose should match the one you pick in the print dialog when you print the document)
- Black Point Compensation: Selected
- Simulate Paper Color: Selected
- Simulate Ink Black: Selected

Then click OK.

This prepares settings for this particular paper and printer combination and turns on soft proofing. To toggle soft proofing for this setup on and off, choose View >Proof Colors. You can perform any editing operation while soft proofing is on.

Chapter 18: Automation

Create data-driven graphics

Data-driven graphics make it possible to produce multiple versions of an image quickly and accurately for print or web projects. For example, you can produce 100 versions of a web banner with different text and images, all based on a template design.

Follow these general steps to create graphics from templates and data sets:

Create the base graphic to use as the template.

Use layers to separate the elements that you want to change in the graphic.

Define variables in the graphic.

Variables specify the parts of the image that change. (See Define variables.)

Create or import the data sets.

You can create the data sets in the template, or import them from a text file. (See Define a data setand Creating data sets in external files.)

Preview the document with each data set.

To see how your final graphics will look, you can preview before you export all the files. (See Preview or apply a data set.)

Generate your graphics by exporting them with the data.

You can export them as Photoshop (PSD) files. (See Generate graphics using data sets.)



A Source file template ***B*** *User defines layers as variables.* ***C*** *Different versions of the image can be created, each with a different variable data set.*

Define variables

You use variables to define which elements in a template change. You can define three types of variables. Visibility variables show or hide the content of a layer. Pixel Replacement variables replace the pixels in the layer with pixels from another image file. Text Replacement variables replace a string of text in a type layer.

Note: *GoLive recognizes all text and visibility variables, but not Pixel Replacement variables.*



A Visibility variable ***B*** *Pixel Replacement variable* ***C*** *Text Replacement variable*

You cannot define variables for the Background layer.

1 Choose Image > Variables > Define.

2 Select a layer from the Layer pop-up menu that contains the content you want to define as a variable.

3 Select one or more types of variables:

Visibility Shows or hides the content of the layer.

Pixel Replacement Replaces the pixels in the layer with pixels from another image file.

Text Replacement Replaces a string of text in a type layer.

4 Do one of the following:

- Choose Name and enter a name for the variable. Variable names must begin with a letter, underscore, or colon and cannot contain spaces or special characters (except for periods, hyphens, underscores, and colons).
- Choose an existing variable from the Name pop-up menu to link this layer to. Layers linked to the same variable are shown next to the Name menu, along with the link icon.

5 For Pixel Replacement variables, set the following options.

- Choose a method for scaling the replacement image: Fit scales the image so that it fits in the bounding box (which may leave parts of the bounding box empty), Fill scales the image so that it fills the bounding box entirely (which may cause the image to extend beyond the bounding box), As Is applies no scaling to the image, and Conform scales the image non-proportionally so that it fits in the bounding box.
- Click a handle on the alignment icon to choose an alignment for placing the image inside the bounding box. (This option is not available for Conform.)
- Select Clip To Bounding Box to clip areas of the image that do not fit in the bounding box. This option is available only when the Fill or As Is replacement method is selected. (This option is not available for Conform.)

6 To define variables for another layer, choose a layer from the Layer pop-up menu. An asterisk appears next to the name of a layer that contains variables. You can use the navigation arrows to move between layers.

7 Click OK.

Rename a variable

1 Choose Image > Variables > Define.

2 Choose the layer that contains the variable from the Layer pop-up menu.

3 To rename the variable, enter a name in the Name text box. Variable names must begin with a letter, underscore, or colon and cannot contain spaces or special characters (except for periods, hyphens, underscores, and colons).

4 To remove the variable, deselect it.

Define a data set

A *data set* is a collection of variables and associated data. You define a data set for each version of the graphic that you want to generate.

1 Do one of the following:

- Choose Image > Variables > Data Sets.
- If the Variables dialog box is open, choose Data Sets from the pop-up menu at the top of the dialog box, or click Next.

Note: *You must define at least one variable before you can edit the default data set.*

2 Click the New Data Set button .

3 Select a variable from the Name pop-up menu or the list at the bottom of the dialog box.

4 Edit the variable data:

- For Visibility variables , select Visible to show the layer's content or Invisible to hide the layer's content.
- For Pixel Replacement variables , click Select File and select a replacement image file. Click Do Not Replace before the data set is applied to leave the layer in its current state.

Note: *Do Not Replace does not reset the file to its original state if another replacement has been applied previously.*

- For Text Replacement variables , enter a text string in the Value text box.

5 Define additional data sets for each version of the graphic you want to generate.

You can edit, rename, or delete the data set later by first choosing it from the Data Set pop-up menu and editing its options. Use the arrow icons to move between data sets. Click the Delete icon to delete a data set.

Preview or apply a data set

You can apply a data set's contents to the base image while leaving all the variables and data sets intact. This changes the look of the PSD document to contain the values of the data set. You can also preview how each version of your graphic will look with each data set.

Note: *Applying a data set overwrites your original document.*

? Choose Image > Apply Data Set. Select the data set from the list and preview the image in the document window. To apply the data set, click Apply. Click cancel if you are previewing and don't want to change the base image.

You can also apply and preview a data set in the Data Set page of the Variables dialog box.

Generate graphics using data sets

After you define variables and one or more data sets, you can output, in batch mode, images using the data set values. You can output images as PSD files.

1 Choose File > Export > Data Sets As Files.

2 Enter a base name for all files generated. You may create your own file-naming scheme if you want.

3 Click the Select Folder button to select a destination directory for your files.

4 Choose data sets to export.

5 Click OK.

Creating data sets in external files

You can quickly create a large number of data sets by creating an external text file that contains all the variable information and loading that file into a PSD document containing variables. One method is to enter your data into a text file or Microsoft Excel spreadsheet and then export it to a tab or comma-separated file.

The syntax of the external text file is as follows (where each line that starts with "Variable" or "Value" is an entire line by itself in your file):

```
VariableName1<sep>VariableName2<sep> <sep>VariableNameN <nl>
Value1-1<sep>Value2-1<sep><sep>ValueN-1<nl>
Value1-2<sep>Value2-2<sep><sep>ValueN-2<nl>
Value1-M<sep>Value2-M<sep><sep>ValueN-M<nl>
```

All the variable names are listed on the first line, in the order that the values are given in subsequent lines. Each subsequent line represents one data set, with the values for each variable given.

To create multiple lines of text in a single line of text in a data set, enclose the text in double quotes and insert hard returns in the tab- or comma-separated file where you want the breaks to occur.

External text file syntax elements
<sep> Either a comma-separated (CSV) or a tab (tab-delimited) file that separates each variable name or value.
<nl> A newline character that ends each data set and can be a line feed, carriage return, or both.
"true" and "false" Allowed values for a visibility variable.
Spaces Spaces around the delimiter are removed when parsing the file; between words in a value string (e.g., two of a kind) spaces are maintained and leading and trailing spaces are maintained if enclosed in double quotes (e.g., "one kind ").
Double quotes Can be part of a value if preceded by another double quote (e.g., ""B"" would be "B" in the data set).

If <sep> or <nl> is part of the variable value, then the entire value must be enclosed in double quotes.

All variables defined in the PSD document must be defined in the text file. An error is displayed if the number of variables in the text file does not match the number in the document.

Example data set:

Using a template for flowers that holds variables for tulip and sunflower, you can set up a text file that looks like this:

```
\{contents of FlowerShow.txt}
Variable 1, Variable 2, Variable 3
true, TULIP, c:\My Documents\tulip.jpg
false, SUNFLOWER, c:\My Documents\sunflower.jpg
false, CALLA LILY, c:\My Documents\calla.jpg
true, VIOLET, c:\My Documents\violet.jpg
```

Note: *You can use a relative path for the image location if the text file is in the same folder as the image file. For example, the last item in the example can be: true, VIOLET, violet.jpg.*

Import a data set

1 Do one of the following:
   - Choose File > Import > Variable Data Sets.
   - Choose Image > Variables > Data Sets and click the Import button.
2 Navigate to the text file to import.
3 Set up your import options.

   Use First Column For Data Set Names Names each data set using the content of the first column of the text file (the values for the first variable listed). Otherwise, the data sets are named "Data Set 1, Data Set 2, and so on."

   Replace Existing Data Sets Deletes any existing data sets before importing.

4 Set the encoding of the text file or leave the setting Automatic.

5 Click OK.

Scripting

Photoshop supports external automation through scripting. In Windows, you can use scripting languages that support COM automation, such as VB Script. In Mac OS, you can use languages such as AppleScript that allow you to send Apple events. These languages are not cross-platform but can control multiple applications such as Adobe Photoshop, Adobe Illustrator, and Microsoft Office. In Mac OS, you can also use Apple's Photoshop Actions for Automator to control tasks in Photoshop.

You can also use JavaScript on either platform. JavaScript support lets you write Photoshop scripts that run on either Windows or Mac OS.

Note: *Refer to the scripting documentation installed in the Photoshop CS5/Scripting/Documents folder and also here. The Scriptlistener Plug-In can be found in Photoshop CS5/Scripting/Utilities and is also available here.*

Run a JavaScript

? Choose File > Scripts and then select the script from the list. The scripts list includes all the script files saved with a .js or .jsx extension and saved in the Photoshop CS5/Presets/Scripts folder. To run a script saved in another location, choose File > Scripts > Browse and navigate to the script.

Set scripts and actions to run automatically

You can have an event, such as opening, saving, or exporting a file in Photoshop, trigger a JavaScript or a Photoshop action. Photoshop provides several default events, or you can have any scriptable Photoshop event trigger the script or action. See the Photoshop Scripting Guide for more information on scriptable events.

1 Choose File > Scripts > Script Events Manager.

2 Select Enable Events To Run Scripts/Actions.

3 From the Photoshop Event menu, choose the event that will trigger the script or action.

4 Select either Script or Action, and then choose the script or action to run when the event occurs.

   Photoshop has several sample scripts you can choose. To run a different script, choose Browse and then navigate to the script. For actions, choose the action set from the first pop-up menu and an action from that set in the second menu. The action must be loaded in the Actions panel to appear in these menus.

5 Click Add. The event and its associated script or action are listed in the dialog box.

6 To disable and remove individual events, select the event in the list and click Remove. To disable all events, but keep them in the list, deselect Enable Events To Run Scripts/Actions.

Process a batch of files

Convert files with the Image Processor

The Image Processor converts and processes multiple files. Unlike the Batch command, the Image Processor lets you process files without first creating an action. You can do any of the following in the Image Processor:

- Convert a set of files to either JPEG, PSD, or TIFF format; or convert files simultaneously to all three formats.
- Process a set of camera raw files using the same options.
- Resize images to fit within specified pixel dimensions.
- Embed a color profile or convert a set of files to sRGB and save them as JPEG images for the web.
- Include copyright metadata in the converted images.

The Image Processor works with Photoshop (PSD), JPEG, and camera raw files.

1 Do any of the following:
   - Choose File > Scripts > Image Processor (Photoshop).
   - Choose Tools > Photoshop > Image Processor (Bridge).
2 Select the images you want to process. You can choose to process any open files, or select a folder of files to process.
3 (Optional) Select Open First Image To Apply Settings to apply the same settings to all the images.

   If you are processing a group of camera raw files taken under the same lighting conditions, you can adjust the setting in the first image to your satisfaction and then apply the same settings to the remaining images.

   Use this option with PSD or JPEG source images if the file's color profile does not match your working profile. You can choose a color profile in which to convert the first image and all images in the folder.

   Note: *The settings you apply with the Image Processor are temporary and used only with the Image Processor. The image's current camera raw settings are used to process the image, unless you change them in the Image Processor.*
4 Select the location where you want to save the processed files.

   If you process the same file multiple times to the same destination, each file is saved with its own filename and not overwritten.
5 Select the file types and options to save.

   Save As JPEG Saves images in JPEG format within a folder called JPEG in the destination folder.

   Quality Sets the JPEG image quality between 0 and 12.

   Resize To Fit Resizes the image to fit within the dimensions you enter in Width and Height. The image retains its original proportions.

   Convert Profile To sRGB Converts the color profile to sRGB. Make sure that Include ICC Profile is selected if you want to save the profile with the image.

   Save As PSD Saves images in Photoshop format within a folder called PSD in the destination folder.

   Maximize Compatibility Saves a composite version of a layered image within the target file for compatibility with applications that can't read layered images.

   Save As TIFF Saves images in TIFF format within a folder called TIFF in the destination folder.

   LZW Compression Saves the TIFF file using the LZW compression scheme.
6 Set other processing options.

   Run Action Runs a Photoshop action. Choose the action set from the first menu and the action from the second menu. The action set must be loaded in the Actions panel before they appear in these menus.

Copyright Info Includes any text you enter in the IPTC copyright metadata for the file. Text you include here overwrites the copyright metadata in the original file.

Include ICC Profile Embeds the color profile with the saved files.

7 Click Run.

Before you process your images, click Save to save the current settings in the dialog box. The next time you need to process files using this group of settings, click Load, and navigate to your saved Image Processor settings.

Process a batch of files

The Batch command runs an action on a folder of files. If you have a digital camera or a scanner with a document feeder, you can also import and process multiple images with a single action. Your scanner or digital camera may need an *acquire* plug-in module that supports actions.

Note: *If the third-party plug-in wasn't written to import multiple documents at a time, it may not work during batch-processing or if used as part of an action. Contact the plug-in's manufacturer for further information.*

You can also import PDF images from Acrobat Capture or other software.

When batch-processing files, you can leave all the files open, close and save the changes to the original files, or save modified versions of the files to a new location (leaving the originals unchanged). If you are saving the processed files to a new location, you may want to create a new folder for the processed files before starting the batch.

To batch-process using multiple actions, create a new action that plays all the other actions, and then batch-process using the new action. To batch-process multiple folders, create aliases within a folder to the other folders you want to process, and select the Include All Subfolders option.

For better batch performance, reduce the number of saved history states and deselect the Automatically Create First Snapshot option in the History panel.

Batch-process files

1 Do one of the following:

- Choose File > Automate > Batch (Photoshop)
- Choose Tools > Photoshop > Batch (Bridge)

2 Specify the action you want to use to process files from the Set and Action pop-up menus. The menus display actions available in the Actions panel. You may need to choose a different set or load a set in the panel if you don't see your action.

3 Choose the files to process from the Source pop-up menu:

Folder Processes files in a folder you specify. Click Choose to locate and select the folder.

Import Processes images from a digital camera, scanner, or a PDF document.

Opened Files Processes all open files.

Bridge Processes selected files in Adobe Bridge. If no files are selected, the files in the current Bridge folder are processed.

4 Set processing, saving, and file naming options. For descriptions of the Batch dialog box settings, see Batch and droplet processing options.

Batch-process files in nested folders into different formats

1 Process your folders as you would normally, until the Destination step.

2 Choose Save And Close for the destination. You can specify options for Override Action "Save As" Commands to do the following:

- If the "Save As" step in the action contains a filename, this name is overridden by the name of the document being saved; all "Save As" steps are treated as if they were recorded without a filename.
- The folder you specified in the "Save As" action step is overridden by the document's original folder.

Note: *You must have a "Save As" step in the action; the Batch command does not automatically save files.*

You can use this procedure, for example, to sharpen, resize, and save images as JPEGs in their original folders. You create an action that has a sharpen step, a resize step, and then a "Save As JPEG" step. When you batch-process this action, you select Include All Subfolders, make the destination Save And Close, and select Override Action "Save As" Commands.

Create a droplet from an action

A *droplet* applies an action to one or more images, or a folder of images, that you drag onto the Droplet icon. You can save a droplet on the desktop or to another location on disk.

Actions are the basis for creating droplets—you must create the desired action in the Actions panel before creating a droplet. (See .)

1 Choose File > Automate > Create Droplet.

2 Specify where to save the droplet. Click Choose in the Save Droplet In section of the dialog box and navigate to the location.

3 Select the Action Set, and then designate which action you intend to use within the Set and Action menus. (Select the action in the Actions panel before you open the dialog box to preselect these menus.)

4 Set processing, saving, and file naming options. For descriptions of the Batch dialog box settings see Batch and droplet processing options.

Tips for cross-platform droplets

When creating droplets for both Windows and Mac OS, keep the following compatibility issues in mind:

- After moving a droplet created in Windows to Mac OS, you must drag the droplet onto the Photoshop icon on your desktop. Photoshop updates the droplet for use in Mac OS.
- When creating a droplet in Mac OS, use the .exe extension to make droplets compatible with both Windows and Mac OS.
- References to filenames are not supported between operating systems. If an action step references a file or folder name (such as an Open command, Save As command, or adjustment command that loads its settings from a file), execution pauses and the user is prompted for a filename.

Process a file with a droplet

? Drag a file or folder onto the droplet icon. Photoshop starts if it is not already running.

Batch and droplet processing options

Specify these options in the Batch and Droplet dialog boxes.

Override Action "Open" Commands Ensures that the files you selected in the Batch command are processed, without opening the file you may have specified in the action's Open command. If the action contains an Open command that opens a saved file and you don't select this option, the Batch command opens and processes only the file you used to record the Open command (This occurs because the Batch command opens the file specified by the action after each of the files in the Batch source folder is opened. Because the most recently opened file is the one named in the action, the Batch command performs the action on that file, and none of the files in the Batch source folder are processed.)

To use this option, the action must contain an Open command. Otherwise, the Batch command won't open the files you've selected for batch-processing. Selecting this option doesn't disregard everything in an Open command—only the choice of files to open.

Deselect this option if the action was recorded to operate on an open file, or if the action contains Open commands for specific files that are required by the action.

Include All Subfolders Processes files in subdirectories of the specified folder.

Suppress Color Profile Warnings Turns off display of color policy messages.

Suppress File Open Options Dialogs Hides File Open Options dialog boxes. This is useful when batching actions on camera raw image files. The default or previously specified settings will be used.

Destination menu Sets where to save the processed files

None Leaves the files open without saving changes (unless the action includes a Save command).

Save And Close Saves the files in their current location, overwriting the original files.

Folder Saves the processed files to another location. Click Choose to specify the destination folder.

Override Action "Save As" Commands Ensures that processed files are saved to the destination folder specified in the Batch command (or to their original folder if you chose Save and Close), with their original names or the names you specified in the File Naming section of the Batch dialog box.

If you don't select this option and your action includes a Save As command, your files will be saved into the folder specified by theSave As command in the action, instead of the folder specified in the Batch command. In addition, if you don't select this option and the Save As command in the action specifies a filename, the Batch command overwrites the same file (the file specified in the action) each time it processes an image.

If you want the Batch command to process files using the original filenames in the folder you specified in the Batch command, save your image in the action. Then, when you create the batch, select Override Action "Save As" Command and specify a destination folder. If you rename the images in the Batch command and don't select Override Action "Save As" Command, Photoshop saves your processed images twice: once with the new name in the specified folder, and once with the original name in the folder specified by the Save As command in the action.

To use this option, the action must contain a Save As command. Otherwise, the Batch command won't save the processed files. Selecting this option doesn't skip everything in the Save As command—only the specified filename and folder.

Note: *Some Save options aren't available in the Batch or Create Droplet commands (such as JPEG compression or TIFF options). To use these options, record a Save As step in the action that contains the desired options, and then use the Override Action "Save As" Commands option to make sure that your files are saved where you specify in the Batch or Create Droplet command. Photoshop disregards the specified filename and path in the Action's Save As command, and retains the Save options using the new path and filename you specify in the Batch dialog.*

File Naming Specifies file naming conventions if writing files to a new folder. Select elements from the pop-up menus or enter text into the fields to be combined into the default names for all files. The fields let you change the order and formatting of the components of the filename. You must include at least one field that is unique for every file (for example, filename, serial number, or serial letter) to prevent files from overwriting each other. Starting Serial Number specifies the starting number for any serial number fields. Serial letter fields always start with the letter "A" for the first file.

Compatibility Makes filenames compatible with Windows, Mac OS, and UNIX operating systems.

Saving files using the Batch command options usually saves the files in the same format as the original files. To create a batch process that saves files in a new format, record the Save As command followed by the Close command as part of your original action. Then choose Override Action "Save As" Commands for the Destination when setting up the batch process.

Error menu Specifies how to handle processing errors:

Stop For Errors Suspends the process until you confirm the error message.

Log Errors to File Records each error in a file without stopping the process. If errors are logged to a file, a message appears after processing. To review the error file, open with a text editor after the Batch command has run.

More Help topics

About actions and the Actions panel

Creating actions

Playing and managing actions

Play and manage actions

Play an action on a file

Playing an action executes the action's recorded commands in the active document. (Some actions require that you make a selection before playing; some can be executed on an entire file.) You can exclude specific commands from an action or play only a single command. If the action includes a modal control, you can specify values or use tools in a dialog box when the action pauses.

Note: *In Button mode, clicking a button executes the entire action—although commands previously excluded are not executed.*

1. If necessary, select objects on which to play the action, or open a file.
2. Do one of the following:
   - To play an entire single action, select the action name, and click the Play button in the Actions panel, or choose Play from the panel menu.

- If you assigned a key combination to the action, press that combination to play the action automatically.
- To play only a part of an action, select the command from which you want to start playing, and click the Play button in the Actions panel, or choose Play from the panel menu.
- To play a single command, select the command, and then Ctrl-click (Windows) or Command-click (Mac OS) the Play button in the Actions panel. You can also press Ctrl (Windows) or Command (Mac OS), and double-click the command.

In Photoshop, to undo an action, take a snapshot in the History panel before you play an action, and then select the snapshot to undo the action.

Specify playback speed

You can adjust an action's playback speed or pause it to help you debug an action.

1 Choose Playback Options from the Actions panel menu.

2 Specify a speed, and click OK:

Accelerated Plays the action at normal speed (the default).

Note: *When you play an action at accelerated speed, the screen may not update as the action executes—files may be opened, modified, saved, and closed without ever appearing on-screen, enabling the action to execute more quickly. If you want to see the files on-screen as the action executes, specify the Step By Step speed instead.*

Step By Step Completes each command and redraws the image before going on to the next command in the action.

Pause For __ Seconds Specifies the amount of time the application should pause between carrying out each command in the action.

Manage actions

Manage actions in the Actions panel to keep them organized and to make available only the actions you need for a project. You can rearrange, duplicate, delete, rename, and change options for actions in the Actions panel.

Rearrange actions in the Actions panel

? In the Actions panel, drag the action to its new location before or after another action. When the highlighted line appears in the desired position, release the mouse button.

Duplicate actions, commands, or sets

? Do one of the following:

- Alt-drag (Windows) or Option-drag (Mac OS) the action or command to a new location in the Actions panel. When the highlighted line appears in the desired location, release the mouse button.
- Select an action or command. Then choose Duplicate from the Actions panel menu.
- Drag an action or command to the Create New Action button at the bottom of the Actions panel.

You can duplicate sets with any of the same methods.

Delete actions, commands, or sets

1 In the Actions panel, select the action, command, or set.

2 Do any of the following:

- Click the Delete icon on the Actions panel. Click OK to complete the deletion.

- Alt-click (Windows) or Option-click (Mac OS) the Delete icon to delete the selection without displaying a confirmation dialog box.
- Drag the selection to the Delete icon on the Actions panel to delete without displaying a confirmation dialog box.
- Choose Delete from the Actions panel menu.

Delete all actions in the Actions panel

? Choose Clear All Actions from the Actions panel menu.

Even after clearing all actions, the Actions panel can be restored to its default set of actions.

Rename an action or change options

1 Select the action, and choose Action Options from the Actions panel menu.
2 Type a new name for the action, or change the options for its set, function key combination, or button color.
3 Click OK.

You can double-click an action in the Actions panel and enter a new name directly in the Actions panel.

Manage action sets

You can create and organize sets of task-related actions that can be saved to disk and transferred to other computers.

Note: *Any actions that you create are automatically listed in the Actions panel, but to truly save an action and not risk losing it if you delete your Actions panel file, you have to save it as part of an action set.*

Save a set of actions

1 Select a set.

If you want to save a single action, first create an action set and move the action to the new set.

2 Choose Save Actions from the Actions panel menu.
3 Type a name for the set, choose a location, and click Save.

You can save the file anywhere. You can save only the entire contents of a set in the Actions panel, not individual actions.

Note: *If you place the saved action-set file in the Presets/Actions folder, the set will appear at the bottom of the Actions panel menu after you restart the application.*

Press Ctrl+Alt (Windows) or Command+Option (Mac OS) when you choose the Save Actions command to save the actions in a text file. You can use this file to review or print the contents of an action. However, you can't reload the text file back into Photoshop.

Load a set of actions

By default, the Actions panel displays predefined actions (shipped with the application) and any actions you create. You can also load additional actions into the Actions panel.

? Do one of the following:

- Choose Load Actions from the Actions panel menu. Locate and select the action set file, and then click Load.

- Select an action set from the bottom of the Actions panel menu.

Photoshop action set files have the extension .atn.

Restore actions to the default set

1 Choose Reset Actions from the Actions panel menu.

2 Click OK to replace the current actions in the Actions panel with the default set, or click Append to add the set of default actions to the current actions in the Actions panel.

Organize action sets

To help you organize your actions, you can create sets of actions and save the sets to disk. You can organize sets of actions for different types of work—such as print publishing and online publishing—and transfer sets to other computers.

- To create a new set of actions, click the Create New Set button in the Actions panel or choose New Set from the panel menu. Then enter the name of the set, and click OK.

Note: *If you plan to create a new action and group it in a new set, make sure you create the set first. Then, the new set will appear in the set pop-up menu when you create your new action.*

- To move an action to a different set, drag the action to that set. When the highlighted line appears in the desired position, release the mouse button.
- To rename a set of actions, double-click the name of the set in the Actions panel or choose Set Options from the Actions panel menu. Then enter the new name of the set, and click OK.
- To replace all actions in the Actions panel with a new set, choose Replace Actions from the Actions panel menu. Select an actions file, and click Load.

Note: *The Replace Actions command replaces all sets of actions in the current document. Before using the command, make sure that you have already saved a copy of your current set of actions using the Save Actions command.*

More Help topics

About actions and the Actions panel

Add conditional actions

Conditional actions let you build actions that choose what to do based on one of several different conditions. First, you choose a condition and then, optionally specify an action that plays if the document meets the condition. Then, you optionally specify an action that plays if the document does not meet the condition.

To insert a conditional action step into an action that you're recording or editing:

1 Make sure that the actions you will be referencing are in the same actions set.

2 Choose Insert Conditional from the Actions panel menu.

3 In the Conditional Action dialog box, choose a condition from the If Current menu.

4 Choose actions from the Then Play Action menu and the Else Play Action menu, and then, click OK.

You can also choose None in one of the menus, but not both. You can run an action only if a particular condition is false by choosing None as the Then Play Action and choosing the desired action as the Else Play Action.

For more information, see About actions and the Actions panel and Creating actions.

Note: *There is a Conditional Mode Change command to specify conditions for a color mode change step in an action. Using this command can prevent an error where a file is not in the source mode specified by the action.*

Testing the opposite of what's in the condition

There might be instances when you want to test the opposite of what's in a condition.

For example, suppose you want "Action 1" to play when when the frontmost document is non-square. You would specify the conditional: "If Current Document is Square, Then Play Action None, ElsePlay Action "Action 1."

To test for the opposite of a particular condition, swap the "Then" and "Else" actions.

About actions and the Actions panel

About actions

An *action* is a series of tasks that you play back on a single file or a batch of files—menu commands, panel options, tool actions, and so on. For example, you can create an action that changes the size of an image, applies an effect to the image, and then saves the file in the desired format.

Actions can include steps that let you perform tasks that cannot be recorded (for example, using a painting tool). Actions can also include modal controls that let you enter values in a dialog box while playing an action.

In Photoshop, actions are the basis for *droplets*, which are small applications that automatically process all files that are dragged onto their icon.

Photoshop and Illustrator come with predefined actions installed that help you perform common tasks. You can use these actions as is, customize them to meet your needs, or create new actions. Actions are stored in sets to help you organize them.

You can record, edit, customize, and batch-process actions, and you can manage groups of actions by working with action sets.

Actions panel overview

You use the Actions panel (Window > Actions) to record, play, edit, and delete individual actions. This panel also lets you save and load action files.



A *Action set* ***B*** *Action* ***C*** *Recorded commands* ***D*** *Included command* ***E*** *Modal control (toggles on or off)*

Expand and collapse sets, actions, and commands

? Click the triangle to the left of the set, action, or command in the Actions panel. Alt-click (Windows) or Option-click (Mac OS) the triangle to expand or collapse all actions in a set or all commands in an action.

View actions by name only

? Choose Button Mode from the Actions panel menu. Choose Button Mode again to return to list mode.

Note: *You can't view individual commands or sets in Button mode.*

Select actions in the Actions panel

? Click an action name. Shift-click action names to select multiple, contiguous actions, and Ctrl-click (Windows) or Command-click (Mac OS) action names to select multiple, discontiguous actions.

More Help topics

Playing and managing actions

Adding conditional actions | CreativeCloud

Video | Play an action

Video | Record actions

Recording tools in actions

Photoshop lets you record tools such as the brush tool in your action. To enable this feature, choose Allow Tool Recording from the Actions panel menu.

A couple of items to keep in mind:

- When recording a tool, choose your brush as part of the action or Photoshop uses the currently selected brush.
- If you are recording the action to play back at a different size, set Photoshop's measurement units to percentage and don't define the brush size as part of a brush preset.

For more information, see About actions and the Actions panel and Creating actions .

Photoshop UI toolkit for plug-ins and scripts

What is changing?

Script-generated UI in Photoshop has now been enhanced to support HiDPI/Retina displays and look consistent with the overall application UI. Also, script-generated UI is now based on a new framework rather than Flex.

List of affected dialogs

The following is a list of dialogs in the application affected by this change:

Dialog	Menu
Contact Sheet II	File > Automate > Contact Sheet II
Conditional Mode Change	File > Automate > Conditional Mode Change
Fit Image	File > Automate > Fit Image
Lens Correction	File > Automate > Lens Correction
Merge to HDR Pro	File > Automate > Merge to HDR Pro
Photomerge	File > Automate > Photomerge
Export Color Lookup	File > Export > Color Lookup Tables
Layer Comps to Files	File > Export > Layer Comps to Files
Layer Comps to PDF	File > Export > Layer Comps to PDF
Artboards to PDF	File > Export > Artboards to PDF
Export Layers to Files	File > Export > Layers to Files
Image Processor	File > Scripts > Image Processor
Scripts Event Manager	File > Scripts > Scripts Event Manager
Load Layers	File > Scripts > Load Files into Stack
Image Statistics	File > Scripts > Statistics
Measurement Scale Marker	Image > Analysis > Place Scale Marker
Flame	Filter > Render > Flame
Picture Frame	Filter > Render > Picture Frame
Tree	Filter > Render > Tree
Upload to Sketchfab	3D > Share 3D Layer on Sketchfab
Export/Import Presets	Edit > Presets > Export/Import Presets
Brick Fill	Edit > Fill Select "Pattern" in the contents drop-down Select "Script" Select the option from Scripts drop-down
Cross Weave	
Place Along Path	
Random Fill	
Symmetry Fill	

UI Layout

There are no changes in the scripting APIs for creating user interfaces. However, there is a difference in the way the grouping widget works.

In Flex, the “group” widget used to act as layout mechanism for grouping widgets and used to be completely invisible itself. Now, “group” is itself a widget with its own background and can’t overlap with other widgets.

For instance, if we have two groups arranged one over the other with widgets in each group such that widgets from one group do not overlap with widgets in the other group, all widgets are visible in Flex.

However, in the new framework, in the same scenario, the group at the top hides the group at the bottom.



Note: *Some users may find that their existing scripts have incorrect UI layout in the new framework because of this same reason. All such scripts should be modified by removing overlaps in the “group” widgets. Scripts created afresh in the new framework or modified to run in it work fine in Flex as well.*

HiDPI support

With this change, script UI now supports HiDPI displays as well. However, no change is required in the scripts to make it work on HiDPI displays. You just need to place the 2x image assets alongside the 1x image assets having same filename as 1x image asset followed by @2X as suffix.

For instance, if the filename for 1x image asset is imageFile.png, then 2x image asset should be named as imageFile@2X.png and present at the same location.

Note: *If the 2x image asset is not found, 1x image asset will be used.*

Known issues

- The Flash Player widget is no longer supported. It is not possible to play SWF/Flash/Flex files through the script UI any longer.
- Treeview widget is not supported.
- Graphics drawing is not supported on Checkbox and Radiobutton widgets.
- Button background color cannot be changed.
- Font styles on text are not supported.

Batch Actions

Batch Actions

Chapter 19: 3D and technical imaging

Creative Cloud 3D Animation (Preview)

Note: This feature is currently available only in English.

The Creative Cloud 3D Animation (Preview) service

The Creative Cloud 3D Animation (Preview) service in Photoshop lets you easily animate 3D characters. This service currently works with human 3D characters assembled in Adobe Fuse CC (Preview). You can apply a variety of poses, animations, and effects to these human characters using intuitive controls right within Photoshop. You can then integrate the character with a larger 3D scene for a variety of use-cases and even print the characters using a 3D printer. Photoshop lets you easily adjust camera angles and lighting to get just the look that you want.

Enable the Creative Cloud 3D Animation service

1. In Photoshop, select Preferences > Technology Previews.
2. Select Enable CC 3D Animations (Preview).
3. Click OK. The service is enabled immediately after you close the Preferences dialog.

Adobe Fuse (Preview) and Creative Cloud Libraries

Adobe Fuse CC (Preview) is a desktop app for creating highly customizable 3D human characters in minutes. Without any prior 3D experience, you can quickly create characters using a library of high-quality 3D content—from faces and bodies to clothing and textures with an option to customize the color, texture, and shape of over 280 attributes.

Once you've created your characters in Adobe Fuse (Preview), you can save them to Creative Cloud Libraries and bring them into the 3D workspace in Photoshop. Now, in Photoshop, you can easily apply animations, poses, and effects to the characters and ready them for compositing into larger 3D scenes.

Animate the 3D character in Photoshop

To animate a character in Photoshop, you work with its properties in the 3D workspace. The following broad animation-related properties are available for tweaking in the 3D workspace:



A Body | *B Face* | *C Coordinates* | *D Properties menu* | *E Search* | *F Search options*

Body Set the properties of the body of your 3D character.

Face Set the properties of the face of your 3D character.

Coordinates Set the precise numerical locations for your 3D character.

Properties menu Customize the thumbnail size and style.

Search Perform a search for body actions or face expressions.

Search options Filter the animations by category and type.

Walkthrough | 3D character animation

1 In the Libraries panel, open the library with which you synced your character. Photoshop displays the Fuse (Preview) character under 3D assets.

2 Double-click the character to open it.



3 Switch to the 3D workspace if you are in some other workspace. Select Window > 3D.

4 Select the character's skeleton in the 3D Layers panel.



Note: *You can right-click on the skeleton bone and choose to center either the character or the face in view for easier navigation.*

5 Now, in the Properties panel, choose Body.

6 Search for an Action, such as Dance.

7 Click a thumbnail to apply animation to the model. If necessary, adjust the parameters for the animation.

Trim Adjust the start and end point of animation. Specify the start point of animation in Min and the end point in Max.

In Place For animations, such as running, which takes the 3D character out of focus, this setting forces the animation to stay in place.

Mirror Switch sides of the animation.

Arm Space Adjust the spread of arms.

Overdrive Adjust how slow or fast the animation should move.



8 Now, in the Properties panel, choose Face.

9 Search for an expression, such as Happy.

10 Click a thumbnail to apply animation to the model. If necessary, adjust the strength of the expression as well as the eye and head positions.



Result

You now have a fully animated and posed character that is ready to be composited into any scene you choose.



See also

- Adobe Fuse CC (Preview) FAQ
- Fuse CC (Preview) Help: Create your first 3D model
- Photoshop 3D workspace Help

3D painting

You can use any Photoshop painting tools to paint directly on a 3D model just as you would on a 2D layer. Use selection tools to target specific model areas or let Photoshop identify and highlight paintable areas. 3D menu commands let you clear away areas of a model to access interior or hidden portions for painting.

When painting directly on the model, you can choose which underlying texture map to apply paint to. Typically paint is applied to the diffuse texture map, which gives a model material its color properties. You can also paint on other texture maps, such as the bump map or opacity map. If you paint on an area of the model that lacks the type of texture map you're painting on, a texture map is automatically created.

Available 3D painting methods

Different painting methods are appropriate for different use cases. Photoshop provides the following 3D painting methods:

Live 3D Painting:(Default in Photoshop CC) Brush strokes made in the 3D model view or the texture view are reflected in real time in the other view. This 3D painting method offers high performance and minimum distortion.

Layer Projection Painting: The Gradient tool and filters use this painting method. The Layer Projection Painting method involves merging a painted layer with the underlying 3D layer. During the merge operation, Photoshop automatically projects the paint onto the appropriate target textures.

Projection Painting:(Default in Photoshop Extended CS6)Projection Painting is suitable for painting multiple textures simultaneously or for painting the seam between two textures. However, in general, it is a lower-performance painting method and may result in cracks when you're painting complex 3D objects.

Texture Painting: You can open the 2D texture and paint it directly.



Some tips to paint 3D models

- If the model area is hidden, you can temporarily cut away surface areas that are blocking your view. See Reveal surfaces to paint on
- If you are painting on curved or irregular surfaces, you can get visual feedback before you paint of which areas can best receive paint. See Identify paintable areas. You can also set the paint fall-off angle, which controls the amount of paint applied to angled surfaces. See Set the paint falloff angle
- While painting texture seams, a single brush stamp applies only to one side of the seam. Move the center of the brush across the seam to paint its other side.
- If you try to paint on a texture map type that the material doesn't contain, Photoshop prompts you to create a map. For information on map types, see 3D Materials settings (Photoshop Extended) .

Paint an object in the Live 3D Painting mode | Photoshop CC

1 Open the 3D model in the 3D model view.

2 Open the texture document that you want to paint. To do so, double-click the name of the texture in the Layers panel.

3 Select Window > Arrange > Tile to view the 3D model view and the texture document side by side.

4 Using the Brush tool, paint the 3D model or the texture document. Your brush stokes reflect automatically in the other view.

Switch to the Projection Painting mode | Photoshop CC

1 Create or open a 3D model.

2 Select 3D > Use Projection Painting.

3 Paint your 3D model.

Note: *In the Master 3D document, Photoshop uses the Projection Painting method by default for painting operations.*

Paint a 3D model texture | CS6

1 Use the 3D position tools to orient the model so that the area you want to paint on is facing forward.

2 Do one of the following to set the texture map to paint on:

- Choose 3D > 3D Paint Mode, and select a map type.
- In the 3D panel, select the Scene panel. Choose a map type from the Paint On menu.

3 (Optional) Using any selection tool, create a selection on the 3D model to restrict the area that you want to paint on.

4 Apply paint using the Paintbrush tool. You can also use any other tool in the second section of the Tools panel, such as the Paint Bucket, Smudge, Dodge, Burn, or Blur tools.

While painting (after completing a stroke), you can view the effect of the painting on the texture map itself. Do one of the following:

- Double-click the texture map in the Layers panel to open it.
- In the Materials section of the 3D panel, select the material for the area you are painting. In the lower section of the panel, click the menu icon for the texture map you're painting, and choose Open Texture.

Target a texture type for painting | Photoshop CC

You can target eight different texture types for painting:

1 With your 3D model open, select 3D > Paint On Target Texture.

2 Choose the texture type that you want to paint.

Note: *In 3D models having multiple textures, only the texture that you open and start painting on is painted.*



Paint in the unlit mode | Photoshop CC

You can choose to paint your 3D objects in the unlit mode. This mode ignores any lighting in your scene and wraps raw texture data of the appropriate type around your 3D objects. Painting in the unlit mode lets you paint without shading and with greater color accuracy.

Follow these steps:

1 In the 3D panel, select Scene.

2 In the Properties panel, select Surface.

3 Select Unlit Texture from the Style pop-up menu.

Reveal surfaces to paint on

For more complex models with interior or hidden areas, you can hide sections of the model for easier access to surfaces you want to paint. For example, to apply paint to the dashboard of a car model, you can temporarily cut away the roof or windshield, then zoom inside the car to get an unobstructed view.

1 Select an area of the model that you want to cut away, using a selection tool such as the Lasso or Marquee tool.

2 Use any of the following 3D menu commands to reveal or hide areas of the model:

Hide Nearest Surface hides only the first layer of model polygons within the 2D selection. To quickly peel away surface of the model, you can use this command repeatedly while keeping the selection area active.

When hiding surfaces, rotate the model if necessary to position surfaces so that they are perpendicular to your currentview.

Only Hide Enclosed Polygons When selected, the Hide Nearest Surface command only affects polygons that are fully within the selection. When unchecked, ithides any polygons touched by the selection.

Invert Visible Surfaces Makes currently visible surfaces invisible, and invisible surfaces visible.

Reveal All Surfaces Makes all hidden surfaces visible again.

Set the paint falloff angle

When painting on a model, the paint falloff angle controls how much paint is applied to a surface as it curves away from the forward-facing view. The falloff angle is calculated based on a "normal", or straight line projecting out from the part of the model surface that faces you. For example, in a spherical model such as a soccer ball, the falloff angle to the exact center of the ball as it faces you is 0 degrees. As the surface of the ball curves away, the falloff angle increases, up to 90 degrees at the edges of the ball.



***A** Eye/camera angle **B** Minimum angle **C** Maximum angle **D** Paint fade start **E** Paint fade end*

1 Choose 3D > 3D Paint Falloff.

2 Set the minimum and maximum angle settings.

- The maximum paint falloff range is 0 - 90 degrees. At 0 degrees, paint is only applied to the surface if it is facing directly forward, with no drop-off angle. At 90 degrees, paint can follow a curved surface such as a sphere to its visible edges. At a 45 degree setting, the painted area is limited to the areas of the sphere that don't curve away at more than 45 degrees.
- The Minimum falloff angle sets a range within which paint gradually fades as it approaches the maximum falloff angle. For example, if the maximum falloff angle is 45, and the minimum falloff is 30, paint opacity decreases from 100 to 0 percent between 30 and 45 degrees of falloff.

Identify paintable areas

It may not be clear just from looking at a 3D model whether you can successfully paint on certain areas. Because the model view may not provide a 1 to 1 correspondence with the 2D texture itself, applying paint directly to the model is different from directly painting on a 2D texture map. What appears to be a small brush on the model may in fact be much larger in relation to the texture, depending on the resolution of the texture, or how close you are to the model when applying paint.

Good paintable areas are areas where you can apply paint or other adjustments to the model surface with the most consistent and predictable effect. In other areas, paint may be undersampled or oversampled due to your angle or distance from the model surface.

? Do one of the following:

- Choose 3D > Select Paintable Areas. A selection marquee highlights the best areas for painting on the model.
- In Scene section of the 3D panel, choose Paint Mask from the Preset menu.

In Paint Mask mode, white shows areas good for painting, blue shows areas where paint will be undersampled, and red shows areas where paint will be oversampled. (To paint on the model, you must change from the Paint Mask render mode to a render mode that supports painting, such as Solid.)

The areas selected by Select Paintable Areas, and the paintable areas shown in Paint Mask mode, are partially determined by the current Paint Falloff setting. A higher paint falloff setting increases the paintable area, a lower setting decreases the paintable area. See Set the paint falloff angle.

More Help topics

Daniel Presedo's YouTube channel

3D panel enhancements | Photoshop CC

The Photoshop 3D panel in Photoshop CC makes it easier for you to work with 3D objects. Modeled after the Layers panel, the 3D panel is structured as a scene graph/tree having root objects and child objects.

You can interact with 3D objects in the scene graph in several ways, such as:

- Delete objects
- Reorder objects
- Reverse object order
- Insert objects
- Duplicate objects
- Make instances of objects
- Group objects

You can access these interactions from the context menu associated with a 3D object. Right-click (Windows) or Control-click (Mac OS).

Some interactions are not available for certain types of 3D objects.

Display the 3D panel

- Select Window > 3D.

Basic interactions

Interaction	Description	How to perform...	Not available for...
Delete an object	Deletes the selected objects from the scene graph	• Drag the object to the trash, or • Use the Delete Object command in the context menu	Objects under Scene, Environment, and View
Add an object	Adds a mesh or a preset 3D object	**1** Right-click the 3D object. **2** From the context menu, select the appropriate option to add an object. For example, select Add Pyramid.	Objects under Environment and Current View
Reorder an object	Changes the position of the selected object within the scene graph	Drag the object to its new position.	Objects under Scene, Environment, and Current View
Reverse order of objects	Reverses the order of the selected objects within the scene graph	**1** Select the objects. **2** From the context menu, select Reorder Objects.	Objects under Scene, Environment, and Current View
Duplicate an object	Duplicates the currently selected object	**1** Select an object. **2** From the context menu, select Duplicate Objects.	Objects under Scene, Environment, and Current View
Group objects	Groups the selected objects	**1** Select the objects. **2** From the context menu, select Group Items.	Materials, constraints, and objects under Scene and Environment
Ungroup objects	Ungroups a group of objects	**1** Select the group. **2** From the context menu, select Ungroup Objects.	Materials, constraints, and objects under Scene and Environment

Create an instance of a 3D object

An instance of a 3D object is a linked copy that reflects the changes made to the original object. If you want to modify the object and its instance independently, you can decouple the two.

Follow these steps to create an instance of a 3D object:

1 In the 3D panel, right-click the mesh object. For example, right-click Hat.

2 From the context menu for the object, select Instance Objects. This will create an instance of the object; for example, Hat1.

By default, the instance is linked with the original object.



Decouple an instance from the original object

When you decouple an instance from the original object, changes made to the original object are no longer reflected on the instance.

1 Right-click the instance in the 3D panel.

2 From the context menu, select Bake Instance.



More Help topics

Daniel Presedo's YouTube channel

3D Scene settings

3D Mesh settings

3D Materials settings

3D Lights settings

3D and technical imaging

Essential 3D concepts and tools

Note: *In Photoshop CS6, 3D functionality was part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

Understand and display 3D files

Photoshop lets you position and animate 3D models, edit textures and lighting, and choose from several render modes.

3D fundamentals

3D files consist of the following components:

Meshes Provide the underlying structure of a 3D model. A mesh is often visualized as a wireframe, a skeletal structure built from thousands of individual polygons. A 3D model always has at least one mesh, and may combine multiple meshes. In Photoshop you can view meshes in a variety of render modes, and manipulate meshes independently of each other. While you can't alter the actual polygons in a mesh, you can change its orientation and transform it by scaling along different axes. You can also create your own 3D meshes, using pre-supplied shapes or by converting existing 2D layers. See 3D Mesh settings .

Note: *To edit the polygon mesh of the 3D model itself, you must use a 3D authoring program.*

Materials A mesh can have one or more materials associated with it, which control the appearance of all or part of the mesh. The material in turn relies on subcomponents called texture maps, whose cumulative effect creates the appearance of a material. The texture map itself is a 2D image file that creates various qualities such as color, pattern, shininess, or bumpiness. A Photoshop material can use up to nine different texture map types to define its overall appearance. See 3D Materials settings .

Lights Types include Infinite, Spot, Point lights, as well as Image-based lights that wrap around a scene. You can move and adjust color and intensity of existing lights, and add new lights to your 3D scene. See 3D Lights settings .

Open a 3D file

Photoshop can open the following 3D formats: DAE (Collada), OBJ, 3DS, U3D, and KMZ (Google Earth).

? Do one of the following:

- To open a 3D file on its own, choose File > Open, and select the file.
- To add a 3D file as a layer in an open file, choose 3D > New Layer From 3D File, and then select the 3D file. The new layer reflects the dimensions of the open file and presents the 3D model over a transparent background.

3D performance and display preferences

1 Choose Edit > Preferences > 3D (Windows) or Photoshop > Preferences 3D (Mac OS).

2 For information about options, hover the pointer over them, and read the Description section at the bottom of the dialog box.

3D object and camera tools

The 3D object and camera tools become active when a 3D layer is selected. Use the 3D object tools to change the position or scale of a 3D model; use the 3D camera tools to change the view of the scene. If your system supports OpenGL, you can also use the 3D Axis to manipulate 3D models and cameras. See 3D Axis.3D Axis

Move, rotate, or scale a model with 3D object tools

You can use the 3D object tools to rotate, reposition, or scale a model. While you manipulate the 3D model, the camera view remains fixed.

For tips about each 3D tool, choose panel Options from the Info panel menu, and select Show Tool Hints. Click a tool, then move the cursor into the image window to view tool details in the Info Panel.

***A** Return to initial object position **B** Rotate **C** Roll **D** Pan **E** Slide **F** Scale **G** Position menu **H** Save current position **I** Delete current position **J** Position coordinates*

? In the Tools panel, click a 3D object tool, and hold down the mouse button to select from the following types:

Hold down Shift as you drag to constrain the Rotate, Pan, Slide, or Scale tool to a single direction of movement.

Rotate Drag up or down to rotate the model around its x-axis, or side to side to rotate it around its y axis. Hold down Alt (Windows) or Option (Mac OS) as you drag to roll the model.

Roll Drag side to side to rotate the model around its z axis.

Pan Drag side to side to move the model horizontally, or up or down to move it vertically. Hold down Alt (Windows) or Option (Mac OS) as you drag to move in the x/z direction.

Slide Drag side to side to move the model horizontally, or up or down to move it closer or farther away. Hold down Alt (Windows) or Option (Mac OS) as you drag to move in the x/y direction.

Scale Drag up or down to scale the model larger or smaller. Hold down Alt (Windows) or Option (Mac OS) as you drag to scale in the z direction.

Click the Return To Initial Position icon in the options bar to return the model to its initial view.

To numerically adjust position, rotation, or scaling, enter values on the right side of the options bar.

Move the 3D camera

Use the 3D camera tools to move the camera view while leaving the position of the 3D object fixed.

For tips about each 3D tool, choose Panel Options from the Info panel menu, and select Show Tool Hints. Click a tool, then move the cursor into the image window to view tool details in the Info panel.



***A** Return to initial camera position **B** Rotate **C** Roll **D** Pan **E** Walk **F** Zoom **G** View menu **H** Save current camera view **I** Delete current camera view **J** Camera position coordinates*

? In the Tools panel, click a 3D camera tool, and hold down the mouse button to select from the following types:

Hold down Shift as you drag to constrain the Rotate, Pan, or Walk tools to a single direction of movement.

Rotate Drag to orbit the camera in the x or y direction. Hold down Alt (Windows) or Option (Mac OS) as you drag to roll the camera.

Roll Drag to roll the camera.

Pan Drag to pan the camera in the x or y direction. Hold down Alt (Windows) or Option (Mac OS) as you drag to pan in the x or z direction.

Walk Drag to walk the camera (z translation and y rotation). Hold down Alt (Windows) or Option (Mac OS) as you drag to walk in the z/x direction (z translation and x rotation).

Zoom Drag to change the field of view of the 3D camera. Maximum field of view is 180.

Perspective Camera (Zoom only) Displays parallel lines converging to vanishing points.

Orthographic Camera (Zoom only) Maintains parallel lines without convergence. Displays the model in accurate scale view without any perspective distortion.

DOF (Zoom only) Sets depth of field. Distance determines how far the in-focus field is from the camera. Blur obscures the remainder of the image.

Animate DOF to simulate camera focusing effects.

In the options bar, numeric values show the x, y, and z position of the 3D camera. You can also edit these values manually to adjust the camera view.

Change or create 3D camera views

? Do one of the following:

- Select a preset camera view of the model from the View menu.

Note: *All preset camera views use orthographic projection.*

- To add a custom view, place the 3D camera in the desired position using the 3D camera tools, then click Save in the options bar.

To return to the default camera view, select a 3D camera tool, and click the Return To Initial Camera Position icon in the options bar.

3D Axis

The 3D Axis shows the current X, Y, and Z-axis orientation of models, cameras, lights, and meshes in 3D space. It appears when you select any 3D tool, providing an alternative way to manipulate the selected item.



A Selected tool ***B*** *Minimize or maximize 3D Axis* ***C*** *Move item along axis* ***D*** *Rotate item* ***E*** *Compress or elongate item* ***F*** *Resize item*

Note: *OpenGL must be enabled to display the 3D Axis.*

Show or hide the 3D Axis

- Choose View > Show > 3D Axis.

Minimize, restore, move, or resize the 3D Axis

1. Move the pointer over the 3D Axis to display the control bar.
2. Do one of the following:
   - To move the 3D Axis, drag the control bar.
   - To minimize, click the minimize icon.
   - To restore to normal size, click the minimized 3D Axis.
   - To resize, drag the zoom icon.

Move, rotate, or scale selected items with the 3D Axis

To use the 3D Axis, move the mouse pointer over an axis control to highlight it, and then drag as follows:

Note: *Available axis controls vary depending upon the current editing mode (object, camera, mesh, or light).*

- To move the selected item along the X, Y, or Z-axis, highlight the conical tip of any axis. Drag in either direction along the axis.
- To rotate the item, click the curved rotation segment just inside an axis tip. A yellow circle appears showing the rotation plane. Drag in a clockwise or counterclockwise circle around the 3D Axis center. To rotate more gradually, move the mouse farther away from the center of the 3D Axis.
- To resize the item, drag the center cube in the 3D Axis up or down.
- To compress or elongate the item along an axis, drag one of the colored transform cubes either toward or away from the center cube.
- To constrain movement to an object plane, move the mouse pointer into the area where two axes intersect, near the center cube. A yellow plane icon appears between two axes. Drag in any direction. You can also move the pointer over the lower part of the center cube to activate the plane icon.

More Help topics

3D panel overview

3D texture editing

3D content: creating, combining, and converting

3D output

Photoshop and MATLAB

Note: *In Photoshop CS6, MATLAB-related functionality was part of Photoshop Extended. All features in the erstwhile Photoshop Extended offering are now part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

About Photoshop and MATLAB

MATLAB is a high-level technical computing language and interactive environment for algorithm development, data visualization, data analysis, and numeric computation. With Photoshop you can view MATLAB image-processing results in Photoshop, and combine MATLAB commands with Photoshop image-editing features.

Once you connect to Photoshop from MATLAB, typing commands into the MATLAB command prompt performs operations in Photoshop. You can run MATLAB algorithms and view the results in your image in Photoshop.

Note: *Communication between Photoshop and MATLAB uses the Photoshop JavaScript interface and the MATLAB library interface.*

Set up MATLAB and Photoshop

Install Photoshop and MATLAB on your computer. Once you have installed Photoshop and MATLAB, you should verify the MATLAB integration.

Install the MATLAB Plug-in

Download and install the MATLAB plug-in package.

Note: *This package contains the MATLAB library and sample scripts for both English and Japanese.*

For 64-bit systems, install the appropriate compiler

To use the Photoshop interface on a 64-bit system, a C compiler must be installed:

- In Windows, install Microsoft Developer Studio.
- In Mac OS, install XCode.

Note: *In Windows, use 64-bit Photoshop with 64-bit MATLAB, and 32-bit Photoshop with 32-bit MATLAB.*

Verify MATLAB integration

1. Start Photoshop and then MATLAB.
2. From MATLAB, add the path Photoshop/MATLAB, including subfolders.
3. At the MATLAB prompt, open the MATLAB folder, locate and open the Tests folder, and then type testall.
4. Photoshop and MATLAB run a series of tests to ensure integration between the two programs and display a summary report.

(Optional) Set access to Photoshop from MATLAB

You can set up a path to Photoshop to allow direct access to Photoshop commands from MATLAB.

1 From MATLAB, choose File > Set Path.
2 Click Add Folder and select the MATLAB folder where Photoshop is installed.
3 Click Save and then Close.
4 From the MATLAB menu, choose File > Preferences.
5 In the Preferences dialog box, click the General tree (upper-left).
6 Click the Update Toolbox Path Cache button.
7 Click Apply and then OK.

Connect/disconnect to Photoshop from MATLAB

? In MATLAB, do one of the following:

- To launch or connect to Photoshop, type pslaunch, and then press Enter (Windows) or Return (Mac OS).
- To disconnect from Photoshop and quit, type psquit and press Enter (Windows) or Return (Mac OS).

Using MATLAB Help

MATLAB's Help system includes examples of a MATLAB/Photoshop workflow.

1 Choose Help > Full Product Family Help.

   You see a Photoshop Toolbox with submenu items, including Examples for getting started. If you don't see the Photoshop Toolbox, try the following steps.

2 Click the Start Button.
3 Choose Desktop Tools > View Source Files.
4 Click the Refresh Start button, then Close, then retry the Help menu.

MATLAB commands

Typing commands in the MATLAB command line lets you connect and disconnect to Photoshop, and generate pixels viewable in a Photoshop document.

For a list of all MATLAB Photoshop commands, browse the file psfunctionscat.html, available in the MATLAB folder in the directory where you installed Photoshop. Enter help (command name) at the MATLAB command prompt for a fuller description of each command, including syntax, arguments, and examples.

Note: *All MATLAB commands are supported for Japanese characters. MATLAB for Windows supports a Japanese language user interface on Japanese language Windows XP systems. MATLAB for Mac OS supports US English only on Japanese language Mac OS systems. For more information, contact The MathWorks, Inc.*

Create a document in MATLAB

1 In MATLAB, enter psnewdoc.
2 To specify the attributes of the new document, enter one of the following:

- To create a document using the default values, enter psnewdoc(). For information on default values, see below.

- To create a document with a specific width and height, enter psnewdoc(W,H). The W and H values use the current units set in the Units & Rulers option in the Photoshop Preferences dialog box. Other document attributes are set to their default values.

Note: *Enter "undefined" as a string to skip input arguments. The default size for a new document is 504 x 360 pixels.*

- To create a document and specify attributes, enter psnewdoc(W,H,R,N,M,F,A,B,P). For information on new document attributes, see below.

Here is an example code for creating a document and specifying all the attributes in MATLAB:

```
psnewdoc(10, 10, 72, 'hi', 'cmyk', 'transparent', 2.5, 16, 'U.S. Web Coated (SWOP) v2')
```

New document attributes and defaults

Entering psnewdoc(W,H,R,N,M,F,A,B,P) creates a document with values for the following attributes:

W Specifies the width of the document using the current units from the Units & Rulers option in the Photoshop Preferences dialog box. The default width is 504 pixels.

H Specifies the height of the document using the current units in the Units & Rulers panel in the Photoshop Preference dialog box. The default height is 360.

R Specifies the resolution. The default is 72 ppi.

N Specifies the document name. The default is Untitled-X, where X is the index for new documents.

M Specifies the color mode: RGB, CMYK, Lab, Bitmap, or Grayscale. The default is RGB.

F Specifies the background contents of the new document: White,Background Color, or Transparent. The default is White.

A Specifies the pixel aspect ratio. The default is 1.0 (square).

B Specifies the bit depth: 1, 8, 16, or 32. The default is 8.

P Specifies the color profile. The default is the working color space for the specified color mode. The working spaces are specified in the Photoshop Color Settings dialog box.

Measurement

Note: *In Photoshop CS6, 3D functionality is part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

About measurement

Using the Photosho Measurement feature you can measure any area defined with the Ruler tool or with a selection tool, including irregular areas selected with the Lasso, Quick Select, or Magic Wand tools. You can also compute the height, width, area, and perimeter, or track measurements of one image or multiple images. Measurement data is recorded in the Measurement Log panel. You can customize the Measurement Log columns, sort data within columns, and export data from the log to a tab-delimited, Unicode text file.

Measurement scale

Setting a measurement scale sets a specified number of pixels in the image equal to a number of scale units, such as inches, millimeters, or microns. Once you've created a scale, you can measure areas and receive calculations and log results in the selected scale units. You can create multiple measurement scale presets, although only one scale can be used in a document at a time.

Scale markers

You can place scale markers on an image to display the measurement scale. Scale markers can appear with or without a caption displaying measurement scale units.

Set the measurement scale

Use the Ruler tool to set the measurement scale for a document. You can create measurement scale presets for frequently used measurement scales. Presets are added to the Image > Analysis > Set Measurement Scale submenu. The current measurement scale for a document is checked in the submenu, and appears in the Info panel.

Note: *Measurement scale is set automatically for DICOM files. See DICOM files.*

Choose Image > Analysis > Set Measurement Scale > Default to return to the default measurement scale, 1 pixel = 1 pixel.

Set measurement scale

1 Open a document.

2 Choose Image > Analysis > Set Measurement Scale > Custom. The Ruler tool is automatically selected. Drag the tool to measure a pixel distance in the image or enter a value in the Pixel Length text box. Your current tool setting is restored when you close the Measurement Scale dialog box.

3 Enter the Logical Length and Logical Units that you want to set equal to the Pixel Length.

For example, if the Pixel Length is 50, and you want to set a scale of 50 pixels per micron, enter 1 for Logical Length, and microns for the Logical Units.

4 Click OK in the Measurement Scale dialog box to set the measurement scale on the document.

5 Choose File > Save to save the current measurement scale setting with the document.

To display the scale in the Info panel, choose Panel Options from the panel menu, and select Measurement Scale in the Status Information area.

To display the measurement scale at the bottom of the document window, choose Show > Measurement Scale from the document window menu.

Create a measurement scale preset

1 Open a document.

2 Choose Image > Analysis > Set Measurement Scale > Custom.

3 Create a measurement scale.

4 Click Save Preset and name the preset.

5 Click OK. The preset you created is added to the Image > Analysis > Set Measurement Scale submenu.

Delete a measurement scale preset

1 Choose Image > Analysis > Set Measurement Scale > Custom.

2 Select the preset you want to delete.

3 Click Delete Preset and click OK.

Use scale markers

Measurement scale markers display the measurement scale used in your document. Set the measurement scale for a document before creating a scale marker. You can set the marker length in logical units, include a text caption indicating the length, and set the marker and caption color to black or white.

Create a scale marker

1 Choose Image > Analysis > Place Scale Marker.

2 In the Measurement Scale Marker dialog box, set the following options:

Length Enter a value to set the length of the scale marker. The length of the marker in pixels depends on the measurement scale that is currently selected for the document.

Font Choose the font for the display text.

Font Size Choose the font size for the display text.

Display Text Select this option to show the logical length and units for the scale marker.

Text position Displays caption above or below the scale marker.

Color Sets the scale marker and caption color to black or white.

3 Click OK.

The scale marker is placed in the lower left corner of the image. The marker adds a layer group to the document, containing a text layer (if the Display Text option is selected) and a graphic layer. You can use the Move tool to move the scale marker, or the Text tool to edit the caption or change text size, font, or color.

Add or replace scale markers

You can place multiple scale markers in a document, or replace existing markers.

Note: *Additional scale markers are placed in the same position on the image and can obscure each other, depending on their length. To view an underlying marker, turn off the scale marker layer set.*

1 Choose Image > Analysis > Place Scale Marker.

2 Click Remove or Keep.

3 Enter settings for the new marker and click OK.

Delete a scale marker

1 In the Layers panel, select the Measurement Scale Marker layer group for the scale marker you want to delete.

2 Right-click the layer group and select Delete Group from the context menu, or click the Delete Layer button.

3 Click Group and Contents.

Perform a measurement

You can measure using the Photoshop selection tools, Ruler tool, or Count tool. Choose a measurement tool that matches the type of data you want to record in the Measurement Log.

- Create a selection area to measure values such as height, width, perimeter, area, and pixel gray values. You can measure one selection or several selections at once.

- Draw a line with the Ruler tool to measure linear distance and angle.
- Use the Count tool to count items on the image, then record the number of items. See Count objects in an image.

Each measurement measures one or more data points. The data points you select determine the information recorded in the Measurement Log. Data points correspond to the type of tool you're measuring with. Area, perimeter, height, and width are available data points for measuring selections. Length and angle are available data points for Ruler tool measurements. You can create and save sets of data points for particular types of measurements to speed your workflow.

1 Open an existing document.

2 Choose Image > Analysis > Set Measurement Scale and choose a measurement scale preset for the document (see Set the measurement scale), or choose Custom and set a custom measurement scale.

Measurements are computed and recorded in the Measurement Log using the scale units in effect when a measurement is recorded. If no measurement scale exists, the default scale is 1 pixel = 1 pixel.

3 (Optional) Choose Image > Analysis > Select Data Points and do one of the following:

- Choose Custom to select data points to measure.
- Select an existing data point preset from the submenu.

In the Select Data Points dialog box, data points are grouped according to the measurement tool that can measure them. The Common data points are available for all tools. They add useful information to the Measurement Log such as the name of the file being measured, the measurement scale, and the date/time of the measurement.

By default all data points are selected. You can select a subset of data points for a particular type of measurement, then save the combination as a data point preset.

Note: *When you measure with a particular tool, only the data points associated with that tool are displayed in the log, even if other data points are selected. For example, if you make a measurement with the Ruler tool, only the Ruler tool data points appear in the Measurement Log, along with any Common data points that are selected.*

4 Choose an image feature and measurement tool to match the selected data points. Do one of the following:

- Create one or more selections on the image.
- Choose Image > Analysis > Ruler Tool, or click the Ruler tool in the toolbox, then use the tool to measure the length of an image area.
- Choose Image > Analysis > Count Tool, or click the Count tool in the toolbox, then count items in the image.

5 Choose Window > Measurement Log to open the Measurement Log panel.

6 Choose Image > Analysis > Record Measurements, or click Record Measurements in the Measurement Log panel.

Note: *If your currently selected data points do not correspond to the current measurement tool, you are asked to select data points for that tool.*

The Measurement log has columns for each data point you selected in the Measurement Data Points dialog box. Each measurement you make enters a new row of data in the Measurement Log.

If you measure multiple selected areas on the image, one row of data is created in the log containing summary or cumulative data for all selected areas, followed by a row of data for each selection area. Each selection area is listed as a separate Feature in the Label column of the log and assigned a unique number.

You can repeat steps 2 through 6 for a variety of different selections in the same or multiple documents. The Document column in the Measurement Log reflects the source of the measurement data.

Measurement data points

Angle Angle of orientation (±0-180) of the Ruler tool.

Area Area of selection in square pixels, or in calibrated units according to the current measurement scale (such as square millimeters).

Circularity 4pi(area/perimeter^2). A value of 1.0 indicates a perfect circle. As the value approaches 0.0, it indicates an increasingly elongated polygon. Values may not be valid for very small selections.

Count Varies according to the measuring tool used. Selection tool: the number of discontiguous selection areas on the image. Count tool: the number of counted items on the image. Ruler tool: the number of Ruler lines visible (1 or 2).

Date and Time Applies a date/time stamp of when the measurement occurred.

Document Identifies the document (file) measured.

Gray Value This is a measurement of brightness, either from 0 to 255 (for 8-bit images), 0 to 32,768 (for 16-bit images), or 0.0 to 10 (for 32-bit images). For all gray value-related measurements, the image is internally converted to grayscale (equivalent to choosing Image > Mode > Grayscale) using the default grayscale profile. Then the requested calculations (mean, median, minimum, maximum) are calculated for each feature and for the summary.

Height Height of the selection (max y - min y), in units according to the current measurement scale.

Histogram Generates histogram data for each channel in the image (three for RGB images, four for CMYK, and so on), recording the number of pixels at each value from 0 to 255 (16-bit or 32-bit values are converted to 8-bit). When you export data from the Measurement Log, the numeric histogram data is exported to a CSV (comma-separated value) file. The file is placed in its own folder at the same location where the measurement log tab-delimited text file is exported. Histogram files are assigned a unique number, starting at 0, and progressing by 1. For multiple selections measured at once, one histogram file is generated for the total selected area, plus additional histogram files for each selection.

Integrated Density The sum of the values of the pixels in the selection. This is equivalent to the product of Area (in pixels) and Mean Gray Value.

Label Identifies and automatically numbers each measurement as Measurement 1, Measurement 2, and so on. For multiple selections measured simultaneously, each selection is assigned an additional Feature label and number.

Length Linear distance defined by the Ruler tool on the image, in units according to the current measurement scale.

Perimeter The perimeter of the selection. For multiple selections measured at once, one measurement is generated for the total perimeter of all selections, plus additional measurements for each selection.

Scale The measurement scale of the source document (for example, 100 px = 3 miles).

Scale Units Logical units of the measurement scale.

Scale Factor The number of pixels assigned to the scale unit.

Source Source of the measurement: Ruler tool, Count tool, or Selection.

Width Width of the selection (max x - min x), in units according to the current measurement scale.

Create a data point preset

1. Choose Image > Analysis > Select Data Points > Custom.
2. Select data points to include in the preset.
3. Click Save Preset and name the preset.
4. Click OK. The preset is saved and is now available from the Analysis > Select Data Points submenu.

Edit a data point preset

1 Choose Image > Analysis > Select Data Points > Custom.

2 Choose the preset you want to edit from the Preset menu.

3 Select or deselect data points. The Preset name changes to Custom.

4 Click Save Preset. Enter the original preset name to replace the existing preset, or a new name to create a new preset.

Delete a data point preset

1 Choose Image > Analysis > Select Data Points > Custom.

2 Choose the preset you want to delete from the Preset menu.

3 Click Delete Preset, then Yes to confirm the deletion.

4 Click OK.

Use the Measurement Log

When you measure an object, the Measurement Log panel records the measurement data. Each row in the log represents a measurement set; columns represent the data points in a measurement set.

When you measure an object, a new row appears in the Measurement Log. You can reorder columns in the log, sort data in columns, delete rows or columns, or export data from the log to a comma-delimited text file.

Display the Measurement Log

? Do one of the following:

- Choose Image > Analysis > Record Measurements.
- Choose Window > Measurement Log.

Select rows in the log

? Do one of the following:

- Click a row in the log to select it.
- To select multiple contiguous rows, click the first row and drag through additional rows, or click the first row and then Shift-click the last row.
- To select noncontiguous rows, click the first row and then Ctrl-click (Windows) or Command-click (Mac) additional rows.
- To select all rows, click Select All.
- To deselect all rows, click Select None.

Select columns in the log

? Do one of the following:

- Click a column header.
- To select contiguous columns, click a column header and drag through additional columns, or click the first column header and then Shift-click the last column header.
- To select noncontiguous columns, click the first column header and then Ctrl-click (Windows) or Command-click (Mac) additional column headers.

Reorder, resize, or sort columns in the log

? Do one of the following:

- Drag selected columns to reorder them in the log. The column position is indicated by a double black line.
- To resize a column, click the column header and then drag the separator.
- To sort data in a column, click the column header to change the sort order, or right-click the header and choose Sort Ascending or Sort Descending. (Rows cannot be manually reordered.)

Delete rows or columns from the log

1 Select one or more rows or columns in the log.

2 Do one of the following:

- Choose Delete from the Measurement Log options menu.
- Click the Delete icon at the top of the panel.
- Right-click in a row or column header, then select Delete from the pop-up menu.

Export Measurement Log data

You can export data from the Measurement Log into a comma-delimited text file. You can open the text file in a spreadsheet application and perform statistical or analytical calculations from the measurement data.

1 Select one or more rows of data in the log.

2 Do one of the following:

- Choose Export from the Measurement Log options menu.
- Click the Export icon at the top of the panel.
- Right-click in a row, then select Export from the pop-up menu.

3 Enter a filename and location, and click Save.

The measurements are exported to a comma-delimited, UTF-8 text file.

Image Stacks

Note: *In Photoshop CS6, 3D functionality is part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

About image stacks

An image stack combines a group of images with a similar frame of reference, but differences of quality or content across the set. Once combined in a stack, you can process the multiple images to produce a composite view that eliminates unwanted content or noise.

You can use image stacks to enhance images in number of ways:

- To reduce image noise and distortion in forensic, medical, or astrophotographic images.
- To remove unwanted or accidental objects from a series of stationary photos or a series of video frames. For example, you want to remove a figure walking through an image, or remove a car passing in front of the main subject matter.

Image stacks are stored as Smart Objects. The processing options you can apply to the stack are called stack modes. Applying a stack mode to an image stack is a non-destructive edit. You can change stack modes to produce different effects; the original image information in the stack remains unchanged. To preserve changes after you apply the stack mode, save the result as a new image, or rasterize the Smart Object. You can create an image stack manually or using a script.

Create an image stack

For best results, images contained in an image stack should have the same dimensions and mostly similar content, such as a set of still images taken from a fixed viewpoint, or a series of frames from a stationary video camera. The content of your images should be similar enough to allow you to register or align them to other images in the set.

1 Combine the separate images into one multi-layered image. See Duplicate Photoshop layers.

   Note: *An image stack must contain at least two layers.*

   You can also combine images using a script (File > Scripts > Load Files into Stack).

2 Choose Select > All Layers.

   Note: *To make the Background layer selectable with the All Layers command, you must first convert it to a regular layer.*

3 Choose Edit > Auto-Align Layers and select Auto as the alignment option. If Auto does not create good registration of your layers, try the Reposition option.

4 Choose Layer > Smart Objects > Convert to Smart Object.

5 Choose Layer > Smart Objects > Stack Mode and select a stack mode from the submenu.

   - For noise reduction, use the Mean or Median plug-ins.
   - For removing objects from the image, use the Median plug-in.

     The output is a composite image the same size as the original image stack. You may need to experiment with different plug-ins to get the best enhancement for a particular image.

     To change the rendering effect, choose a different Stack Mode from the submenu. Stack rendering is not cumulative—each render effect operates on the original image data in the stack and replaces previous effects.

Stack modes

Stack modes operate on a per-channel basis only, and only on non-transparent pixels. For example, the Maximum mode returns the maximum red, green, and blue channel values for a pixel cross section and merges them into one composite pixel value in the rendered image.

Rendering plug-in name	Result	Comments
Entropy	entropy = - sum((probability of value) * log2(probability of value)) Probability of value = (number of occurrences of value) / (total number of non-transparent pixels)	The binary entropy (or zero order entropy) defines a lower bound on how many bits would be necessary to losslessly encode the information in a set.
Kurtosis	kurtosis = (sum((value - mean)^4) over non-transparent pixels) / ((number of non-transparent pixels - 1) * (standard deviation)^4).	A measure of peakedness or flatness compared to a normal distribution. The kurtosis for a standard normal distribution is 3.0. Kurtosis greater than 3 indicates a peaked distribution, and kurtosis less than 3 indicates a flat distribution (compared to a normal distribution).
Maximum	The maximum channel values for all non-transparent pixels	
Mean	The mean channel values for all non-transparent pixels	Effective for noise reduction
Median	The median channel values for all non-transparent pixels	Effective for noise reduction and removal of unwanted content from the image
Minimum	The minimum channel values for all non-transparent pixels	
Range	Maximum minus the minimum of the non-transparent pixel values	
Skewness	skewness = (sum((value - mean)^3) over non-transparent pixels) / ((number of non-transparent pixels - 1) * (standard deviation)^3)	Skewness is a measure of symmetry or asymmetry around the statistical mean
Standard Deviation	standard deviation = Square Root(variance)	
Summation	The sum channel values for all non-transparent pixels	
Variance	variance = (sum((value-mean)^2) over non-transparent pixels) / (number of non-transparent pixels - 1)	

Remove stack rendering

? Choose Layers > Smart Objects > Stack Mode > None to remove any rendering from an image stack and convert it back to a regular Smart Object.

Edit an image stack

Because an image stack is a Smart Object, you can edit the original images that make up the stack layers at any time.

? Choose Layer > Smart Objects > Edit Contents, or double-click the layer thumbnail. After you save the edited Smart Object, the stack is automatically rendered with the last rendering option applied to the stack.

Convert an image stack

To preserve rendering effects on an image stack, convert the Smart Object to a regular layer. (You can copy the Smart Object before converting, in case you want to later re-render the image stack.)

? Choose Layer > Smart Objects > Rasterize.

Use a script to create an image stack

You can use the Statistics script to automate creating and rendering an image stack.

1 Choose File > Scripts > Statistics.

2 Choose a stack mode from the Choose Stack Mode menu.

3 Apply the stack mode to currently open files, or browse to select a folder or individual files.

   Files you select are listed in the dialog box.

4 If desired, select Attempt To Automatically Align Source Images (equivalent to choosing Edit > Auto-Align Layers). Then click OK.

   Photoshop combines the multiple images into a single multilayered image, converts the layers into a Smart Object, and applies the selected stack mode.

More Help topics

Automatically align image layers

DICOM files

Note: *In Photoshop CS6, 3D functionality is part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

About DICOM files

Note: *DICOM (an acronym for Digital Imaging and Communications in Medicine) is the most common standard for receiving medical scans. Photoshop allows you to open and work with DICOM (.dc3, .dcm, .dic, or no extension) files. DICOM files can contain multiple "slices" or frames, which represent different layers of a scan.Photoshop reads all frames from a DICOM file and converts them to Photoshop layers. Photoshop can also place all DICOM frames in a grid on one layer, or open frames as a 3D volume which you can rotate in 3D space. Photoshop can read 8-, 10-, 12-, or 16-bit DICOM files. (Photoshop converts 10- and 12-bit files to 16-bit files.)Once you've opened a DICOM file in Photoshop, you can use any Photoshop tool to adjust, mark up, or annotate the file. For example, use the Notes tool to add a comment to the file, the Pencil tool to mark a specific area of the scan or the Dust And Scratches filter to remove dust or scratches from a scan. Use the Ruler or selection tools to make measurements of image content.*

Note: *Any measurement scale present in a DICOM file is automatically imported with the file. If no scale is present, the default scale of 1 pixel = 1 mm is added as a custom measurement scale. See Set the measurement scale (Photoshop Extended) .*

You can save 8-bit DICOM files in any file format Photoshop supports (16-bit files must be saved as DICOM, Large Document Format, Photoshop, Photoshop PDF, Photoshop Raw, PNG, or TIFF files).

Note: *When you save a file as DICOM, any layer styles, adjustments, blend modes, or masks are discarded.*

You can also view and edit metadata for DICOM files in Bridge or in the Photoshop File Info dialog box. DICOM files support external automation through scripting (see Scripting).

Open a DICOM file

Before you open a DICOM file, you can specify how DICOM frames are opened (as layers, in a grid, or as a 3D volume), and set options (in the DICOM File Import dialog box) that anonymize patient metadata and display overlays. During the import you can also perform pans, zooms, and window leveling.

The DICOM import dialog box also displays DICOM header information—textual information about the file, such as its dimensions, data resolution, and whether the data has been compressed.

You can import a sequence of multiple, single-frame DICOM files into a single multilayered Photoshop file, using the New Video Layer from File command. See Import image sequences.

1 Choose File > Open, select a DICOM file, and click Open.

2 Select the frames you want to open. Shift-click to select contiguous frames. To select noncontiguous frames, Ctrl-click (Windows) or Command-click (Mac OS). Click Select All to select all frames.

To quickly scroll through frames, use the mouse scroll wheel (Windows) or click the Right or Left Arrow buttons below the large preview area.

3 Choose from the following options, and then click Open.

Frame Import Import Frames As Layers places DICOM frames on layers. N-Up Configuration displays multiple frames in a grid (enter values in the Rows and Columns boxes to specify height and width of grid). Import as volume opens the DICOM frames as a volume, where the z-distance is determined by DICOM settings and data is interpolated between the frames. You can view the volume from any angle, using a variety of rendering modes to highlight data.

DICOM Dataset Anonymize overwrites patient metadata with "anonymize." Show Overlays displays overlays such as annotations, curves, or text.

Windowing Select Show Windowing Options to adjust the contrast (Window Width) and brightness (Window Level) of the frame. Alternatively, you can drag the Window Level tool up or down to adjust the level, or to the right or left to adjust the width. You can also choose common radiology presets from the Window Preset menu (Default, Lung, Bone, or Abdomen). Select Reverse Image to invert the brightness values of the frame.

To zoom, choose a zoom level from the Select Zoom Level menu (or click the plus and minus signs to zoom in and out). To pan, click the Hand icon at the top of the dialog box and drag across the frame.

Create a 3D volume from DICOM frames

1 Choose File > Open, select a DICOM file, and click Open.

2 Select the frames you want to convert to a 3D volume. Shift-click to select contiguous frames. To select noncontiguous frames, Ctrl-click (Windows) or Command-click (Mac OS). Click Select All to select all frames.

3 In Frame Import Options, select Import as volume, then click Open.

Photoshop creates a 3D volume of the DICOM frames and places it on a 3D layer in the Layers panel. You can use Photoshop's 3D position tools to view the 3D volume from any angle, or change render settings to better visualize data.

- The original DICOM file is preserved as a Diffuse texture layer associated with the 3D volume layer. For information on 3D textures, see 3D texture editing.
- Double-click the texture layer to open the DICOM file as a Smart Object in its own document window. The DICOM frames appear as separate layers in the Layers panel.
- Any changes you make to individual layers are applied to the 3D volume when you close and save the Smart Object.

To save the 3D volume, you can export the 3D layer or save the file in PSD format. See Saving and exporting 3D files.

View a 3D volume from different angles

1 Select the 3D layer containing the DICOM volume in the Layers panel.

2 Select either the 3D Position tool or a 3D camera tool in the Tools panel.

3 Use the position or camera tools in the options bar to rotate, move, or scale the 3D volume. See 3D object and camera tools.

If OpenGL support is enabled on your system, you can also use the 3D Axis to rotate, move, or scale the 3D volume. See 3D Axis.

View a 3D volume in different render modes

1 Select the 3D layer containing the DICOM volume in the Layers panel.

2 Choose Window > 3D to open the 3D panel.

3 From the Preset menu in the lower section of the 3D panel, select a render mode.

Note: *Render modes that use a transfer function use a Photoshop gradient to render values in the volume. The gradient color and opacity values are combined with the grayscale values in the volume to optimize or highlight different types of content. Transfer function render modes are only available for grayscale DICOM images.*

Enhanced Boundaries Lowers the opacity of homogeneous regions while retaining the opacity of the boundaries. It can also reduce noise in the volume.

Full Range Color Scale Transfer function that uses a full "rainbow" Photoshop color gradient.

High Range Highlights Transfer function that uses the color white for the entire value range, zero opacity for low range values, and high opacity for high range values.

Low Range Highlights Transfer function that uses the color white for the entire value range, zero opacity for high range values, and high opacity for low range values.

Maximum Intensity Projection Displays maximum values in the volume to provides a quick preview of volume structure. Does not provide any depth cues.

Red-Blue Color Scale Transfer function that uses a full red-blue color gradient.

Thin Isolines Transfer function that uses constant color, while opacity component is a function with multiple spikes, to display isovalues.

X-Ray Approximates X-ray radiation transport through an X-ray translucent medium. This effect is useful for generating an image from a CT scan that looks like an X-ray shot of the same object.

White-Black Color Scale Transfer function using a white-black color component.

4 (Optional) To create a custom render mode, click Render Settings in the 3D panel to open the 3D Render Settings dialog box. Select options in the Volume Styles section of the dialog. See Change 3D render settings.

Export DICOM frames as JPEG files

1 Open a DICOM file and set options in the DICOM File Import dialog box (see Open a DICOM file (Photoshop Extended)).

2 Select frames in the DICOM File Import dialog box: Shift-click to select contiguous frames, Ctrl-click (Windows) or Command-click (Mac OS) to select noncontiguous frames, or click Select All to select all frames.

3 Enter a prefix in the Prefix box in the Export Options area.

4 Click Export Presentation (JPEG), select a folder, and click Select.

The JPEG files are saved in the specified location with the prefix added to the filenames. If you selected multiple frames, Photoshop appends successive numbering to the end of each filename (for example, DICOM Frame1, DICOM Frame2, DICOM Frame3).

DICOM metadata

You can view and edit several categories of DICOM metadata in the Photoshop File Info dialog box. **Patient data**Includes patient name, ID, sex, and date of birth.**Study data**Includes study ID, referring physician, study date and time, and study description. **Series data**Includes series number, modality, series date and time, and series description. **Equipment data**Includes the equipment institution and manufacturer. **Image data**Includes the transfer syntax, photometric interpretation, image width and height, bits per pixel, and frames. (These fields are not editable.)

Animate DICOM files

To animate DICOM slices or frames, select all DICOM layers and choose Make Frames From Layers from the Animation (Timeline) panel menu.

After creating frames in the (Animation) Timeline panel, you can save DICOM files as QuickTime movies (change grayscale DICOM files to RGB, and then render to video). You can also save frames as animated GIF files (choose File > Save for Web and Devices).

You can also use the Timeline panel to animate a 3D volume created from a DICOM file. See Create 3D objects and animations.

More Help topics

Notes

Paint with the Brush tool or Pencil tool

Apply the Dust And Scratches filter

About metadata

Export video files or image sequences

Create frame animations

Timeline animation workflow

Count objects in an image

Note: *In Photoshop CS6, 3D functionality is part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

You can use the Count tool to count objects in an image. To count objects manually, you click the image with the Count tool and Photoshop tracks the number of clicks. The count number is displayed on the item and in the Count tool options bar. Count numbers are saved when you save a file.

Photoshop can also automatically count multiple selected areas in an image, and record the results in the Measurement Log panel. See Perform a measurement.

Manually count items in an image

1 Select the Count tool (located beneath the Eyedropper tool in the Tools panel).

2 Choose Count tool options.

Count Group A default count group is created when you add count numbers to the image. You can create multiple count groups, each with its own name, marker and label size, and color. When you add count numbers to the image, the currently selected count group is incremented. Click the eye icon to show or hide a count group. Click the folder icon to create a count group, the Delete icon to delete a count group. Choose Rename from the Count Group menu to rename a count group.

Color To set the color for the count group, click the Color Picker.

Marker Size Enter a value from 1 to 10, or use the scrubby slider to change the value.

Label Size Enter a value from 8 to 72, or use the scrubby slider to change the value.

3 Click in the image to add a count marker and label:

- To move a count marker, move the pointer over the marker or number until the cursor changes to the direction arrows, then drag. (Shift-click to constrain the drag horizontally or vertically.)
- Alt-click (Windows) or Option-click (Mac OS) to remove a marker. The total count is updated.
- Click Clear in the options bar to reset the count for the currently selected count group to 0.

Note: *Counts already recorded in the Measurement Log are not changed by clearing count numbers from the image.*

4 (Optional) To change count groups, select a different group from the Count Group menu, or click the folder icon to create a count group. Subsequent clicks update the currently selected count group.

5 (Optional) To display or hide the count numbers:

- Choose View > Show > Count.
- Choose View > Extras, View > Show > All, or View > Show > None.

6 (Optional) Choose Analysis > Record Measurements or click Record Measurements in the Measurement Log panel to record the count number to the Measurement Log.

Note: *To record a count to the Measurement Log, you must have Count selected as a measurement data point. Choose Analysis > Select Data Points > Custom and select the Count data point in the Count Tool area.*

7 (Optional) Choose File > Save to save any count numbers and count groups you've added to the image.

Automatic counting using a selection

Use the Photoshop automatic counting feature to count multiple selection areas in an image. Define selection areas using the Magic Wand tool or the Color Range command.

1 Select the Magic Wand tool, or choose Select > Color Range.

2 Create a selection that includes the objects in the image that you want to count. For best results, use an image with objects that contrast well against their background.

- If you are using the Magic Wand tool, increase or decrease the Tolerance option to optimize the selection of the objects you want to count in the image. Deselect the Anti-alias and Contiguous options.
- For Color Range, set Fuzziness and Selected Colors to fine-tune the selected areas in the image (see Select a color range in an image).

3 Choose Analysis > Select Data Points > Custom.

4 In the Selections area, select the Count data point and click OK.

5 Choose Window > Measurement Log.

6 Choose Analysis > Record Measurements, or click Record Measurements in the Measurement Log. (If this option isn't available, select a tool other than the Count tool.)

   Photoshop counts the selection areas and enters the number in the Count column in the Measurement Log.

More Help topics

Select with the Magic Wand tool

Combine and convert 3D objects

Combine 3D objects

Merging 3D layers allows you to combine multiple 3D models in one scene. Once combined, each 3D model can be manipulated separately, or you can use position and camera tools on all models simultaneously.

1 Open two document windows, each containing a 3D layer.

2 Make the source document (the file from which you are copying the 3D layer) active.

3 Select the 3D layer in the Layers panel and drag it into the window of the target document (the file which will contain the combined 3D objects).

   The 3D layer is added as a new 3D layer in the target document. It becomes the active layer in the Layers panel of the target document.

4 In the Tools panel, select a 3D camera tool.

5 In the options bar, from the Position menu, select the layer name for the original 3D layer in the target file.

   After you match the camera position of the two 3D layers, the two 3D objects appear together in the scene. Use the 3D object tools to reposition the objects before merging.

6 From the Layers panel options menu, choose Merge Down.

   The two 3D layers are combined into one 3D layer. The point of origin of each model is aligned.

   Note: *Depending on the size of each 3D model, one model may appear partially or completely embedded in the other model after merging 3D layers.*

After merging two 3D models, all meshes and materials from each 3D file are contained in the target file and appear in the 3D panel. In the Meshes panel, you can select and reposition individual meshes using the 3D position tools in the panel. See 3D Mesh settings (Photoshop Extended) .

To alternate between moving all models at once and moving individual models in the layer, switch between the 3D position tools in the Tools panel and the tools in the Meshes panel.

Combine 3D and 2D layers

You can combine 3D layers with one or more 2D layers to create composite effects. For example, you can place a model against a background image and change its position or viewing angle to match the background.

? Do one of the following:

- With the 2D file open, choose 3D > New Layer from 3D File, and open a 3D file.
- With both a 2D file and a 3D file open, drag either the 2D or 3D layer from one file into the open document window of the other file. The layer you add moves to the top of the Layers panel.

When working in a file with combined 2D and 3D layers, you can temporarily hide the 2D layers while working with the 3D layer.

Hide layers for better performance

In a multi-layer document with 2D layers above a 3D layers, you can temporarily move the 3D layer to the top of the layer stack for faster screen rendering.

1. Choose 3D > Auto-Hide Layers For Performance.
2. Select a 3D Position or Camera tool.

When you hold down the mouse button with either tool, all 2D layers are temporarily hidden. When you release the mouse, all 2D layers reappear. Moving any part of the 3D Axis also hides all 2D layers.

Convert a 3D layer to a 2D layer

Converting a 3D layer to a 2D layer rasterizes the 3D content in its current state. Convert a 3D layer to a regular layer only if you no longer want to edit the 3D model position, render mode, textures, or lights. The rasterized image retains the appearance of the 3D scene, but in a flattened 2D format.

? Select the 3D layer in the Layers panel, and choose 3D > Rasterize.

Convert a 3D layer to a Smart Object

Converting a 3D layer to a Smart Object allows you to retain the 3D information contained in the 3D layer. After converting, you can apply transforms or other adjustments like Smart Filters to the Smart Object. You can reopen the Smart Object layer to edit the original 3D scene. Any transforms or adjustments applied to the Smart Object are then applied to the updated 3D content.

1. Select the 3D layer in the Layers panel.
2. From the Layers panel option menu, choose Convert to Smart Object.
3. (Optional) To reedit the 3D content, double-click the Smart Object layer in the Layers panel.

More Help topics

Understand Smart Objects

3D texture editing

You can use the Photoshop painting and adjustment tools to edit the textures contained in a 3D file, or to create new textures. Textures are imported as 2D files with the 3D model. They appear as entries in the Layers panel, nested under the 3D layer, and grouped by map type: Diffuse, Bump, Glossiness, and so on.

To view a thumbnail of a particular texture file, hover the mouse pointer over the name of the texture in the Layers panel. The image size and color mode are also displayed.



***A** 3D layer **B** Texture map types **C** Texture map filename*

***Note:** Texture maps used by a particular material also appear in the lower section of the 3D panel when a material is selected. See 3D Materials settings .*

To edit 3D textures in Photoshop, do either of the following:

- Edit a texture in 2D format. The texture opens as a Smart Object in a separate document window.
- Edit a texture directly on the model. If necessary you can temporarily cut away model surfaces to access areas to paint on. See 3D painting.

Edit a texture in 2D format

1 Do one of the following:
   - Double-click the texture in the Layers panel.
   - In the Materials panel, select the material that contains the texture. In the bottom section of the panel, click the texture menu icon for the texture you want to edit, and choose Open Texture.
2 Use any Photoshop tool to paint on or edit the texture.
3 Make the window containing the 3D model active to see the updated texture applied to the model.
4 Close the texture document and save changes.

Display or hide a texture

You can display and hide a texture to help identify what area of the model the texture is applied to.

? Click the eye icon next to the Texture layer. To hide or display all textures, click the eye icon next to the top-level Texture layer.

Create UV overlays

A diffuse texture file used by multiple materials on a 3D model can group several content areas that are applied to different surfaces on the model. The process called *UV mapping* matches coordinates in the 2D texture map with specific coordinates on the 3D model. UV mapping allows the 2D texture to be painted correctly onto the 3D model.

For 3D content created outside Photoshop, UV mapping occurs in the program where the content was created. However, Photoshop can create UV overlays as guides to help you visualize how a 2D texture map matches up with the 3D model surfaces. These overlays act as guides when editing a texture.

1 Double-click a texture in the Layers panel to open it for editing.

   Note: *Create UV Overlays is only enabled when a texture map is open and is the active window.*

2 Choose 3D > Create UV Overlays, then select an overlay option.

   Wireframe Shows edge data of the UV mapping.

   Shaded Shows model areas using a solid rendering mode.

   Normal Map Shows geometric normals translated to RGB values, where R=X, G=Y, and B=Z.

UV overlays are added as additional layers in the Layers panel for the texture file. You can show, hide, move, or delete a UV overlay. The overlays appear on the model surface when you close and save the texture file, or switch from the texture file to the associated 3D layer (the texture file is auto saved).

Note: *Delete or hide UV overlays before performing a final render.*

Reparameterize a texture map

Occasionally you may open a 3D model whose textures are poorly mapped to the underlying model mesh. Poor texture mapping can produce obvious distortions in the surface appearance of the model, such as unwanted seams or areas of stretching or squeezing of the texture pattern. Poor texture mapping can also cause unpredictable results when you paint directly on the model.

To check texture parameterization, open a texture for editing, then apply a UV Overlay to see how the texture aligns with the model surfaces. See Create UV overlays.

The Reparameterization command remaps a texture to the model to correct distortion and create more effective surface coverage.

1 Open a 3D file with a poorly mapped diffuse texture, and select the 3D layer containing the model.

2 Choose 3D > Reparameterize. Photoshop notifies you that you are reapplying the texture to the model. Click OK.

3 Choose a reparameterization option:

   - Low Distortion keeps the texture pattern more intact, but can create more seams on the model surface.
   - Fewer Seams minimizes the number of seams that appear on the model. This can produce more stretching or pinching of the texture, depending on the model.

4 (Optional) If the reparameterization option you chose does not create optimal surface coverage, choose Edit > Undo and try the other option.

You can also use the Reparameterize command to improve the default texture mapping that occurs when you create 3D models from 2D layers. See Create 3D objects from 2D images.

Create a tile for a repeating texture

A repeating texture is composed of identical tiles in a grid pattern. A repeating texture can provide more realistic surface coverage of the model, use less storage, and improve rendering performance. You can convert any 2D file into a tiled painting. After previewing how multiple tiles interact in the painting, you save one tile for use as a repeating texture.

To set up a mesh for a repeating texture, use the 3D application that created the model.

1 Open a 2D file.

2 Select one or more layers in the file, then choose 3D > New Tiled Painting.

   The 2D file is converted to a 3D plane containing nine identical tiles of the original content. Image dimensions remain the same.

3 Edit the tiled texture with painting tools, filters, or other techniques. (Changes you make to one tile automatically appear in the others.)

4 Save a single tile as a 2D image: In the Materials section of the 3D panel, choose Open Texture from the Diffuse menu. Then choose File > Save As, and specify a name, location, and format.

   Unless you plan to use the original, nine-tile painting independently, close it without saving.

5 To load the tile as a repeating texture, open a 3D model file. In the Materials section of the 3D panel, choose Load Texture from the Diffuse menu, and select the file you saved above.

More Help topics

Paint with the Brush tool or Pencil tool

3D workflow

Note: *In Photoshop CS6, 3D functionality was part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

Beginning Photoshop CS6, Photoshop has a more intuitive 3D workflow, with consolidated tools and contextual on-image controls. For a quick description of these new features, see 3D imagingand What's New in CS6 .

3D features | Creative Cloud-only

For users who are new to Creative Cloud, the following features have been updated and added.

- 32-bit color pickers can now be used when specifying colors for materials, lines, surfaces, or lights in the Properties panel.

- Normal maps can be generated from Diffuse maps. In the 3D panel, select the 3D object you want to affect and then, click the Filter By Materials icon in the top area of the panel. Then, in the Properties panel, click the folder icon next to Normal: and choose Generate Normals From Diffuse from the menu.
- If you pause a rendering and make one or more selections, resuming the rendering will be applied to the selections. Resuming a rendering also works even after saving your document as a PSD.
- Cross Section now works with reflective surfaces and other surface styles such as Constant, Cartoon, and Sketch.
- By default, an Image-Based Light (IBL) is added your 3D environment. Adobe offers other IBLs for download from Adobe® Photoshop® Extended 3D Content.
- You can change the Ray Trace rendering tile size from its default, which is set based on how many cores are in your computer. Choose Edit > Preferences > 3D (Windows) or Photoshop > Preferences > 3D (Mac OS) and then, choose a size from the Render Tile Size menu in the Ray Tracer section of the Preferences dialog box.
- During rendering, both the time remaining and percentage rendered are displayed in the Status Bar at the bottom of the document window.
- Photoshop now offers better OpenGL shadows. To specify the shadow quality that works best with your computer, choose Edit > Preferences > 3D (Windows) or Photoshop > Preferences > 3D (Mac OS). Then, choose an option from the Shadow Quality menu in the Interactive Rendering section of the Preferences dialog box.

Click the following link to view a video of Photoshop Senior Product Manager, Zorana Gee, presenting the new 3D features in the Creative Cloud version of Photoshop.

Note: *A minimum of 512 MB of VRAM is required for the 3D features in the Creative Cloud version of Photoshop.*

3D panel targets scene elements

In the streamlined 3D panel, select specific elements you want to edit:

1. At the top of the 3D panel, select Scene , Meshes , Materials , or Lights .
2. Select an individual element (such as Current View in the Scene section). Or select multiple elements to apply uniform properties.
3. Adjust settings in the Properties panel, or drag in the document window. (If you drag a specific object or light, the 3D panel then selects that element.)

Note: To add new lights, click the document icon at the bottom of the Scene and Lights sections. Or click the panel menu to save and load groups of lights as a preset.

Properties panel provides contextual settings

After you select individual elements in the 3D panel or document window, the Properties panel displays related settings. When you finish adjusting, click the Render icon at the bottom of the panel.

Note: Click the Coordinates icon at the top of the panel to enter precise numerical locations for objects, cameras, and lights. To quickly cycle between properties and coordinates, press the V key.

Environment settings include global ambient and image-based lights, and ground plane shadows and reflections.

Scene settings include render presets such as Bounding Box and Wireframe, and custom render options for cross-sections, surfaces, and points.

Camera settings include field of view (FOV), depth of field, and stereo options for anaglyph, lenticular, or side-by-side viewing.

Mesh settings let you catch and cast shadows, adjust 3D extrusions, and edit source text and paths.

Note: To hide an object, but retain its shadows for compositing with 2D images, select Invisible.

Materials settings include texture and bump map settings such as the new Roughness option.

Light settings let you choose from infinite, spot, and point types, and adjust color, intensity, and shadows.

Move tool consolidates object and camera adjustments

The Move tool lets you adjust the placement of objects and camera:

- In the options bar, choose between Rotate , Roll , Drag , Slide , and Scale modes.
- To quickly cycle through these modes, press Shift+V.
- To quickly switch between camera and Environment controls, click away from 3D objects.

Note: In the document window, a gold document border indicates camera control, a blue border Environment control, a green border Scene control, and no border Mesh control.

On-image controls directly edit elements

With on-image controls, you can often edit an entire 3D scene without accessing any workspace panels. To maximize your view, press the F key to cycle between full screen and standard screen modes.

In the document window, you can directly interact with the following elements:

Scene, Mesh, and Light settings To quickly access Scene properties in the document window, right-click the canvas away from 3D objects. Or right-click meshes and lights to access their properties.

Shadows Shift-click them, and then drag to reposition the related light.

Object bounding box controls Click an object once to activate, and then position the mouse pointer over various planes; when a plane is shaded yellow, drag to adjust the object along that axis. Or drag corners to rotate on the X or Y axis.

Create and adjust 3D extrusions

3D extrusion lets you extend type, selections, closed paths, shapes, and image layers into three dimensions.

1 Select a path, shape layer, type layer, image layer, or specific pixel areas.

2 Choose 3D > New 3D Extrusion From Selected Path, Layer, or Current Selection.

Note: To quickly extrude type while editing with the Type tool, click the 3D button in the options bar.

3 With the mesh selected in the 3D panel, select the Deform or Cap icons at the top of the Properties panel.

4 Edit numerical settings in the Properties panel, or drag the interactive extrusion controls in the document window.

To edit the original path, type, or image layer, select the related mesh in the 3D panel, and click Edit Source in the Properties panel.

Define ground planes for imported objects

Quickly create perspective planes with the Vanishing Point filter, and snap an imported object to them.

1 Select an image layer, and choose Filter > Vanishing Point.

2 Using the Create Plane and Edit Plane tools, create a grid to define a ground plane. Then click OK.

3 Choose 3D > New 3D Layer from File.

The imported object is placed on the ground plane you defined.

Make paths from 3D layers

Choose 3D > Make Work Path from 3D Layer to convert the current rendering into a Work Path. This command traces a path over the alpha channel of the layer.

If you render in wireframe mode and adjust the crease threshold value to eliminate some unnecessary lines, you can create a rendering that looks hand drawn when stroked with a Photoshop brush.

Merge multiple 3D layers

To improve performance and interact shadows and reflections for multiple objects, merge as many 3D layers as you need.

Before merging 3D layers, use the Orthographic camera view to position meshes with maximum precision:

1 At the top of the 3D panel, click the Scene icon , and select Current View.

2 In the Properties panel, select Orthographic.

More Help topics

Daniel Presedo's YouTube channel

3D rendering and saving

Note: *In Photoshop CS6, 3D functionality was part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

Change 3D render settings

Render settings determine how 3D models are drawn. Photoshop installs several presets with common settings. Customize settings to create your own presets.

Note: *Render settings are layer-specific. If a document contains multiple 3D layers, specify separate render settings for each.*

Select a render preset

The standard render preset is Default, which displays the visible surfaces of models. Wireframe and Vertices presets reveal the underlying structure. To combine solid and wireframe rendering, choose the Solid Wireframe preset. To view a model as a simple box reflecting its outermost dimensions, choose a Bounding Box preset.

1 At the top of the 3D panel, click the Scene button .

2 In the lower half of the panel, choose an option from the Preset menu.



A Default (Quality set to Interactive) ***B*** *Default (Quality set to Ray Traced and ground plane visible)* ***C*** *Bounding Box* ***D*** *Depth Map* ***E*** *Hidden Wireframe* ***F*** *Line Illustration* ***G*** *Normals* ***H*** *Paint mask* ***I*** *Shaded Illustration* ***J*** *Shaded Vertices* ***K*** *Shaded Wireframe* ***L*** *Solid Wireframe* ***M*** *Transparent Bounding Box Outline* ***N*** *Transparent Bounding Box* ***O*** *Two-Sided* ***P*** *Vertices* ***Q*** *Wireframe*

The Two-Sided preset applies only to cross sections, displaying a solid model on one half of the section, and a wireframe on the other.

Customize render settings

1 At the top of the 3D panel, click the Scene button .

2 To the right of the Render Settings menu, click Edit.

3 (Optional) To see the effect of new settings as you make changes, select Preview. Or, deselect this option to slightly improve performance.

To specify unique settings for each half of a cross section, click the cross section buttons at the top of the dialog box.

4 Enable Face, Edge, Vertex, Volume, or Stereo rendering by clicking the checkboxes on the left side of the dialog box. Then adjust the related settings below.

For information about Volume options, used primarily with DICOM images, see *View the 3D volume in different render modes* .

Face options

Face options determine how model surfaces appear.

Face Style Draws surfaces using any of these methods:

Solid Draws without shadows or reflections using the GPU on an OpenGL video card.

Unlit Texture Draws without lighting, instead displaying only the selected Texture option. (Diffuse is selected by default.)

Flat Applies the same surface normal for all vertices in a face, creating a faceted look.

Constant Replaces textures with currently specified color.

To adjust face, edge, or vertex color, click the Color box.

Bounding Box Displays boxes reflecting the outermost dimensions of each component.

Normals Displays X, Y, and Z components for surface normals in different RGB colors.

Depth Map Displays a gray model, using luminosity to reveal depth.

Paint Mask Displays paintable regions as white, oversampled regions in red, and undersampled regions in blue. (See Identify paintable areas.)

Texture When Face Style is set to Unlit Texture, specifies the texture map. (See 3D Materials settings .)

Render For Final Output For exported video animations, produces smoother shadows and realistic color bleeds from reflected objects and environments. This option requires more processing time, however.

Reflections, Refractions, Shadows Show or hide these Ray Traced rendering features.

Remove Backfaces Hides surfaces on the back of two-sided components.

Edge options

Edge options determine how wireframe lines appear.

Edge Style Reflects the Constant, Flat, Solid, and Bounding Box options described for Face Style above.

Crease Threshold Adjusts the number of structural lines that appear in the model. A crease, or line, is formed when two polygons in a model come together at a particular angle. If edges meet at an angle below the Crease Threshold setting (0-180), the line they form is removed. At a setting of 0, the entire wireframe is displayed.

Line Width Specifies width in pixels.

Remove Backfaces Hides edges on the back of two-sided components.

Remove Hidden Lines Removes lines that foreground lines overlap.

Vertex options

Vertex options adjust the appearance of *vertices* (intersections of polygons that make up the wireframe model).

Vertex Style Reflects the Constant, Flat, Solid, and Bounding Box options described for Face Style above.

Radius Determines the pixel radius of each vertex.

Remove Backfaces Hides vertices on the back of two-sided components.

Remove Hidden Vertices Removes vertices that foreground vertices overlap.

Stereo options

Stereo options adjust settings for images that will either be viewed with red-blue glasses or printed to objects that include a lenticular lens.

Stereo Type Specifies Red/Blue for images viewed with colored glasses or Vertical Interlaced for lenticular prints.

Parallax Adjusts the distance between the two stereo cameras. Higher settings increase three-dimensional depth but reduce depth of field, making items ahead or behind the focal plane appear out of focus.

Lenticular Spacing For vertically interlaced images, specifies how many lines per inch the lenticular lens has.

Focal Plane Determines the position of the focal plane relative to the center of the model's bounding box. Enter negative values to move the plane forward, and positive values to move it backward.

Save or delete a render preset

1 At the top of the 3D panel, click the Scene button .

2 Click Render Settings.

3 Do either of the following:

- To save a preset, customize settings, and click the Save button .
- To delete a preset, select it from the Preset menu, and click the Delete button .

Render a 3D file for final output

When you've finished working with your 3D file, create a final render to produce the highest quality version for output to web, print, or animation. Final rendering uses ray tracing and a higher sampling rate to capture more realistic lighting and shadow effects.

Use final render mode to enhance the following effects in your 3D scene:

- Image-based lighting and global ambient color.
- Lighting from object reflectance (color bleed).
- Reduced noise in soft shadows.

Note: *A final render can be time-consuming, depending on the model, lighting, and maps in your 3D scene.*

1 Make any necessary adjustments to your model, including lighting and shadow effects.

You don't need to change Anti-Alias settings for the scene before rendering. By default, the Best setting is used.

2 At the top of the 3D panel, click the Scene button , and then click the Scene entry in the list below.

3 From the Quality menu in the lower half of the panel, select Ray Traced Final.

After the render is complete, you can flatten the 3D scene for output in anther format, composite the 3D scene with 2D content, or print directly from the 3D layer.

For exported video animations, Render For Final Output is available as an option in the 3D Render Settings dialog box. See Customize render settings .

Save and export 3D files

To preserve the 3D content in a file, save the file in Photoshop format or another supported image format. You can also export a 3D layer as a file in a supported 3D file format.

Export a 3D layer

You can export 3D layers in all supported 3D formats: Collada DAE, Wavefront/OBJ, U3D, and Google Earth 4 KMZ. When choosing an export format, consider the following factors:

- Wavefront/OBJ format does not save camera settings, lights, or animation.
- Only Collada DAE saves render settings.

To export a 3D layer, do the following:

1. Choose 3D > Export 3D layer.
2. Choose a format for exporting textures:
   - U3D and KMZ support JPEG or PNG as texture formats.
   - DAE and OBJ support all Photoshop-supported image formats for textures.
3. (Optional) If exporting to U3D format, choose an encoding option. ECMA 1 is compatible with Acrobat 7.0; ECMA 3 is compatible with Acrobat 8.0 and later and provides some mesh compression.
4. Click OK to export.

Limitations while exporting to the U3D format

Ensure that any 3D layers that you're exporting as U3D have only triangular object geometry. Additionally, while exporting 3D layers as U3D, keep the following limitations in mind:

- Higher-level primitives, such as NURBS, splines, and curves, are not supported.
- Texture mapping is limited to only one diffuse map per material. Ambient, specular, luminous, or opacity texture maps are not supported.
- Material animation is not supported.

Save a 3D file

To preserve 3D model position, lighting, render mode, and cross sections, save files with 3D layers in PSD, PSB, TIFF, or PDF format.

? Choose File > Save or File > Save As, select Photoshop (PSD), Photoshop PDF, or TIFF format, and click OK.

3D panel settings

Note: *In Photoshop CS6, 3D functionality was part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

3D panel overview

When you select a 3D layer, the 3D panel shows the components of the associated 3D file. The top section of the panel lists the meshes, materials, and lights in the file. The bottom section of the panel shows settings and options for the 3D component selected in the top section.



A Display Scene, Meshes, Materials, or Lights options ***B*** *Render presets menu* ***C*** *Customize render settings* ***D*** *Select texture to paint on* ***E*** *Cross section settings* ***F*** *Toggle overlays* ***G*** *Add new light* ***H*** *Delete light*

The buttons at the top of the 3D panel filter the components that appear in the top section. Click the Scene button to show all components, click Materials to see just materials, and so on.

Display the 3D panel

? Do one of the following:

- Choose Window > 3D.
- Double-click the 3D layer icon in the Layers panel.
- Choose Window > Workspace > Advanced 3D.

Filter the 3D options displayed

? Click the Scene, Mesh, Materials, or Lights button at the top of the 3D panel.

Show or hide a 3D mesh or light

? Click the eye icon next to the mesh or light entry in the top section of the 3D panel.

Note: *You cannot turn material display on or off from the 3D panel. To show or hide materials, change the visibility settings for their associated textures in the Layers panel. See 3D Materials settings .*

Access settings for the 3D scene

1 Click the Scene button.

2 If not already selected, click the Scene entry at the top of the component list.

Access settings for a mesh, material, or light

? Do one of the following:

- Click the Scene button to show all scene components. Then select a mesh, material, or light in the top section.
- Click the Meshes, Materials, or Lights button to temporarily display just those components. Then select a single mesh, material, or light.

Expand or collapse materials for a mesh

1 Click the Scene button.

2 Click the triangle to the left of a mesh icon.

View the ground plane

The ground plane is a grid that reflects the position of the ground relative to the 3D model.

- To view the ground plane, click the Toggle icon at the bottom of the 3D panel, and select 3D Ground Plane.

Note: *The Toggle icon is enabled only if OpenGL is available on your system.*

Show or hide light guides

? At the bottom of the 3D panel, click the Toggle icon , and select 3D Light

Outline the selected material or mesh in the document window

? At the bottom of the 3D panel, click the Toggle icon , and select 3D Selection.

When you select materials or meshes in the panel, a colored outline appears in the document window, helping you identify the current item.

To change the color of 3D overlays like material and mesh outlines, customize options in the 3D section of the Preferences dialog box.



A B

A *Materials are surrounded by a colored line* ***B*** *Meshes by a bounding box*

3D Scene settings

Use 3D Scene settings to change render modes, select a texture to paint on, or create cross sections. To access scene settings, click the Scene button in the 3D panel, then select the Scene entry in the top section of the panel.

Render Settings Specifies the render preset for the model. To customize options, click Edit. For more information, see Change 3D render settings .

Quality Choose a setting which provides the best display quality while maintaining good performance:

Interactive (Painting) Renders with OpenGL using the GPU on the video card, producing high-quality results, but lacking detailed reflections and shadows. For most systems, this option is best for editing.

Ray Traced Draft Renders using the CPU on the computer motherboard, with draft-quality reflections and shadows. If your system has a powerful video card, the Interactive option may produce faster results.

Ray Traced Final Best reserved for final output, this option fully renders reflections and shadows. For more information, see Render a 3D file for final output .

Note: *Tiles are temporarily drawn across the image during Ray Traced rendering. To interrupt the rendering process, click the mouse or spacebar. To change the number of tiling passes, trading processing speed for quality, change the High Quality Threshold in the 3D preferences.*



Paint On When painting directly on the 3D model, use this menu to choose which texture map to paint on. See 3D painting.

You can also choose the target texture from the 3D > 3D Paint Mode menu.

Global Ambient Color Sets the color for global ambient light visible on reflective surfaces. This color interacts with the ambient color for specific materials. See 3D Materials settings .

Cross Section Select to create a planar cross section that can intersect the model at an angle you choose. Allows you to slice through a model and view interior content. See View cross sections .

View cross sections

You can view a cross section of a 3D model by intersecting it with an invisible plane that slices through the model at any angle and displays content only on one side of the plane.

1 Select Cross Section in the bottom section of the Scenes tab.

2 Choose options for alignment, position, and orientation:

Plane Select to display the intersecting plane that creates the cross section. You can choose plane color and opacity.

Intersection Select to highlight the areas of the model that the cross section plane intersects. Click the color swatch to select the highlight color.

Flip Cross Section Changes the displayed area of the model to the opposite side of the intersecting plane.

Offset and Tilt Use Offset to shift the plane along its axis, without changing its tilt. At a default offset of 0, the plane intersects the 3D model at its midpoint. At maximum positive or negative offsets, the plane moves beyond any intersection with the model. Use Tilt settings to rotate the plane up to 360° in either of its possible tilt directions. For a particular axis, the tilt settings rotate the plane along the other two axes. For example, a plane aligned to the y-axis can be rotated around the x-axis (Tilt 1) or the z-axis (Tilt 2).

Alignment Select an axis (x, y, or z) for the intersecting plane. The plane is perpendicular to the selected axis.

Apply different render modes to each cross section

You can vary the render settings for each side of a cross section to combine different views of the same 3D model, such as Wireframe with Solid.

1 Select Cross Section, and choose options in the bottom section of the Scenes tab. Your current render settings are applied to the visible cross section.

2 Click Render Settings, or choose 3D > Render Settings.

3 At the top of the dialog box, click the currently unselected Cross Section button .

By default all render settings are turned off for the alternate cross section, making it appear invisible.

4 Choose render options for the alternate cross section, and click OK.

3D Mesh settings

Each mesh in the 3D model appears on a separate line in the top section of the 3D panel. Select a mesh to access mesh settings and information in the lower section of the 3D panel.

Information includes the number of materials and textures applied to the mesh, as well as the number of vertices and faces it contains. You can also set the following mesh display options:

Note: *To see shadows, set the lights and select Ray Traced for render quality. See 3D Scene settings .*

Catch Shadows Controls whether the selected mesh displays shadows on its surface from other meshes.

Note: *To catch shadows from the ground plane on meshes, select 3D > Ground Plane Shadow Catcher. To align these shadows with objects, select 3D > Snap Object To Ground Plane*

Cast Shadows Controls whether the selected mesh casts shadows on other mesh surfaces.

Invisible Hides the mesh, but displays any shadows on its surface.

Shadow Opacity Controls the softness of shadows cast by the selected mesh. The setting is helpful when blending 3D objects with layers below.

Show or hide a mesh

? Click the eye icon next to a mesh name in the top section of the 3D panel.

Manipulate individual meshes

Use the mesh position tools to move, rotate, or scale a selected mesh without moving the model as a whole. The position tools operate in the same way as the main 3D position tools in the Tools panel. For information on each tool, see Move, rotate, or scale a model with 3D object tools.

1 Select a mesh in the top section of the 3D panel. The selected mesh is highlighted with a red box in the lower section of the panel.

2 Select and use a mesh position tool in the lower section of the panel to move the mesh.

To manipulate the entire model while an individual mesh is selected, use the 3D tools in the Tools panel.

3D Materials settings

The top part of the 3D panel lists the materials used in the 3D file. One or multiple materials may be used to create the overall appearance of the model. If a model contains several meshes, there may be a specific material associated with each mesh. Or a model can be built from one mesh but use different materials in different areas.



***A** Displays Materials options **B** Selected material **C** Materials picker **D** Material Drop and Select tools **E** Texture map menu icon **F** Texture map types*

For a selected material in the top section of the 3D panel, the lower section shows the particular texture maps used by that material. Some texture types, such as Diffuse and Bump, commonly rely on 2D files to supply a particular color or pattern that creates the texture. For other texture types, you may not need a separate 2D file. For example, you can directly adjust Gloss, Shine, Opacity, or Reflection by entering values.

The texture maps used by a material appear as Textures in the Layers panel, grouped by the texture map category.

To see a thumbnail of a texture map image, hover the mouse over the texture name (for example, Reflection or Illumination).

Diffuse The color of the material. The diffuse map can be a solid color or any 2D content. The Diffuse color swatch value sets the diffuse color if you choose to remove the diffuse texture map. You can also create a diffuse map by painting directly on the model. See 3D painting.

Opacity Increases or decreases opacity of the material (0-100%). You can use a texture map or the scrubby slider to control opacity. The grayscale values of the texture map control the opacity of the material. White values create complete opacity and black values create complete transparency.

Bump Creates bumps in the material surface, without altering the underlying mesh. A bump map is a grayscale image in which lighter values create raised surface areas and darker values create flatter surface areas. You can create or load a bump map file, or begin painting on the model to automatically create a bump map file. See 3D painting.

The Bump field increases or reduces bumpiness. It is only active if a bump map exists. Enter a number in the field or use the scrubby slider to increase or decrease bump strength.

Bumpiness is most pronounced when a surface is viewed head on, rather than at an angle.

Normal Like a bump map texture, a normal map increases surface detail. Unlike a bump texture map, which is based on a single-channel grayscale image, a normal map is based on a multi-channel (RGB) image. The values of each color channel represent the x, y, and z components of a normal on the model surface. A normal map can be used to smooth the surfaces of low polygon meshes.

Note: *Photoshop uses World-space normal maps, which offer the fastest processing.*

Environment Stores the image of the environment surrounding the 3D model. Environment maps are applied as spherical panoramas. The contents of the environment map can be seen in the reflective areas of the model.

To prevent an environment map from reflecting on a given material, change Reflectivity to 0%, add a reflectivity map that masks the material area, or remove the environment map for that material.

Reflection Increases the reflection of other objects in the 3D scene, and the environment map, on the material surface.

Illumination Defines a color that doesn't rely on lighting to display. Creates the effect that the 3D object is lit from within.

Gloss Defines the amount of light from a source that reflects off the surface and back to the viewer. You can adjust glossiness by entering a value in the field or using the scrubby slider. If you create a separate glossiness map, the intensity of colors in the map controls glossiness in the material. Black areas create full glossiness, white areas remove all glossiness, and middle values reduce the size of a highlight.

Shine Defines the dispersion of the reflected light generated by the Gloss setting. Low shininess (high dispersion) produces more apparent light, with less focus. High shininess (low dispersion) produces less apparent light and brighter, crisper highlights.



Note: *If a 3D object has more than the nine texture types Photoshop supports, additional textures appear in the Layers panel and the 3D Paint Mode list. (To display the latter, choose 3D > 3D Paint Mode, or use the Paint On menu in the Scene section of the 3D panel*

Specular The color displayed for specular properties (for example, highlight glossiness and shininess).

Ambient Sets the color for ambient light visible on reflective surfaces. This color interacts with the Global Ambient Color for the entire scene. See 3D Scene settings .

Refraction Sets the refractive index when scene Quality is set to Ray Traced and the Refractions option is selected in the 3D > Render Settings dialog box. Refraction is the change in light direction that occurs at the intersection of two media (such as air and water) with different refractive indexes. The default value for new materials is 1.0 (the approximate value for air).

Sample and apply materials directly on objects

The 3D Material Drop tool works much like the traditional Paint Bucket tool, letting you sample and apply materials directly on 3D objects.

1. In 3D panel, select the 3D Material Drop tool .
2. Move the pointer over the 3D object in the document window. When the material you want to sample is outlined, Alt-click (Windows) or Option-click (Mac OS).
3. Move the pointer to outline the material you want to change, and click.

For a visual example of an outlined material, see Outline the selected material or mesh in the document window .

Select materials directly on objects

1 In 3D panel, hold down the 3D Material Drop tool , and select the 3D Select Material tool .

2 Move the pointer over the 3D object in the document window. When the material you want to select is outlined, click.

Apply, save, or load material presets

Material presets let you quickly apply groups of texture settings. The default presets provide various materials like steel, fabric, and wood.



1 In the 3D panel, click the material preview.

2 In the preset pop-up panel, do any of the following:

- To apply a preset, double-click a thumbnail preview.
- To create a preset from the current texture settings, click the pop-up menu icon , and choose New Material.
- To rename or delete selected presets, click the pop-up menu icon, and choose Rename or Delete Material.
- To save the current group of presets, click the pop-up menu icon, and choose Save Materials.
- To change the displayed group, click the pop-up menu icon. Then choose Reset Materials to restore a saved group, Load Materials to append a saved group, or Replace Materials.

Create a texture map

1 Click the folder icon next to the texture map type.

2 Choose New Texture.

3 Enter the name, dimensions, resolution, and color mode for the new map, then click OK.

To match the aspect ratio of an existing texture map, view its dimensions by hovering the mouse pointer over the map name in the Layers panel.

The name of the new texture map is displayed next to the texture map type in the Materials panel. It is also added to the texture list under the 3D layer in the Layers panel. The default name is the texture map type appended to the material name.

Load a texture map

You can load an existing 2D texture file for any of the nine available texture map types.

1 Click the folder icon next to the texture type.

2 Choose Load Texture, then select and open the 2D texture file.

Create a bump texture map

A bump texture map filled with a neutral grayscale value provides more range when painting on the map.

1 In the Tools panel, click the Set Background Color swatch.

2 In the Color Picker, set brightness to 50%, and set R, G, and B values to equal values. Click OK.

3 In the 3D panel, click the folder icon next to Bump.

4 Choose New Texture.

5 Choose the following settings in the New dialog box:

- For Color Mode, choose Grayscale
- For Background Contents, choose Background Color.
- (Optional) Set Width and Height to match the dimensions of the diffuse texture map for the material.

6 Click OK.

The bump texture map is created and added to the texture map files listed in the Materials panel. It also appears as a texture in the Layers panel.

Open a texture map for editing

? Click the image icon , and choose Open Texture.

The texture map opens as a Smart Object in its own document window. After editing the texture, make the 3D model document window active to see updates to the model. See 3D texture editing.

Delete a texture map

1 Click the image icon next to the texture type.

2 Choose Remove Texture.

If the deleted texture is an external file, you can reload it using the Load Texture command from the texture map menu. For textures that are internally referenced by the 3D file, choose Undo or Step Backward to restore a deleted texture.

Edit texture properties

A texture map is applied to a particular surface area of the model, depending on its UV mapping parameters. You can adjust UV scale and offset if necessary to improve how the texture maps to the model.

1 Click the image icon next to the texture type.

2 Choose Edit Properties.

3 Choose a target layer and set UV Scale and Offset values. You can enter values directly or use the scrubby sliders.

Target Determines whether settings apply to a specific layer or the composite image.

U and V Scale Resize mapped textures. To create a repeating pattern, decrease the value.

U and V Offset Reposition mapped textures.

3D Lights settings

3D lights illuminate models from different angles, adding realistic depth and shadows.

Add or delete individual lights

? In the 3D panel, do either of the following:

- To add a light, click the Create A New Light button , and choose the light type:
  - Point lights shine in all directions, like light bulbs.
  - Spot lights shine in a cone shape, which you can adjust.
  - Infinite lights shine from one directional plane, like sunlight.
  - Image-based lights map an illuminated image around the 3D scene.
- To delete a light, select it from the list at the top of the Lights section . Then click the Delete button at the bottom of the panel.

Adjust light properties

1 In the Lights section of the 3D panel, select a light from the list.

2 In the lower half of the panel, set the following options:

Preset applies a saved group of lights and settings. (See Save, replace, or add groups of lights .)

Light Type Choose from the options described in Add or delete individual lights .

Intensity Adjusts brightness.

Color Defines the color of the light. Click the box to access the Color Picker.

Image For image-based lights, specifies a bitmap or 3D file. (For dramatic effects, try 32-bit HDR images.)

Create Shadows Casts shadows from foreground surfaces onto background surfaces, from a single mesh onto itself or from one mesh onto another. Disabling this option improves performance slightly.

Softness Blurs the edge of shadows, producing a gradual falloff.

3 For point or spot lights, set these additional options:

Hotspot (Spot lights only) Sets the width of the bright center of the light.

Falloff (Spot lights only) Sets the outer width of the light.

Use Attenuation Inner and Outer options determine the cone of attenuation and how fast light intensity decreases as distance from objects increases. When an object is closer than Inner limit, light is full strength. When an object is further than Outer limit, light is at zero strength. At intermediate distances, light attenuates linearly from full strength to zero.

Hover the pointer over the Hotspot, Falloff, and Inner and Outer attenuation options. Red outlines in the icon to the right indicate the affected light element.

Position lights

? In the Lights section of the 3D panel, select any of the following:

Rotate tool

(Spot, infinite, and image-based lights) Rotates light while maintaining its position in 3D space.

To quickly aim a light at a specific area, Alt-click (Windows) or Option-click (Mac OS) in the document window.

Pan tool

(Spot and point lights only) Moves the light to a different position in the same 3D plane.

Slide tool

(Spot and point lights only) Moves the light to a different 3D plane.

Point Light at Origin

(Spot light only) Directs light at the center of the model.

Move to Current View

Places light in the same position as the camera.

To precisely position image-based lights, use the 3D Axis, which wraps the image around a sphere. (See 3D Axis.)

Add light guides

Light guides provide spatial reference points for your adjustments. These guides reflect the type, angle, and attenuation of each light. Point lights appear as a ball, spot lights as a cone, and infinite lights as a line.

? At the bottom of the 3D panel, click the Toggle icon , and select 3D Light.

You can change the guide color in the 3D section of the Preferences dialog box.



***A** Point light **B** Spot light **C** Infinite light*

Save, replace, or add groups of lights

To store groups of lights for later use, save them as a preset. To include the preset in other projects, either add to or replace the existing lights.

? From the 3D panel menu , select any of the following:

Save Lights Preset Saves the current group of lights as a preset that you can reload with the following commands.

Add Lights To the existing lights, adds a lights preset that you select.

Replace Lights Replaces the existing lights with a preset that you select.

More Help topics

Create UV overlays

Create 3D objects and animations

Note: *In Photoshop CS6, 3D functionality was part of Photoshop Extended. All features in Photoshop Extended are part of Photoshop CC. Photoshop CC does not have a separate Extended offering.*

Create 3D repoussé | CS5

Note: *Beginning Photoshop CS6, the repousse feature has changed and is now called 3D Extrusion. For details, see Create and adjust 3D extrusions*

The term repoussé describes a metalworking technique in which object faces are shaped and patterned by hammering on the opposite side. In Photoshop, the Repoussé command converts 2D objects into 3D meshes, which you can precisely extrude, inflate, and reposition in 3D space.

The Repoussé command works with RGB images. If you start with a grayscale image, Repoussé converts it to RGB. The Repoussé command is not available for CMYK or Lab images.

For a video about converting from 2D to 3D with Repoussé, see www.adobe.com/go/lrvid5003_ps_en



A *Increasing the depth of extrusion* ***B*** *Twisting the extrusion 180°* ***C*** *Inflating the front*

1 Create a pixel selection, or select a text layer, layer mask, or work path.

2 Choose 3D > Repoussé, then choose the item that reflects your selection in step 1.

3 Set the following options:

Mesh tools Available along the upper left of the dialog box, these tools function like 3D object tools. See Move, rotate, or scale a model with 3D object toolsand Move, rotate, or scale selected items with the 3D Axis.

Repoussé Presets Apply a predefined group of settings. To create your own preset from custom settings, click the pop-up menu , and choose New Repoussé Preset.

To organize groups of presets, see Work with the Preset Manager.

Extrude Extends the original 2D shape in 3D space. Depth controls the length of extrusion; Scale controls the width. Select Bend for a curved extrusion, or Shear for a straight one, then set X and Y Angle to control the horizontal and vertical tilt. If desired, enter Twist in degrees.

To change the bend or shear origin, click a point on the reference icon .

Inflate Expands or collapses the middle of the front or back. Positive Angle settings expand, negative collapse. Strength controls the level of inflation.

Materials Apply materials such as brick or cotton either globally or to various sides of the object. (Bevel1 is the front bevel; Bevel2 the back.) For more information, see Apply, save, or load material presets .

Bevel Applies beveled edges to the front or back of the object. Contour options are similar to those for layer effects. See Modify layer effects with contours.

Scene Settings Lights in the form of a spherical panorama shine onto the object; choose a style of lights from the menu. Render Settings control how object surfaces look. (See Select a render preset .) Higher Mesh Quality settings increase mesh density, improving appearance but reducing processing speed.

The Shaded and Solid Wireframe render settings superimpose the 3D mesh on objects, revealing any mesh distortion that will distort textures.

Readjust repoussé settings

1 Select a text layer, layer mask, or work path to which you previously applied repoussé.

2 Choose 3D > Repoussé > Edit In Repoussé.

Split repoussé meshes

By default, the Repoussé command creates a single mesh with five materials. If you want to separately control different elements (such as each letter in a string of text), you can create separate meshes for each closed path.

Note: *If numerous closed paths exist, the resulting meshes can create highly complex 3D scenes that are difficult to edit.*

1 Select a text layer, layer mask, or work path to which you previously applied repoussé.

2 Choose 3D > Repoussé > Split Repoussé Meshes.

Understand internal constraints

Internal constraints let you improve mesh resolution in specific areas, precisely vary inflation, or poke holes in surfaces. Along a path you specify on a repoussé object, constraint curves extend away from the object for an expansion, or toward the object for a contraction. You manipulate these curves using constraint tools that are similar to 3D object tools.

Inactive constraints Guarantee sufficient mesh resolution, creating smooth paths.



Active Constraints Expand or contract the surface along constraint paths.



Hole Constraints Cut out the surface along constraint paths.



Create internal constraints from selections, work paths, or text

1 Do one of the following:

- Create a selection or path that falls entirely within the front surface of a repoussé object.
- For text objects that already have internal paths, like the letter *A*, skip to step 3.

2 Choose 3D > Repoussé > Create Constraints From Selection or Work Path.

3 In the Repoussé dialog box, click the triangle to expand the Internal Constraints section.

4 Choose a Type option. For Active or Hole, the following options are available:

Constraint tools Adjust the constraint curve and function similarly to 3D object tools. See 3D object and camera tools.

If the repoussé object contains multiple internal paths (for example, both ovals in the number 8), select each path individually with the constraint tools.

Position coordinates Let you precisely place constraints in 3D space.

Side Lets you apply uniform Strength and Angle settings to both sides, or unique settings to each.

Each constraint curve has two sides; the orientation of those sides depends on how a curve divides the surface. The Left and Right menu options reflect a vertical constraint. For a horizontal constraint, Left and Right mean up and down, and for a closed constraint, those options mean inside and outside.



A B

A Both creates consistent deformation. ***B*** *Left or Right allows for varied deformation.*

Strength Controls the level of inflation along the path.

Angle Controls the direction of inflation.

Remove an internal constraint

1 Select a 3D repoussé layer that includes an internal constraint.

2 Choose 3D > Repoussé > Edit In Repoussé.

3 In the Internal Constraints section, click Delete.

To reapply a deleted constraint, click Add Selection or Add Path.

Create 3D objects from 2D images

Photoshop can build a variety of basic 3D objects using 2D layers as a starting point. After creating a 3D object, you can move it in 3D space, change render settings, add lighting, or merge it with other 3D layers.

- Convert 2D layers into 3D postcards (planes with 3D properties). If your starting layer is a text layer, any transparency is retained.
- Wrap a 2D layer around a 3D object, such as a cone, cube, or cylinder.
- Create a 3D mesh from the grayscale information in a 2D image.
- Simulate a metalworking technique called repoussé by extruding a 2D object in 3D space. See Create 3D repoussé | CS5.
- Build a 3D volume from a multi-frame file such as a DICOM medical imaging file. Photoshop combines the individual slices of the file into a 3D object that you can manipulate in 3D space and view from any angle. You can apply various 3D volume render effects to optimize the display of various materials in the scan, such as bone or soft tissue. See Create a 3D volume .

Create a 3D postcard

You can add a 3D postcard to an existing 3D scene to create a surface that displays shadows and reflections from other objects in the scene.

1 Open a 2D image and select the layer you want to convert to a postcard.

2 Choose 3D > New 3D Postcard From Layer.

- The 2D layer is converted to a 3D layer in the Layers panel. The 2D layer content is applied as a material to both sides of the postcard.
- The original 2D layer appears in the Layers panel as the Diffuse texture map for the 3D postcard object. (See 3D panel overview .)

- The 3D layer retains the dimensions of the original 2D image.

3 (Optional) To add the 3D postcard as a surface plane to a 3D scene, merge the new 3D layer with an existing 3D layer containing other 3D objects, then align it as necessary. (See Combine 3D objects.)

4 To retain the new 3D content, export the 3D layer in a 3D file format or save it in PSD format. (See Export 3D layers .)

Create 3D shapes

Depending on the object type you choose, the resulting 3D model can contain one or more meshes. The Spherical Panorama option maps a panoramic image inside a 3D sphere.

1 Open a 2D image and select the layer that you want to convert to a 3D shape.

2 Choose 3D > New Shape From Layer, and select a shape from the menu. Shapes include single-mesh objects like a donut, sphere, or hat, as well as multiple mesh objects such as a cone, cube, cylinder, soda can, or wine bottle.

__Note:__ You can add your own custom shapes to the shape menu. Shapes are Collada (.dae) 3D model files. To add a shape, place the Collada model file in the Presets\Meshes folder inside the Photoshop program folder.

- The 2D layer is converted to a 3D layer in the Layers panel.
- The original 2D layer appears in the Layers panel as a Diffuse texture map. It may be used on one or more surfaces of the new 3D object. Other surfaces may be assigned a default diffuse texture map with a default color setting. See 3D panel overview .

3 (Optional) Use the Spherical Panorama option if you are using a panoramic image as your 2D input. This option converts a complete 360 x 180 degree spherical panorama to a 3D layer. Once converted to a 3D object, you can paint areas of the panorama that are typically difficult to reach, such as the poles or areas containing straight lines. For information on creating a 2D panorama by stitching images together, see Create 360-degree panoramas.

4 Export the 3D layer in a 3D file format or save in PSD format to retain the new 3D content. See Export 3D layers .

Create a 3D mesh

The New Mesh from Grayscale command converts a grayscale image into a depth map, which translates lightness values into a surface of varying depth. Lighter values create raised areas in the surface, darker values create lower areas. Photoshop then applies the depth map to one of four possible geometries to create a 3D model.

1 Open a 2D image and select one or more layers that you want to convert to a 3D mesh.

2 (Optional) Convert the image to grayscale mode. (Choose Image > Mode > Grayscale, or use Image > Adjustments > Black & White to fine-tune the grayscale conversion.

__Note:__ If you use an RGB image as input when creating a mesh, the green channel is used to generate the depth map.

3 (Optional) Make adjustments to the grayscale image if necessary to limit the range of lightness values.

4 Choose 3D > New Mesh From Grayscale, and then select a mesh option.

Plane Applies depth map data to a planar surface.

Two-Sided Plane Creates two planes reflected along a central axis and applies depth map data to both planes.

Cylinder Applies depth map data outward from the center of a vertical axis.

Sphere Applies depth map data radially outward from a center point.

Photoshop creates a 3D layer containing the new mesh. It also creates Diffuse, Opacity, and Planar Depth Map texture maps for the 3D object, using the original grayscale or color layer.

You can reopen the Planar Depth Map as a Smart Object at any time and edit it. When you save it, the mesh is regenerated.

Note: *The Opacity texture map does not appear in the Layers panel, because that map uses the same texture file as the Diffuse map (the original 2D layer). When two texture maps reference the same file, the file appears only once in the Layers panel.*

Create 3D animations

Using the Photoshop Animation timeline, you can create 3D animations that move a 3D model through space and change the way it displays over time. You can animate any of the following properties of a 3D layer:

- 3D object or camera position. Use the 3D position or camera tools to move the model or 3D camera over time. Photoshop can tween frames between position or camera movements to create smooth motion effects.
- 3D render settings. Change render modes, with the ability to tween transitions between some render modes. For example, change Vertices mode gradually to Wireframe over time, to simulate the sketching-in of a model's structure.
- 3D cross section. Rotate an intersecting plane to display a changing cross section over time. Change cross section settings between frames to highlight different model areas during an animation.

For high quality animations, you can render each animation frame using the Render for Final Output render setting. See Change rendering effects .

More Help topics

Creating timeline animations

New 3D reflections and dragable shadows

Add realism with ease.

New 3D reflections and dragable shadows

Streamlined 3d controls

Expand creative possibilities into another dimension.

Streamlined 3d controls

Chapter 20: Color management

Understanding color management

A color management system reconciles color differences among devices so that you can confidently predict the colors your system ultimately produces. Viewing color accurately allows you to make sound color decisions throughout your workflow, from digital capture through final output. Color management also allows you to create output based on ISO, SWOP, and Japan Color print production standards.

Why colors sometimes don't match

No device in a publishing system is capable of reproducing the full range of colors viewable to the human eye. Each device operates within a specific color space that can produce a certain range, or gamut, of colors.

A color model determines the relationship between values, and the color space defines the absolute meaning of those values as colors. Some color models (such as CIE L*a*b) have a fixed color space because they relate directly to the way humans perceive color. These models are described as being device-independent. Other color models (RGB, HSL, HSB, CMYK, and so forth) can have many different color spaces. Because these models vary with each associated color space or device, they are described as being device-dependent.

Because of these varying color spaces, colors can shift in appearance as you transfer documents between different devices. Color variations can result from differences in image sources; the way software applications define color; print media (newsprint paper reproduces a smaller gamut than magazine-quality paper); and other natural variations, such as manufacturing differences in monitors or monitor age.



***A** Lab color space **B** Documents (working space) **C** Devices*

What is a color management system?

Color-matching problems result from various devices and software using different color spaces. One solution is to have a system that interprets and translates color accurately between devices. A color management system (CMS) compares the color space in which a color was created to the color space in which the same color will be output, and makes the necessary adjustments to represent the color as consistently as possible among different devices.

A color management system translates colors with the help of color profiles. A profile is a mathematical description of a device's color space. For example, a scanner profile tells a color management system how your scanner "sees" colors. Adobe color management uses ICC profiles, a format defined by the International Color Consortium (ICC) as a cross-platform standard.

Because no single color-translation method is ideal for all types of graphics, a color management system provides a choice of rendering intents, or translation methods, so that you can apply a method appropriate to a particular graphics element. For example, a color translation method that preserves correct relationships among colors in a wildlife photograph may alter the colors in a logo containing flat tints of color.

Note: *Don't confuse color management with color correction. A color management system won't correct an image that was saved with tonal or color balance problems. It provides an environment where you can evaluate images reliably in the context of your final output.*

Do you need color management?

Without a color management system, your color specifications are device-dependent. You might not need color management if your production process is tightly controlled for one medium only. For example, you or your print service provider can tailor CMYK images and specify color values for a known, specific set of printing conditions. The value of color management increases when you have more variables in your production process. Color management is recommended if you anticipate reusing color graphics for print and online media, using various kinds of devices within a single medium (such as different printing presses), or if you manage multiple workstations.

You will benefit from a color management system if you need to accomplish any of the following:

- Get predictable and consistent color output on multiple output devices including color separations, your desktop printer, and your monitor. Color management is especially useful for adjusting color for devices with a relatively limited gamut, such as a four-color process printing press.
- Accurately soft-proof (preview) a color document on your monitor by making it simulate a specific output device. (Soft-proofing is subject to the limitations of monitor display, and other factors such as room lighting conditions.)
- Accurately evaluate and consistently incorporate color graphics from many different sources if they also use color management, and even in some cases if they don't.
- Send color documents to different output devices and media without having to manually adjust colors in documents or original graphics. This is valuable when creating images that will eventually be used both in print and online.
- Print color correctly to an unknown color output device; for example, you could store a document online for consistently reproducible on-demand color printing anywhere in the world.

Creating a viewing environment for color management

Your work environment influences how you see color on your monitor and on printed output. For best results, control the colors and light in your work environment by doing the following:

- View your documents in an environment that provides a consistent light level and color temperature. For example, the color characteristics of sunlight change throughout the day and alter the way colors appear on your screen, so keep shades closed or work in a windowless room. To eliminate the blue-green cast from fluorescent lighting, you can install D50 (5000° Kelvin) lighting. You can also view printed documents using a D50 lightbox.
- View your document in a room with neutral-colored walls and ceiling. A room's color can affect the perception of both monitor color and printed color. The best color for a viewing room is neutral gray. Also, the color of your clothing reflecting off the glass of your monitor may affect the appearance of colors on-screen.

- Remove colorful background patterns on your monitor desktop. Busy or bright patterns surrounding a document interfere with accurate color perception. Set your desktop to display neutral grays only.
- View document proofs in the real-world conditions under which your audience will see the final piece. For example, you might want to see how a housewares catalog looks under the incandescent light bulbs used in homes, or view an office furniture catalog under the fluorescent lighting used in offices. However, always make final color judgements under the lighting conditions specified by the legal requirements for contract proofs in your country.

Keeping colors consistent

About color management in Adobe applications

Adobe color management helps you maintain the appearance of colors as you bring images in from external sources, edit documents and transfer them between Adobe applications, and output your finished compositions. This system is based on conventions developed by the International Color Consortium, a group responsible for standardizing profile formats and procedures so that consistent and accurate color can be achieved throughout a workflow. By default, color management is turned on in color-managed Adobe applications. If you purchased the Adobe Creative Suite, color settings are synchronized across applications to provide consistent display for RGB and CMYK colors. This means that colors look the same no matter which application you view them in.



If you decide to change the default settings, easy-to-use presets let you configure Adobe color management to match common output conditions. You can also customize color settings to meet the demands of your particular color workflow.

Keep in mind that the kinds of images you work with and your output requirements influence how you use color management. For example, there are different color-consistency issues for an RGB photo printing workflow, a CMYK commercial printing workflow, a mixed RGB/CMYK digital printing workflow, and an Internet publishing workflow.

Basic steps for producing consistent color

1. Consult with your production partners (if you have any) to ensure that all aspects of your color management workflow integrate seamlessly with theirs.

Discuss how the color workflow will be integrated with your workgroups and service providers, how software and hardware will be configured for integration into the color management system, and at what level color management will be implemented. (See Do you need color management?.)

2. Calibrate and profile your monitor.

A monitor profile is the first profile you should create. Seeing accurate color is essential if you are making creative decisions involving the color you specify in your document. (See Calibrate and profile your monitor.)

3. Add color profiles to your system for any input and output devices you plan to use, such as scanners and printers.

The color management system uses profiles to know how a device produces color and what the actual colors in a document are. Device profiles are often installed when a device is added to your system. You can also use third-party software and hardware to create more accurate profiles for specific devices and conditions. If your document will be commercially printed, contact your service provider to determine the profile for the printing device or press condition. (See About color profilesand Install a color profile.)

4. Set up color management in Adobe applications.

The default color settings are sufficient for most users. However, you can change the color settings by doing one of the following:

- If you use multiple Adobe applications, use Adobe® Bridge to choose a standard color management configuration and synchronize color settings across applications before working with documents. (See Synchronize color settings across Adobe applications.)
- If you use only one Adobe application, or if you want to customize advanced color management options, you can change color settings for a specific application. (See Set up color management.)

5. (Optional) Preview colors using a soft proof.

After you create a document, you can use a soft proof to preview how colors will look when printed or viewed on a specific device. (See Soft-proof colors.)

Note: *A soft proof alone doesn't let you preview how overprinting will look when printed on an offset press. If you work with documents that contain overprinting, turn on Overprint Preview to accurately preview overprints in a soft proof. For Acrobat, the Overprint Preview option is automatically applied.*

6. Use color management when printing and saving files.

Keeping the appearance of colors consistent across all of the devices in your workflow is the goal of color management. Leave color management options enabled when printing documents, saving files, and preparing files for online viewing. (See Printing with color management and Color-managing documents for online viewing.)

Synchronize color settings across Adobe applications

If you use Adobe Creative Suite, you can use Adobe Bridge to automatically synchronize color settings across applications. This synchronization ensures that colors look the same in all color-managed Adobe applications.

If color settings are not synchronized, a warning message appears at the top of the Color Settings dialog box in each application. Adobe recommends that you synchronize color settings before you work with new or existing documents.

1. Open Bridge. To open Bridge from a Creative Suite application, choose File > Browse. To open Bridge directly, either choose Adobe Bridge from the Start menu (Windows) or double-click the Adobe Bridge icon (Mac OS).

2 Choose Edit > Creative SuiteColor Settings.

3 Select a color setting from the list, and click Apply. If none of the default settings meet your requirements, select Show Expanded List Of Color Setting Files to view additional settings. To install a custom settings file, such as a file you received from a print service provider, click Show Saved Color Settings Files.

Set up color management

1 Do one of the following:

- (Illustrator, InDesign, Photoshop) Choose Edit > Color Settings.
- (Acrobat) Select the Color Management category of the Preferences dialog box.

2 Select a color setting from the Settings menu, and click OK.

The setting you select determines which color working spaces are used by the application, what happens when you open and import files with embedded profiles, and how the color management system converts colors. To view a description of a setting, select the setting and then position the pointer over the setting name. The description appears at the bottom of the dialog box.

Note: *Acrobat color settings are a subset of those used in InDesign, Illustrator, and Photoshop.In certain situations, such as if your service provider supplies you with a custom output profile, you may need to customize specific options in the Color Settings dialog box. However, customizing is recommended for advanced users only.*

Note: *If you work with more than one Adobe application, it is highly recommended that you synchronize your color settings across applications. (See Synchronize color settings across Adobe applications.)*

Change the appearance of CMYK black (Illustrator, InDesign)

Pure CMYK black (K=100) appears jet black (or rich black) when viewed on-screen, printed to a non-PostScript desktop printer, or exported to an RGB file format. If you prefer to see the difference between pure black and rich black as it will appear when printed on a commercial press, you can change the Appearance Of Black preferences. These preferences do not change the color values in a document.

1 Choose Edit > Preferences > Appearance Of Black (Windows) or [application name] > Preferences > Appearance Of Black (Mac OS).

2 Choose an option for On Screen:**Display All Blacks Accurately** Displays pure CMYK black as dark gray. This setting allows you to see the difference between pure black and rich black.**Display All Blacks As Rich Black** Displays pure CMYK black as jet black (RGB=000). This setting makes pure black and rich black appear the same on-screen.

3 Choose an option for Printing/Exporting:**Output All Blacks Accurately** When printing to a non-PostScript desktop printer or exporting to an RGB file format, outputs pure CMYK black using the color numbers in the document. This setting allows you to see the difference between pure black and rich black.**Output All Blacks As Rich Black** When printing to a non-PostScript desktop printer or exporting to an RGB file format, outputs pure CMYK black as jet black (RGB=000). This setting makes pure black and rich black appear the same.

Managing process and spot colors

When color management is on, any color you apply or create within a color-managed Adobe application automatically uses a color profile that corresponds to the document. If you switch color modes, the color management system uses the appropriate profiles to translate the color to the new color model you choose.

Keep in mind the following guidelines for working with process and spot colors:

- Choose a CMYK working space that matches your CMYK output conditions to ensure that you can accurately define and view process colors.
- Select colors from a color library. Adobe applications come with several standard color libraries, which you can load using the Swatches panel menu.
- (Illustrator, and InDesign) Turn on Overprint Preview to get an accurate and consistent preview of spot colors.
- (Acrobat, Illustrator, and InDesign) Use Lab values (the default) to display predefined spot colors (such as colors from the TOYO, PANTONE, DIC, and HKS libraries) and convert these colors to process colors. Using Lab values provides the greatest accuracy and guarantees the consistent display of colors across Creative Suite applications. If you want the display and output of these colors to match earlier versions of Illustrator or InDesign, use CMYK equivalent values instead. For instructions on switching between Lab values and CMYK values for spot colors, search Illustrator or InDesign Help.

Note: *Color-managing spot colors provides a close approximation of a spot color on your proofing device and monitor. However, it is difficult to exactly reproduce a spot color on a monitor or proofing device because many spot color inks exist outside the gamuts of many of those devices.*

Color settings

Customize color settings

For most color-managed workflows, it is best to use a preset color setting that has been tested by Adobe Systems. Changing specific options is recommended only if you are knowledgeable about color management and very confident about the changes you make.

After you customize options, you can save them as a preset. Saving color settings ensures that you can reuse them and share them with other users or applications.

- To save color settings as a preset, click Save in the Color Settings dialog box. To ensure that the application displays the setting name in the Color Settings dialog box, save the file in the default location. If you save the file to a different location, you must load the file before you can select the setting.
- To load a color settings preset that's not saved in the standard location, click Load in the Color Settings dialog box, select the file you want to load, and click Open.

Note: *In Acrobat, you cannot save customized color settings. To share customized color settings with Acrobat, you must create the file in InDesign, Illustrator, or Photoshop, and then save it in the default Settings folder. It will then be available in the Color Management category of the Preferences dialog box. You can also add settings manually to the default Settings folder.*

About color working spaces

A working space is an intermediate color space used to define and edit color in Adobe applications. Each color model has a working space profile associated with it. You can choose working space profiles in the Color Settings dialog box.

A working space profile acts as the source profile for newly created documents that use the associated color model. For example, if Adobe RGB (1998) is the current RGB working space profile, each new RGB document that you create will use colors within the Adobe RGB (1998) gamut. Working spaces also determine the appearance of colors in untagged documents.

If you open a document embedded with a color profile that doesn't match the working space profile, the application uses a color management policy to determine how to handle the color data. In most cases, the default policy is to preserve the embedded profile.

Working space options

To display working space options in Photoshop, Illustrator and InDesign, choose Edit > Color Settings. In Acrobat, select the Color Management category of the Preferences dialog box.

To view a description of any profile, select the profile and then position the pointer over the profile name. The description appears at the bottom of the dialog box.

RGB Determines the RGB color space of the application. In general, it's best to choose Adobe RGB or sRGB, rather than the profile for a specific device (such as a monitor profile). sRGB is recommended when you prepare images for the web, because it defines the color space of the standard monitor used to view images on the web. sRGB is also a good choice when you work with images from consumer-level digital cameras, because most of these cameras use sRGB as their default color space.

Adobe RGB is recommended when you prepare documents for print, because Adobe RGB's gamut includes some printable colors (cyans and blues in particular) that can't be defined using sRGB. Adobe RGB is also a good choice when working with images from professional-level digital cameras, because most of these cameras use Adobe RGB as their default color space.

CMYK Determines the CMYK color space of the application. All CMYK working spaces are device-dependent, meaning that they are based on actual ink and paper combinations. The CMYK working spaces Adobe supplies are based on standard commercial print conditions.

Gray (Photoshop) or Grayscale (Acrobat) Determines the grayscale color space of the application.

Spot (Photoshop) Specifies the dot gain to use when displaying spot color channels and duotones.

Note: *In Acrobat, you can use the color space in an embedded output intent instead of a document color space for viewing and printing. For more information on output intents, see Acrobat Help.*

Adobe applications ship with a standard set of working space profiles that have been recommended and tested by Adobe Systems for most color management workflows. By default, only these profiles appear in the working space menus. To display additional color profiles that you have installed on your system, select Advanced Mode (Illustrator and InDesign) or More Options (Photoshop). A color profile must be bi-directional (that is, contain specifications for translating both into and out of color spaces) in order to appear in the working space menus.

Note: *In Photoshop, you can create custom working space profiles. However, Adobe recommends that you use a standard working space profile rather than create a custom profile. For more information, see the Photoshop support knowledgebase at www.adobe.com/support/products/photoshop.html.*

About missing and mismatched color profiles

For a newly created document, the color workflow usually operates seamlessly: Unless specified otherwise, the document uses the working space profile associated with its color mode for creating and editing colors.

However, some existing documents may not use the working space profile that you have specified, and some existing documents may not be color-managed. It is common to encounter the following exceptions to your color-managed workflow:

- You might open a document or import color data (for example, by copying and pasting or dragging and dropping) from a document that is not tagged with a profile. This is often the case when you open a document created in an application that either does not support color management or has color management turned off.
- You might open a document or import color data from a document that is tagged with a profile different from the current working space. This may be the case when you open a document that was created using different color management settings, or scanned and tagged with a scanner profile.

In either case, the application uses a color management policy to decide how to handle the color data in the document.

If the profile is missing or does not match the working space, the application may display a warning message, depending on options you set in the Color Settings dialog box. Profile warnings are turned off by default, but you can turn them on to ensure the appropriate color management of documents on a case-by-case basis. The warning messages vary between applications, but in general you have the following options:

- (Recommended) Leave the document or imported color data as it is. For example, you can choose to use the embedded profile (if one exists), leave the document without a color profile (if one doesn't exist), or preserve the numbers in pasted color data.
- Adjust the document or imported color data. For example, when opening a document with a missing color profile, you can choose to assign the current working space profile or a different profile. When opening a document with a mismatched color profile, you can choose to discard the profile or convert the colors to the current working space. When importing color data, you can choose to convert the colors to the current working space in order to preserve their appearance.

Color management policy options

A color management policy determines how the application handles color data when you open a document or import an image. You can choose different policies for RGB and CMYK images, and you can specify when you want warning messages to appear. To display color management policy options, choose Edit > Color Settings.

To view a description of a policy, select the policy and then position the pointer over the policy name. The description appears at the bottom of the dialog box.

RGB, CMYK, And Gray (Gray option is available for Photoshop only.) Specifies a policy to follow when bringing colors into the current working space (either by opening files or importing images into the current document). Choose from the following options:

Preserve Embedded Profiles Always preserves embedded color profiles when opening files. This is the recommended option for most workflows because it provides consistent color management. One exception is if you're concerned about preserving CMYK numbers, in which case you should select Preserve Numbers (Ignore Linked Profiles) instead.

Convert To Working Space Converts colors to the current working space profile when opening files and importing images. Select this option if you want to force all colors to use a single profile (the current working space profile).

Preserve Numbers (Ignore Linked Profiles) This option is available in InDesign and Illustrator for CMYK. Preserves color numbers when opening files and importing images, but still allows you to use color management to view colors accurately in Adobe applications. Select this option if you want to use a safe CMYK workflow. In InDesign, you can override this policy on a per-object basis by choosing Object > Image Color Settings.

Off Ignores embedded color profiles when opening files and importing images, and does not assign the working space profile to new documents. Select this option if you want to discard any color metadata provided by the original document creator.

Profile Mismatches: Ask When Opening Displays a message whenever you open a document tagged with a profile other than the current working space. You will be given the option to override the policy's default behavior. Select this option if you want to ensure the appropriate color management of documents on a case-by-case basis.

Profile Mismatches: Ask When Pasting Displays a message whenever color profile mismatches occur as colors are imported into a document through pasting or dragging-and-dropping. You will be given the option to override the policy's default behavior. Select this option if you want to ensure the appropriate color management of pasted colors on a case-by-case basis.

Missing Profiles: Ask When Opening Displays a message whenever you open an untagged document. You will be given the option to override the policy's default behavior. Select this option if you want to ensure the appropriate color management of documents on a case-by-case basis.

Color conversion options

Color conversion options let you control how the application handles the colors in a document as it moves from one color space to another. Changing these options is recommended only if you are knowledgeable about color management and very confident about the changes you make. To display conversion options, choose Edit > Color Settings, and select Advanced Mode (Illustrator and InDesign) or More Options (Photoshop). In Acrobat, select the Color Management category of the Preferences dialog box.

Engine Specifies the Color Management Module (CMM) used to map the gamut of one color space to the gamut of another. For most users, the default Adobe (ACE) engine fulfills all conversion needs.

To view a description of an engine or intent option, select the option and then position the pointer over the option name. The description appears at the bottom of the dialog box.

Intent (Photoshop, Illustrator, InDesign) Specifies the rendering intent used to translate one color space to another. Differences between rendering intents are apparent only when you print a document or convert it to a different working space.

Use Black Point Compensation Ensures that the shadow detail in the image is preserved by simulating the full dynamic range of the output device. Select this option if you plan to use black point compensation when printing (which is recommended in most situations).

Use Dither (Photoshop) Controls whether to dither colors when converting 8-bit-per-channel images between color spaces. When the Use Dither option is selected, Photoshop mixes colors in the destination color space to simulate a missing color that existed in the source space. Although dithering helps to reduce the blocky or banded appearance of an image, it may also result in larger file sizes when images are compressed for web use.

Compensate For Scene-Rendered Profiles (Photoshop) Compares video contrast when converting from scene to output profiles. This option reflects default color management in After Effects.

Advanced controls in Photoshop

In Photoshop you display advanced controls for managing color by choosing Edit > Color Settings and selecting More Options.

Desaturate Monitor Colors By Determines whether to desaturate colors by the specified amount when displayed on the monitor. When selected, this option can aid in visualizing the full range of color spaces with gamuts larger than that of the monitor. However, this causes a mismatch between the monitor display and the output. When the option is deselected, distinct colors in the image may display as a single color.

Blend RGB Colors Using Gamma Controls how RGB colors blend together to produce composite data (for example, when you blend or paint layers using Normal mode). When the option is selected, RGB colors are blended in the color space corresponding to the specified gamma. A gamma of 1.00 is considered "colorimetrically correct" and should result in the fewest edge artifacts. When the option is deselected, RGB colors are blended directly in the document's color space.

Note: *When you select Blend RGB Colors Using Gamma, layered documents will look different when displayed in other applications than they do in Photoshop.*

Working with color profiles

About color profiles

Precise, consistent color management requires accurate ICC-compliant profiles of all of your color devices. For example, without an accurate scanner profile, a perfectly scanned image may appear incorrect in another program, simply due to any difference between the scanner and the program displaying the image. This misleading representation may cause you to make unnecessary, time-wasting, and potentially damaging "corrections" to an already satisfactory image. With an accurate profile, a program importing the image can correct for any device differences and display a scan's actual colors.

A color management system uses the following kinds of profiles:

Monitor profiles Describe how the monitor is currently reproducing color. This is the first profile you should create because viewing color accurately on your monitor allows for critical color decisions in the design process. If what you see on your monitor is not representative of the actual colors in your document, you will not be able to maintain color consistency.

Input device profiles Describe what colors an input device is capable of capturing or scanning. If your digital camera offers a choice of profiles, Adobe recommends that you select Adobe RGB. Otherwise, use sRGB (which is the default for most cameras). Advanced users may also consider using different profiles for different light sources. For scanner profiles, some photographers create separate profiles for each type or brand of film scanned on a scanner.

Output device profiles Describe the color space of output devices like desktop printers or a printing press. The color management system uses output device profiles to properly map the colors in a document to the colors within the gamut of an output device's color space. The output profile should also take into consideration specific printing conditions, such as the type of paper and ink. For example, glossy paper is capable of displaying a different range of colors than matte paper. Most printer drivers come with built-in color profiles. It's a good idea to try these profiles before you invest in custom profiles.

Document profiles Define the specific RGB or CMYK color space of a document. By assigning, or tagging, a document with a profile, the application provides a definition of actual color appearances in the document. For example, R=127, G=12, B=107 is just a set of numbers that different devices will display differently. But when tagged with the Adobe RGB color space, these numbers specify an actual color or wavelength of light–in this case, a specific color of purple. When color management is on, Adobe applications automatically assign new documents a profile based on Working Space options in the Color Settings dialog box. Documents without assigned profiles are known as untagged and contain only raw color numbers. When working with untagged documents, Adobe applications use the current working space profile to display and edit colors.



A Profiles describe the color spaces of the input device and the document ***B*** *Using the profiles' descriptions, the color management system identifies the document's actual colors* ***C*** *The monitor's profile tells the color management system how to translate the document's numeric values to the monitor's color space* ***D*** *Using the output device's profile, the color management system translates the document's numeric values to the color values of the output device so the correct appearance of colors is printed*

About monitor calibration and characterization

Profiling software can both calibrate and characterize your monitor. Calibrating your monitor brings it into compliance with a predefined standard—for example, adjusting your monitor so that it displays color using the graphics arts standard white point color temperature of 5000° K (Kelvin). Characterizing your monitor simply creates a profile that describes how the monitor is currently reproducing color.

Monitor calibration involves adjusting the following video settings:

Brightness and contrast The overall level and range, respectively, of display intensity. These parameters work just as they do on a television. A monitor calibration utility helps you set an optimum brightness and contrast range for calibration.

Gamma The brightness of the midtone values. The values produced by a monitor from black to white are nonlinear—if you graph the values, they form a curve, not a straight line. Gamma defines the value of that curve halfway between black and white.

Phosphors The substances that CRT monitors use to emit light. Different phosphors have different color characteristics.

White point The color and intensity of the brightest white the monitor can reproduce.

Calibrate and profile your monitor

When you calibrate your monitor, you are adjusting it so it conforms to a known specification. Once your monitor is calibrated, the profiling utility lets you save a color profile. The profile describes the color behavior of the monitor—what colors can or cannot be displayed on the monitor and how the numeric color values in an image must be converted so that colors are displayed accurately.

1. Make sure your monitor has been turned on for at least a half hour. This gives it sufficient time to warm up and produce more consistent output.
2. Make sure your monitor is displaying thousands of colors or more. Ideally, make sure it is displaying millions of colors or 24-bit or higher.
3. Remove colorful background patterns on your monitor desktop and set your desktop to display neutral grays. Busy patterns or bright colors surrounding a document interfere with accurate color perception.
4. Do one of the following to calibrate and profile your monitor:
   - In Windows, install and use a monitor calibration utility.
   - In Mac OS, use the Calibrate utility, located on the System Preferences/Displays/Color tab.
   - For the best results, use third-party software and measuring devices. In general, using a measuring device such as a colorimeter along with software can create more accurate profiles because an instrument can measure the colors displayed on a monitor far more accurately than the human eye.

Note: Monitor performance changes and declines over time; recalibrate and profile your monitor every month or so. If you find it difficult or impossible to calibrate your monitor to a standard, it may be too old and faded.

Most profiling software automatically assigns the new profile as the default monitor profile. For instructions on how to manually assign the monitor profile, refer to the Help system for your operating system.

Install a color profile

Color profiles are often installed when a device is added to your system. The accuracy of these profiles (often called generic profiles or canned profiles) varies from manufacturer to manufacturer. You can also obtain device profiles from your service provider, download profiles from the web, or create custom profiles using professional profiling equipment.

- In Windows, right-click a profile and select Install Profile. Alternatively, copy the profiles into the WINDOWS\system32\spool\drivers\color folder.
- In Mac OS, copy profiles into the /Library/ColorSync/Profiles folder or the /Users/[username]/Library/ColorSync/Profiles folder.

After installing color profiles, be sure to restart Adobe applications.

Embed a color profile

To embed a color profile in a document you created in Illustrator, InDesign, or Photoshop, you must save or export the document in a format that supports ICC profiles.

1. Save or export the document in one of the following file formats: Adobe PDF, PSD (Photoshop), AI (Illustrator), INDD (InDesign), JPEG, Photoshop EPS, Large Document Format, or TIFF.
2. Select the option for embedding ICC profiles. The exact name and location of this option varies between applications. Search Adobe Help for additional instructions.

Embed a color profile (Acrobat)

You can embed a color profile in an object or an entire PDF. Acrobat attaches the appropriate profile, as specified in the Convert Colors dialog box, to the selected color space in the PDF. For more information, see the color conversion topics in Acrobat Help.

Changing the color profile for a document

There are very few situations that require you to change the color profile for a document. This is because your application automatically assigns the color profile based on the settings you select in the Color Settings dialog box. The only times you should manually change a color profile are when preparing a document for a different output destination or correcting a policy behavior that you no longer want implemented in the document. Changing the profile is recommended for advanced users only.

You can change the color profile for a document in the following ways:

- Assign a new profile. The color numbers in the document remain the same, but the new profile may dramatically change the appearance of the colors as displayed on your monitor.
- Remove the profile so that the document is no longer color-managed.
- (Acrobat, Photoshop and InDesign) Convert the colors in the document to the color space of a different profile. The color numbers are shifted in an effort to preserve the original color appearances.

Assign or remove a color profile (Illustrator, Photoshop)

Choose Edit > Assign Profile.

Select an option, and click OK:

Don't Color Manage This Document Removes the existing profile from the document. Select this option only if you are sure that you do not want to color-manage the document. After you remove the profile from a document, the appearance of colors is defined by the application's working space profiles.

Working [color model: working space] Assigns the working space profile to the document.

Profile Lets you select a different profile. The application assigns the new profile to the document without converting colors to the profile space. This may dramatically change the appearance of the colors as displayed on your monitor.

Assign or remove a color profile (InDesign)

1 Choose Edit > Assign Profiles.

2 For RGB Profile and CMYK Profile, select one of the following:

Discard (Use Current Working Space) Removes the existing profile from the document. Select this option only if you are sure that you do not want to color-manage the document. After you remove the profile from a document, the appearance of colors is defined by the application's working space profiles, and you can no longer embed a profile in the document.

Assign Current Working Space [working space] Assigns the working space profile to the document.

Assign Profile Lets you select a different profile. The application assigns the new profile to the document without converting colors to the profile space. This may dramatically change the appearance of the colors as displayed on your monitor.

? Choose a rendering intent for each type of graphic in your document. For each graphic type, you can choose one of the four standard intents, or the Use Color Settings Intent, which uses the rendering intent currently specified in the Color Settings dialog box. For more information on rendering intents, search in Help.

The graphic types include the following:

Solid Color Intent Sets the rendering intent for all vector art (solid areas of color) in InDesign native objects.

Default Image Intent Sets the default rendering intent for bitmap images placed in InDesign. You can still override this setting on an image-by-image basis.

After-Blending Intent Sets the rendering intent to the proofing or final color space for colors that result from transparency interactions on the page. Use this option when your document includes transparent objects.

? To preview the effects of the new profile assignment in the document, select Preview, and then click OK.

Convert document colors to another profile (Photoshop)

1 Choose Edit > Convert To Profile.

2 Under Destination Space, choose the color profile to which you want to convert the document's colors. The document will be converted to and tagged with this new profile.

3 Under Conversion Options, specify a color management engine, a rendering intent, and black point and dither options (if available). (See Color conversion options.)

4 To flatten all layers of the document onto a single layer upon conversion, select Flatten Image.

5 To preview the effects of the conversion in the document, select Preview.

Convert document colors to Multichannel, Device Link, or Abstract color profiles (Photoshop)

1 Choose Edit > Convert To Profile.

2 Click Advanced. The following additional ICC profile types are available under Destination Space:

Multichannel Profiles that support more than four color channels. These are useful when printing with more than four inks.

Device Link Profiles that transform from one device color space to another, without using an intermediate color space in the process. These are useful when specific mappings of device values (like 100% black) are required.

Abstract Profiles that enable custom image effects. Abstract profiles can have LAB/XYZ values for both input and output values, which enables generation of a custom LUT to achieve the desired special effect.

Note: Gray, RGB, LAB, and CMYK color profiles are grouped by category in Advanced view. They are combined on the Profile menu in Basic view.

? To preview the effects of the conversion in the document, select Preview.

Convert document colors to another profile (Acrobat)

You convert colors in a PDF by using Tools > Print Production > Convert Colors. For more information, see the color conversion topics in Acrobat Help.

Color-managing documents for online viewing

Color-managing documents for online viewing

Color management for online viewing is very different from color management for printed media. With printed media, you have far more control over the appearance of the final document. With online media, your document will appear on a wide range of possibly uncalibrated monitors and video display systems, significantly limiting your control over color consistency.

When you color-manage documents that will be viewed exclusively on the web, Adobe recommends that you use the sRGB color space. sRGB is the default working space for most Adobe color settings, but you can verify that sRGB is selected in the Color Settings dialog box (Photoshop, Illustrator, InDesign) or the Color Management preferences (Acrobat). With the working space set to sRGB, any RGB graphics you create will use sRGB as the color space.

When working with images that have an embedded color profile other than sRGB, you should convert the image's colors to sRGB before you save the image for use on the web. If you want the application to automatically convert the colors to sRGB when you open the image, select Convert To Working Space as the RGB color management policy. (Make sure that your RGB working space is set to sRGB.) In Photoshop and InDesign, you can also manually convert the colors to sRGB using the Edit > Convert To Profile command.

Note: *In InDesign, the Convert To Profile command only converts colors for native, not placed, objects in the document.*

Color-managing PDFs for online viewing

When you export PDFs, you can choose to embed profiles. PDFs with embedded profiles reproduce color consistently in Acrobat 4.0 or later running under a properly configured color management system.

Keep in mind that embedding color profiles increases the size of PDFs. RGB profiles are usually small (around 3 KB); however, CMYK profiles can range from 0.5 to 2 MB.

Color-managing HTML documents for online viewing

Many web browsers do not support color management. Of the browsers that do support color management, not all instances can be considered color-managed because they may be running on systems where the monitors are not calibrated. In addition, few web pages contain images with embedded profiles. If you manage a highly controlled environment, such as the intranet of a design studio, you may be able to achieve some degree of HTML color management for images by equipping everyone with a browser that supports color management and calibrating all monitors.

You can approximate how colors will look on uncalibrated monitors by using the sRGB color space. However, because color reproduction varies among uncalibrated monitors, you still won't be able to anticipate the true range of potential display variations.

Color-managing documents when printing

About color profiles

Precise, consistent color management requires accurate ICC-compliant profiles of all of your color devices. For example, without an accurate scanner profile, a perfectly scanned image may appear incorrect in another program, simply due to any difference between the scanner and the program displaying the image. This misleading representation may cause you to make unnecessary, time-wasting, and potentially damaging "corrections" to an already satisfactory image. With an accurate profile, a program importing the image can correct for any device differences and display a scan's actual colors.A color management system uses the following kinds of profiles:

Monitor profiles Describe how the monitor is currently reproducing color. This is the first profile you should create because viewing color accurately on your monitor allows for critical color decisions in the design process. If what you see on your monitor is not representative of the actual colors in your document, you will not be able to maintain color consistency.

Input device profiles Describe what colors an input device is capable of capturing or scanning. If your digital camera offers a choice of profiles, Adobe recommends that you select Adobe RGB. Otherwise, use sRGB (which is the default for most cameras). Advanced users may also consider using different profiles for different light sources. For scanner profiles, some photographers create separate profiles for each type or brand of film scanned on a scanner.

Output device profiles Describe the color space of output devices like desktop printers or a printing press. The color management system uses output device profiles to properly map the colors in a document to the colors within the gamut of an output device's color space. The output profile should also take into consideration specific printing conditions, such as the type of paper and ink. For example, glossy paper is capable of displaying a different range of colors than matte paper.

Most printer drivers come with built-in color profiles. It's a good idea to try these profiles before you invest in custom profiles.

Document profiles Define the specific RGB or CMYK color space of a document. By assigning, or tagging, a document with a profile, the application provides a definition of actual color appearances in the document. For example, R=127, G=12, B=107 is just a set of numbers that different devices will display differently. But when tagged with the Adobe RGB color space, these numbers specify an actual color or wavelength of light–in this case, a specific color of purple. When color management is on, Adobe applications automatically assign new documents a profile based on Working Space options in the Color Settings dialog box. Documents without assigned profiles are known as untagged and contain only raw color numbers. When working with untagged documents, Adobe applications use the current working space profile to display and edit colors.



A Profiles describe the color spaces of the input device and the document. B Using the profiles' descriptions, the color management system identifies the document's actual colors. C The monitor's profile tells the color management system how to translate the document's numeric values to the monitor's color space. D Using the output device's profile, the color management system translates the document's numeric values to the color values of the output device so the correct appearance of colors is printed.

About monitor calibration and characterization

Profiling software can both calibrate and characterize your monitor. Calibrating your monitor brings it into compliance with a predefined standard—for example, adjusting your monitor so that it displays color using the graphics arts standard white point color temperature of 5000° K (Kelvin). Characterizing your monitor simply creates a profile that describes how the monitor is currently reproducing color.

Monitor calibration involves adjusting the following video settings:

Brightness and contrast The overall level and range, respectively, of display intensity. These parameters work just as they do on a television. A monitor calibration utility helps you set an optimum brightness and contrast range for calibration.

Gamma The brightness of the midtone values. The values produced by a monitor from black to white are nonlinear—if you graph the values, they form a curve, not a straight line. Gamma defines the value of that curve halfway between black and white.

Phosphors The substances that CRT monitors use to emit light. Different phosphors have different color characteristics.

White point The color and intensity of the brightest white the monitor can reproduce.

Calibrate and profile your monitor

When you calibrate your monitor, you are adjusting it so it conforms to a known specification. Once your monitor is calibrated, the profiling utility lets you save a color profile. The profile describes the color behavior of the monitor—what colors can or cannot be displayed on the monitor and how the numeric color values in an image must be converted so that colors are displayed accurately.

1 Make sure your monitor has been turned on for at least a half hour. This gives it sufficient time to warm up and produce more consistent output.

2 Make sure your monitor is displaying thousands of colors or more. Ideally, make sure it is displaying millions of colors or 24-bit or higher.

3 Remove colorful background patterns on your monitor desktop and set your desktop to display neutral grays. Busy patterns or bright colors surrounding a document interfere with accurate color perception.

4 Do one of the following to calibrate and profile your monitor:

- In Windows, install and use a monitor calibration utility.
- In Mac OS, use the Calibrate utility, located on the System Preferences/Displays/Color tab.
- For the best results, use third-party software and measuring devices. In general, using a measuring device such as a colorimeter along with software can create more accurate profiles because an instrument can measure the colors displayed on a monitor far more accurately than the human eye.

Note: *Monitor performance changes and declines over time; recalibrate and profile your monitor every month or so. If you find it difficult or impossible to calibrate your monitor to a standard, it may be too old and faded.*

Most profiling software automatically assigns the new profile as the default monitor profile. For instructions on how to manually assign the monitor profile, refer to the Help system for your operating system.

Install a color profile

Color profiles are often installed when a device is added to your system. The accuracy of these profiles (often called generic profiles or canned profiles) varies from manufacturer to manufacturer. You can also obtain device profiles from your service provider, download profiles from the web, or create custom profiles using professional profiling equipment.

- In Windows, right-click a profile and select Install Profile. Alternatively, copy the profiles into the WINDOWS\system32\spool\drivers\color folder.
- In Mac OS, copy profiles into the /Library/ColorSync/Profiles folder or the /Users/[username]/Library/ColorSync/Profiles folder.

After installing color profiles, be sure to restart Adobe applications.

Embed a color profile

To embed a color profile in a document you created in Illustrator, InDesign, or Photoshop, you must save or export the document in a format that supports ICC profiles.

- Save or export the document in one of the following file formats: Adobe PDF, PSD (Photoshop), AI (Illustrator), INDD (InDesign), JPEG, Photoshop EPS, Large Document Format, or TIFF.
- Select the option for embedding ICC profiles. The exact name and location of this option varies between applications. Search Adobe Help for additional instructions.

Embed a color profile (Acrobat)

You can embed a color profile in an object or an entire PDF. Acrobat attaches the appropriate profile, as specified in the Convert Colors dialog box, to the selected color space in the PDF. For more information, see the color conversion topics in Acrobat Help.

Changing the color profile for a document

There are very few situations that require you to change the color profile for a document. This is because your application automatically assigns the color profile based on the settings you select in the Color Settings dialog box. The only times you should manually change a color profile are when preparing a document for a different output destination or correcting a policy behavior that you no longer want implemented in the document. Changing the profile is recommended for advanced users only.

You can change the color profile for a document in the following ways:

- Assign a new profile. The color numbers in the document remain the same, but the new profile may dramatically change the appearance of the colors as displayed on your monitor.
- Remove the profile so that the document is no longer color-managed.
- (Acrobat, Photoshop and InDesign) Convert the colors in the document to the color space of a different profile. The color numbers are shifted in an effort to preserve the original color appearances.

Assign or remove a color profile (Illustrator, Photoshop)

1 Choose Edit > Assign Profile.

2 Select an option, and click OK:

Don't Color Manage This Document Removes the existing profile from the document. Select this option only if you are sure that you do not want to color-manage the document. After you remove the profile from a document, the appearance of colors is defined by the application's working space profiles.

Working [color model: working space] Assigns the working space profile to the document.

Profile Lets you select a different profile. The application assigns the new profile to the document without converting colors to the profile space. This may dramatically change the appearance of the colors as displayed on your monitor.

Assign or remove a color profile (InDesign)

1 Choose Edit > Assign Profiles.

2 For RGB Profile and CMYK Profile, select one of the following: **Discard (Use Current Working Space)** Removes the existing profile from the document. Select this option only if you are sure that you do not want to color-manage the document. After you remove the profile from a document, the appearance of colors is defined by the application's working space profiles, and you can no longer embed a profile in the document.**Assign Current Working Space [working space]** Assigns the working space profile to the document.**Assign Profile** Lets you select a different profile. The application assigns the new profile to the document without converting colors to the profile space. This may dramatically change the appearance of the colors as displayed on your monitor.

3 Choose a rendering intent for each type of graphic in your document. For each graphic type, you can choose one of the four standard intents, or the Use Color Settings Intent, which uses the rendering intent currently specified in the Color Settings dialog box. For more information on rendering intents, search in Help. The graphic types include the following:**Solid Color Intent** Sets the rendering intent for all vector art (solid areas of color) in InDesign native objects.**Default Image Intent** Sets the default rendering intent for bitmap images placed in InDesign. You can still override this setting on an image-by-image basis.**After-Blending Intent** Sets the rendering intent to the proofing or final color space for colors that result from transparency interactions on the page. Use this option when your document includes transparent objects.

4 To preview the effects of the new profile assignment in the document, select Preview, and then click OK.

Convert document colors to another profile (Photoshop)

1 Choose Edit > Convert To Profile.

2 Under Destination Space, choose the color profile to which you want to convert the document's colors. The document will be converted to and tagged with this new profile.

3 Under Conversion Options, specify a color management engine, a rendering intent, and black point and dither options (if available). (See Color conversion options.)

4 To flatten all layers of the document onto a single layer upon conversion, select Flatten Image.

5 To preview the effects of the conversion in the document, select Preview.

Convert document colors to Multichannel, Device Link, or Abstract color profiles (Photoshop)

1 Choose Edit > Convert To Profile.

2 Click Advanced. The following additional ICC profile types are available under Destination Space:

Multichannel Profiles that support more than four color channels. These are useful when printing with more than four inks.

Device Link Profiles that transform from one device color space to another, without using an intermediate color space in the process. These are useful when specific mappings of device values (like 100% black) are required.

Abstract Profiles that enable custom image effects. Abstract profiles can have LAB/XYZ values for both input and output values, which enables generation of a custom LUT to achieve the desired special effect.

Note: Gray, RGB, LAB, and CMYK color profiles are grouped by category in Advanced view. They are combined on the Profile menu in Basic view.

? To preview the effects of the conversion in the document, select Preview.

Convert document colors to another profile (Acrobat)

You convert colors in a PDF by using Tools > Print Production > Convert Colors. For more information, see the color conversion topics in Acrobat Help.

Color-managing imported images

Color-managing imported images (Illustrator, InDesign)

How imported images are integrated into a document's color space depends on whether or not the image has an embedded profile:

- When you import an image that contains no profile, the Adobe application uses the current document profile to define the colors in the image.
- When you import an image that contains an embedded profile, color policies in the Color Settings dialog box determine how the Adobe application handles the profile.

Using a safe CMYK workflow

A safe CMYK workflow ensures that CMYK color numbers are preserved all the way to the final output device, as opposed to being converted by your color management system. This workflow is beneficial if you want to incrementally adopt color management practices. For example, you can use CMYK profiles to soft-proof and hard-proof documents without the possibility of unintended color conversions occurring during final output.

Illustrator and InDesign support a safe CMYK workflow by default. As a result, when you open or import a CMYK image with an embedded profile, the application ignores the profile and preserves the raw color numbers. If you want your application to adjust color numbers based on an embedded profile, change the CMYK color policy to Preserve Embedded Profiles in the Color Settings dialog box. You can easily restore the safe CMYK workflow by changing the CMYK color policy back to Preserve Numbers (Ignore Linked Profiles).

You can override safe CMYK settings when you print a document or save it to Adobe PDF. However, doing so may cause colors to be reseparated. For example, pure CMYK black objects may be reseparated as rich black. For more information on color management options for printing and saving PDFs, search in Help.

Preparing imported graphics for color management

Use the following general guidelines to prepare graphics for being color-managed in Adobe applications:

- Embed an ICC-compliant profile when you save the file. The file formats that support embedded profiles are JPEG, PDF, PSD (Photoshop), AI (Illustrator), INDD (InDesign), Photoshop EPS, Large Document Format, and TIFF.
- If you plan to reuse a color graphic for multiple final output devices or media, such as for print, video, and the web, prepare the graphic using RGB or Lab colors whenever possible. If you must save in a color model other than RGB or Lab, keep a copy of the original graphic. RGB and Lab color models represent larger color gamuts than most output devices can reproduce, retaining as much color information as possible before being translated to a smaller output color gamut.

View or change profiles for imported bitmap images (InDesign)

InDesign allows you to view, override, or disable profiles for imported bitmap images. This may be necessary when you are importing an image containing no profile or an incorrectly embedded profile. For example, if the scanner manufacturer's default profile was embedded but you have since generated a custom profile, you can assign the newer profile.

? Do one of the following:

- If the graphic is already in layout, select it and choose Object > Image Color Settings.
- If you're about to import the graphic, choose File > Place, select Show Import Options, select and open the file, and then select the Color tab.

1. For Profile, choose the source profile to apply to the graphic in your document. If a profile is currently embedded, the profile name appears at the top of the Profile menu.
2. (Optional) Choose a rendering intent, and then click OK. In most cases, it's best to use the default rendering intent.

Note: *You can also view or change profiles for objects in Acrobat.*

Proofing colors

About soft-proofing colors

In a traditional publishing workflow, you print a hard proof of your document to preview how its colors will look when reproduced on a specific output device. In a color-managed workflow, you can use the precision of color profiles to soft-proof your document directly on the monitor. You can display an on-screen preview of how your document's colors will look when reproduced on a particular output device. Keep in mind that the reliability of the soft proof depends upon the quality of your monitor, the profiles of your monitor and output devices, and the ambient lighting conditions of your work environment.

Note: *A soft proof alone doesn't let you preview how overprinting will look when printed on an offset press. If you work with documents that contain overprinting, turn on Overprint Preview to accurately preview overprints in a soft proof. For Acrobat, the Overprint Preview option is automatically applied.*



A *Document is created in its working color space.* ***B*** *Document's color values are translated to color space of chosen proof profile (usually the output device's profile).* ***C*** *Monitor displays proof profile's interpretation of document's color values.*

Soft-proof colors

1 Choose View > Proof Setup, and do one of the following:
   - Choose a preset that corresponds to the output condition you want to simulate.
   - Choose Custom (Photoshop and InDesign) or Customize (Illustrator) to create a custom proof setup for a specific output condition. This option is recommended for the most accurate preview of your final printed piece.

2 Choose View > Proof Colors to toggle the soft-proof display on and off. When soft proofing is on, a check mark appears next to the Proof Colors command, and the name of the proof preset or profile appears at the top of the document window.

To compare the colors in the original image and the colors in the soft proof, open the document in a new window before you set up the soft proof.

Soft-proof presets

Working CMYK Creates a soft proof of colors using the current CMYK working space as defined in the Color Settings dialog box.

Document CMYK (InDesign) Creates a soft proof of colors using the document's CMYK profile.

Working Cyan Plate, Working Magenta Plate, Working Yellow Plate, Working Black Plate, or Working CMY Plates (Photoshop) Creates a soft proof of specific CMYK ink colors using the current CMYK working space.

Legacy Macintosh RGB (Photoshop and Illustrator) Creates a soft proof of colors simulating Mac OS 10.5 and earlier.

Internet Standard RGB (Photoshop and Illustrator) Creates a soft proof of colors simulating Windows and Mac OS 10.6 and later.

Monitor RGB (Photoshop and Illustrator) Creates a soft proof of RGB colors using your current monitor profile as the proof profile.

The Legacy Macintosh, Internet Standard, and Monitor RGB options assume that the simulated device will display your document without using color management. These options are unavailable for Lab or CMYK documents.

Color Blindness (Photoshop and Illustrator) Creates a soft proof that reflects colors visible to a person with color blindness. The two soft proof options, Protanopia and Deuteranopia, approximate color perception for the most common forms of color blindness. For more information, see Soft-proof for color blindness (Photoshop and Illustrator).

Custom soft-proof options

Device To Simulate Specifies the color profile of the device for which you want to create the proof. The usefulness of the chosen profile depends on how accurately it describes the device's behavior. Often, custom profiles for specific paper and printer combinations create the most accurate soft proof.

Preserve CMYK Numbers or Preserve RGB Numbers Simulates how the colors will appear without being converted to the color space of the output device. This option is most useful when you are following a safe CMYK workflow.

Rendering Intent (Photoshop and Illustrator) When the Preserve Numbers option is deselected, specifies a rendering intent for converting colors to the device you are trying to simulate.

Use Black Point Compensation (Photoshop) Ensures that the shadow detail in the image is preserved by simulating the full dynamic range of the output device. Select this option if you plan to use black point compensation when printing (which is recommended in most situations).

Simulate Paper Color Simulates the dingy white of real paper, according to the proof profile. Not all profiles support this option.

Simulate Black Ink Simulates the dark gray you really get instead of a solid black on many printers, according to the proof profile. Not all profiles support this option.

In Photoshop, if you want the custom proof setup to be the default proof setup for documents, close all document windows before choosing the View > Proof Setup > Custom command.

Soft-proof for color blindness (Photoshop and Illustrator)

Color Universal Design (CUD) ensures that graphical information is conveyed accurately to people with various types of color vision, including people with color blindness. Several countries have guidelines that require CUD-compliant graphics in public spaces.

The most common types of color blindness are protanopia (reduced sensitivity to red) and deuteranopia (reduced sensitivity to green). A third of color blind people are affected strongly; the remainder have milder forms of color blindness.



***A** Original image **B** Color-blind proof **C** Optimized design*

To determine whether a document is CUD-compliant, do the following:

1. Convert the document to RGB color mode, which provides the most accurate soft-proofs for color blindness.
2. (Optional) To simultaneously view the original document and a soft-proof, choose Window > New Window (Illustrator) or Window > Arrange > New Window (Photoshop).
3. Choose View > Proof Setup > Color Blindness, and then choose either Protanopia-type or Deuteranopia-type. (To comply with CUD, check your document in both views.)

In Photoshop, you can print the proof. For more information, search for "Print a hard proof" in Photoshop Help.

If objects are difficult to distinguish in color blind proofs, adjust the design by doing any of the following:

- Change color brightness or hue:
  - Pure red tends to appear dark and muddy; orange-red is easier to recognize.
  - Bluish green is less confusing than yellowish green.
  - Gray may be confused with magenta, pale pink, pale green, or emerald green.
  - Avoid the following combinations: red and green; yellow and bright green; light blue and pink; dark blue and violet.
  - Avoid red items on dark-colored backgrounds, or white items on yellow or orange-red backgrounds.
- Apply different patterns or shapes.
- Add white, black, or dark-colored borders on color boundaries.
- Use different font families or styles.

Save or load a custom proof setup (Photoshop, InDesign)

1. Choose View > Proof Setup > Custom.
2. Do either of the following:
   - To save a custom proof setup, click Save. To ensure that the new preset appears in the View > Proof Setup menu, save the preset in the default location.
   - To load a custom proof setup, click Load.

Soft-proof colors (Acrobat)

1. Do one of the following, depending on your version of Acrobat:
   - (Acrobat 9) Choose Advanced > Print Production > Output Preview.
   - (Acrobat X) Choose Tools > Print Production > Output Preview.
2. Choose the color profile of a specific output device from the Simulation Profile menu.
3. Choose a soft-proof option:

   Simulate Black Ink Simulates the dark gray you really get instead of a solid black on many printers, according to the proof profile. Not all profiles support this option.

   Simulate Paper Color Simulates the dingy white of real paper, according to the proof profile. Not all profiles support this option.